

**CLEAN WATER INFRASTRUCTURE
REPLACEMENT PLAN UPDATE
for the
KENT COUNTY WATER AUTHORITY**

OCTOBER 1, 2014



Table of Contents

Section 1
Inventory

Section 2
Infrastructure Adequacy

Section 3
Infrastructure Adequacy (Water Main Details)

Section 4
Cost Summary

Section 5
Financial Adequacy



System Information	
System Name	Kent County Water Authority
PWSID	RI1559511
System Type	CWS
Contact Name	Timothy Brown
Contact Phone	401-821-9300
Contact E-mail	tbrown@kentcountywater.org
Fiscal Year Used	July 1- June 30
Current System Information	
Retail Population	88,779
Consecutive Population	Wholesale to Warwck
Total Population	
# of Service Connections	27,259
Type of Source Water	Blended: Purchased SW and Produced GW
Purchaser or Wholesaler	Both
Annual Usage (Million Gallons)	11.6 billion gallons

Infrastructure Type	Infrastructure Subtype	Brief Infrastructure Description	Number of Infrastructure Subtype	Age (in years)	Condition (poor, fair, good, excellent; or rating scale)	Remaining Useful Life (in years)	Need for Rehabilitation or Replacement (20-year timeframe) (Yes/No)	Evaluation/Prioritization for Rehabilitation or Replacement (5-year intervals) (Yes/No)	Infrastructure Supports SDWA Compliance (Yes/No)	Financial Forecast (in dollars)	O&M Notes	Other Notes
Source	Well	Mishnock Well #3, Gravel Packed Well 67.5', Developed March 2000, Cleaned in 2013, 18" Steel Cased 10' SS Screen	1	14	Excellent	40-50	No	No	Yes	\$0		Water Treatment Plant Online Dec 2013
Source	Well	Mishnock Well #4, Gravel Packed Well 72', Developed 2001, Cleaned in 2013, 18" Steel Cased 10' SS Screen	1	13	Excellent	40-50	No	No	Yes	\$0		Water Treatment Plant Online Dec 2013
Source	Well	Mishnock Well #5, Gravel Packed Well 85', Developed 2001, Cleaned in 2013, 18" Steel Cased 10' SS Screen	1	13	Excellent	40-50	No	No	Yes	\$0		Water Treatment Plant Online Dec 2013
Treatment	Treatment Building	Mishnock treatment facility	1	1	Excellent	35-40	No	No	Yes	\$0		Water Treatment Plant Online Dec 2013
Treatment	Generator	600 kW GenSet with ATS	1	1	Excellent	15-20	No	No	Yes	\$0		Water Treatment Plant Online Dec 2013

Infrastructure Type	Infrastructure Subtype	Brief Infrastructure Description	Number of Infrastructure Subtype	Age (in years)	Condition (poor, fair, good, excellent; or rating scale)	Remaining Useful Life (in years)	Need for Rehabilitation or Replacement (20-year timeframe) (Yes/No)	Evaluation/Prioritization for Rehabilitation or Replacement (5-year intervals) (Yes/No)	Infrastructure Supports SDWA Compliance (Yes/No)	Financial Forecast (in dollars)	O&M Notes	Other Notes
Treatment	Finished Water Pumps	Low Lift Pumps. 50 HP Multistate Turbines.	2	1	Excellent	15-20	No	No	Yes	\$0		Water Treatment Plant Online Dec 2013. Replace motor and pump.
Treatment	Finished Water Pumps	High Lift Pumps. 100 HP Multistate Turbines.	3	1	Excellent	15-20	No	No	Yes	\$0		Water Treatment Plant Online Dec 2013. Replace motor and pump.
Source	Well	Ground water, gravel-packed, well Spring Lake, offline	1	11	Poor (offline)	>10 with repairs	Yes	Yes	Yes	\$1,000,000	Budgetd \$25,000 for cleaning and inspection.	Facility refurbishment (5yr) and complete redevelopment in (20yr). 5yr costs included in CIP.
Source	Well Pump	Mishnock Well Pump # 3, 25 HP Submersible Vertical Turbine Pump	1	1	Excellent	10-15	No	No	Yes	\$0	0	Water Treatment Plant Online Dec 2013
Source	Well Pump	Mishnock Well Pump # 4, 30 HP Submersible Vertical Turbine Pump	1	1	Excellent	10-15	No	No	Yes	\$0	0	Water Treatment Plant Online Dec 2013

Infrastructure Type	Infrastructure Subtype	Brief Infrastructure Description	Number of Infrastructure Subtype	Age (in years)	Condition (poor, fair, good, excellent; or rating scale)	Remaining Useful Life (in years)	Need for Rehabilitation or Replacement (20-year timeframe) (Yes/No)	Evaluation/Prioritization for Rehabilitation or Replacement (5-year intervals) (Yes/No)	Infrastructure Supports SDWA Compliance (Yes/No)	Financial Forecast (in dollars)	O&M Notes	Other Notes
Source	Well Pump	Mishnock Well Pump #5, 20 HP Submersible Vertical Turbine Pump	1	1	Excellent	10-15	No	No	Yes	\$0	0	Water Treatment Plant Online Dec 2013
Source	Well	Ground water, gravel-packed well, East Greenwich	1	50	Poor	Replacement Required	Yes	Yes	Yes	\$0	\$0	5 yr costs included in CIP. Screen failure. \$100,000 to drill replacement well
Treatment	Treatment Building	East Greenwich Well Treatment Facility	1	50	Poor	Replacement Required	Yes	Yes	Yes	\$1,500,000	\$0	Construction of new wellfield facility.
Transmission_Distribution	Transmission Pump Station	Clinton Ave. Pump Station	1	6	Excellent	35-40 years	No	No	Yes	\$0	0	Rehabilitated in 2006
Transmission_Distribution	Booster Pumps	3,800 gpm vertical turbine pumps at Clinton Ave. Pump Station	5	8	Excellent	10-15 years	Yes	No	Yes	\$100,000	0	Replace pumps and motors

Infrastructure Type	Infrastructure Subtype	Brief Infrastructure Description	Number of Infrastructure Subtype	Age (in years)	Condition (poor, fair, good, excellent; or rating scale)	Remaining Useful Life (in years)	Need for Rehabilitation or Replacement (20-year timeframe) (Yes/No)	Evaluation/Prioritization for Rehabilitation or Replacement (5-year intervals) (Yes/No)	Infrastructure Supports SDWA Compliance (Yes/No)	Financial Forecast (in dollars)	O&M Notes	Other Notes
Transmission_Distribution	Booster Pumps	2,100 gpm vertical turbine pumps at Clinton Ave. Pump Station	2	8	Excellent	10-15 years	Yes	No	Yes	\$45,000	0	Replace pumps and motors
Transmission_Distribution	Water Meters	12 inch master meter at Oaklawn Ave for interconnection with Providence Water Supply Board, Underground station.	1	10	Functional	30 years	Yes	No	Yes	\$500,000	0	Rehabilitated in 2004
Transmission_Distribution	Transmission Pump Station	Bald Hill Road Pump Station	1	1	Very good	35-40 years	No	No	Yes	\$0	0	Rehabilitated in 2014
Storage	Reservoir	3,000,000 gallon Setian Lane Steel Tank, no cathodic protection	1	11	Good	20	Yes	No	Yes	\$300,000	0	Costs for cleaning and inspecting (20yr). Rehabilitate when coating system fails.
Storage	Reservoir	Frenchtown Tank. 1,500,000 gallon concrete tank, no cathodic protection	1	10	Good	20-50	Yes	No	Yes	\$100,000	0	Costs for cleaning and inspecting (20yr). Blast the outer surfaces when coating system fails

Infrastructure Type	Infrastructure Subtype	Brief Infrastructure Description	Number of Infrastructure Subtype	Age (in years)	Condition (poor, fair, good, excellent; or rating scale)	Remaining Useful Life (in years)	Need for Rehabilitation or Replacement (20-year timeframe) (Yes/No)	Evaluation/Prioritization for Rehabilitation or Replacement (5-year intervals) (Yes/No)	Infrastructure Supports SDWA Compliance (Yes/No)	Financial Forecast (in dollars)	O&M Notes	Other Notes
Storage	Standpipe	Tiogue Avenue Tank. 771,000 gallon steel standpipe, no cathodic protection. OUT OF SERVICE.	1	57	N/A	0	Yes	No	No	\$100,000	0	Out of service. \$100,000 to demolish.
Storage	Reservoir	Wakefield Street Tank. 2,000,000 gallon concrete reservoir. No cathodic protection. OUT OF SERVICE.	1	24	N/A	0	Yes	No	Yes	\$100,000	0	Out of service. \$100,000 to demolish.
Storage	Standpipe	West Street Tank. 1,000,000 gallon steel standpipe. No cathodic protection. OUT OF SERVICE.	Enter number of components included in the infrastructure if more than 1	58	N/A	0	Yes	No	Yes	\$100,000	0	Out of service. \$100,000 to demolish?
Storage	Standpipe	Read School House Road Tank. 1,500,000 gallon concrete tank. No cathodic protection	1	5	Good	50+ years	Yes	No	Yes	\$0	\$5,000 for cleaning and inspection	Constructed at 500ft elevation in 2009. Recoat exterior as coating system fails.
Storage	Elevated Water Storage	Technology Park Elevated Tank. 1,500,000 spheroid steel tank with cathodic protection	1	26	Very good	50+ years	Yes	No	Yes	\$1,000,000	\$5,000 for cleaning and inspection	Costs for complete recoating, cleaning, and inspection. \$1 million expense for complete rehabilitation at the end of coating system life cycle.

Infrastructure Type	Infrastructure Subtype	Brief Infrastructure Description	Number of Infrastructure Subtype	Age (in years)	Condition (poor, fair, good, excellent; or rating scale)	Remaining Useful Life (in years)	Need for Rehabilitation or Replacement (20-year timeframe) (Yes/No)	Evaluation/Prioritization for Rehabilitation or Replacement (5-year intervals) (Yes/No)	Infrastructure Supports SDWA Compliance (Yes/No)	Financial Forecast (in dollars)	O&M Notes	Other Notes
Storage	Reservoir	Carr Pond Road Tank. 3,000,000 gallon concrete reservoir. No cathodic protection	Enter number of components included in the infrastructure if more than 1	13	Very good	50+ years	Yes	No	Yes	\$100,000	\$5,000 for cleaning and inspection	Recoat exterior when coating system fails
Transmission_Distribution	Booster Pump Station Building	Knotty Oak Rd.	1	14	Fair	10	Yes	No	No	\$60,000		Demolish building
Transmission_Distribution	Booster Pumps	1,200 gpm pump at Johnson Blvd. pumping station	1	23	Good	10	Yes	No	Yes	\$50,000	0	Remove from service once Mishnock Treatment Plant high service capacity is online.
Transmission_Distribution	Booster Pump Station	West Warwick Industrial Park	1	11	Excellent	20+	Yes	No	Yes	\$50,000	0	Structure consists of a prefabricated buried steel vault with ladder access. Replace pumps and motors.
Transmission_Distribution	Booster Pump Station	Seitan Lane Booster Pump Station	1	10	Excellent	20+	Yes	No	Yes	\$150,000	0	Structure consists of a prefabricated buried steel vault with ladder access. Replace pumps and motors.

Infrastructure Type	Infrastructure Subtype	Brief Infrastructure Description	Number of Infrastructure Subtype	Age (in years)	Condition (poor, fair, good, excellent; or rating scale)	Remaining Useful Life (in years)	Need for Rehabilitation or Replacement (20-year timeframe) (Yes/No)	Evaluation/Prioritization for Rehabilitation or Replacement (5-year intervals) (Yes/No)	Infrastructure Supports SDWA Compliance (Yes/No)	Financial Forecast (in dollars)	O&M Notes	Other Notes
Transmission_Distribution	Pressure reducing station	Middle Road	1	16	Good	20	Yes	No	Yes	\$75,000	0	Installed in 1999. 20+ years with proper maintenance. A mechanical/electric upgrade is recommended at 16-20 years at a cost of \$75,000.
Transmission_Distribution	Pressure reducing station	Cowesett Road	1	16	Good	20 years	Yes	No	Yes	\$75,000	0	Installed in 1999. 20+ years with proper maintenance. A mechanical/electric upgrade is recommended at 16-20 years at a cost of \$75,000.
Transmission_Distribution	Pressure reducing station	Love Lane	1	16	Good	20 years	Yes	No	Yes	\$75,000	0	Installed in 1999. 20+ years with proper maintenance. A mechanical/electric upgrade is recommended at 16-20 years at a cost of \$75,000.
Transmission_Distribution	Pressure reducing station	Post Road	1	16	Good	20 years	Yes	No	Yes	\$75,000	0	Installed in 1999. 20+ years with proper maintenance. A mechanical/electric upgrade is recommended at 16-20 years at a cost of \$75,000.
Transmission_Distribution	Pressure reducing station	Centerville Road	1	16	Good	20 years	Yes	No	Yes	\$75,000	0	Installed in 1999. 20+ years with proper maintenance. A mechanical/electric upgrade is recommended at 16-20 years at a cost of \$75,000.

Infrastructure Type	Infrastructure Subtype	Brief Infrastructure Description	Number of Infrastructure Subtype	Age (in years)	Condition (poor, fair, good, excellent; or rating scale)	Remaining Useful Life (in years)	Need for Rehabilitation or Replacement (20-year timeframe) (Yes/No)	Evaluation/Prioritization for Rehabilitation or Replacement (5-year intervals) (Yes/No)	Infrastructure Supports SDWA Compliance (Yes/No)	Financial Forecast (in dollars)	O&M Notes	Other Notes
Transmission_Distribution	Pressure reducing station	Division Road	1	16	Excellent	20 years	Yes	No	Yes	\$75,000	0	Installed in 1999. 20+ years with proper maintenance. A mechanical/electric upgrade is recommended at 16-20 years at a cost of \$75,000.
Transmission_Distribution	Pressure reducing station	Helen Street	1	23	Poor	5 years	Yes	No	Yes	\$300,000	0	This facility should be replaced with a modern, buried capsule-type valve vault with confined space entry provisions at the estimated cost of \$300,000.
Transmission_Distribution	Pressure reducing station	Mishnock Road	1	23	Poor	5 years	Yes	No	Yes	\$300,000	0	This facility should be replaced with a modern, buried capsule-type valve vault with confined space entry provisions at the estimated cost of \$300,000.
Other	Office Building	Main Street Administrative and Maintenance Building	1	100 years	Poor-Fair	Reached end of useful life	Yes	Yes	Yes	\$0	0	Complete replacement using CIP funds at a cost of \$15,000,000.
Other	Other (describe)	Hydraulic model update	1	Enter Value	Enter Value	Enter Value	Yes	No	Yes	\$100,000	0	Ongoing; provides guidance on implementing system improvements

Infrastructure Type	Infrastructure Subtype	Brief Infrastructure Description	Number of Infrastructure Subtype	Age (in years)	Condition (poor, fair, good, excellent; or rating scale)	Remaining Useful Life (in years)	Need for Rehabilitation or Replacement (20-year timeframe) (Yes/No)	Evaluation/Prioritization for Rehabilitation or Replacement (5-year intervals) (Yes/No)	Infrastructure Supports SDWA Compliance (Yes/No)	Financial Forecast (in dollars)	O&M Notes	Other Notes
Other	Other (describe)	GIS for the system	1	Enter Value	Enter Value	Enter Value	Yes	Yes	Meets SDWA Requirements (Yes/No)	\$50,000	0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-7252	COV	Abbotts Crossing Rd.	6	Asbestos Cement	138	64	2.58 out of 5	\$345	\$47,610	
Distribution Mains	P-7253	COV	Abbotts Crossing Rd.	6	Asbestos Cement	1,447	64	2.58 out of 5	\$345	\$499,215	
Transmission Mains	P-8329	COV	Abbotts Crossing Rd. Easement	12	Ductile Iron	1,356	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8330	COV	Abbotts Crossing Rd. Easement	12	Ductile Iron	218	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8346	COV	Abbotts Crossing Rd. Easement	8	Ductile Iron	422	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7145	COV	Acacia Ct.	8	Asbestos Cement	551	34	1.58 out of 5	\$345	\$190,095	
Distribution Mains	P-8302	COV	Acorn St.	6	Asbestos Cement	315	48	2.43 out of 5	\$345	\$108,675	
Distribution Mains	P-8980	COV	Acorn St.	6	Asbestos Cement	19	48	2.43 out of 5	\$345	\$6,555	
Distribution Mains	P-8982	COV	Acorn St.	6	Asbestos Cement	445	48	2.43 out of 5	\$345	\$153,525	
Distribution Mains	P-7604	COV	Ada Ct.	6	Asbestos Cement	205	55	2.43 out of 5	\$345	\$70,725	
Distribution Mains	P-7175	COV	Adams Dr.	8	Asbestos Cement	317	36	1.58 out of 5	\$345	\$109,365	
Distribution Mains	P-7176	COV	Adams Dr.	8	Asbestos Cement	437	36	1.58 out of 5	\$345	\$150,765	
Distribution Mains	P-7445	COV	Adams Dr.	8	Asbestos Cement	499	37	1.58 out of 5	\$345	\$172,155	
Distribution Mains	P-8225	COV	Adams Dr.	8	Asbestos Cement	68	36	1.58 out of 5	\$345	\$23,460	
Transmission Mains	P-8386	COV	Adams Dr.	12	Ductile Iron	136	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8387	COV	Adams Dr.	12	Ductile Iron	318	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7171	COV	Adams Dr.	8	Ductile Iron	412	15	0 out of 5	N/A	\$0	
Distribution Mains	P-7578	COV	Alaska St.	2	Galvanized iron	467	81	3.44 out of 5	\$345	\$161,115	
Distribution Mains	P-8297	COV	Alaska St.	8	Ductile Iron	94	14	0 out of 5	N/A	\$0	
Distribution Mains	P-9030	COV	Albro Ln.	1	Copper	194	76	2.44 out of 5	\$345	\$66,930	
Distribution Mains	P-7853	COV	Albro Ln.	6	Cast iron	440	76	2.29 out of 5	\$345	\$151,800	
Distribution Mains	P-9067	COV	Alex St.	1	Copper	210	61	2.44 out of 5	\$345	\$72,450	
Distribution Mains	P-8116	COV	Alexis St.	8	Ductile Iron	570	22	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8117	COV	Alexis St.	8	Ductile Iron	316	22	0.15 out of 5	N/A	\$0	
Distribution Mains	P-9056	COV	Alice St.	1	Copper	123	127	2.73 out of 5	\$345	\$42,435	
Distribution Mains	P-7354	COV	Almond Way	8	Ductile Iron	189	16	0 out of 5	N/A	\$0	
Distribution Mains	P-7230	COV	Alvero Rd.	8	Asbestos Cement	445	51	1.72 out of 5	\$345	\$153,525	
Distribution Mains	P-7237	COV	Alvero Rd.	8	Asbestos Cement	383	51	1.72 out of 5	\$345	\$132,135	
Distribution Mains	P-7248	COV	Alvero Rd.	8	Ductile Iron	733	13	0 out of 5	N/A	\$0	
Transmission Mains	P-8370	COV	Ames St.	16	Ductile Iron	399	7	0 out of 5	N/A	\$0	
Transmission Mains	P-8371	COV	Ames St.	16	Ductile Iron	486	7	0 out of 5	N/A	\$0	
Transmission Mains	P-8838	COV	Ames St.	12	Ductile Iron	387	5	0 out of 5	N/A	\$0	
Transmission Mains	P-8841	COV	Ames St.	12	Ductile Iron	508	5	0 out of 5	N/A	\$0	
Distribution Mains	P-7816	COV	Amherst Ave.	6	Asbestos Cement	292	47	2.43 out of 5	\$345	\$100,740	
Distribution Mains	P-7996	COV	Anderson Ave.	6	Asbestos Cement	553	53	2.43 out of 5	\$345	\$190,785	
Distribution Mains	P-7622	COV	Angelwood Dr.	6	Asbestos Cement	315	55	2.43 out of 5	\$345	\$108,675	
Distribution Mains	P-7623	COV	Angelwood Dr.	6	Asbestos Cement	425	55	2.43 out of 5	\$345	\$146,625	
Transmission Mains	P-8141	COV	Angus St.	12	Ductile Iron	578	6	0 out of 5	N/A	\$0	
Transmission Mains	P-8142	COV	Angus St.	12	Ductile Iron	922	6	0 out of 5	N/A	\$0	
Distribution Mains	P-8024	COV	Ann Ct.	2	Copper	287	74	2.44 out of 5	\$345	\$99,015	
Distribution Mains	P-7866	COV	Anthony St.	6	Cast iron	479	81	2.43 out of 5	\$345	\$165,255	
Distribution Mains	P-9031	COV	Anthony St.	6	Cast iron	455	81	2.43 out of 5	\$345	\$156,975	
Distribution Mains	P-7034	COV	Apple Blossom Ln.	6	Asbestos Cement	713	52	2.43 out of 5	\$345	\$245,985	
Distribution Mains	P-7035	COV	Apple Blossom Ln.	6	Asbestos Cement	594	52	2.43 out of 5	\$345	\$204,930	
Distribution Mains	P-8955	COV	Apple Blossom Ln.	6	Asbestos Cement	244	52	2.43 out of 5	\$345	\$84,180	
Distribution Mains	P-8389	COV	Arbor Dr.	8	Ductile Iron	500	7	0 out of 5	N/A	\$0	
Distribution Mains	P-8390	COV	Arbor Dr.	8	Ductile Iron	530	7	0 out of 5	N/A	\$0	
Distribution Mains	P-8391	COV	Arbor Dr.	8	Ductile Iron	530	7	0 out of 5	N/A	\$0	
Distribution Mains	P-8392	COV	Arbor Dr.	8	Ductile Iron	200	7	0 out of 5	N/A	\$0	
Distribution Mains	P-8397	COV	Arbor Dr.	8	Ductile Iron	320	7	0 out of 5	N/A	\$0	
Distribution Mains	P-8404	COV	Arbor Dr.	8	Ductile Iron	230	4	0 out of 5	N/A	\$0	
Distribution Mains	P-7120	COV	Arbutus Tr.	8	Ductile Iron	570	22	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7123	COV	Arbutus Tr.	8	Ductile Iron	320	22	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7124	COV	Arbutus Tr.	8	Ductile Iron	351	22	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7579	COV	Arizona St.	2	Galvanized iron	574	81	4.15 out of 5	\$345	\$198,030	
Distribution Mains	P-7582	COV	Arizona St.	2	Cast iron	156	81	3.86 out of 5	\$345	\$53,820	
Distribution Mains	P-8295	COV	Arizona St.	8	Ductile Iron	82	14	0 out of 5	N/A	\$0	
Transmission Mains	P-7588	COV	Arnold Rd.	16	Cast iron	398	124	1.87 out of 5	\$345	\$137,310	
Transmission Mains	P-7589	COV	Arnold Rd.	16	Cast iron	89	124	1.87 out of 5	\$345	\$30,705	
Transmission Mains	P-7596	COV	Arnold Rd.	16	Cast iron	166	124	1.87 out of 5	\$345	\$57,270	
Transmission Mains	P-7597	COV	Arnold Rd.	16	Cast iron	134	124	1.87 out of 5	\$345	\$46,230	
Transmission Mains	P-7649	COV	Arnold Rd.	16	Cast iron	47	124	1.87 out of 5	\$345	\$16,215	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-7650	COV	Arnold Rd.	16	Cast iron	945	124	1.87 out of 5	\$345	\$326,025	
Transmission Mains	P-7651	COV	Arnold Rd.	16	Cast iron	298	124	1.87 out of 5	\$345	\$102,810	
Transmission Mains	P-7659	COV	Arnold Rd.	16	Cast iron	181	124	1.87 out of 5	\$345	\$62,445	
Transmission Mains	P-7663	COV	Arnold Rd.	16	Cast iron	241	124	1.87 out of 5	\$345	\$83,145	
Transmission Mains	P-7688	COV	Arnold Rd.	16	Cast iron	178	124	1.87 out of 5	\$345	\$61,410	
Transmission Mains	P-7690	COV	Arnold Rd.	16	Cast iron	170	124	1.87 out of 5	\$345	\$58,650	
Transmission Mains	P-7692	COV	Arnold Rd.	16	Cast iron	59	124	1.87 out of 5	\$345	\$20,355	
Transmission Mains	P-7694	COV	Arnold Rd.	16	Cast iron	235	124	1.87 out of 5	\$345	\$81,075	
Transmission Mains	P-7697	COV	Arnold Rd.	16	Cast iron	858	124	1.87 out of 5	\$345	\$296,010	
Transmission Mains	P-7707	COV	Arnold Rd.	16	Cast iron	360	124	1.87 out of 5	\$345	\$124,200	
Transmission Mains	P-7712	COV	Arnold Rd.	16	Cast iron	42	124	1.87 out of 5	\$345	\$14,490	
Transmission Mains	P-8228	COV	Arnold Rd.	16	Cast iron	55	124	1.87 out of 5	\$345	\$18,975	
Transmission Mains	P-8267	COV	Arnold Rd.	16	Cast iron	224	124	1.87 out of 5	\$345	\$77,280	
Transmission Mains	P-8299	COV	Arnold Rd.	16	Cast iron	163	124	1.87 out of 5	\$345	\$56,235	
Transmission Mains	P-8306	COV	Arnold Rd.	16	Cast iron	234	124	1.87 out of 5	\$345	\$80,730	
Transmission Mains	P-8307	COV	Arnold Rd.	16	Cast iron	204	124	1.87 out of 5	\$345	\$70,380	
Transmission Mains	P-8310	COV	Arnold Rd.	16	Cast iron	273	124	1.87 out of 5	\$345	\$94,185	
Transmission Mains	P-8311	COV	Arnold Rd.	16	Cast iron	47	124	1.87 out of 5	\$345	\$16,215	
Transmission Mains	P-8793	COV	Arnold Rd.	16	Cast iron	241	124	1.87 out of 5	\$345	\$83,145	
Transmission Mains	P-8984	COV	Arnold Rd.	16	Cast iron	299	124	1.87 out of 5	\$345	\$103,155	
Distribution Mains	P-7711	COV	Arnold Rd.	8	Asbestos Cement	995	45	1.72 out of 5	\$345	\$343,275	
Distribution Mains	P-8176	COV	Arnold Rd.	8	Asbestos Cement	329	45	1.72 out of 5	\$345	\$113,505	
Distribution Mains	P-8313	COV	Arnold Rd.	8	Asbestos Cement	431	45	1.72 out of 5	\$345	\$148,695	
Distribution Mains	P-8314	COV	Arnold Rd.	8	Asbestos Cement	1,082	45	1.72 out of 5	\$345	\$373,290	
Transmission Mains	P-8183	COV	Arnold Rd.	16	Ductile Iron	453	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8184	COV	Arnold Rd.	16	Ductile Iron	172	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8185	COV	Arnold Rd.	16	Ductile Iron	1,798	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8186	COV	Arnold Rd.	16	Ductile Iron	239	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8187	COV	Arnold Rd.	16	Ductile Iron	772	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8188	COV	Arnold Rd.	16	Ductile Iron	2,904	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7134	COV	Ash Ln.	8	Ductile Iron	267	15	0 out of 5	N/A	\$0	
Distribution Mains	P-7606	COV	Audrey Ct.	6	Asbestos Cement	195	55	2.43 out of 5	\$345	\$67,275	
Distribution Mains	P-7107	COV	Azalea Way	8	Asbestos Cement	803	35	1.58 out of 5	\$345	\$277,035	
Distribution Mains	P-7699	COV	Balsam Dr.	6	Asbestos Cement	328	55	2.43 out of 5	\$345	\$113,160	
Distribution Mains	P-7700	COV	Balsam Dr.	6	Asbestos Cement	123	55	2.43 out of 5	\$345	\$42,435	
Distribution Mains	P-7538	COV	Bank St.	8	PVC	240	30	0.44 out of 5	\$345	\$82,800	
Distribution Mains	P-7518	COV	Barber St.	2	Galvanized iron	599	116	3.59 out of 5	\$345	\$206,655	
Distribution Mains	P-7520	COV	Barber St.	1	Galvanized iron	196	87	3.44 out of 5	\$345	\$67,620	
Distribution Mains	P-7897	COV	Barberry Ct.	6	Asbestos Cement	243	34	2.29 out of 5	\$345	\$83,835	
Distribution Mains	P-8030	COV	Bassett St.	2	Galvanized iron	319	104	3.59 out of 5	\$345	\$110,055	
Distribution Mains	P-9057	COV	Bates Ave.	2	Cast iron	115	127	3.3 out of 5	\$345	\$39,675	
Distribution Mains	P-8279	COV	Bates Ave.	2	Cast iron	189	74	3.01 out of 5	\$345	\$65,205	
Distribution Mains	P-8034	COV	Bates Ave.	6	Cast iron	222	127	2.58 out of 5	\$345	\$76,590	
Distribution Mains	P-8035	COV	Bates Ave.	6	Cast iron	393	127	2.58 out of 5	\$345	\$135,585	
Distribution Mains	P-8280	COV	Bates Ave.	6	Cast iron	619	74	2.29 out of 5	\$345	\$213,555	
Distribution Mains	P-8278	COV	Bates Ave.	8	Cast iron	668	74	1.58 out of 5	\$345	\$230,460	
Distribution Mains	P-7847	COV	Batley Ave.	6	Ductile Iron	305	24	0.86 out of 5	\$345	\$105,225	
Distribution Mains	P-7783	COV	Baylor Dr.	6	Asbestos Cement	489	48	2.43 out of 5	\$345	\$168,705	
Distribution Mains	P-7787	COV	Baylor Dr.	6	Asbestos Cement	247	48	2.43 out of 5	\$345	\$85,215	
Distribution Mains	P-8989	COV	Beach St.	8	Ductile Iron	60	7	0 out of 5	N/A	\$0	
Distribution Mains	P-8988	COV	Beach St.	2	Copper	99	60	2.44 out of 5	\$345	\$34,155	
Distribution Mains	P-8992	COV	Beach St.	2	Copper	259	60	2.44 out of 5	\$345	\$89,355	
Distribution Mains	P-7660	COV	Beach St.	6	Cast iron	335	60	2.29 out of 5	\$345	\$115,575	
Distribution Mains	P-7531	COV	Beaton St.	6	Asbestos Cement	469	66	2.58 out of 5	\$345	\$161,805	
Distribution Mains	P-9040	COV	Beaulieu Ave.	1	Copper	451	70	2.44 out of 5	\$345	\$155,595	
Distribution Mains	P-8836	COV	Bee St.	8	Ductile Iron	298	3	0 out of 5	N/A	\$0	
Distribution Mains	P-8303	COV	Beechwood St.	6	Asbestos Cement	338	60	2.58 out of 5	\$345	\$116,610	
Distribution Mains	P-8304	COV	Beechwood St.	6	Asbestos Cement	240	60	2.58 out of 5	\$345	\$82,800	
Distribution Mains	P-8977	COV	Beechwood St.	6	Asbestos Cement	277	60	2.58 out of 5	\$345	\$95,565	
Distribution Mains	P-8886	COV	Bellmare Rd.	8	Ductile Iron	361	8	0 out of 5	N/A	\$0	
Distribution Mains	P-8037	COV	Bennett St.	2	Galvanized iron	302	114	4.3 out of 5	\$345	\$104,190	
Distribution Mains	P-9059	COV	Bennett St.	6	Cast iron	137	119	2.58 out of 5	\$345	\$47,265	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-7870	COV	Benoit St.	6	Cast iron	94	76	2.29 out of 5	\$345	\$32,430	
Distribution Mains	P-8223	COV	Benoit St.	6	Cast iron	314	76	2.29 out of 5	\$345	\$108,330	
Distribution Mains	P-7401	COV	Benoit St.	6	Ductile Iron	921	22	0.86 out of 5	\$345	\$317,745	
Distribution Mains	P-9033	COV	Benoit St.	6	Ductile Iron	437	22	0.86 out of 5	\$345	\$150,765	
Distribution Mains	P-9010	COV	Berkshire Rd.	1	Copper	97	8	2 out of 5	\$345	\$33,465	
Distribution Mains	P-9011	COV	Berkshire Rd.	8	Ductile Iron	26	8	0 out of 5	N/A	\$0	
Distribution Mains	P-7813	COV	Bernard Dr.	6	Asbestos Cement	278	60	2.58 out of 5	\$345	\$95,910	
Distribution Mains	P-7924	COV	Birchwood Ln.	8	PVC	533	34	0.44 out of 5	\$345	\$183,885	
Distribution Mains	P-8338	COV	Birdie Ct.	6	Ductile Iron	283	25	0.86 out of 5	\$345	\$97,635	
Distribution Mains	P-7917	COV	Black Walnut Dr.	8	PVC	274	31	0.44 out of 5	\$345	\$94,530	
Distribution Mains	P-7919	COV	Black Walnut Dr.	8	PVC	105	31	0.44 out of 5	\$345	\$36,225	
Distribution Mains	P-7921	COV	Black Walnut Dr.	8	PVC	331	31	0.44 out of 5	\$345	\$114,195	
Distribution Mains	P-7923	COV	Black Walnut Dr.	8	PVC	528	31	0.44 out of 5	\$345	\$182,160	
Distribution Mains	P-7925	COV	Black Walnut Dr.	8	PVC	464	31	0.44 out of 5	\$345	\$160,080	
Distribution Mains	P-7927	COV	Black Walnut Dr.	8	PVC	215	31	0.44 out of 5	\$345	\$74,175	
Distribution Mains	P-7929	COV	Black Walnut Dr.	8	PVC	674	31	0.44 out of 5	\$345	\$232,530	
Distribution Mains	P-8874	COV	Black Walnut Dr.	8	Ductile Iron	38	10	0 out of 5	N/A	\$0	
Distribution Mains	P-7397	COV	Blackrock Rd.	8	Asbestos Cement	1,765	65	1.87 out of 5	\$345	\$608,925	
Distribution Mains	P-8379	COV	Blackrock Rd.	8	PVC	500	26	0.44 out of 5	\$345	\$172,500	
Distribution Mains	P-8378	COV	Blackrock Rd.	8	Ductile Iron	710	24	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7396	COV	Blackrock Rd.	12	Ductile Iron	601	9	0 out of 5	N/A	\$0	
Transmission Mains	P-7936	COV	Blackrock Rd.	24	Ductile Iron	1,081	9	0 out of 5	N/A	\$0	
Transmission Mains	P-7940	COV	Blackrock Rd.	24	Ductile Iron	267	9	0 out of 5	N/A	\$0	
Transmission Mains	P-7944	COV	Blackrock Rd.	24	Ductile Iron	380	9	0 out of 5	N/A	\$0	
Transmission Mains	P-7955	COV	Blackrock Rd.	24	Ductile Iron	269	9	0 out of 5	N/A	\$0	
Transmission Mains	P-7970	COV	Blackrock Rd.	24	Ductile Iron	847	9	0 out of 5	N/A	\$0	
Transmission Mains	P-8499	COV	Blackrock Rd.	24	Ductile Iron	1,771	9	0 out of 5	N/A	\$0	
Transmission Mains	P-8500	COV	Blackrock Rd.	24	Ductile Iron	922	9	0 out of 5	N/A	\$0	
Transmission Mains	P-8501	COV	Blackrock Rd.	24	Ductile Iron	1,830	9	0 out of 5	N/A	\$0	
Transmission Mains	P-8502	COV	Blackrock Rd.	24	Ductile Iron	528	9	0 out of 5	N/A	\$0	
Distribution Mains	P-7060	COV	Blue Spruce Dr.	8	Asbestos Cement	1,017	38	1.58 out of 5	\$345	\$350,865	
Distribution Mains	P-7050	COV	Blueberry Ln.	6	Asbestos Cement	357	47	2.43 out of 5	\$345	\$123,165	
Distribution Mains	P-7766	COV	Bonney St.	6	Asbestos Cement	548	54	2.43 out of 5	\$345	\$189,060	
Distribution Mains	P-9015	COV	Bonney St.	6	Ductile Iron	56	7	0.71 out of 5	\$345	\$19,320	
Distribution Mains	P-7867	COV	Boston St.	6	Cast iron	346	86	3.14 out of 5	\$345	\$119,370	
Distribution Mains	P-9037	COV	Boston St.	6	Cast iron	532	86	3.14 out of 5	\$345	\$183,540	
Distribution Mains	P-8377	COV	Boston St.	6	Asbestos Cement	1,063	65	2.58 out of 5	\$345	\$366,735	
Distribution Mains	P-7402	COV	Boston St.	6	Cast iron	144	86	2.43 out of 5	\$345	\$49,680	
Distribution Mains	P-7403	COV	Boston St.	6	Cast iron	886	86	2.43 out of 5	\$345	\$305,670	
Distribution Mains	P-7871	COV	Boston St.	6	Cast iron	141	86	2.43 out of 5	\$345	\$48,645	
Distribution Mains	P-8222	COV	Boston St.	6	Cast iron	174	86	2.43 out of 5	\$345	\$60,030	
Distribution Mains	P-7399	COV	Boston St.	6	Ductile Iron	43	22	0.86 out of 5	\$345	\$14,835	
Distribution Mains	P-8376	COV	Boston St.	6	Ductile Iron	1,107	22	0.86 out of 5	\$345	\$381,915	
Distribution Mains	P-7213	COV	Boulder Dr.	8	Ductile Iron	708	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7214	COV	Boulder Dr.	8	Ductile Iron	315	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8335	COV	Brassie Ct.	6	Ductile Iron	288	25	0.86 out of 5	\$345	\$99,360	
Distribution Mains	P-8884	COV	Breezy Lake Dr.	1	Galvanized iron	61	49	3.15 out of 5	\$345	\$21,045	
Distribution Mains	P-8882	COV	Breezy Lake Dr.	6	Asbestos Cement	505	49	3.14 out of 5	\$345	\$174,225	
Distribution Mains	P-7364	COV	Breezy Lake Dr.	6	Asbestos Cement	247	49	2.43 out of 5	\$345	\$85,215	
Distribution Mains	P-7365	COV	Breezy Lake Dr.	6	Asbestos Cement	490	49	2.43 out of 5	\$345	\$169,050	
Distribution Mains	P-7366	COV	Breezy Lake Dr.	6	Asbestos Cement	146	49	2.43 out of 5	\$345	\$50,370	
Distribution Mains	P-7367	COV	Breezy Lake Dr.	6	Asbestos Cement	181	49	2.43 out of 5	\$345	\$62,445	
Distribution Mains	P-8883	COV	Breezy Lake Dr.	6	Asbestos Cement	215	49	2.43 out of 5	\$345	\$74,175	
Distribution Mains	P-7184	COV	Brenda Dr.	6	Asbestos Cement	475	43	2.43 out of 5	\$345	\$163,875	
Distribution Mains	P-8895	COV	Brenda Dr.	6	Ductile Iron	35	3	0.71 out of 5	\$345	\$12,075	
Distribution Mains	P-7556	COV	Brentwood Dr.	6	Asbestos Cement	418	61	2.58 out of 5	\$345	\$144,210	
Distribution Mains	P-7695	COV	Briar Point Ave.	6	Asbestos Cement	420	67	2.58 out of 5	\$345	\$144,900	
Distribution Mains	P-8995	COV	Briar Point Ave.	8	Ductile Iron	181	6	0 out of 5	N/A	\$0	
Distribution Mains	P-7926	COV	Briarwood Ct.	8	PVC	228	34	0.44 out of 5	\$345	\$78,660	
Transmission Mains	P-8219	COV	Broad St.	12	Ductile Iron	243	7	0 out of 5	N/A	\$0	
Distribution Mains	P-7387	COV	Brookfield Rd.	8	Ductile Iron	489	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8905	COV	Brookside Ln.	2	Copper	318	64	2.44 out of 5	\$345	\$109,710	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-8074	COV	Brown St.	8	Cast iron	1,080	86	1.72 out of 5	\$345	\$372,600	
Distribution Mains	P-7157	COV	Butternut Dr.	8	Asbestos Cement	711	36	1.58 out of 5	\$345	\$245,295	
Distribution Mains	P-7076	COV	Butternut Dr. Easement	8	Ductile Iron	201	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8934	COV	Cady St.	8	Ductile Iron	229	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-9065	COV	Callahan Way	8	Ductile Iron	47	6	0 out of 5	N/A	\$0	
Distribution Mains	P-8113	COV	Canyon Dr.	6	Asbestos Cement	358	54	2.43 out of 5	\$345	\$123,510	
Distribution Mains	P-7667	COV	Cape Way	6	Asbestos Cement	101	39	2.29 out of 5	\$345	\$34,845	
Distribution Mains	P-8292	COV	Capwell St.	6	Cast iron	580	127	2.58 out of 5	\$345	\$200,100	
Distribution Mains	P-8289	COV	Capwell St.	8	Cast iron	485	127	1.87 out of 5	\$345	\$167,325	
Distribution Mains	P-7573	COV	Card St.	6	Cast iron	413	127	2.58 out of 5	\$345	\$142,485	
Distribution Mains	P-7814	COV	Card St.	2	PVC	158	25	1.87 out of 5	\$345	\$54,510	
Distribution Mains	P-7987	COV	Cardinal Ave.	6	Asbestos Cement	219	66	2.58 out of 5	\$345	\$75,555	
Distribution Mains	P-7634	COV	Carolyn St.	6	Asbestos Cement	157	53	2.43 out of 5	\$345	\$54,165	
Distribution Mains	P-7519	COV	Carr's Tr.	1	Galvanized iron	284	87	3.44 out of 5	\$345	\$97,980	
Distribution Mains	P-7122	COV	Catalpa Way	8	Ductile Iron	775	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7130	COV	Catalpa Way	8	Ductile Iron	385	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7135	COV	Catalpa Way	8	Ductile Iron	463	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7136	COV	Catalpa Way	8	Ductile Iron	474	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7990	COV	Cecile Ave.	6	Asbestos Cement	229	62	2.58 out of 5	\$345	\$79,005	
Distribution Mains	P-7992	COV	Cecile Ave.	6	Asbestos Cement	237	62	2.58 out of 5	\$345	\$81,765	
Distribution Mains	P-7994	COV	Cecile Ave.	6	Asbestos Cement	680	62	2.58 out of 5	\$345	\$234,600	
Distribution Mains	P-8108	COV	Cedar St.	6	Asbestos Cement	263	55	2.43 out of 5	\$345	\$90,735	
Distribution Mains	P-8109	COV	Cedar St.	6	Asbestos Cement	279	55	2.43 out of 5	\$345	\$96,255	
Distribution Mains	P-8121	COV	Cedar St.	6	Ductile Iron	600	20	0.86 out of 5	\$345	\$207,000	
Distribution Mains	P-8985	COV	Cedar Tree Ln.	2	Copper	241	79	2.44 out of 5	\$345	\$83,145	
Distribution Mains	P-8986	COV	Cedar Tree Ln.	2	Copper	103	79	2.44 out of 5	\$345	\$35,535	
Distribution Mains	P-7375	COV	Centennial St.	8	Asbestos Cement	296	43	2.43 out of 5	\$345	\$102,120	
Distribution Mains	P-7376	COV	Centennial St.	8	Asbestos Cement	161	43	1.72 out of 5	\$345	\$55,545	
Distribution Mains	P-7384	COV	Centennial St.	8	Asbestos Cement	765	43	1.72 out of 5	\$345	\$263,925	
Distribution Mains	P-8849	COV	Centennial St.	6	Ductile Iron	112	21	0.86 out of 5	\$345	\$38,640	
Distribution Mains	P-7385	COV	Centennial St.	8	Ductile Iron	276	21	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7822	COV	Centre St.	8	Asbestos Cement	838	51	1.72 out of 5	\$345	\$289,110	
Distribution Mains	P-7835	COV	Centre St.	6	Ductile Iron	516	20	0.86 out of 5	\$345	\$178,020	
Distribution Mains	P-7198	COV	Chandler Dr.	8	Asbestos Cement	469	40	1.72 out of 5	\$345	\$161,805	
Distribution Mains	P-7208	COV	Chandler Dr.	8	Asbestos Cement	1,649	40	1.72 out of 5	\$345	\$568,905	
Distribution Mains	P-7211	COV	Chandler Dr.	8	Asbestos Cement	389	40	1.72 out of 5	\$345	\$134,205	
Distribution Mains	P-7611	COV	Charlotte St.	6	Asbestos Cement	134	55	2.43 out of 5	\$345	\$46,230	
Distribution Mains	P-7612	COV	Charlotte St.	6	Asbestos Cement	467	55	2.43 out of 5	\$345	\$161,115	
Distribution Mains	P-7329	COV	Charwood Dr.	8	Asbestos Cement	454	36	1.58 out of 5	\$345	\$156,630	
Distribution Mains	P-7334	COV	Charwood Dr.	8	Asbestos Cement	381	36	1.58 out of 5	\$345	\$131,445	
Distribution Mains	P-7038	COV	Cherry Blossom Ln.	6	Asbestos Cement	1,129	52	2.43 out of 5	\$345	\$389,505	
Distribution Mains	P-8119	COV	Chestnut St.	6	Asbestos Cement	173	58	2.43 out of 5	\$345	\$59,685	
Distribution Mains	P-8858	COV	Chestnut St.	6	Asbestos Cement	307	58	2.43 out of 5	\$345	\$105,915	
Distribution Mains	P-8522	COV	Chole Ct.	8	Ductile Iron	415	9	0 out of 5	N/A	\$0	
Distribution Mains	P-9042	COV	Chopin St.	2	Galvanized iron	260	119	3.59 out of 5	\$345	\$89,700	
Distribution Mains	P-7290	COV	Cindy Ln.	6	Asbestos Cement	477	48	2.43 out of 5	\$345	\$164,565	
Distribution Mains	P-7340	COV	Cinnamon Ct.	8	Ductile Iron	434	16	0 out of 5	N/A	\$0	
Distribution Mains	P-7022	COV	Circlewood Dr.	8	Asbestos Cement	1,709	36	1.58 out of 5	\$345	\$589,605	
Distribution Mains	P-7024	COV	Circlewood Dr.	8	Asbestos Cement	569	36	1.58 out of 5	\$345	\$196,305	
Distribution Mains	P-8519	COV	Circlewood Dr.	8	Asbestos Cement	221	36	1.58 out of 5	\$345	\$76,245	
Distribution Mains	P-8200	COV	Clark Mill St.	8	Ductile Iron	735	17	0 out of 5	N/A	\$0	
Distribution Mains	P-8399	COV	Clark Mill St.	8	Ductile Iron	220	4	0 out of 5	N/A	\$0	
Distribution Mains	P-8525	COV	Clark Mill St.	8	Ductile Iron	1,603	9	0 out of 5	N/A	\$0	
Distribution Mains	P-8966	COV	Clark Mill St.	8	Ductile Iron	322	9	0 out of 5	N/A	\$0	
Transmission Mains	P-8968	COV	Clark Mill St.	12	Ductile Iron	150	17	0 out of 5	N/A	\$0	
Transmission Mains	P-7892	COV	Clarke Rd.	20	Asbestos Cement	675	46	2.43 out of 5	\$345	\$232,875	
Transmission Mains	P-7911	COV	Clarke Rd.	20	Asbestos Cement	370	46	2.43 out of 5	\$345	\$127,650	
Transmission Mains	P-7916	COV	Clarke Rd.	20	Asbestos Cement	1,801	46	2.43 out of 5	\$345	\$621,345	
Transmission Mains	P-7907	COV	Clarke Rd.	20	Asbestos Cement	354	46	1.72 out of 5	\$345	\$122,130	
Transmission Mains	P-7908	COV	Clarke Rd.	20	Asbestos Cement	373	46	1.72 out of 5	\$345	\$128,685	
Transmission Mains	P-7909	COV	Clarke Rd.	20	Asbestos Cement	270	46	1.72 out of 5	\$345	\$93,150	
Transmission Mains	P-8488	COV	Clarke Rd.	20	Asbestos Cement	258	46	1.72 out of 5	\$345	\$89,010	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-8490	COV	Clarke Rd.	20	Ductile Iron	500	9	0 out of 5	N/A	\$0	
Distribution Mains	P-7566	COV	Clearview Dr.	6	Asbestos Cement	252	62	2.58 out of 5	\$345	\$86,940	
Distribution Mains	P-7571	COV	Clearview Dr.	6	Asbestos Cement	286	62	2.58 out of 5	\$345	\$98,670	
Distribution Mains	P-7491	COV	Clifton Ave.	6	Asbestos Cement	167	58	2.43 out of 5	\$345	\$57,615	
Distribution Mains	P-7493	COV	Clifton Ave.	6	Asbestos Cement	357	58	2.43 out of 5	\$345	\$123,165	
Distribution Mains	P-8514	COV	Clifton Ave.	6	Asbestos Cement	74	58	2.43 out of 5	\$345	\$25,530	
Distribution Mains	P-8969	COV	Clifton Ave.	6	Asbestos Cement	162	58	2.43 out of 5	\$345	\$55,890	
Distribution Mains	P-7091	COV	Clubhouse Rd.	8	Asbestos Cement	165	40	1.72 out of 5	\$345	\$56,925	
Distribution Mains	P-7092	COV	Clubhouse Rd.	8	Asbestos Cement	745	40	1.72 out of 5	\$345	\$257,025	
Distribution Mains	P-7147	COV	Clubhouse Rd.	8	Asbestos Cement	1,000	40	1.72 out of 5	\$345	\$345,000	
Distribution Mains	P-7148	COV	Clubhouse Rd.	8	Asbestos Cement	562	40	1.72 out of 5	\$345	\$193,890	
Distribution Mains	P-8361	COV	Clubhouse Rd.	8	Asbestos Cement	142	40	1.72 out of 5	\$345	\$48,990	
Distribution Mains	P-7149	COV	Clubhouse Rd.	8	PVC	76	26	0.44 out of 5	\$345	\$26,220	
Distribution Mains	P-7150	COV	Clubhouse Rd.	8	PVC	600	26	0.44 out of 5	\$345	\$207,000	
Distribution Mains	P-7154	COV	Clubhouse Rd.	8	PVC	312	26	0.44 out of 5	\$345	\$107,640	
Distribution Mains	P-8364	COV	Clubhouse Rd.	8	Ductile Iron	147	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7188	COV	Cobblestone Ter.	8	Ductile Iron	748	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7189	COV	Cobblestone Ter.	8	Ductile Iron	697	20	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7190	COV	Cobblestone Ter.	12	Ductile Iron	771	20	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7191	COV	Cobblestone Ter.	12	Ductile Iron	1,833	21	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8808	COV	Cobblestone Ter.	8	Ductile Iron	448	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8892	COV	Cobblestone Ter.	8	Ductile Iron	40	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8893	COV	Cobblestone Ter.	8	Ductile Iron	129	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8894	COV	Cobblestone Ter.	8	Ductile Iron	34	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7784	COV	Colby Dr.	6	Asbestos Cement	483	51	2.43 out of 5	\$345	\$166,635	
Distribution Mains	P-8908	COV	Collier Way	6	Asbestos Cement	217	60	2.58 out of 5	\$345	\$74,865	
Distribution Mains	P-7644	COV	Colonial Rd.	6	Asbestos Cement	362	48	2.43 out of 5	\$345	\$124,890	
Distribution Mains	P-7645	COV	Colonial Rd.	6	Asbestos Cement	376	48	2.43 out of 5	\$345	\$129,720	
Distribution Mains	P-7646	COV	Colonial Rd.	6	Asbestos Cement	227	48	2.43 out of 5	\$345	\$78,315	
Distribution Mains	P-7581	COV	Colorado St.	2	Galvanized iron	520	81	4.87 out of 5	\$345	\$179,400	
Distribution Mains	P-7773	COV	Columbia Ave.	6	Asbestos Cement	664	55	2.43 out of 5	\$345	\$229,080	
Distribution Mains	P-7795	COV	Columbia Ave.	6	Asbestos Cement	405	55	2.43 out of 5	\$345	\$139,725	
Distribution Mains	P-7796	COV	Columbia Ave.	6	Asbestos Cement	1,443	55	2.43 out of 5	\$345	\$497,835	
Transmission Mains	P-8101	COV	Colvin St.	16	Asbestos Cement	966	58	1.72 out of 5	\$345	\$333,270	
Transmission Mains	P-8507	COV	Colvin St.	24	Ductile Iron	374	9	0 out of 5	N/A	\$0	
Transmission Mains	P-8508	COV	Colvin St.	24	Ductile Iron	160	9	0 out of 5	N/A	\$0	
Transmission Mains	P-8872	COV	Colvin St.	24	Ductile Iron	420	9	0 out of 5	N/A	\$0	
Distribution Mains	P-8873	COV	Colvin St.	8	Ductile Iron	24	10	0 out of 5	N/A	\$0	
Distribution Mains	P-7212	COV	Colvintown Rd.	8	Asbestos Cement	56	43	1.72 out of 5	\$345	\$19,320	
Distribution Mains	P-7218	COV	Colvintown Rd.	8	Asbestos Cement	728	43	1.72 out of 5	\$345	\$251,160	
Distribution Mains	P-7220	COV	Colvintown Rd.	8	Asbestos Cement	115	43	1.72 out of 5	\$345	\$39,675	
Distribution Mains	P-7240	COV	Colvintown Rd.	8	Asbestos Cement	472	43	1.72 out of 5	\$345	\$162,840	
Distribution Mains	P-7294	COV	Colvintown Rd.	8	Asbestos Cement	435	43	1.72 out of 5	\$345	\$150,075	
Distribution Mains	P-7314	COV	Colvintown Rd.	8	Asbestos Cement	715	43	1.72 out of 5	\$345	\$246,675	
Distribution Mains	P-7315	COV	Colvintown Rd.	8	Asbestos Cement	341	43	1.72 out of 5	\$345	\$117,645	
Distribution Mains	P-7316	COV	Colvintown Rd.	8	Asbestos Cement	716	43	1.72 out of 5	\$345	\$247,020	
Distribution Mains	P-7421	COV	Colvintown Rd.	8	Asbestos Cement	84	43	1.72 out of 5	\$345	\$28,980	
Distribution Mains	P-8270	COV	Colvintown Rd.	8	Asbestos Cement	912	43	1.72 out of 5	\$345	\$314,640	
Distribution Mains	P-8273	COV	Colvintown Rd.	8	Asbestos Cement	1,048	43	1.72 out of 5	\$345	\$361,560	
Distribution Mains	P-8774	COV	Colvintown Rd.	8	Asbestos Cement	109	43	1.72 out of 5	\$345	\$37,605	
Distribution Mains	P-8269	COV	Colvintown Rd.	8	Ductile Iron	3,147	11	0 out of 5	N/A	\$0	
Distribution Mains	P-8474	COV	Colvintown Rd.	8	Ductile Iron	4,536	10	0 out of 5	N/A	\$0	
Distribution Mains	P-8890	COV	Colvintown Rd.	8	Ductile Iron	2,314	10	0 out of 5	N/A	\$0	
Distribution Mains	P-8891	COV	Colvintown Rd.	8	Ductile Iron	32	11	0 out of 5	N/A	\$0	
Transmission Mains	P-8174	COV	Compton Rd.	12	Asbestos Cement	347	42	1.72 out of 5	\$345	\$119,715	
Transmission Mains	P-8172	COV	Compton Rd.	16	Ductile Iron	195	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8173	COV	Compton Rd.	16	Ductile Iron	116	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8538	COV	Compton Rd.	16	Ductile Iron	250	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8711	COV	Compton Rd.	16	Ductile Iron	118	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-9036	COV	Congdon St.	4	Cast iron	516	65	3.01 out of 5	\$345	\$178,020	
Distribution Mains	P-7398	COV	Congdon St.	6	Cast iron	472	65	2.29 out of 5	\$345	\$162,840	
Distribution Mains	P-8393	COV	Conifer Ct.	8	Ductile Iron	370	7	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-8394	COV	Conifer Ct.	8	Ductile Iron	160	7	0 out of 5	N/A	\$0	
Distribution Mains	P-8395	COV	Conifer Ct.	8	Ductile Iron	210	4	0 out of 5	N/A	\$0	
Distribution Mains	P-8396	COV	Conifer Ct.	8	Ductile Iron	380	4	0 out of 5	N/A	\$0	
Distribution Mains	P-7858	COV	Contentment Dr.	8	Asbestos Cement	800	45	1.72 out of 5	\$345	\$276,000	
Distribution Mains	P-8312	COV	Cook St.	6	Ductile Iron	553	14	0.71 out of 5	\$345	\$190,785	
Distribution Mains	P-7800	COV	Cornell Ct.	6	Asbestos Cement	395	47	2.43 out of 5	\$345	\$136,275	
Distribution Mains	P-7838	COV	Cote Ct.	6	Ductile Iron	645	14	0.71 out of 5	\$345	\$222,525	
Distribution Mains	P-7842	COV	Cote Ct.	6	Ductile Iron	230	14	0.71 out of 5	\$345	\$79,350	
Distribution Mains	P-7841	COV	Cote Ct. Easement	6	Ductile Iron	441	14	0.71 out of 5	\$345	\$152,145	
Distribution Mains	P-7386	COV	Country View Dr.	8	Ductile Iron	282	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7388	COV	Country View Dr.	8	Ductile Iron	901	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7670	COV	Cove Rd.	6	Asbestos Cement	420	51	2.43 out of 5	\$345	\$144,900	
Distribution Mains	P-7671	COV	Cove Rd.	6	Asbestos Cement	151	51	2.43 out of 5	\$345	\$52,095	
Distribution Mains	P-8971	COV	Cove Rd.	6	Asbestos Cement	128	51	2.43 out of 5	\$345	\$44,160	
Distribution Mains	P-7603	COV	Coventry Dr.	6	Asbestos Cement	205	55	2.43 out of 5	\$345	\$70,725	
Distribution Mains	P-7605	COV	Coventry Dr.	6	Asbestos Cement	283	55	2.43 out of 5	\$345	\$97,635	
Distribution Mains	P-7607	COV	Coventry Dr.	6	Asbestos Cement	498	55	2.43 out of 5	\$345	\$171,810	
Distribution Mains	P-7614	COV	Coventry Dr.	6	Asbestos Cement	124	55	2.43 out of 5	\$345	\$42,780	
Distribution Mains	P-7619	COV	Coventry Dr.	6	Asbestos Cement	428	55	2.43 out of 5	\$345	\$147,660	
Distribution Mains	P-7620	COV	Coventry Dr.	6	Asbestos Cement	150	55	2.43 out of 5	\$345	\$51,750	
Distribution Mains	P-8945	COV	Coventry Dr.	6	Ductile Iron	25	14	0.71 out of 5	\$345	\$8,625	
Distribution Mains	P-8944	COV	Coventry Dr.	8	Ductile Iron	57	14	0 out of 5	N/A	\$0	
Transmission Mains	P-7497	COV	Coventry/Spring Lake Well	12	Ductile Iron	426	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7498	COV	Coventry/Spring Lake Well	8	Ductile Iron	240	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7499	COV	Coventry/Spring Lake Well	8	Ductile Iron	25	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7905	COV	Crabapple Ct.	6	Asbestos Cement	231	34	2.29 out of 5	\$345	\$79,695	
Distribution Mains	P-7708	COV	Crestwood Rd.	8	Asbestos Cement	483	55	1.72 out of 5	\$345	\$166,635	
Distribution Mains	P-7232	COV	Cynthia Dr.	8	Asbestos Cement	179	49	1.72 out of 5	\$345	\$61,755	
Distribution Mains	P-7233	COV	Cynthia Dr.	8	Asbestos Cement	1,021	49	1.72 out of 5	\$345	\$352,245	
Distribution Mains	P-7235	COV	Cynthia Dr.	8	Asbestos Cement	501	49	1.72 out of 5	\$345	\$172,845	
Distribution Mains	P-7236	COV	Cynthia Dr.	8	Asbestos Cement	444	49	1.72 out of 5	\$345	\$153,180	
Distribution Mains	P-7764	COV	Cypruss Rd.	6	Asbestos Cement	598	52	2.43 out of 5	\$345	\$206,310	
Distribution Mains	P-7199	COV	Daniel Dr.	6	Asbestos Cement	386	39	2.29 out of 5	\$345	\$133,170	
Distribution Mains	P-7202	COV	Daniel Dr.	6	Asbestos Cement	618	39	2.29 out of 5	\$345	\$213,210	
Distribution Mains	P-7203	COV	Daniel Dr.	6	Asbestos Cement	388	39	2.29 out of 5	\$345	\$133,860	
Distribution Mains	P-7209	COV	Daniel Dr.	6	Asbestos Cement	172	39	2.29 out of 5	\$345	\$59,340	
Distribution Mains	P-7210	COV	Daniel Dr.	6	Asbestos Cement	398	39	2.29 out of 5	\$345	\$137,310	
Distribution Mains	P-7721	COV	Darton St.	8	Ductile Iron	221	8	0 out of 5	N/A	\$0	
Distribution Mains	P-7767	COV	Dawley St.	6	Asbestos Cement	575	61	2.58 out of 5	\$345	\$198,375	
Distribution Mains	P-9017	COV	Dawley St.	6	Ductile Iron	36	7	0.71 out of 5	\$345	\$12,420	
Distribution Mains	P-7283	COV	Dawn Ln.	6	Asbestos Cement	396	52	2.43 out of 5	\$345	\$136,620	
Distribution Mains	P-7284	COV	Dawn Ln.	6	Asbestos Cement	177	52	2.43 out of 5	\$345	\$61,065	
Distribution Mains	P-7469	COV	Deborah Ave.	6	Asbestos Cement	595	52	2.43 out of 5	\$345	\$205,275	
Distribution Mains	P-7473	COV	Deborah Ave.	6	Asbestos Cement	47	52	2.43 out of 5	\$345	\$16,215	
Distribution Mains	P-7310	COV	Deer Run Rd.	6	Asbestos Cement	1,112	30	2.29 out of 5	\$345	\$383,640	
Distribution Mains	P-7761	COV	Deerfield Rd.	6	Asbestos Cement	654	50	2.43 out of 5	\$345	\$225,630	
Distribution Mains	P-7760	COV	Deerfield Rd.	8	Ductile Iron	233	14	0 out of 5	N/A	\$0	
Distribution Mains	P-7546	COV	Dell St.	6	Asbestos Cement	323	64	2.58 out of 5	\$345	\$111,435	
Distribution Mains	P-8835	COV	Dennis St.	8	Ductile Iron	216	3	0 out of 5	N/A	\$0	
Distribution Mains	P-7811	COV	Dexter St.	6	Asbestos Cement	538	64	2.58 out of 5	\$345	\$185,610	
Distribution Mains	P-7205	COV	Diane Dr.	8	Asbestos Cement	531	35	1.58 out of 5	\$345	\$183,195	
Distribution Mains	P-7206	COV	Diane Dr.	8	Asbestos Cement	432	35	1.58 out of 5	\$345	\$149,040	
Distribution Mains	P-9058	COV	Dion Ave.	2	Cast iron	90	127	3.3 out of 5	\$345	\$31,050	
Distribution Mains	P-8007	COV	Dion Ave.	6	Asbestos Cement	270	65	2.58 out of 5	\$345	\$93,150	
Distribution Mains	P-9050	COV	Dion Ave.	6	Asbestos Cement	94	65	2.58 out of 5	\$345	\$32,430	
Distribution Mains	P-9051	COV	Dion Ave.	6	Asbestos Cement	72	65	2.58 out of 5	\$345	\$24,840	
Distribution Mains	P-9049	COV	Dion Ave.	0.8	Copper	118	64	2.44 out of 5	\$345	\$40,710	
Distribution Mains	P-9052	COV	Dion Ave.	1	Copper	132	65	2.44 out of 5	\$345	\$45,540	
Distribution Mains	P-7658	COV	Dixie Rd.	6	Ductile Iron	443	20	0.86 out of 5	\$345	\$152,835	
Distribution Mains	P-8991	COV	Dixie Rd.	6	Ductile Iron	21	7	0.71 out of 5	\$345	\$7,245	
Distribution Mains	P-8990	COV	Dixie Rd.	8	Ductile Iron	91	7	0 out of 5	N/A	\$0	
Distribution Mains	P-9016	COV	Dodd St.	8	Ductile Iron	326	7	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-7019	COV	Dogwood Dr.	6	PVC	606	28	1.15 out of 5	\$345	\$209,070	
Distribution Mains	P-8271	COV	Donna's Way	8	Ductile Iron	406	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7809	COV	Donovan St.	6	Asbestos Cement	242	56	2.43 out of 5	\$345	\$83,490	
Distribution Mains	P-8001	COV	Doolittle St.	6	Asbestos Cement	441	56	3.14 out of 5	\$345	\$152,145	
Distribution Mains	P-7981	COV	Doolittle St.	6	Asbestos Cement	467	56	2.43 out of 5	\$345	\$161,115	
Distribution Mains	P-7989	COV	Doolittle St.	6	Asbestos Cement	528	56	2.43 out of 5	\$345	\$182,160	
Distribution Mains	P-7143	COV	Doric Ct.	6	Asbestos Cement	271	34	2.29 out of 5	\$345	\$93,495	
Distribution Mains	P-8052	COV	Doris St.	6	Asbestos Cement	175	52	2.43 out of 5	\$345	\$60,375	
Distribution Mains	P-9048	COV	Douglas Ct.	8	Ductile Iron	271	5	0 out of 5	N/A	\$0	
Distribution Mains	P-7330	COV	Driftwood Dr.	6	Asbestos Cement	1,321	43	2.43 out of 5	\$345	\$455,745	
Distribution Mains	P-8276	COV	Dumont Farm Rd.	6	Ductile Iron	300	12	0.71 out of 5	\$345	\$103,500	
Distribution Mains	P-8951	COV	Eagle Dr.	8	PVC	22	29	0.44 out of 5	\$345	\$7,590	
Distribution Mains	P-8375	COV	Easement	6	Cast iron	330	114	2.58 out of 5	\$345	\$113,850	
Distribution Mains	P-8380	COV	Easement	6	Asbestos Cement	205	48	2.43 out of 5	\$345	\$70,725	
Distribution Mains	P-7737	COV	East Shore Dr.	8	Asbestos Cement	418	44	1.72 out of 5	\$345	\$144,210	
Distribution Mains	P-7738	COV	East Shore Dr.	8	Asbestos Cement	265	44	1.72 out of 5	\$345	\$91,425	
Distribution Mains	P-7739	COV	East Shore Dr.	6	Ductile Iron	347	22	0.86 out of 5	\$345	\$119,715	
Distribution Mains	P-7741	COV	East Shore Dr.	8	Ductile Iron	257	22	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7719	COV	East Shore Dr.	8	Ductile Iron	182	9	0 out of 5	N/A	\$0	
Distribution Mains	P-7720	COV	East Shore Dr.	8	Ductile Iron	225	9	0 out of 5	N/A	\$0	
Distribution Mains	P-7722	COV	East Shore Dr.	8	Ductile Iron	247	9	0 out of 5	N/A	\$0	
Distribution Mains	P-7733	COV	East Shore Dr.	8	Ductile Iron	319	9	0 out of 5	N/A	\$0	
Distribution Mains	P-8763	COV	East Shore Dr.	8	Ductile Iron	275	9	0 out of 5	N/A	\$0	
Distribution Mains	P-8767	COV	East Shore Dr.	8	Ductile Iron	460	9	0 out of 5	N/A	\$0	
Distribution Mains	P-9009	COV	East Shore Dr.	8	Ductile Iron	256	9	0 out of 5	N/A	\$0	
Distribution Mains	P-9012	COV	East Shore Dr.	8	Ductile Iron	253	9	0 out of 5	N/A	\$0	
Distribution Mains	P-7142	COV	Eastgate Dr.	8	Asbestos Cement	378	35	1.58 out of 5	\$345	\$130,410	
Distribution Mains	P-7144	COV	Eastgate Dr.	8	Asbestos Cement	509	35	1.58 out of 5	\$345	\$175,605	
Distribution Mains	P-7146	COV	Eastgate Dr.	8	Asbestos Cement	411	35	1.58 out of 5	\$345	\$141,795	
Distribution Mains	P-7635	COV	Edna St.	6	Asbestos Cement	309	53	2.43 out of 5	\$345	\$106,605	
Distribution Mains	P-7971	COV	Edward St.	2	Galvanized iron	198	84	3.44 out of 5	\$345	\$68,310	
Distribution Mains	P-8281	COV	Edward St.	2	Galvanized iron	108	16	2.86 out of 5	\$345	\$37,260	
Distribution Mains	P-9043	COV	Edward St.	2	Galvanized iron	296	16	2.86 out of 5	\$345	\$102,120	
Distribution Mains	P-7972	COV	Edward St.	6	Asbestos Cement	79	67	2.58 out of 5	\$345	\$27,255	
Distribution Mains	P-7991	COV	Edward St.	6	Asbestos Cement	183	62	2.58 out of 5	\$345	\$63,135	
Distribution Mains	P-9044	COV	Edward St.	6	Asbestos Cement	172	70	2.58 out of 5	\$345	\$59,340	
Distribution Mains	P-7968	COV	Edward St.	6	Ductile Iron	315	16	0.71 out of 5	\$345	\$108,675	
Distribution Mains	P-9046	COV	Edward St.	8	Ductile Iron	402	5	0 out of 5	N/A	\$0	
Distribution Mains	P-9047	COV	Edward St.	8	Ductile Iron	48	5	0 out of 5	N/A	\$0	
Distribution Mains	P-7984	COV	Eisenhower St.	6	Asbestos Cement	317	43	2.43 out of 5	\$345	\$109,365	
Distribution Mains	P-8110	COV	Eleanor Dr.	6	Asbestos Cement	775	54	2.43 out of 5	\$345	\$267,375	
Distribution Mains	P-8125	COV	Elm St.	6	Cast iron	416	114	2.58 out of 5	\$345	\$143,520	IFR 2014A
Distribution Mains	P-8856	COV	Elmonte Dr.	6	Asbestos Cement	118	54	3.14 out of 5	\$345	\$40,710	
Distribution Mains	P-8111	COV	Elmonte Dr.	6	Asbestos Cement	235	54	2.43 out of 5	\$345	\$81,075	
Distribution Mains	P-8112	COV	Elmonte Dr.	6	Asbestos Cement	348	54	2.43 out of 5	\$345	\$120,060	
Distribution Mains	P-7928	COV	Elmwood Ct.	8	PVC	141	34	0.44 out of 5	\$345	\$48,645	
Distribution Mains	P-7723	COV	Elton St.	8	Ductile Iron	531	9	0 out of 5	N/A	\$0	
Distribution Mains	P-7728	COV	Elton St.	8	Ductile Iron	190	12	0 out of 5	N/A	\$0	
Distribution Mains	P-9009	COV	Elton St.	8	Ductile Iron	37	14	0 out of 5	N/A	\$0	
Distribution Mains	P-7762	COV	Englewood Rd.	6	Asbestos Cement	335	50	2.43 out of 5	\$345	\$115,575	
Distribution Mains	P-9020	COV	Englewood Rd.	6	Ductile Iron	31	6	0.71 out of 5	\$345	\$10,695	
Distribution Mains	P-8028	COV	Ernest St.	8	Ductile Iron	265	13	0 out of 5	N/A	\$0	
Distribution Mains	P-7933	COV	Evergreen Ct.	8	Ductile Iron	593	16	0 out of 5	N/A	\$0	
Distribution Mains	P-7442	COV	Fairview Ave.	6	Cast iron	752	127	2.58 out of 5	\$345	\$259,440	
Distribution Mains	P-7475	COV	Fairview Ave.	6	Cast iron	73	127	2.58 out of 5	\$345	\$25,185	
Distribution Mains	P-7501	COV	Fairview Ave.	6	Cast iron	166	127	2.58 out of 5	\$345	\$57,270	
Distribution Mains	P-7521	COV	Fairview Ave.	6	Cast iron	769	127	2.58 out of 5	\$345	\$265,305	
Distribution Mains	P-7554	COV	Fairview Ave.	6	Cast iron	300	127	2.58 out of 5	\$345	\$103,500	
Distribution Mains	P-7827	COV	Fairview Ave.	6	Cast iron	638	127	2.58 out of 5	\$345	\$220,110	
Distribution Mains	P-7959	COV	Fairview Ave.	6	Cast iron	467	127	2.58 out of 5	\$345	\$161,115	
Distribution Mains	P-7960	COV	Fairview Ave.	6	Cast iron	170	127	2.58 out of 5	\$345	\$58,650	
Distribution Mains	P-7961	COV	Fairview Ave.	6	Cast iron	531	127	2.58 out of 5	\$345	\$183,195	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-7974	COV	Fairview Ave.	6	Cast iron	264	127	2.58 out of 5	\$345	\$91,080	
Distribution Mains	P-8217	COV	Fairview Ave.	6	Cast iron	270	127	2.58 out of 5	\$345	\$93,150	
Distribution Mains	P-8845	COV	Fairview Ave.	6	Cast iron	260	127	2.58 out of 5	\$345	\$89,700	
Transmission Mains	P-7036	COV	Fairview Ave.	16	Asbestos Cement	302	70	1.87 out of 5	\$345	\$104,190	
Transmission Mains	P-7072	COV	Fairview Ave.	16	Asbestos Cement	279	70	1.87 out of 5	\$345	\$96,255	
Transmission Mains	P-7319	COV	Fairview Ave.	16	Asbestos Cement	124	70	1.87 out of 5	\$345	\$42,780	
Transmission Mains	P-7977	COV	Fairview Ave.	16	Asbestos Cement	1,006	70	1.87 out of 5	\$345	\$347,070	
Transmission Mains	P-7978	COV	Fairview Ave.	16	Asbestos Cement	47	70	1.87 out of 5	\$345	\$16,215	
Transmission Mains	P-8057	COV	Fairview Ave.	16	Asbestos Cement	379	70	1.87 out of 5	\$345	\$130,755	
Transmission Mains	P-8059	COV	Fairview Ave.	16	Asbestos Cement	394	70	1.87 out of 5	\$345	\$135,930	
Transmission Mains	P-8061	COV	Fairview Ave.	16	Asbestos Cement	251	70	1.87 out of 5	\$345	\$86,595	
Transmission Mains	P-8065	COV	Fairview Ave.	16	Asbestos Cement	616	70	1.87 out of 5	\$345	\$212,520	
Transmission Mains	P-8066	COV	Fairview Ave.	16	Asbestos Cement	328	70	1.87 out of 5	\$345	\$113,160	
Transmission Mains	P-8070	COV	Fairview Ave.	16	Asbestos Cement	229	70	1.87 out of 5	\$345	\$79,005	
Transmission Mains	P-8071	COV	Fairview Ave.	16	Asbestos Cement	889	70	1.87 out of 5	\$345	\$306,705	
Transmission Mains	P-8072	COV	Fairview Ave.	16	Asbestos Cement	193	70	1.87 out of 5	\$345	\$66,585	
Transmission Mains	P-9039	COV	Fairview Ave.	16	Asbestos Cement	749	70	1.87 out of 5	\$345	\$258,405	
Distribution Mains	P-7975	COV	Fairview Ave.	8	Ductile Iron	810	15	0 out of 5	N/A	\$0	
Distribution Mains	P-8326	COV	Fairway Dr.	8	Ductile Iron	115	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8327	COV	Fairway Dr.	12	Ductile Iron	134	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8328	COV	Fairway Dr.	12	Ductile Iron	471	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8331	COV	Fairway Dr.	8	Ductile Iron	345	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8332	COV	Fairway Dr.	8	Ductile Iron	1,294	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8333	COV	Fairway Dr.	8	Ductile Iron	700	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8334	COV	Fairway Dr.	8	Ductile Iron	128	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8337	COV	Fairway Dr.	8	Ductile Iron	192	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8339	COV	Fairway Dr.	8	Ductile Iron	267	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8340	COV	Fairway Dr.	8	Ductile Iron	209	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8343	COV	Fairway Dr.	8	Ductile Iron	836	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7318	COV	Fairview Ave.	16	Asbestos Cement	402	70	1.87 out of 5	\$345	\$138,690	
Transmission Mains	P-7963	COV	Fairview Ave.	16	Asbestos Cement	1,341	70	1.87 out of 5	\$345	\$462,645	
Distribution Mains	P-8342	COV	Fairway Dr.	8	Ductile Iron	187	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8967	COV	Fawn's Ct.	8	Ductile Iron	34	17	0 out of 5	N/A	\$0	
Distribution Mains	P-7540	COV	Ferncrest Dr.	6	Asbestos Cement	493	45	3.14 out of 5	\$345	\$170,085	
Distribution Mains	P-8322	COV	Ferncrest St.	8	Ductile Iron	486	13	0 out of 5	N/A	\$0	
Distribution Mains	P-7740	COV	Ferris Dr.	6	Ductile Iron	177	22	0.86 out of 5	\$345	\$61,065	
Distribution Mains	P-7226	COV	First St.	6	Asbestos Cement	237	60	2.58 out of 5	\$345	\$81,765	
Distribution Mains	P-7227	COV	First St.	6	Asbestos Cement	50	60	2.58 out of 5	\$345	\$17,250	
Distribution Mains	P-7229	COV	Flat River Rd.	8	Asbestos Cement	876	64	1.87 out of 5	\$345	\$302,220	
Distribution Mains	P-7249	COV	Flat River Rd.	8	Asbestos Cement	500	64	1.87 out of 5	\$345	\$172,500	
Distribution Mains	P-8344	COV	Flat River Rd.	8	Asbestos Cement	562	64	1.87 out of 5	\$345	\$193,890	
Distribution Mains	P-8345	COV	Flat River Rd.	8	Asbestos Cement	148	64	1.87 out of 5	\$345	\$51,060	
Distribution Mains	P-8907	COV	Flat River Rd.	8	Asbestos Cement	49	64	1.87 out of 5	\$345	\$16,905	
Transmission Mains	P-8272	COV	Flat River Rd.	12	Asbestos Cement	95	48	1.72 out of 5	\$345	\$32,775	
Transmission Mains	P-7182	COV	Flat River Rd.	20	Ductile Iron	146	3	0 out of 5	N/A	\$0	
Transmission Mains	P-7183	COV	Flat River Rd.	20	Ductile Iron	366	3	0 out of 5	N/A	\$0	
Transmission Mains	P-7185	COV	Flat River Rd.	20	Ductile Iron	769	3	0 out of 5	N/A	\$0	
Transmission Mains	P-7193	COV	Flat River Rd.	20	Ductile Iron	2,065	3	0 out of 5	N/A	\$0	
Transmission Mains	P-7222	COV	Flat River Rd.	16	Ductile Iron	293	3	0 out of 5	N/A	\$0	
Transmission Mains	P-8897	COV	Flat River Rd.	16	Ductile Iron	584	3	0 out of 5	N/A	\$0	
Transmission Mains	P-8900	COV	Flat River Rd.	16	Ductile Iron	110	3	0 out of 5	N/A	\$0	
Transmission Mains	P-8901	COV	Flat River Rd.	16	Ductile Iron	614	3	0 out of 5	N/A	\$0	
Transmission Mains	P-8904	COV	Flat River Rd.	16	Ductile Iron	875	3	0 out of 5	N/A	\$0	
Distribution Mains	P-7693	COV	Florida Ave.	6	Asbestos Cement	416	60	2.58 out of 5	\$345	\$143,520	
Distribution Mains	P-8998	COV	Florida Ave.	1	Copper	258	60	2.44 out of 5	\$345	\$89,010	
Distribution Mains	P-8078	COV	Fones St.	8	Ductile Iron	480	3	0 out of 5	N/A	\$0	
Distribution Mains	P-8834	COV	Fones St.	8	Ductile Iron	91	3	0 out of 5	N/A	\$0	
Distribution Mains	P-8308	COV	Forest St.	6	Asbestos Cement	464	60	2.58 out of 5	\$345	\$160,080	
Distribution Mains	P-7569	COV	Forestdale St.	6	Asbestos Cement	500	46	2.43 out of 5	\$345	\$172,500	
Distribution Mains	P-9007	COV	Forestdale St.	6	Asbestos Cement	243	46	2.43 out of 5	\$345	\$83,835	
Distribution Mains	P-8974	COV	Forge Rd.	8	Ductile Iron	330	8	0 out of 5	N/A	\$0	
Distribution Mains	P-7900	COV	Forsythia Ct.	6	Asbestos Cement	250	35	3 out of 5	\$345	\$86,250	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-7276	COV	Foster Dr.	6	Asbestos Cement	270	67	2.58 out of 5	\$345	\$93,150	
Distribution Mains	P-7278	COV	Foster Dr.	6	Asbestos Cement	112	67	2.58 out of 5	\$345	\$38,640	
Distribution Mains	P-7244	COV	Frances Ct.	6	Asbestos Cement	170	51	2.43 out of 5	\$345	\$58,650	
Distribution Mains	P-7266	COV	Francis St.	6	Cast iron	511	70	2.29 out of 5	\$345	\$176,295	
Distribution Mains	P-7980	COV	Gadoury St.	6	Asbestos Cement	409	65	2.58 out of 5	\$345	\$141,105	
Distribution Mains	P-7250	COV	Gail Ct.	8	Asbestos Cement	640	45	1.72 out of 5	\$345	\$220,800	
Distribution Mains	P-7174	COV	Garfield Dr.	8	Asbestos Cement	893	35	1.58 out of 5	\$345	\$308,085	
Distribution Mains	P-8177	COV	Gay St.	8	PVC	330	28	0.44 out of 5	\$345	\$113,850	
Distribution Mains	P-8005	COV	Gerald Ave.	6	Asbestos Cement	493	65	2.58 out of 5	\$345	\$170,085	
Transmission Mains	P-7363	COV	Gervais St.	12	Ductile Iron	1,575	9	0 out of 5	N/A	\$0	
Transmission Mains	P-7368	COV	Gervais St.	12	Ductile Iron	357	9	0 out of 5	N/A	\$0	
Transmission Mains	P-7390	COV	Gervais St.	12	Ductile Iron	275	9	0 out of 5	N/A	\$0	
Transmission Mains	P-7391	COV	Gervais St.	12	Ductile Iron	271	9	0 out of 5	N/A	\$0	
Transmission Mains	P-7395	COV	Gervais St.	12	Ductile Iron	383	9	0 out of 5	N/A	\$0	
Transmission Mains	P-8497	COV	Gervais St.	20	Ductile Iron	3,147	9	0 out of 5	N/A	\$0	
Transmission Mains	P-8498	COV	Gervais St.	12	Ductile Iron	111	9	0 out of 5	N/A	\$0	
Distribution Mains	P-7110	COV	Giblin Ln.	8	Ductile Iron	312	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7111	COV	Giblin Ln.	8	Ductile Iron	920	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7752	COV	Gilles St.	8	Ductile Iron	373	14	0 out of 5	N/A	\$0	
Distribution Mains	P-7335	COV	Ginger Tr.	8	Ductile Iron	720	16	0 out of 5	N/A	\$0	
Distribution Mains	P-7337	COV	Ginger Tr.	8	Ductile Iron	1,294	16	0 out of 5	N/A	\$0	
Distribution Mains	P-7339	COV	Ginger Tr.	8	Ductile Iron	548	16	0 out of 5	N/A	\$0	
Distribution Mains	P-7341	COV	Ginger Tr.	8	Ductile Iron	373	16	0 out of 5	N/A	\$0	
Distribution Mains	P-7353	COV	Ginger Tr.	8	Ductile Iron	208	16	0 out of 5	N/A	\$0	
Distribution Mains	P-7355	COV	Ginger Tr.	8	Ductile Iron	325	16	0 out of 5	N/A	\$0	
Distribution Mains	P-8888	COV	Ginger Tr.	8	Ductile Iron	525	16	0 out of 5	N/A	\$0	
Distribution Mains	P-7216	COV	Glacier Way	8	Ductile Iron	580	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8906	COV	Glacier Way	8	Ductile Iron	410	12	0 out of 5	N/A	\$0	
Distribution Mains	P-7657	COV	Glen Ave.	8	Ductile Iron	186	13	0 out of 5	N/A	\$0	
Distribution Mains	P-7912	COV	Glenview Ct.	8	Asbestos Cement	555	38	1.58 out of 5	\$345	\$191,475	
Distribution Mains	P-7326	COV	Glenwood Dr.	8	Asbestos Cement	462	38	1.58 out of 5	\$345	\$159,390	
Distribution Mains	P-7328	COV	Glenwood Dr.	8	Asbestos Cement	700	38	1.58 out of 5	\$345	\$241,500	
Distribution Mains	P-8787	COV	Glenwood Subdivision	8	Ductile Iron	745	4	0 out of 5	N/A	\$0	
Distribution Mains	P-8788	COV	Glenwood Subdivision	8	Ductile Iron	290	4	0 out of 5	N/A	\$0	
Distribution Mains	P-8789	COV	Glenwood Subdivision	8	Ductile Iron	170	19	0 out of 5	N/A	\$0	
Distribution Mains	P-8790	COV	Glenwood Subdivision	8	Ductile Iron	185	4	0 out of 5	N/A	\$0	
Distribution Mains	P-8791	COV	Glenwood Subdivision	8	Ductile Iron	100	4	0 out of 5	N/A	\$0	
Distribution Mains	P-8792	COV	Glenwood Subdivision	8	Ductile Iron	150	4	0 out of 5	N/A	\$0	
Transmission Mains	P-8044	COV	Gough Ave.	16	Asbestos Cement	602	70	2.58 out of 5	\$345	\$207,690	
Distribution Mains	P-8179	COV	Grafton St.	8	PVC	373	28	0.44 out of 5	\$345	\$128,685	
Distribution Mains	P-8181	COV	Grand View St.	8	Ductile Iron	345	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8999	COV	Grand View St.	8	Ductile Iron	75	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8180	COV	Grand View St.	8	Ductile Iron	144	11	0 out of 5	N/A	\$0	
Distribution Mains	P-7674	COV	Grant Dr.	6	Asbestos Cement	298	52	2.43 out of 5	\$345	\$102,810	
Distribution Mains	P-7675	COV	Grant Dr.	6	Asbestos Cement	457	52	2.43 out of 5	\$345	\$157,665	
Distribution Mains	P-7691	COV	Grant Dr.	6	Asbestos Cement	732	52	2.43 out of 5	\$345	\$252,540	
Distribution Mains	P-7833	COV	Greene St.	2	Galvanized iron	468	68	3.3 out of 5	\$345	\$161,460	
Distribution Mains	P-8049	COV	Greenwood Ave.	6	Asbestos Cement	269	51	2.43 out of 5	\$345	\$92,805	
Distribution Mains	P-7177	COV	Hancock Dr.	8	Asbestos Cement	942	37	1.58 out of 5	\$345	\$324,990	
Distribution Mains	P-7178	COV	Hancock Dr.	8	Asbestos Cement	219	37	1.58 out of 5	\$345	\$75,555	
Distribution Mains	P-8224	COV	Hancock St.	8	Asbestos Cement	106	37	1.58 out of 5	\$345	\$36,570	
Distribution Mains	P-8935	COV	Harding St.	1	Copper	360	13	2 out of 5	\$345	\$124,200	
Transmission Mains	P-7001	COV	Harkney Hill Rd.	12	Ductile Iron	1,269	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7002	COV	Harkney Hill Rd.	12	Ductile Iron	20	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7701	COV	Harrington Dr.	6	Asbestos Cement	268	49	2.43 out of 5	\$345	\$92,460	
Distribution Mains	P-7706	COV	Harrington Rd.	6	Asbestos Cement	345	49	2.43 out of 5	\$345	\$119,025	
Distribution Mains	P-7074	COV	Harris Ave.	8	Asbestos Cement	576	64	1.87 out of 5	\$345	\$198,720	
Distribution Mains	P-8124	COV	Harris St.	6	Cast iron	243	114	2.58 out of 5	\$345	\$83,835	
Distribution Mains	P-8129	COV	Harris St.	6	Cast iron	172	114	2.58 out of 5	\$345	\$59,340	
Distribution Mains	P-8133	COV	Harris St.	6	Cast iron	552	114	2.58 out of 5	\$345	\$190,440	
Distribution Mains	P-7946	COV	Hawthorne Rd.	8	Asbestos Cement	449	50	1.72 out of 5	\$345	\$154,905	
Distribution Mains	P-7947	COV	Hawthorne Rd.	8	Asbestos Cement	521	50	1.72 out of 5	\$345	\$179,745	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-8260	COV	Hawthorne Rd. Easement	8	Ductile Iron	403	9	0 out of 5	N/A	\$0	
Distribution Mains	P-8227	COV	Haywood Dr.	8	Ductile Iron	555	15	0 out of 5	N/A	\$0	
Distribution Mains	P-7602	COV	Haywood Rd.	8	Asbestos Cement	229	55	1.72 out of 5	\$345	\$79,005	
Distribution Mains	P-7966	COV	Hazard St.	6	Cast iron	451	74	2.29 out of 5	\$345	\$155,595	
Distribution Mains	P-7976	COV	Hazard St.	6	Cast iron	191	74	2.29 out of 5	\$345	\$65,895	
Distribution Mains	P-8282	COV	Hazard St.	6	Cast iron	176	74	2.29 out of 5	\$345	\$60,720	
Distribution Mains	P-8283	COV	Hazard St.	6	Cast iron	449	74	2.29 out of 5	\$345	\$154,905	
Distribution Mains	P-9041	COV	Hazard St.	6	Cast iron	310	74	2.29 out of 5	\$345	\$106,950	
Distribution Mains	P-8300	COV	Hazel St.	2	Copper	300	73	2.44 out of 5	\$345	\$103,500	
Distribution Mains	P-7305	COV	Heather Ct.	8	Asbestos Cement	236	29	1.58 out of 5	\$345	\$81,420	
Distribution Mains	P-7457	COV	Helen Ave.	6	Asbestos Cement	659	60	2.58 out of 5	\$345	\$227,355	
Distribution Mains	P-7458	COV	Helen Ave.	6	Asbestos Cement	209	60	2.58 out of 5	\$345	\$72,105	
Distribution Mains	P-7461	COV	Helen Ave.	6	Asbestos Cement	115	60	2.58 out of 5	\$345	\$39,675	
Distribution Mains	P-7468	COV	Helen Ave.	6	Asbestos Cement	250	60	2.58 out of 5	\$345	\$86,250	
Distribution Mains	P-7482	COV	Helen Ave.	6	Asbestos Cement	266	60	2.58 out of 5	\$345	\$91,770	
Distribution Mains	P-7483	COV	Helen Ave.	6	Asbestos Cement	241	60	2.58 out of 5	\$345	\$83,145	
Distribution Mains	P-7484	COV	Helen Ave.	6	Asbestos Cement	150	60	2.58 out of 5	\$345	\$51,750	
Distribution Mains	P-8518	COV	Helen Ave.	6	Asbestos Cement	897	60	2.58 out of 5	\$345	\$309,465	
Transmission Mains	P-8268	COV	Helen Ave.	12	Asbestos Cement	113	60	1.87 out of 5	\$345	\$38,985	
Transmission Mains	P-7164	COV	Helen Ave.	12	Ductile Iron	1,023	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7165	COV	Helen Ave.	12	Ductile Iron	270	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8198	COV	Helen Ave.	12	Ductile Iron	162	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8264	COV	Helen Ave.	12	Ductile Iron	69	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8266	COV	Helen Ave.	12	Ductile Iron	666	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7655	COV	Henry Ave.	8	Ductile Iron	221	13	0 out of 5	N/A	\$0	
Distribution Mains	P-8871	COV	Henry Ct.	4	Cast iron	200	127	3.3 out of 5	\$345	\$69,000	
Distribution Mains	P-9019	COV	Hibiscus Ln.	8	Ductile Iron	945	6	0 out of 5	N/A	\$0	
Distribution Mains	P-7943	COV	Hickory Rd.	6	Asbestos Cement	955	29	2.29 out of 5	\$345	\$329,475	
Distribution Mains	P-8126	COV	Highland Ave.	6	Ductile Iron	732	20	0.86 out of 5	\$345	\$252,540	
Transmission Mains	P-8127	COV	Highland Ave.	12	Ductile Iron	218	7	0 out of 5	N/A	\$0	
Transmission Mains	P-8752	COV	Highland Ave.	12	Ductile Iron	590	7	0 out of 5	N/A	\$0	
Distribution Mains	P-8830	COV	Highland Ave.	8	Ductile Iron	26	5	0 out of 5	N/A	\$0	
Distribution Mains	P-7324	COV	Highwood Dr.	8	Asbestos Cement	250	50	1.72 out of 5	\$345	\$86,250	
Distribution Mains	P-7327	COV	Highwood Dr.	8	Asbestos Cement	687	50	1.72 out of 5	\$345	\$237,015	
Distribution Mains	P-7331	COV	Highwood Dr.	8	Asbestos Cement	483	36	1.58 out of 5	\$345	\$166,635	
Distribution Mains	P-7332	COV	Highwood Dr.	8	Asbestos Cement	2,027	36	1.58 out of 5	\$345	\$699,315	
Transmission Mains	P-7004	COV	Hill Farm Rd.	12	Asbestos Cement	381	32	1.58 out of 5	\$345	\$131,445	
Transmission Mains	P-7008	COV	Hill Farm Rd.	12	Asbestos Cement	1,635	32	1.58 out of 5	\$345	\$564,075	
Transmission Mains	P-8523	COV	Hill Farm Rd.	12	Asbestos Cement	69	32	1.58 out of 5	\$345	\$23,805	
Transmission Mains	P-8769	COV	Hill Farm Rd.	12	Asbestos Cement	1,106	32	1.58 out of 5	\$345	\$381,570	
Transmission Mains	P-8962	COV	Hill Farm Rd.	12	Asbestos Cement	25	32	1.58 out of 5	\$345	\$8,625	
Transmission Mains	P-7010	COV	Hill Farm Rd.	12	PVC	1,084	26	0.44 out of 5	\$345	\$373,980	
Transmission Mains	P-8803	COV	Hill Farm Rd.	12	PVC	160	26	0.44 out of 5	\$345	\$55,200	
Transmission Mains	P-7003	COV	Hill Farm Rd.	12	Ductile Iron	555	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8770	COV	Hill Farm Rd.	12	Ductile Iron	220	8	0 out of 5	N/A	\$0	
Distribution Mains	P-8105	COV	Hill St.	4	Cast iron	160	127	3.3 out of 5	\$345	\$55,200	
Distribution Mains	P-8870	COV	Hill St.	1	Asbestos Cement	29	67	3.3 out of 5	\$345	\$10,005	
Distribution Mains	P-8098	COV	Hill St.	6	Cast iron	248	127	2.58 out of 5	\$345	\$85,560	
Distribution Mains	P-8103	COV	Hill St.	6	Cast iron	187	127	2.58 out of 5	\$345	\$64,515	
Distribution Mains	P-8868	COV	Hill St.	6	Cast iron	192	127	2.58 out of 5	\$345	\$66,240	
Distribution Mains	P-8081	COV	Hill St.	6	Cast iron	197	86	2.43 out of 5	\$345	\$67,965	
Distribution Mains	P-8083	COV	Hill St.	6	Cast iron	195	86	2.43 out of 5	\$345	\$67,275	
Transmission Mains	P-8100	COV	Hill St.	16	Asbestos Cement	74	58	2.43 out of 5	\$345	\$25,530	
Distribution Mains	P-7939	COV	Hill St.	8	Asbestos Cement	624	67	1.87 out of 5	\$345	\$215,280	
Distribution Mains	P-7953	COV	Hill St.	8	Asbestos Cement	331	67	1.87 out of 5	\$345	\$114,195	
Distribution Mains	P-8073	COV	Hill St.	8	Asbestos Cement	661	67	1.87 out of 5	\$345	\$228,045	
Distribution Mains	P-8095	COV	Hill St.	8	Asbestos Cement	104	67	1.87 out of 5	\$345	\$35,880	
Distribution Mains	P-8096	COV	Hill St.	8	Asbestos Cement	545	67	1.87 out of 5	\$345	\$188,025	
Distribution Mains	P-8097	COV	Hill St.	8	Asbestos Cement	223	67	1.87 out of 5	\$345	\$76,935	
Distribution Mains	P-8869	COV	Hill St.	8	Asbestos Cement	82	67	1.87 out of 5	\$345	\$28,290	
Transmission Mains	P-8099	COV	Hill St.	16	Asbestos Cement	987	58	1.72 out of 5	\$345	\$340,515	
Transmission Mains	P-7930	COV	Hill St.	24	Ductile Iron	460	9	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-7935	COV	Hill St.	24	Ductile Iron	1,214	9	0 out of 5	N/A	\$0	
Transmission Mains	P-8090	COV	Hill St.	24	Ductile Iron	842	9	0 out of 5	N/A	\$0	
Transmission Mains	P-8091	COV	Hill St.	24	Ductile Iron	128	9	0 out of 5	N/A	\$0	
Transmission Mains	P-8092	COV	Hill St.	24	Ductile Iron	461	9	0 out of 5	N/A	\$0	
Distribution Mains	P-8372	COV	Hill St.	8	Ductile Iron	462	13	0 out of 5	N/A	\$0	
Transmission Mains	P-8504	COV	Hill St.	24	Ductile Iron	128	9	0 out of 5	N/A	\$0	
Transmission Mains	P-8505	COV	Hill St.	24	Ductile Iron	205	9	0 out of 5	N/A	\$0	
Transmission Mains	P-8506	COV	Hill St.	24	Ductile Iron	1,150	9	0 out of 5	N/A	\$0	
Transmission Mains	P-8839	COV	Hill St.	16	Ductile Iron	37	8	0 out of 5	N/A	\$0	
Distribution Mains	P-8080	COV	Hillside Ave.	6	Ductile Iron	502	4	0.71 out of 5	\$345	\$173,190	
Distribution Mains	P-8075	COV	Hillside Ave.	8	Ductile Iron	160	3	0 out of 5	N/A	\$0	
Distribution Mains	P-8077	COV	Hillside Ave.	8	Ductile Iron	232	3	0 out of 5	N/A	\$0	
Distribution Mains	P-8079	COV	Hillside Ave.	8	Ductile Iron	204	3	0 out of 5	N/A	\$0	
Distribution Mains	P-9001	COV	Hilltop Ave.	6	Ductile Iron	239	14	0.71 out of 5	\$345	\$82,455	
Distribution Mains	P-7264	COV	Holden St.	6	Cast iron	112	50	2.14 out of 5	\$345	\$38,640	
Distribution Mains	P-7265	COV	Holden St.	6	Cast iron	96	50	2.14 out of 5	\$345	\$33,120	
Distribution Mains	P-7777	COV	Holloway Ave.	6	Asbestos Cement	247	56	3.14 out of 5	\$345	\$85,215	
Distribution Mains	P-7774	COV	Holloway Ave.	6	Asbestos Cement	258	56	2.43 out of 5	\$345	\$89,010	
Distribution Mains	P-7781	COV	Holloway Ave.	6	Asbestos Cement	247	56	2.43 out of 5	\$345	\$85,215	
Distribution Mains	P-8876	COV	Holly Ct.	8	Asbestos Cement	151	34	1.58 out of 5	\$345	\$52,095	
Distribution Mains	P-7685	COV	Holmes Rd.	6	Asbestos Cement	877	60	2.58 out of 5	\$345	\$302,565	
Distribution Mains	P-7687	COV	Holmes Rd.	6	Asbestos Cement	394	60	2.58 out of 5	\$345	\$135,930	
Distribution Mains	P-7528	COV	Homestead Dr.	6	Asbestos Cement	248	53	2.43 out of 5	\$345	\$85,560	
Distribution Mains	P-7899	COV	Honey Locust Ct.	6	Asbestos Cement	337	35	2.29 out of 5	\$345	\$116,265	
Distribution Mains	P-7172	COV	Hoover Dr.	8	Asbestos Cement	357	36	1.58 out of 5	\$345	\$123,165	
Distribution Mains	P-7173	COV	Hoover Dr.	8	Asbestos Cement	325	36	1.58 out of 5	\$345	\$112,125	
Distribution Mains	P-8026	COV	Hope Ct.	2	Galvanized iron	258	68	3.3 out of 5	\$345	\$89,010	
Distribution Mains	P-8060	COV	Hope View St.	1.5	Copper	235	66	2.44 out of 5	\$345	\$81,075	
Distribution Mains	P-7231	COV	Hopkins Ct.	6	Asbestos Cement	282	51	2.43 out of 5	\$345	\$97,290	
Transmission Mains	P-7542	COV	Hopkins Hill Rd.	12	PVC	523	28	0.44 out of 5	\$345	\$180,435	
Transmission Mains	P-7477	COV	Hopkins Hill Rd.	12	Ductile Iron	667	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7479	COV	Hopkins Hill Rd.	12	Ductile Iron	189	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7480	COV	Hopkins Hill Rd.	12	Ductile Iron	60	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7485	COV	Hopkins Hill Rd.	12	Ductile Iron	254	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7488	COV	Hopkins Hill Rd.	12	Ductile Iron	205	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7489	COV	Hopkins Hill Rd.	12	Ductile Iron	220	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7490	COV	Hopkins Hill Rd.	12	Ductile Iron	257	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7494	COV	Hopkins Hill Rd.	12	Ductile Iron	300	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7495	COV	Hopkins Hill Rd.	12	Ductile Iron	1,053	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8197	COV	Hopkins Hill Rd.	12	Ductile Iron	80	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8199	COV	Hopkins Hill Rd.	12	Ductile Iron	240	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8201	COV	Hopkins Hill Rd.	12	Ductile Iron	396	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8388	COV	Hopkins Hill Rd.	12	Ductile Iron	1,410	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8464	COV	Hopkins Hill Rd.	12	Ductile Iron	279	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8512	COV	Hopkins Hill Rd.	12	Ductile Iron	55	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7948	COV	Hornbeam Rd.	8	Asbestos Cement	955	50	2.43 out of 5	\$345	\$329,475	
Distribution Mains	P-7945	COV	Hornbeam Rd.	8	Asbestos Cement	292	50	1.72 out of 5	\$345	\$100,740	
Distribution Mains	P-8412	COV	Hornbeam Rd.	8	Ductile Iron	795	9	0 out of 5	N/A	\$0	
Distribution Mains	P-8416	COV	Hornbeam Rd.	8	Ductile Iron	550	9	0 out of 5	N/A	\$0	
Distribution Mains	P-8417	COV	Hornbeam Rd.	8	Ductile Iron	860	5	0 out of 5	N/A	\$0	
Distribution Mains	P-8115	COV	Howard Ave.	6	Cast iron	1,267	127	2.58 out of 5	\$345	\$437,115	
Distribution Mains	P-8857	COV	Howard Ave.	6	Cast iron	319	127	2.58 out of 5	\$345	\$110,055	
Transmission Mains	P-8094	COV	Howard Ave.	16	Asbestos Cement	104	58	1.72 out of 5	\$345	\$35,880	
Distribution Mains	P-8114	COV	Howard Ave.	8	Asbestos Cement	1,213	58	1.72 out of 5	\$345	\$418,485	
Transmission Mains	P-8118	COV	Howard Ave.	16	Asbestos Cement	121	58	1.72 out of 5	\$345	\$41,745	
Transmission Mains	P-8120	COV	Howard Ave.	16	Asbestos Cement	253	58	1.72 out of 5	\$345	\$87,285	
Transmission Mains	P-8122	COV	Howard Ave.	16	Asbestos Cement	980	58	1.72 out of 5	\$345	\$338,100	
Transmission Mains	P-8277	COV	Howard Ave.	16	Asbestos Cement	136	57	1.72 out of 5	\$345	\$46,920	
Transmission Mains	P-8369	COV	Howard Ave.	16	Asbestos Cement	253	57	1.72 out of 5	\$345	\$87,285	
Transmission Mains	P-8509	COV	Howard Ave.	16	Asbestos Cement	255	57	1.72 out of 5	\$345	\$87,975	
Transmission Mains	P-8859	COV	Howard Ave.	16	Asbestos Cement	1,384	58	1.72 out of 5	\$345	\$477,480	
Distribution Mains	P-8366	COV	Howard Ave.	8	Ductile Iron	110	13	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-8957	COV	Huckleberry Rd.	6	Asbestos Cement	364	52	2.43 out of 5	\$345	\$125,580	
Transmission Mains	P-7344	COV	Hunters Crossing Dr.	16	Ductile Iron	779	19	0 out of 5	N/A	\$0	
Transmission Mains	P-7349	COV	Hunters Crossing Dr.	16	Ductile Iron	1,328	19	0 out of 5	N/A	\$0	
Transmission Mains	P-7350	COV	Hunters Crossing Dr.	16	Ductile Iron	763	19	0 out of 5	N/A	\$0	
Transmission Mains	P-7357	COV	Hunters Crossing Dr.	16	Ductile Iron	664	19	0 out of 5	N/A	\$0	
Transmission Mains	P-7358	COV	Hunters Crossing Dr.	16	Ductile Iron	166	19	0 out of 5	N/A	\$0	
Transmission Mains	P-7360	COV	Hunters Crossing Dr.	16	Ductile Iron	408	19	0 out of 5	N/A	\$0	
Transmission Mains	P-8885	COV	Hunters Crossing Dr.	16	Ductile Iron	410	19	0 out of 5	N/A	\$0	
Distribution Mains	P-8887	COV	Hunters Crossing Dr.	8	Ductile Iron	28	19	0 out of 5	N/A	\$0	
Distribution Mains	P-7580	COV	Idaho St.	2	Galvanized iron	539	81	4.87 out of 5	\$345	\$185,955	
Distribution Mains	P-7583	COV	Idaho St.	2	Galvanized iron	292	81	4.87 out of 5	\$345	\$100,740	
Distribution Mains	P-8898	COV	Industrial Dr.	8	Ductile Iron	1,201	3	0 out of 5	N/A	\$0	
Distribution Mains	P-7404	COV	Irene St.	6	Asbestos Cement	517	45	2.43 out of 5	\$345	\$178,365	
Distribution Mains	P-9034	COV	Irene St.	6	Asbestos Cement	275	45	2.43 out of 5	\$345	\$94,875	
Distribution Mains	P-7302	COV	Ironwood Dr.	8	Asbestos Cement	382	29	1.58 out of 5	\$345	\$131,790	
Distribution Mains	P-7304	COV	Ironwood Dr.	8	Asbestos Cement	369	29	1.58 out of 5	\$345	\$127,305	
Distribution Mains	P-7306	COV	Ironwood Dr.	8	Asbestos Cement	364	29	1.58 out of 5	\$345	\$125,580	
Distribution Mains	P-7093	COV	Island Dr.	8	Asbestos Cement	341	38	1.58 out of 5	\$345	\$117,645	
Distribution Mains	P-7096	COV	Island Dr.	8	Asbestos Cement	823	38	1.58 out of 5	\$345	\$283,935	
Distribution Mains	P-7098	COV	Island Dr.	6	Ductile Iron	773	21	0.86 out of 5	\$345	\$266,685	
Distribution Mains	P-7099	COV	Island Dr.	6	Ductile Iron	179	21	0.86 out of 5	\$345	\$61,755	
Distribution Mains	P-7100	COV	Island Dr.	6	Ductile Iron	173	21	0.86 out of 5	\$345	\$59,685	
Distribution Mains	P-7007	COV	Isle of Capri Rd.	6	Ductile Iron	820	23	0.86 out of 5	\$345	\$282,900	
Distribution Mains	P-7299	COV	Ivy Dr.	8	Asbestos Cement	513	35	1.58 out of 5	\$345	\$176,985	
Distribution Mains	P-7031	COV	Jack Pine Rd.	6	Asbestos Cement	257	52	3.14 out of 5	\$345	\$88,665	
Distribution Mains	P-7042	COV	Jack Pine Rd.	6	Asbestos Cement	231	52	2.43 out of 5	\$345	\$79,695	
Distribution Mains	P-7043	COV	Jack Pine Rd.	6	Asbestos Cement	243	52	2.43 out of 5	\$345	\$83,835	
Distribution Mains	P-7048	COV	Jack Pine Rd.	6	Asbestos Cement	354	52	2.43 out of 5	\$345	\$122,130	
Distribution Mains	P-7681	COV	Jade Rd.	8	Asbestos Cement	241	45	1.72 out of 5	\$345	\$83,145	
Distribution Mains	P-7682	COV	Jade Rd.	8	Asbestos Cement	923	45	1.72 out of 5	\$345	\$318,435	
Distribution Mains	P-7336	COV	Jasmine Ct.	8	Ductile Iron	169	16	0 out of 5	N/A	\$0	
Distribution Mains	P-7443	COV	Jefferson Dr.	8	Asbestos Cement	1,149	37	1.58 out of 5	\$345	\$396,405	
Distribution Mains	P-7444	COV	Jefferson Dr.	8	Asbestos Cement	855	37	1.58 out of 5	\$345	\$294,975	
Transmission Mains	P-7161	COV	Jefferson Dr.	12	Ductile Iron	1,061	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7162	COV	Jefferson Dr.	12	Ductile Iron	857	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7746	COV	Jennifer Ln.	8	Ductile Iron	203	22	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7748	COV	Jennifer Ln.	8	Ductile Iron	232	22	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7750	COV	Jennifer Ln.	8	Ductile Iron	552	19	0 out of 5	N/A	\$0	
Distribution Mains	P-7486	COV	Johnson Blvd.	10	Asbestos Cement	244	53	1.72 out of 5	\$345	\$84,180	
Transmission Mains	P-7627	COV	Johnson Blvd.	12	Asbestos Cement	723	53	1.72 out of 5	\$345	\$249,435	
Distribution Mains	P-7629	COV	Johnson Blvd.	10	Asbestos Cement	263	58	1.72 out of 5	\$345	\$90,735	
Distribution Mains	P-7631	COV	Johnson Blvd.	10	Asbestos Cement	249	58	1.72 out of 5	\$345	\$85,905	
Distribution Mains	P-7637	COV	Johnson Blvd.	10	Asbestos Cement	706	58	1.72 out of 5	\$345	\$243,570	
Transmission Mains	P-7642	COV	Johnson Blvd.	12	Asbestos Cement	294	53	1.72 out of 5	\$345	\$101,430	
Transmission Mains	P-7643	COV	Johnson Blvd.	12	Asbestos Cement	246	53	1.72 out of 5	\$345	\$84,870	
Transmission Mains	P-7647	COV	Johnson Blvd.	12	PVC	392	23	0.44 out of 5	\$345	\$135,240	
Transmission Mains	P-7648	COV	Johnson Blvd.	12	PVC	236	23	0.44 out of 5	\$345	\$81,420	
Transmission Mains	P-8189	COV	Johnson Blvd.	16	Ductile Iron	251	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8190	COV	Johnson Blvd.	16	Ductile Iron	167	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8191	COV	Johnson Blvd.	16	Ductile Iron	1,242	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8193	COV	Johnson Blvd.	16	Ductile Iron	1,142	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8194	COV	Johnson Blvd.	16	Ductile Iron	192	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7638	COV	Johnson Blvd. PS	16	Ductile Iron	263	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7639	COV	Johnson Blvd. PS	16	Ductile Iron	964	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7640	COV	Johnson Blvd. PS	16	Ductile Iron	203	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7641	COV	Johnson Blvd. PS	16	Ductile Iron	337	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8229	COV	Johnson Blvd. PS	16	Ductile Iron	352	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8230	COV	Johnson Blvd. PS	16	Ductile Iron	120	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8231	COV	Johnson Blvd. PS	12	Ductile Iron	152	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8232	COV	Johnson Blvd. PS	12	Ductile Iron	160	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8233	COV	Johnson Blvd. PS	16	Ductile Iron	122	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8234	COV	Johnson Blvd. PS	16	Ductile Iron	127	23	0.15 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-8235	COV	Johnson Blvd. PS	12	Ductile Iron	154	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8236	COV	Johnson Blvd. PS	12	Ductile Iron	160	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8237	COV	Johnson Blvd. PS	16	Ductile Iron	129	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8238	COV	Johnson Blvd. PS	16	Ductile Iron	131	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8239	COV	Johnson Blvd. PS	10	Ductile Iron	152	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8240	COV	Johnson Blvd. PS	10	Ductile Iron	160	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8241	COV	Johnson Blvd. PS	16	Ductile Iron	129	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7894	COV	Juniper Ct.	6	Asbestos Cement	142	35	3 out of 5	\$345	\$48,990	
Distribution Mains	P-7106	COV	Juniper Hill Dr.	8	Asbestos Cement	660	35	1.58 out of 5	\$345	\$227,700	
Distribution Mains	P-7109	COV	Juniper Hill Dr.	8	Asbestos Cement	398	35	1.58 out of 5	\$345	\$137,310	
Distribution Mains	P-7114	COV	Juniper Hill Dr.	8	Ductile Iron	938	16	0 out of 5	N/A	\$0	
Distribution Mains	P-7999	COV	Justa Ave.	6	Asbestos Cement	241	67	2.58 out of 5	\$345	\$83,145	
Distribution Mains	P-8000	COV	Justa Ave.	6	Asbestos Cement	231	67	2.58 out of 5	\$345	\$79,695	
Distribution Mains	P-8211	COV	Kathy Ave.	8	Ductile Iron	357	3	0 out of 5	N/A	\$0	
Distribution Mains	P-7763	COV	Kennedy Dr.	8	Asbestos Cement	575	53	1.72 out of 5	\$345	\$198,375	
Distribution Mains	P-7765	COV	Kennedy Dr.	8	Asbestos Cement	280	53	1.72 out of 5	\$345	\$96,600	
Distribution Mains	P-8205	COV	Kennington Ave.	8	Ductile Iron	543	3	0 out of 5	N/A	\$0	
Distribution Mains	P-7139	COV	Kiley Way	8	Ductile Iron	497	10	0 out of 5	N/A	\$0	
Distribution Mains	P-7140	COV	Kiley Way	8	Ductile Iron	120	10	0 out of 5	N/A	\$0	
Distribution Mains	P-8948	COV	Kiley Way	8	Ductile Iron	938	15	0 out of 5	N/A	\$0	
Distribution Mains	P-8949	COV	Kiley Way	8	Ductile Iron	1,042	10	0 out of 5	N/A	\$0	
Distribution Mains	P-7141	COV	Kiley Way Easement	8	Ductile Iron	447	10	0 out of 5	N/A	\$0	
Distribution Mains	P-7541	COV	Kilton Ln.	8	Ductile Iron	472	13	0 out of 5	N/A	\$0	
Distribution Mains	P-8208	COV	Kimberly Ave.	8	Ductile Iron	488	3	0 out of 5	N/A	\$0	
Distribution Mains	P-8216	COV	King St.	6	Ductile Iron	993	20	0.86 out of 5	\$345	\$342,585	
Transmission Mains	P-8196	COV	King St.	12	Ductile Iron	337	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7095	COV	Kingfisher Dr.	8	PVC	224	29	0.44 out of 5	\$345	\$77,280	
Distribution Mains	P-8950	COV	Kingfisher Dr.	8	PVC	332	29	0.44 out of 5	\$345	\$114,540	
Distribution Mains	P-7027	COV	Kingswood Dr.	6	Asbestos Cement	504	46	2.43 out of 5	\$345	\$173,880	
Distribution Mains	P-7028	COV	Kingswood Dr.	6	Asbestos Cement	311	46	2.43 out of 5	\$345	\$107,295	
Distribution Mains	P-7967	COV	Knight St.	6	Cast iron	558	74	2.29 out of 5	\$345	\$192,510	
Distribution Mains	P-8880	COV	Knotty Oak Ln.	8	Ductile Iron	59	10	0 out of 5	N/A	\$0	
Distribution Mains	P-7274	COV	Knotty Oak Rd.	8	Asbestos Cement	68	67	1.87 out of 5	\$345	\$23,460	
Distribution Mains	P-7275	COV	Knotty Oak Rd.	8	Asbestos Cement	412	67	1.87 out of 5	\$345	\$142,140	
Distribution Mains	P-7279	COV	Knotty Oak Rd.	8	Asbestos Cement	871	67	1.87 out of 5	\$345	\$300,495	
Distribution Mains	P-7317	COV	Knotty Oak Rd.	8	Asbestos Cement	129	67	1.87 out of 5	\$345	\$44,505	
Distribution Mains	P-8242	COV	Knotty Oak Rd.	8	Asbestos Cement	27	67	1.87 out of 5	\$345	\$9,315	
Distribution Mains	P-8245	COV	Knotty Oak Rd.	8	Asbestos Cement	589	67	1.87 out of 5	\$345	\$203,205	
Distribution Mains	P-8918	COV	Knotty Oak Rd.	8	Asbestos Cement	180	67	1.87 out of 5	\$345	\$62,100	
Distribution Mains	P-8919	COV	Knotty Oak Rd.	8	Asbestos Cement	24	67	1.87 out of 5	\$345	\$8,280	
Transmission Mains	P-7323	COV	Knotty Oak Rd.	12	Asbestos Cement	192	52	1.72 out of 5	\$345	\$66,240	
Transmission Mains	P-7362	COV	Knotty Oak Rd.	12	Asbestos Cement	1,582	52	1.72 out of 5	\$345	\$545,790	
Transmission Mains	P-7851	COV	Knotty Oak Rd.	20	Asbestos Cement	199	46	1.72 out of 5	\$345	\$68,655	
Transmission Mains	P-7873	COV	Knotty Oak Rd.	20	Asbestos Cement	898	46	1.72 out of 5	\$345	\$309,810	
Transmission Mains	P-7875	COV	Knotty Oak Rd.	20	Asbestos Cement	619	46	1.72 out of 5	\$345	\$213,555	
Transmission Mains	P-7876	COV	Knotty Oak Rd.	20	Asbestos Cement	93	46	1.72 out of 5	\$345	\$32,085	
Transmission Mains	P-7877	COV	Knotty Oak Rd.	12	Asbestos Cement	73	52	1.72 out of 5	\$345	\$25,185	
Transmission Mains	P-7878	COV	Knotty Oak Rd.	12	Asbestos Cement	744	52	1.72 out of 5	\$345	\$256,680	
Transmission Mains	P-7879	COV	Knotty Oak Rd.	12	Asbestos Cement	111	52	1.72 out of 5	\$345	\$38,295	
Transmission Mains	P-7880	COV	Knotty Oak Rd.	20	Asbestos Cement	1,846	46	1.72 out of 5	\$345	\$636,870	
Transmission Mains	P-8253	COV	Knotty Oak Rd.	20	Asbestos Cement	543	46	1.72 out of 5	\$345	\$187,335	
Transmission Mains	P-8495	COV	Knotty Oak Rd.	20	Asbestos Cement	1,992	46	1.72 out of 5	\$345	\$687,240	
Transmission Mains	P-8496	COV	Knotty Oak Rd.	20	Asbestos Cement	218	46	1.72 out of 5	\$345	\$75,210	
Transmission Mains	P-8916	COV	Knotty Oak Rd.	12	Asbestos Cement	1,348	52	1.72 out of 5	\$345	\$465,060	
Transmission Mains	P-8926	COV	Knotty Oak Rd.	20	Asbestos Cement	109	46	1.72 out of 5	\$345	\$37,605	
Transmission Mains	P-7891	COV	Knotty Oak Rd.	12	Ductile Iron	628	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7361	COV	Knotty Oak Rd.	16	Ductile Iron	364	19	0 out of 5	N/A	\$0	
Transmission Mains	P-7782	COV	Knotty Oak Rd.	20	Ductile Iron	74	9	0 out of 5	N/A	\$0	
Transmission Mains	P-7887	COV	Knotty Oak Rd.	20	Ductile Iron	54	9	0 out of 5	N/A	\$0	
Transmission Mains	P-7888	COV	Knotty Oak Rd.	20	Ductile Iron	787	9	0 out of 5	N/A	\$0	
Transmission Mains	P-7890	COV	Knotty Oak Rd.	20	Ductile Iron	2,377	9	0 out of 5	N/A	\$0	
Transmission Mains	P-8489	COV	Knotty Oak Rd.	20	Ductile Iron	167	9	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-8491	COV	Knotty Oak Rd.	20	Ductile Iron	101	9	0 out of 5	N/A	\$0	
Transmission Mains	P-8494	COV	Knotty Oak Rd.	20	Ductile Iron	89	9	0 out of 5	N/A	\$0	
Transmission Mains	P-8877	COV	Knotty Oak Rd.	20	Ductile Iron	870	9	0 out of 5	N/A	\$0	
Transmission Mains	P-8879	COV	Knotty Oak Rd.	20	Ductile Iron	2,600	9	0 out of 5	N/A	\$0	
Transmission Mains	P-8881	COV	Knotty Oak Rd.	20	Ductile Iron	288	9	0 out of 5	N/A	\$0	
Distribution Mains	P-8920	COV	Knotty Oak Rd. PS	10	Ductile Iron	23	19	0 out of 5	N/A	\$0	
Transmission Mains	P-8921	COV	Knotty Oak Rd. PS	12	Ductile Iron	56	19	0 out of 5	N/A	\$0	
Transmission Mains	P-8922	COV	Knotty Oak Rd. PS	12	Ductile Iron	27	19	0 out of 5	N/A	\$0	
Transmission Mains	P-8923	COV	Knotty Oak Rd. PS	12	Ductile Iron	28	19	0 out of 5	N/A	\$0	
Transmission Mains	P-8924	COV	Knotty Oak Rd. PS	12	Ductile Iron	27	19	0 out of 5	N/A	\$0	
Distribution Mains	P-8925	COV	Knotty Oak Rd. PS	10	Ductile Iron	20	19	0 out of 5	N/A	\$0	
Distribution Mains	P-8927	COV	Knotty Oak Rd. PS	10	Ductile Iron	20	19	0 out of 5	N/A	\$0	
Distribution Mains	P-8878	COV	Knotty Oak Shores	8	Ductile Iron	407	10	0 out of 5	N/A	\$0	
Distribution Mains	P-7378	COV	La Casa Dr.	6	Asbestos Cement	335	44	2.43 out of 5	\$345	\$115,575	
Distribution Mains	P-7380	COV	La Casa Dr.	6	Asbestos Cement	324	44	2.43 out of 5	\$345	\$111,780	
Distribution Mains	P-7377	COV	La Forge Dr.	8	Asbestos Cement	376	46	1.72 out of 5	\$345	\$129,720	
Distribution Mains	P-7913	COV	Labrea Way	8	Ductile Iron	680	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7379	COV	Laforge Dr.	8	Asbestos Cement	306	46	2.43 out of 5	\$345	\$105,570	
Distribution Mains	P-8851	COV	Laforge Dr.	6	Asbestos Cement	283	46	2.43 out of 5	\$345	\$97,635	
Distribution Mains	P-7369	COV	Laforge Dr.	8	Asbestos Cement	347	46	1.72 out of 5	\$345	\$119,715	
Distribution Mains	P-8850	COV	Laforge Dr.	8	Asbestos Cement	169	46	1.72 out of 5	\$345	\$58,305	
Distribution Mains	P-7005	COV	Lakehurst Ave.	6	Ductile Iron	633	23	0.86 out of 5	\$345	\$218,385	
Distribution Mains	P-7584	COV	Lakeside Dr.	3	Galvanized iron	534	81	3.44 out of 5	\$345	\$184,230	
Distribution Mains	P-7585	COV	Lakeside Dr.	2	Galvanized iron	1,033	81	3.44 out of 5	\$345	\$356,385	
Distribution Mains	P-9002	COV	Lakeside Dr.	1.5	Copper	1,374	81	2.58 out of 5	\$345	\$474,030	
Distribution Mains	P-8320	COV	Lambert St.	1	Ductile Iron	100	17	1.43 out of 5	\$345	\$34,500	
Distribution Mains	P-7771	COV	Lantern Ln.	6	Asbestos Cement	610	54	2.43 out of 5	\$345	\$210,450	
Distribution Mains	P-7702	COV	Larch Dr.	6	Asbestos Cement	641	55	2.43 out of 5	\$345	\$221,145	
Distribution Mains	P-7703	COV	Larch Dr.	6	Asbestos Cement	576	55	2.43 out of 5	\$345	\$198,720	
Distribution Mains	P-7704	COV	Larch Dr.	6	Asbestos Cement	171	55	2.43 out of 5	\$345	\$58,995	
Distribution Mains	P-7698	COV	Larch Dr.	8	Asbestos Cement	256	55	1.72 out of 5	\$345	\$88,320	
Distribution Mains	P-7599	COV	Larchmont Dr.	8	Asbestos Cement	202	48	1.72 out of 5	\$345	\$69,690	
Distribution Mains	P-7600	COV	Larchmont Dr.	8	Asbestos Cement	1,102	48	1.72 out of 5	\$345	\$380,190	
Distribution Mains	P-7303	COV	Laura Ct.	8	Asbestos Cement	347	29	1.58 out of 5	\$345	\$119,715	
Distribution Mains	P-7828	COV	Laurel Ave.	6	Cast iron	215	127	2.58 out of 5	\$345	\$74,175	
Distribution Mains	P-7829	COV	Laurel Ave.	6	Cast iron	229	127	2.58 out of 5	\$345	\$79,005	
Distribution Mains	P-7830	COV	Laurel Ave.	6	Cast iron	153	127	2.58 out of 5	\$345	\$52,785	
Distribution Mains	P-7820	COV	Laurel Ave.	6	Asbestos Cement	292	47	2.43 out of 5	\$345	\$100,740	
Distribution Mains	P-7821	COV	Laurel Ave.	6	Asbestos Cement	245	47	2.43 out of 5	\$345	\$84,525	
Distribution Mains	P-7826	COV	Laurel Ave.	6	Asbestos Cement	342	47	2.43 out of 5	\$345	\$117,990	
Distribution Mains	P-7839	COV	Laurel Ave.	6	Asbestos Cement	156	45	2.43 out of 5	\$345	\$53,820	
Distribution Mains	P-7840	COV	Laurel Ave.	6	Asbestos Cement	549	45	2.43 out of 5	\$345	\$189,405	
Transmission Mains	P-7863	COV	Laurel Ave.	12	Cast iron	358	86	1.72 out of 5	\$345	\$123,510	
Distribution Mains	P-7463	COV	Laurie Ave.	6	Asbestos Cement	620	44	2.43 out of 5	\$345	\$213,900	
Distribution Mains	P-7624	COV	Lawnwood Rd.	6	Asbestos Cement	480	45	2.43 out of 5	\$345	\$165,600	
Distribution Mains	P-7625	COV	Lawnwood Rd.	6	Asbestos Cement	312	45	2.43 out of 5	\$345	\$107,640	
Distribution Mains	P-7224	COV	Leader St.	6	Asbestos Cement	292	64	2.58 out of 5	\$345	\$100,740	
Distribution Mains	P-7225	COV	Leader St.	6	Asbestos Cement	201	52	2.43 out of 5	\$345	\$69,345	
Distribution Mains	P-7630	COV	Ledo St.	6	Asbestos Cement	545	52	2.43 out of 5	\$345	\$188,025	
Distribution Mains	P-8135	COV	Lemis St.	6	Asbestos Cement	1,081	54	2.43 out of 5	\$345	\$372,945	
Distribution Mains	P-7194	COV	Leuba Rd.	8	Asbestos Cement	116	40	1.72 out of 5	\$345	\$40,020	
Distribution Mains	P-7196	COV	Leuba Rd.	8	Asbestos Cement	524	40	1.72 out of 5	\$345	\$180,780	
Distribution Mains	P-7197	COV	Leuba Rd.	8	Asbestos Cement	593	40	1.72 out of 5	\$345	\$204,585	
Distribution Mains	P-7192	COV	Leuba Rd.	8	Ductile Iron	2,176	21	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8899	COV	Leuba Rd.	8	Ductile Iron	79	3	0 out of 5	N/A	\$0	
Distribution Mains	P-8102	COV	Leveilee St.	6	Cast iron	544	127	2.58 out of 5	\$345	\$187,680	
Transmission Mains	P-8368	COV	Lincoln Ave.	16	Asbestos Cement	179	57	1.72 out of 5	\$345	\$61,755	
Distribution Mains	P-8367	COV	Lincoln Ave.	8	Ductile Iron	293	13	0 out of 5	N/A	\$0	
Transmission Mains	P-8754	COV	Lincoln Ave.	16	Ductile Iron	317	7	0 out of 5	N/A	\$0	
Transmission Mains	P-8840	COV	Lincoln Ave.	16	Ductile Iron	24	7	0 out of 5	N/A	\$0	
Transmission Mains	P-8842	COV	Lincoln Ave.	16	Ductile Iron	151	7	0 out of 5	N/A	\$0	
Distribution Mains	P-8843	COV	Lincoln Ave.	8	Ductile Iron	43	7	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-7234	COV	Linda Ct.	6	Asbestos Cement	218	46	2.43 out of 5	\$345	\$75,210	
Distribution Mains	P-7059	COV	Linden Ln.	6	Asbestos Cement	368	41	2.43 out of 5	\$345	\$126,960	
Distribution Mains	P-8148	COV	Linray St.	6	Asbestos Cement	239	49	2.43 out of 5	\$345	\$82,455	
Distribution Mains	P-7459	COV	Linwood Dr.	6	Asbestos Cement	545	52	2.43 out of 5	\$345	\$188,025	
Distribution Mains	P-7464	COV	Linwood Dr.	6	Asbestos Cement	329	52	2.43 out of 5	\$345	\$113,505	
Distribution Mains	P-7470	COV	Linwood Dr.	6	Asbestos Cement	326	51	2.43 out of 5	\$345	\$112,470	
Distribution Mains	P-7474	COV	Linwood Dr.	6	Asbestos Cement	95	51	2.43 out of 5	\$345	\$32,775	
Distribution Mains	P-7478	COV	Linwood Dr.	6	Asbestos Cement	129	51	2.43 out of 5	\$345	\$44,505	
Distribution Mains	P-8515	COV	Linwood Dr.	6	Asbestos Cement	85	51	2.43 out of 5	\$345	\$29,325	
Distribution Mains	P-7610	COV	Lionel Ave.	8	Asbestos Cement	488	55	1.72 out of 5	\$345	\$168,360	
Distribution Mains	P-7615	COV	Lionel Ave.	8	Asbestos Cement	462	55	1.72 out of 5	\$345	\$159,390	
Distribution Mains	P-7618	COV	Lionel Ave.	8	Asbestos Cement	282	55	1.72 out of 5	\$345	\$97,290	
Distribution Mains	P-8942	COV	Lionel Ave.	8	Ductile Iron	62	14	0 out of 5	N/A	\$0	
Distribution Mains	P-8154	COV	Lions Dr.	8	Asbestos Cement	423	41	1.72 out of 5	\$345	\$145,935	
Distribution Mains	P-7238	COV	Lloyd Dr.	8	Asbestos Cement	339	51	1.72 out of 5	\$345	\$116,955	
Distribution Mains	P-7239	COV	Lloyd Dr.	8	Asbestos Cement	292	51	1.72 out of 5	\$345	\$100,740	
Distribution Mains	P-7243	COV	Lloyd Dr.	8	Asbestos Cement	305	51	1.72 out of 5	\$345	\$105,225	
Distribution Mains	P-7245	COV	Lloyd Dr.	8	Asbestos Cement	344	51	1.72 out of 5	\$345	\$118,680	
Distribution Mains	P-7247	COV	Lloyd Dr.	8	Asbestos Cement	277	51	1.72 out of 5	\$345	\$95,565	
Distribution Mains	P-8323	COV	Locust St.	8	Ductile Iron	246	13	0 out of 5	N/A	\$0	
Distribution Mains	P-7280	COV	Long Pond Rd.	8	Asbestos Cement	225	55	1.72 out of 5	\$345	\$77,625	
Distribution Mains	P-7281	COV	Long Pond Rd.	8	Asbestos Cement	350	55	1.72 out of 5	\$345	\$120,750	
Distribution Mains	P-7285	COV	Long Pond Rd.	8	Asbestos Cement	516	55	1.72 out of 5	\$345	\$178,020	
Distribution Mains	P-8153	COV	Longfellow Dr.	8	Asbestos Cement	248	41	1.72 out of 5	\$345	\$85,560	
Distribution Mains	P-8155	COV	Longfellow Dr.	8	Asbestos Cement	382	41	1.72 out of 5	\$345	\$131,790	
Distribution Mains	P-8156	COV	Longfellow Dr.	8	Asbestos Cement	343	41	1.72 out of 5	\$345	\$118,335	
Distribution Mains	P-8159	COV	Longfellow Dr.	8	Asbestos Cement	758	41	1.72 out of 5	\$345	\$261,510	
Distribution Mains	P-7653	COV	Loretta Ave.	8	Ductile Iron	241	13	0 out of 5	N/A	\$0	
Distribution Mains	P-7467	COV	Lorraine Ave.	6	Asbestos Cement	619	55	2.43 out of 5	\$345	\$213,555	
Distribution Mains	P-7476	COV	Lorraine Ave.	6	Asbestos Cement	110	55	2.43 out of 5	\$345	\$37,950	
Distribution Mains	P-8516	COV	Lorraine Ave.	6	Asbestos Cement	515	55	2.43 out of 5	\$345	\$177,675	
Distribution Mains	P-7512	COV	Lowell St.	6	Asbestos Cement	442	65	2.58 out of 5	\$345	\$152,490	
Distribution Mains	P-7516	COV	Lowell St.	6	Asbestos Cement	318	65	2.58 out of 5	\$345	\$109,710	
Distribution Mains	P-7669	COV	Lydia Rd.	8	Asbestos Cement	286	51	1.72 out of 5	\$345	\$98,670	
Distribution Mains	P-7672	COV	Lydia Rd.	8	Asbestos Cement	143	51	1.72 out of 5	\$345	\$49,335	
Distribution Mains	P-7676	COV	Lydia Rd.	8	Asbestos Cement	264	51	1.72 out of 5	\$345	\$91,080	
Distribution Mains	P-7677	COV	Lydia Rd.	8	Asbestos Cement	235	51	1.72 out of 5	\$345	\$81,075	
Distribution Mains	P-7680	COV	Lydia Rd.	8	Asbestos Cement	762	51	1.72 out of 5	\$345	\$262,890	
Distribution Mains	P-8973	COV	Lydia Rd.	8	Asbestos Cement	601	51	1.72 out of 5	\$345	\$207,345	
Transmission Mains	P-7061	COV	Lynn Dr.	12	PVC	303	27	0.44 out of 5	\$345	\$104,535	
Transmission Mains	P-7065	COV	Lynn Dr.	12	PVC	1,047	27	0.44 out of 5	\$345	\$361,215	
Transmission Mains	P-7077	COV	Lynn Dr.	12	PVC	294	28	0.44 out of 5	\$345	\$101,430	
Transmission Mains	P-7062	COV	Lynn Dr. Easement	12	PVC	105	27	0.44 out of 5	\$345	\$36,225	
Transmission Mains	P-8347	COV	Lynn Dr. Easement	12	PVC	379	27	0.44 out of 5	\$345	\$130,755	
Transmission Mains	P-8348	COV	Lynn Dr. Easement	12	PVC	87	27	0.44 out of 5	\$345	\$30,015	
Distribution Mains	P-7985	COV	Macarthur Blvd.	8	Asbestos Cement	851	66	1.87 out of 5	\$345	\$293,595	
Distribution Mains	P-7986	COV	Macarthur Blvd.	8	Asbestos Cement	453	66	1.87 out of 5	\$345	\$156,285	
Distribution Mains	P-7993	COV	Macarthur Blvd.	8	Asbestos Cement	268	66	1.87 out of 5	\$345	\$92,460	
Distribution Mains	P-7997	COV	Macarthur Blvd.	8	Asbestos Cement	272	66	1.87 out of 5	\$345	\$93,840	
Distribution Mains	P-7998	COV	Macarthur Blvd.	8	Asbestos Cement	148	66	1.87 out of 5	\$345	\$51,060	
Distribution Mains	P-8004	COV	Macarthur Blvd.	8	Asbestos Cement	150	66	1.87 out of 5	\$345	\$51,750	
Distribution Mains	P-8008	COV	Macarthur Blvd.	8	Asbestos Cement	1,169	66	1.87 out of 5	\$345	\$403,305	
Distribution Mains	P-9053	COV	Macarthur Blvd.	8	Asbestos Cement	264	66	1.87 out of 5	\$345	\$91,080	
Distribution Mains	P-7014	COV	Magnolia Ln.	8	Asbestos Cement	196	46	1.72 out of 5	\$345	\$67,620	
Distribution Mains	P-7016	COV	Magnolia Ln.	8	Asbestos Cement	1,096	46	1.72 out of 5	\$345	\$378,120	
Distribution Mains	P-7018	COV	Magnolia Ln.	8	Asbestos Cement	635	46	1.72 out of 5	\$345	\$219,075	
Distribution Mains	P-7020	COV	Magnolia Ln.	8	Asbestos Cement	210	46	1.72 out of 5	\$345	\$72,450	
Distribution Mains	P-7021	COV	Magnolia Ln.	8	Asbestos Cement	431	46	1.72 out of 5	\$345	\$148,695	
Distribution Mains	P-8958	COV	Magnolia Ln.	8	Asbestos Cement	54	46	1.72 out of 5	\$345	\$18,630	
Transmission Mains	P-8544	COV	Main St.	12	Cast iron	1,976	128	2.58 out of 5	\$345	\$681,720	
Distribution Mains	P-8911	COV	Main St.	8	Asbestos Cement	956	64	2.58 out of 5	\$345	\$329,820	
Distribution Mains	P-8912	COV	Main St.	8	Cast iron	251	124	2.58 out of 5	\$345	\$86,595	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-7255	COV	Main St.	8	Asbestos Cement	530	64	1.87 out of 5	\$345	\$182,850	
Distribution Mains	P-7256	COV	Main St.	8	Cast iron	248	124	1.87 out of 5	\$345	\$85,560	
Transmission Mains	P-7257	COV	Main St.	16	Cast iron	66	124	1.87 out of 5	\$345	\$22,770	
Transmission Mains	P-7258	COV	Main St.	16	Cast iron	484	124	1.87 out of 5	\$345	\$166,980	
Transmission Mains	P-7259	COV	Main St.	16	Cast iron	58	124	1.87 out of 5	\$345	\$20,010	
Transmission Mains	P-7260	COV	Main St.	16	Cast iron	596	124	1.87 out of 5	\$345	\$205,620	
Transmission Mains	P-7587	COV	Main St.	16	Cast iron	611	124	1.87 out of 5	\$345	\$210,795	
Transmission Mains	P-7844	COV	Main St.	16	Cast iron	333	124	1.87 out of 5	\$345	\$114,885	
Transmission Mains	P-7846	COV	Main St.	16	Cast iron	888	124	1.87 out of 5	\$345	\$306,360	
Transmission Mains	P-8132	COV	Main St.	12	Cast iron	280	128	1.87 out of 5	\$345	\$96,600	
Transmission Mains	P-8373	COV	Main St.	12	Cast iron	1,024	128	1.87 out of 5	\$345	\$353,280	
Transmission Mains	P-8374	COV	Main St.	12	Cast iron	406	128	1.87 out of 5	\$345	\$140,070	
Transmission Mains	P-8828	COV	Main St.	12	Cast iron	263	128	1.87 out of 5	\$345	\$90,735	
Distribution Mains	P-8910	COV	Main St.	8	Asbestos Cement	735	64	1.87 out of 5	\$345	\$253,575	
Distribution Mains	P-7632	COV	Majorie St.	6	Asbestos Cement	240	52	2.43 out of 5	\$345	\$82,800	
Distribution Mains	P-7633	COV	Majorie St.	6	Asbestos Cement	383	52	2.43 out of 5	\$345	\$132,135	
Distribution Mains	P-7937	COV	Manning Ct.	6	Asbestos Cement	369	55	2.43 out of 5	\$345	\$127,305	
Distribution Mains	P-7527	COV	Manor Dr.	6	Asbestos Cement	483	53	2.43 out of 5	\$345	\$166,635	
Distribution Mains	P-8940	COV	Manor Dr.	6	Asbestos Cement	288	53	2.43 out of 5	\$345	\$99,360	
Distribution Mains	P-7422	COV	Maple Root Rd.	6	Asbestos Cement	1,064	49	2.43 out of 5	\$345	\$367,080	
Distribution Mains	P-7268	COV	Maple St.	8	Asbestos Cement	1,078	58	1.72 out of 5	\$345	\$371,910	
Distribution Mains	P-7270	COV	Maple St.	8	Asbestos Cement	761	58	1.72 out of 5	\$345	\$262,545	
Distribution Mains	P-7271	COV	Maple St.	8	Asbestos Cement	205	58	1.72 out of 5	\$345	\$70,725	
Distribution Mains	P-7272	COV	Maple St.	8	Asbestos Cement	64	58	1.72 out of 5	\$345	\$22,080	
Distribution Mains	P-7273	COV	Maple St.	8	Asbestos Cement	195	58	1.72 out of 5	\$345	\$67,275	
Distribution Mains	P-7854	COV	Mapledale St.	4	Cast iron	317	124	3.3 out of 5	\$345	\$109,365	
Distribution Mains	P-7855	COV	Mapledale St.	4	Cast iron	399	124	3.3 out of 5	\$345	\$137,655	
Distribution Mains	P-7856	COV	Mapledale St.	4	Cast iron	82	124	3.3 out of 5	\$345	\$28,290	
Distribution Mains	P-7325	COV	Maplewood Dr.	8	Asbestos Cement	1,140	50	1.72 out of 5	\$345	\$393,300	
Distribution Mains	P-7884	COV	Marie Dr.	8	Asbestos Cement	504	45	1.72 out of 5	\$345	\$173,880	
Distribution Mains	P-7885	COV	Marie Dr.	8	Asbestos Cement	674	45	1.72 out of 5	\$345	\$232,530	
Distribution Mains	P-7886	COV	Marie Dr.	8	Asbestos Cement	207	45	1.72 out of 5	\$345	\$71,415	
Distribution Mains	P-8492	COV	Marie Dr.	8	Asbestos Cement	177	45	1.72 out of 5	\$345	\$61,065	
Transmission Mains	P-8493	COV	Marie Dr.	20	Ductile Iron	291	9	0 out of 5	N/A	\$0	
Distribution Mains	P-7492	COV	Marion Ave.	6	Asbestos Cement	205	52	2.43 out of 5	\$345	\$70,725	
Distribution Mains	P-7101	COV	Marion Dr.	8	Asbestos Cement	798	39	1.58 out of 5	\$345	\$275,310	
Distribution Mains	P-7103	COV	Marion Dr.	8	Asbestos Cement	369	39	1.58 out of 5	\$345	\$127,305	
Distribution Mains	P-8058	COV	Marshall Cir.	6	Asbestos Cement	345	66	2.58 out of 5	\$345	\$119,025	
Distribution Mains	P-8063	COV	Marshall Cir.	6	Ductile Iron	281	22	0.86 out of 5	\$345	\$96,945	
Distribution Mains	P-8064	COV	Marshall Cir.	6	Ductile Iron	444	22	0.86 out of 5	\$345	\$153,180	
Distribution Mains	P-8149	COV	Martin St.	6	Asbestos Cement	309	54	2.43 out of 5	\$345	\$106,605	
Distribution Mains	P-8150	COV	Martin St.	6	Asbestos Cement	144	54	2.43 out of 5	\$345	\$49,680	
Distribution Mains	P-8182	COV	Martin St.	6	Asbestos Cement	296	54	2.43 out of 5	\$345	\$102,120	
Distribution Mains	P-8336	COV	Mashie Cir.	6	Ductile Iron	201	25	0.86 out of 5	\$345	\$69,345	
Distribution Mains	P-7825	COV	Matteson St.	6	Asbestos Cement	711	47	2.43 out of 5	\$345	\$245,295	
Distribution Mains	P-7481	COV	Maude Ave.	6	Asbestos Cement	1,018	56	2.43 out of 5	\$345	\$351,210	
Distribution Mains	P-8517	COV	Maude Ave.	6	Asbestos Cement	140	56	2.43 out of 5	\$345	\$48,300	
Distribution Mains	P-7724	COV	Mead St.	8	Ductile Iron	237	9	0 out of 5	N/A	\$0	
Distribution Mains	P-7726	COV	Mead St.	8	Ductile Iron	263	9	0 out of 5	N/A	\$0	
Distribution Mains	P-7287	COV	Meadow Ln.	6	Asbestos Cement	385	38	2.29 out of 5	\$345	\$132,825	
Distribution Mains	P-7872	COV	Meeting St.	2	Galvanized iron	142	76	3.3 out of 5	\$345	\$48,990	
Distribution Mains	P-7868	COV	Meeting St.	6	Cast iron	237	76	2.29 out of 5	\$345	\$81,765	
Distribution Mains	P-7869	COV	Meeting St.	6	Cast iron	520	76	2.29 out of 5	\$345	\$179,400	
Distribution Mains	P-7452	COV	Melrose Dr.	8	Ductile Iron	764	21	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7282	COV	Meredith Dr.	6	Asbestos Cement	371	55	2.43 out of 5	\$345	\$127,995	
Distribution Mains	P-7286	COV	Meredith Dr.	6	Asbestos Cement	300	55	2.43 out of 5	\$345	\$103,500	
Distribution Mains	P-7291	COV	Meredith Dr.	6	Asbestos Cement	393	55	2.43 out of 5	\$345	\$135,585	
Distribution Mains	P-7292	COV	Meredith Dr.	6	Asbestos Cement	204	55	2.43 out of 5	\$345	\$70,380	
Distribution Mains	P-7200	COV	Metro Dr.	8	Asbestos Cement	647	39	1.58 out of 5	\$345	\$223,215	
Distribution Mains	P-7201	COV	Metro Dr.	8	Asbestos Cement	378	39	1.58 out of 5	\$345	\$130,410	
Distribution Mains	P-7204	COV	Metro Dr.	8	Asbestos Cement	385	39	1.58 out of 5	\$345	\$132,825	
Distribution Mains	P-7207	COV	Metro Dr.	8	Asbestos Cement	557	39	1.58 out of 5	\$345	\$192,165	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-9061	COV	Michael Ter.	1	Copper	241	127	2.73 out of 5	\$345	\$83,145	
Distribution Mains	P-9013	COV	Middle Rd.	8	Ductile Iron	89	8	0 out of 5	N/A	\$0	
Distribution Mains	P-8130	COV	Mill St.	6	Cast iron	504	114	2.58 out of 5	\$345	\$173,880	
Distribution Mains	P-8833	COV	Mill St.	6	Ductile Iron	21	5	0.71 out of 5	\$345	\$7,245	
Distribution Mains	P-8832	COV	Mill St.	8	Ductile Iron	23	5	0 out of 5	N/A	\$0	
Transmission Mains	P-7456	COV	Mishnock Rd.	12	Ductile Iron	534	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8202	COV	Mishnock Rd.	8	Ductile Iron	167	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8262	COV	Mishnock Rd.	8	Ductile Iron	104	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8263	COV	Mishnock Rd.	12	Ductile Iron	636	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8265	COV	Mishnock Rd.	12	Ductile Iron	79	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7406	COV	Mishnock WTP	16	Ductile Iron	250	1	0 out of 5	N/A	\$0	
Transmission Mains	P-7407	COV	Mishnock WTP	16	Ductile Iron	53	1	0 out of 5	N/A	\$0	
Transmission Mains	P-7408	COV	Mishnock WTP	16	Ductile Iron	250	1	0 out of 5	N/A	\$0	
Transmission Mains	P-7409	COV	Mishnock WTP	16	Ductile Iron	250	1	0 out of 5	N/A	\$0	
Transmission Mains	P-7410	COV	Mishnock WTP	16	Ductile Iron	122	1	0 out of 5	N/A	\$0	
Transmission Mains	P-7412	COV	Mishnock WTP	16	Ductile Iron	250	1	0 out of 5	N/A	\$0	
Transmission Mains	P-7413	COV	Mishnock WTP	16	Ductile Iron	250	1	0 out of 5	N/A	\$0	
Transmission Mains	P-7415	COV	Mishnock WTP	16	Ductile Iron	47	1	0 out of 5	N/A	\$0	
Transmission Mains	P-7416	COV	Mishnock WTP	16	Ductile Iron	100	1	0 out of 5	N/A	\$0	
Transmission Mains	P-8257	COV	Mishnock WTP	16	Ductile Iron	250	1	0 out of 5	N/A	\$0	
Transmission Mains	P-8258	COV	Mishnock WTP	16	Ductile Iron	250	1	0 out of 5	N/A	\$0	
Transmission Mains	P-8963	COV	Mishnock WTP	16	Ductile Iron	250	1	0 out of 5	N/A	\$0	
Distribution Mains	P-7727	COV	Mohawk St.	8	Ductile Iron	325	9	0 out of 5	N/A	\$0	
Distribution Mains	P-7734	COV	Mohawk St.	8	Ductile Iron	92	9	0 out of 5	N/A	\$0	
Distribution Mains	P-7735	COV	Mohawk St.	8	Ductile Iron	702	9	0 out of 5	N/A	\$0	
Distribution Mains	P-8766	COV	Mohawk St.	8	Ductile Iron	519	9	0 out of 5	N/A	\$0	
Distribution Mains	P-8768	COV	Mohawk St.	8	Ductile Iron	244	9	0 out of 5	N/A	\$0	
Distribution Mains	P-9014	COV	Mohawk St.	8	Ductile Iron	92	8	0 out of 5	N/A	\$0	
Distribution Mains	P-7167	COV	Monroe Dr.	8	Asbestos Cement	435	37	2.29 out of 5	\$345	\$150,075	
Distribution Mains	P-7166	COV	Monroe Dr.	8	Asbestos Cement	554	37	1.58 out of 5	\$345	\$191,130	
Distribution Mains	P-7168	COV	Monroe Dr.	8	Asbestos Cement	842	29	1.58 out of 5	\$345	\$290,490	
Distribution Mains	P-7169	COV	Monroe Dr.	8	Ductile Iron	357	15	0 out of 5	N/A	\$0	
Distribution Mains	P-7170	COV	Monroe Dr.	8	Ductile Iron	596	15	0 out of 5	N/A	\$0	
Distribution Mains	P-7576	COV	Montana Ave.	3	Galvanized iron	229	81	4.15 out of 5	\$345	\$79,005	
Distribution Mains	P-7574	COV	Montana Ave.	3	Galvanized iron	381	81	3.44 out of 5	\$345	\$131,445	
Distribution Mains	P-7575	COV	Montana Ave.	3	Galvanized iron	235	81	3.44 out of 5	\$345	\$81,075	
Distribution Mains	P-7577	COV	Montana Ave.	3	Galvanized iron	231	81	3.44 out of 5	\$345	\$79,695	
Distribution Mains	P-7979	COV	Morin Ave.	1	Copper	406	49	2.29 out of 5	\$345	\$140,070	
Distribution Mains	P-7613	COV	Morris St.	6	Asbestos Cement	375	55	2.43 out of 5	\$345	\$129,375	
Distribution Mains	P-7616	COV	Morris St.	6	Asbestos Cement	213	55	2.43 out of 5	\$345	\$73,485	
Distribution Mains	P-7346	COV	Moss Ln.	8	Ductile Iron	912	19	0 out of 5	N/A	\$0	
Distribution Mains	P-8413	COV	Mountain Laurel Dr.	8	Ductile Iron	565	9	0 out of 5	N/A	\$0	
Distribution Mains	P-8415	COV	Mountain Laurel Dr.	8	Ductile Iron	325	9	0 out of 5	N/A	\$0	
Distribution Mains	P-7920	COV	Mulberry Ct.	8	PVC	225	34	0.44 out of 5	\$345	\$77,625	
Distribution Mains	P-8084	COV	Mumford St.	8	Ductile Iron	376	13	0 out of 5	N/A	\$0	
Distribution Mains	P-8085	COV	Mumford St.	8	Ductile Iron	390	13	0 out of 5	N/A	\$0	
Distribution Mains	P-8086	COV	Mumford St.	8	Ductile Iron	613	13	0 out of 5	N/A	\$0	
Distribution Mains	P-8088	COV	Mumford St.	8	Ductile Iron	230	13	0 out of 5	N/A	\$0	
Distribution Mains	P-8089	COV	Mumford St.	8	Ductile Iron	286	13	0 out of 5	N/A	\$0	
Distribution Mains	P-8837	COV	Mumford St.	8	Ductile Iron	23	13	0 out of 5	N/A	\$0	
Distribution Mains	P-9035	COV	Murray St.	6	Ductile Iron	489	22	0.86 out of 5	\$345	\$168,705	
Distribution Mains	P-7679	COV	Myra Rd.	6	Asbestos Cement	237	51	2.43 out of 5	\$345	\$81,765	
Distribution Mains	P-7683	COV	Myra Rd.	6	Asbestos Cement	630	51	2.43 out of 5	\$345	\$217,350	
Distribution Mains	P-7684	COV	Myra Rd.	6	Asbestos Cement	129	51	2.43 out of 5	\$345	\$44,505	
Distribution Mains	P-7954	COV	Nancy Ct.	6	Asbestos Cement	445	51	2.43 out of 5	\$345	\$153,525	
Distribution Mains	P-7636	COV	Nancy St.	6	Asbestos Cement	203	54	2.43 out of 5	\$345	\$70,035	
Transmission Mains	P-8151	COV	New London Tpk.	12	Asbestos Cement	118	54	2.43 out of 5	\$345	\$40,710	
Transmission Mains	P-8136	COV	New London Tpk.	12	Asbestos Cement	297	54	1.72 out of 5	\$345	\$102,465	
Transmission Mains	P-8137	COV	New London Tpk.	12	Asbestos Cement	260	54	1.72 out of 5	\$345	\$89,700	
Transmission Mains	P-8145	COV	New London Tpk.	12	Asbestos Cement	268	54	1.72 out of 5	\$345	\$92,460	
Transmission Mains	P-8162	COV	New London Tpk.	12	Asbestos Cement	383	54	1.72 out of 5	\$345	\$132,135	
Transmission Mains	P-8166	COV	New London Tpk.	12	Asbestos Cement	769	54	1.72 out of 5	\$345	\$265,305	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-8168	COV	New London Tpk.	12	Asbestos Cement	160	54	1.72 out of 5	\$345	\$55,200	
Distribution Mains	P-8169	COV	New London Tpk.	8	Asbestos Cement	409	45	1.72 out of 5	\$345	\$141,105	
Distribution Mains	P-8170	COV	New London Tpk.	8	Asbestos Cement	241	45	1.72 out of 5	\$345	\$83,145	
Transmission Mains	P-8316	COV	New London Tpk.	12	PVC	147	26	0.44 out of 5	\$345	\$50,715	
Transmission Mains	P-8318	COV	New London Tpk.	12	PVC	635	26	0.44 out of 5	\$345	\$219,075	
Transmission Mains	P-8175	COV	New London Tpk.	16	Ductile Iron	418	19	0 out of 5	N/A	\$0	
Transmission Mains	P-8317	COV	New London Tpk.	12	Ductile Iron	567	19	0 out of 5	N/A	\$0	
Transmission Mains	P-8424	COV	New London Tpk.	16	Ductile Iron	301	19	0 out of 5	N/A	\$0	
Distribution Mains	P-8913	COV	Newell Ct.	8	Cast iron	393	124	1.87 out of 5	\$345	\$135,585	
Distribution Mains	P-8341	COV	Niblick Cir.	6	Ductile Iron	634	25	0.86 out of 5	\$345	\$218,730	
Distribution Mains	P-7460	COV	Noella Ave.	6	Asbestos Cement	224	54	2.43 out of 5	\$345	\$77,280	
Distribution Mains	P-7462	COV	Noella Ave.	6	Asbestos Cement	136	54	2.43 out of 5	\$345	\$46,920	
Distribution Mains	P-7465	COV	Noella Ave.	6	Asbestos Cement	334	54	2.43 out of 5	\$345	\$115,230	
Distribution Mains	P-7471	COV	Noella Ave.	6	Asbestos Cement	367	51	2.43 out of 5	\$345	\$126,615	
Distribution Mains	P-7472	COV	Noella Ave.	6	Asbestos Cement	360	52	2.43 out of 5	\$345	\$124,200	
Transmission Mains	P-7417	COV	Nooseneck Hill Rd.	12	Asbestos Cement	710	49	1.72 out of 5	\$345	\$244,950	
Transmission Mains	P-7419	COV	Nooseneck Hill Rd.	12	Asbestos Cement	661	49	1.72 out of 5	\$345	\$228,045	
Transmission Mains	P-7952	COV	Nooseneck Hill Rd.	12	Asbestos Cement	739	49	1.72 out of 5	\$345	\$254,955	
Transmission Mains	P-8215	COV	Nooseneck Hill Rd.	12	Asbestos Cement	1,514	49	1.72 out of 5	\$345	\$522,330	
Transmission Mains	P-8226	COV	Nooseneck Hill Rd.	12	Asbestos Cement	1,827	49	1.72 out of 5	\$345	\$630,315	
Transmission Mains	P-8357	COV	Nooseneck Hill Rd.	12	Asbestos Cement	112	49	1.72 out of 5	\$345	\$38,640	
Transmission Mains	P-8358	COV	Nooseneck Hill Rd.	12	Asbestos Cement	319	49	1.72 out of 5	\$345	\$110,055	
Transmission Mains	P-8750	COV	Nooseneck Hill Rd.	12	Asbestos Cement	1,684	49	1.72 out of 5	\$345	\$580,980	
Transmission Mains	P-8751	COV	Nooseneck Hill Rd.	12	Asbestos Cement	837	49	1.72 out of 5	\$345	\$288,765	
Transmission Mains	P-8760	COV	Nooseneck Hill Rd.	12	Asbestos Cement	927	49	1.72 out of 5	\$345	\$319,815	
Transmission Mains	P-8953	COV	Nooseneck Hill Rd.	12	Asbestos Cement	32	49	1.72 out of 5	\$345	\$11,040	
Distribution Mains	P-8954	COV	Nooseneck Hill Rd.	8	Asbestos Cement	30	49	1.72 out of 5	\$345	\$10,350	
Transmission Mains	P-7000	COV	Nooseneck Hill Rd.	12	Ductile Iron	441	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7159	COV	Nooseneck Hill Rd.	12	Ductile Iron	2,321	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8755	COV	Nooseneck Hill Rd.	12	Ductile Iron	3,186	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8759	COV	Nooseneck Hill Rd.	12	Ductile Iron	209	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7426	COV	Nooseneck Hill Rd.	12	Ductile Iron	573	14	0 out of 5	N/A	\$0	
Transmission Mains	P-8959	COV	Nooseneck Hill Rd.	16	Ductile Iron	504	9	0 out of 5	N/A	\$0	
Distribution Mains	P-7709	COV	North Glen Dr.	6	Asbestos Cement	676	55	2.43 out of 5	\$345	\$233,220	
Distribution Mains	P-8013	COV	North St.	6	Cast iron	426	86	2.43 out of 5	\$345	\$146,970	
Distribution Mains	P-8524	COV	Northup Plat Rd.	8	Ductile Iron	2,410	9	0 out of 5	N/A	\$0	
Distribution Mains	P-8082	COV	Notre Dame St.	1.5	Copper	396	77	2.44 out of 5	\$345	\$136,620	
Distribution Mains	P-8889	COV	Nutmeg Cir.	8	Ductile Iron	204	16	0 out of 5	N/A	\$0	
Distribution Mains	P-7593	COV	Oak Rd.	8	Ductile Iron	250	14	0 out of 5	N/A	\$0	
Distribution Mains	P-7598	COV	Oak Rd.	8	Ductile Iron	338	14	0 out of 5	N/A	\$0	
Distribution Mains	P-8860	COV	Oak St.	0.8	Copper	280	58	2.29 out of 5	\$345	\$96,600	
Distribution Mains	P-7889	COV	Old Hope Rd.	8	Ductile Iron	599	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7221	COV	Old Main St.	8	Asbestos Cement	551	64	1.87 out of 5	\$345	\$190,095	
Distribution Mains	P-7223	COV	Old Main St.	8	Asbestos Cement	508	64	1.87 out of 5	\$345	\$175,260	
Distribution Mains	P-8274	COV	Old Main St.	8	Asbestos Cement	569	43	1.72 out of 5	\$345	\$196,305	
Distribution Mains	P-8275	COV	Old Main St.	8	Asbestos Cement	208	43	1.72 out of 5	\$345	\$71,760	
Distribution Mains	P-8902	COV	Old Main St.	8	Ductile Iron	34	3	0 out of 5	N/A	\$0	
Distribution Mains	P-8903	COV	Old Main St.	8	Ductile Iron	38	3	0 out of 5	N/A	\$0	
Distribution Mains	P-7446	COV	Old Mishnock Tr.	8	Ductile Iron	1,021	21	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7447	COV	Old Mishnock Tr.	8	Ductile Iron	498	21	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8964	COV	Old Mishnock Tr.	8	Ductile Iron	26	21	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7756	COV	Old North Rd.	12	PVC	723	38	0.44 out of 5	\$345	\$249,435	
Transmission Mains	P-8143	COV	Old North Rd.	12	Ductile Iron	518	6	0 out of 5	N/A	\$0	
Transmission Mains	P-8144	COV	Old North Rd.	12	Ductile Iron	665	6	0 out of 5	N/A	\$0	
Transmission Mains	P-8286	COV	Old North Rd.	12	Ductile Iron	171	12	0 out of 5	N/A	\$0	
Transmission Mains	P-8713	COV	Old North Rd.	12	Ductile Iron	1,388	6	0 out of 5	N/A	\$0	
Transmission Mains	P-8714	COV	Old North Rd.	12	Ductile Iron	764	6	0 out of 5	N/A	\$0	
Transmission Mains	P-9021	COV	Old North Rd.	12	Ductile Iron	157	12	0 out of 5	N/A	\$0	
Transmission Mains	P-9022	COV	Old North Rd.	12	Ductile Iron	193	12	0 out of 5	N/A	\$0	
Transmission Mains	P-9024	COV	Old North Rd.	12	Ductile Iron	459	6	0 out of 5	N/A	\$0	
Distribution Mains	P-7115	COV	Orchard Tr.	8	Ductile Iron	379	22	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7116	COV	Orchard Tr.	8	Ductile Iron	484	22	0.15 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-8978	COV	Osceola Ave.	6	Asbestos Cement	235	60	2.58 out of 5	\$345	\$81,075	
Distribution Mains	P-8983	COV	Osceola Ave.	6	Asbestos Cement	205	48	2.43 out of 5	\$345	\$70,725	
Distribution Mains	P-8981	COV	Osceola Ave.	2	PVC	323	25	1.87 out of 5	\$345	\$111,435	
Distribution Mains	P-7094	COV	Osprey Dr.	8	PVC	1,103	33	0.44 out of 5	\$345	\$380,535	
Distribution Mains	P-7097	COV	Osprey Dr.	8	PVC	129	29	0.44 out of 5	\$345	\$44,505	
Distribution Mains	P-7592	COV	Overview Dr.	6	Asbestos Cement	95	65	2.58 out of 5	\$345	\$32,775	
Distribution Mains	P-9000	COV	Overview Dr.	1.5	Copper	474	74	2.44 out of 5	\$345	\$163,530	
Distribution Mains	P-7591	COV	Overview Dr.	6	Ductile Iron	227	14	1.42 out of 5	\$345	\$78,315	
Distribution Mains	P-7086	COV	Pamela Ct.	8	Ductile Iron	111	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8051	COV	Park Ave.	6	Asbestos Cement	271	52	2.43 out of 5	\$345	\$93,495	
Distribution Mains	P-8053	COV	Park Ave.	6	Asbestos Cement	125	52	2.43 out of 5	\$345	\$43,125	
Distribution Mains	P-8054	COV	Park Ave.	6	Asbestos Cement	276	52	2.43 out of 5	\$345	\$95,220	
Distribution Mains	P-7263	COV	Park St.	6	Cast iron	274	81	2.43 out of 5	\$345	\$94,530	
Distribution Mains	P-7539	COV	Parker St.	8	Ductile Iron	583	13	0 out of 5	N/A	\$0	
Distribution Mains	P-7956	COV	Partridge Dr.	8	Ductile Iron	502	19	0 out of 5	N/A	\$0	
Distribution Mains	P-7958	COV	Partridge Dr.	8	Ductile Iron	373	19	0 out of 5	N/A	\$0	
Distribution Mains	P-7747	COV	Patience Ln.	8	Ductile Iron	330	22	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7988	COV	Patton St.	6	Asbestos Cement	659	65	3.29 out of 5	\$345	\$227,355	
Distribution Mains	P-7246	COV	Patty St.	8	Asbestos Cement	425	48	2.43 out of 5	\$345	\$146,625	
Distribution Mains	P-8106	COV	Paulette Dr.	6	Asbestos Cement	555	54	2.43 out of 5	\$345	\$191,475	
Distribution Mains	P-8853	COV	Paulette Dr.	8	Ductile Iron	34	10	0 out of 5	N/A	\$0	
Distribution Mains	P-7032	COV	Peachtree Ln.	6	Asbestos Cement	946	39	2.29 out of 5	\$345	\$326,370	
Distribution Mains	P-8956	COV	Peachtree Ln.	6	Asbestos Cement	465	39	2.29 out of 5	\$345	\$160,425	
Distribution Mains	P-8002	COV	Peacock Dr.	8	Ductile Iron	628	19	0 out of 5	N/A	\$0	
Distribution Mains	P-8915	COV	Pearl St.	2	Galvanized iron	307	82	3.44 out of 5	\$345	\$105,915	
Distribution Mains	P-7778	COV	Pembroke Ln.	6	Asbestos Cement	655	48	3.14 out of 5	\$345	\$225,975	
Distribution Mains	P-7772	COV	Pembroke Ln.	6	Asbestos Cement	286	48	2.43 out of 5	\$345	\$98,670	
Distribution Mains	P-7775	COV	Pembroke Ln.	6	Asbestos Cement	263	48	2.43 out of 5	\$345	\$90,735	
Distribution Mains	P-7782	COV	Pembroke Ln.	6	Asbestos Cement	300	48	2.43 out of 5	\$345	\$103,500	
Distribution Mains	P-7786	COV	Pembroke Ln.	6	Asbestos Cement	864	48	2.43 out of 5	\$345	\$298,080	
Distribution Mains	P-7788	COV	Pembroke Ln.	6	Asbestos Cement	570	48	2.43 out of 5	\$345	\$196,650	
Distribution Mains	P-7790	COV	Pembroke Ln.	6	Asbestos Cement	440	48	2.43 out of 5	\$345	\$151,800	
Distribution Mains	P-7053	COV	Peninsula Ct.	8	Ductile Iron	510	8	0 out of 5	N/A	\$0	
Distribution Mains	P-7338	COV	Peppermint Ct.	8	Ductile Iron	178	16	0 out of 5	N/A	\$0	
Distribution Mains	P-7779	COV	Pettine St.	6	Asbestos Cement	240	55	2.43 out of 5	\$345	\$82,800	
Distribution Mains	P-7785	COV	Pettine St.	6	Asbestos Cement	667	55	2.43 out of 5	\$345	\$230,115	
Distribution Mains	P-7789	COV	Pettine St.	6	Asbestos Cement	370	55	2.43 out of 5	\$345	\$127,650	
Distribution Mains	P-8041	COV	Phillip St.	8	Ductile Iron	972	6	0 out of 5	N/A	\$0	
Distribution Mains	P-8042	COV	Phillip St.	8	Ductile Iron	195	4	0 out of 5	N/A	\$0	
Distribution Mains	P-9064	COV	Phillip St.	8	Ductile Iron	105	6	0 out of 5	N/A	\$0	
Distribution Mains	P-8104	COV	Pierce St.	4	Cast iron	134	127	3.3 out of 5	\$345	\$46,230	
Distribution Mains	P-8862	COV	Pierce St.	4	Cast iron	211	127	3.3 out of 5	\$345	\$72,795	
Distribution Mains	P-8866	COV	Pierce St.	4	Cast iron	190	127	3.3 out of 5	\$345	\$65,550	
Distribution Mains	P-8867	COV	Pierce St.	4	Cast iron	188	127	3.3 out of 5	\$345	\$64,860	
Distribution Mains	P-8861	COV	Pierce St.	4	Cast iron	234	66	3.01 out of 5	\$345	\$80,730	
Distribution Mains	P-7812	COV	Pilgrim Ave.	6	Asbestos Cement	972	65	2.58 out of 5	\$345	\$335,340	
Distribution Mains	P-7861	COV	Pilgrim Ave.	6	Asbestos Cement	777	65	2.58 out of 5	\$345	\$268,065	
Distribution Mains	P-7862	COV	Pilgrim Ave.	6	Asbestos Cement	167	65	2.58 out of 5	\$345	\$57,615	
Distribution Mains	P-7808	COV	Pilgrim Ave.	8	Asbestos Cement	889	56	1.72 out of 5	\$345	\$306,705	
Distribution Mains	P-7810	COV	Pilgrim Ave.	8	Asbestos Cement	339	56	1.72 out of 5	\$345	\$116,955	
Distribution Mains	P-7818	COV	Pilgrim Ave.	8	Asbestos Cement	262	56	1.72 out of 5	\$345	\$90,390	
Distribution Mains	P-7823	COV	Pilgrim Ave.	8	Asbestos Cement	280	56	1.72 out of 5	\$345	\$96,600	
Distribution Mains	P-7824	COV	Pilgrim Ave.	8	Asbestos Cement	371	56	1.72 out of 5	\$345	\$127,995	
Distribution Mains	P-7922	COV	Pin Oak Ct.	8	PVC	225	34	0.44 out of 5	\$345	\$77,625	
Distribution Mains	P-7594	COV	Pine Ave.	8	Ductile Iron	173	14	0 out of 5	N/A	\$0	
Distribution Mains	P-7595	COV	Pine Ave.	8	Ductile Iron	721	14	0 out of 5	N/A	\$0	
Distribution Mains	P-7454	COV	Pine Hill Rd.	8	Ductile Iron	106	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7455	COV	Pine Hill Rd.	8	Ductile Iron	197	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7570	COV	Pinehurst St.	6	Asbestos Cement	407	60	2.58 out of 5	\$345	\$140,415	
Distribution Mains	P-7046	COV	Plum Tree Ln.	8	Asbestos Cement	882	41	1.72 out of 5	\$345	\$304,290	
Distribution Mains	P-7392	COV	Pond View Dr.	6	Asbestos Cement	240	48	2.43 out of 5	\$345	\$82,800	
Distribution Mains	P-7393	COV	Pond View Dr.	6	Asbestos Cement	380	48	2.43 out of 5	\$345	\$131,100	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-7394	COV	Pond View Dr.	6	Asbestos Cement	751	48	2.43 out of 5	\$345	\$259,095	
Distribution Mains	P-7918	COV	Poplar Ct.	8	PVC	235	34	0.44 out of 5	\$345	\$81,075	
Distribution Mains	P-7543	COV	Potter St.	6	Asbestos Cement	250	64	2.58 out of 5	\$345	\$86,250	
Distribution Mains	P-7544	COV	Potter St.	6	Asbestos Cement	172	64	2.58 out of 5	\$345	\$59,340	
Distribution Mains	P-8941	COV	Potter St.	6	Asbestos Cement	138	64	2.58 out of 5	\$345	\$47,610	
Distribution Mains	P-8831	COV	Potter St.	6	Ductile Iron	31	20	0.86 out of 5	\$345	\$10,695	
Transmission Mains	P-8128	COV	Potter St.	12	Ductile Iron	317	7	0 out of 5	N/A	\$0	
Transmission Mains	P-8753	COV	Potter St.	12	Ductile Iron	690	7	0 out of 5	N/A	\$0	
Distribution Mains	P-8305	COV	Powhatan Ave.	6	Asbestos Cement	389	48	2.43 out of 5	\$345	\$134,205	
Distribution Mains	P-8938	COV	Prince St.	2	Galvanized iron	247	124	3.59 out of 5	\$345	\$85,215	
Distribution Mains	P-8939	COV	Prince St.	1	Copper	86	57	2.29 out of 5	\$345	\$29,670	
Distribution Mains	P-8937	COV	Princess St.	2	Galvanized iron	318	56	3.15 out of 5	\$345	\$109,710	
Distribution Mains	P-7776	COV	Princeton Ave.	8	Asbestos Cement	606	54	1.72 out of 5	\$345	\$209,070	
Distribution Mains	P-7793	COV	Princeton Ave.	8	Asbestos Cement	835	54	1.72 out of 5	\$345	\$288,075	
Distribution Mains	P-7794	COV	Princeton Ave.	8	Asbestos Cement	486	54	1.72 out of 5	\$345	\$167,670	
Distribution Mains	P-7797	COV	Princeton Ave.	8	Asbestos Cement	245	54	1.72 out of 5	\$345	\$84,525	
Distribution Mains	P-7801	COV	Princeton Ave.	8	Asbestos Cement	481	54	1.72 out of 5	\$345	\$165,945	
Distribution Mains	P-7802	COV	Princeton Ave.	8	Asbestos Cement	273	54	1.72 out of 5	\$345	\$94,185	
Distribution Mains	P-7803	COV	Princeton Ave.	8	Asbestos Cement	243	54	1.72 out of 5	\$345	\$83,835	
Distribution Mains	P-7805	COV	Princeton Ave.	8	Asbestos Cement	370	54	1.72 out of 5	\$345	\$127,650	
Distribution Mains	P-7807	COV	Princeton Ave.	8	Asbestos Cement	261	54	1.72 out of 5	\$345	\$90,045	
Distribution Mains	P-9028	COV	Princeton Ave.	8	Asbestos Cement	257	54	1.72 out of 5	\$345	\$88,665	
Distribution Mains	P-7545	COV	Prospect Ave.	6	Asbestos Cement	347	62	2.58 out of 5	\$345	\$119,715	
Distribution Mains	P-8319	COV	Prospect Ave.	6	Asbestos Cement	152	62	2.58 out of 5	\$345	\$52,440	
Transmission Mains	P-8012	COV	Pulaski St.	12	Ductile Iron	361	11	0 out of 5	N/A	\$0	
Transmission Mains	P-8014	COV	Pulaski St.	12	Ductile Iron	177	11	0 out of 5	N/A	\$0	
Transmission Mains	P-8017	COV	Pulaski St.	12	Ductile Iron	531	11	0 out of 5	N/A	\$0	
Transmission Mains	P-8019	COV	Pulaski St.	12	Ductile Iron	626	11	0 out of 5	N/A	\$0	
Distribution Mains	P-7400	COV	Puritan Ave.	6	Asbestos Cement	1,026	52	2.43 out of 5	\$345	\$353,970	
Distribution Mains	P-8976	COV	Quiet Ave.	6	Ductile Iron	130	26	0.86 out of 5	\$345	\$44,850	
Distribution Mains	P-7666	COV	Quiet Ave.	8	Ductile Iron	218	8	0 out of 5	N/A	\$0	
Distribution Mains	P-8972	COV	Quiet Ave.	8	Ductile Iron	29	8	0 out of 5	N/A	\$0	
Distribution Mains	P-9069	COV	Rainville Ave.	1	Copper	298	61	2.44 out of 5	\$345	\$102,810	
Distribution Mains	P-7552	COV	Rathbun St.	2	Copper	864	73	2.44 out of 5	\$345	\$298,080	
Distribution Mains	P-7742	COV	Rawlinson Dr.	6	Asbestos Cement	1,357	55	2.43 out of 5	\$345	\$468,165	
Distribution Mains	P-7736	COV	Rawlinson Dr.	8	Ductile Iron	202	9	0 out of 5	N/A	\$0	
Distribution Mains	P-7071	COV	Ray St.	6	PVC	644	33	1.15 out of 5	\$345	\$222,180	
Distribution Mains	P-8055	COV	Ray St.	6	PVC	347	33	1.15 out of 5	\$345	\$119,715	
Distribution Mains	P-8846	COV	Ray St.	6	PVC	51	33	1.15 out of 5	\$345	\$17,595	
Distribution Mains	P-8003	COV	Raymond St.	6	Asbestos Cement	263	65	3.29 out of 5	\$345	\$90,735	
Distribution Mains	P-7995	COV	Raymond St.	6	Asbestos Cement	249	65	2.58 out of 5	\$345	\$85,905	
Distribution Mains	P-8006	COV	Raymond St.	6	Asbestos Cement	257	65	2.58 out of 5	\$345	\$88,665	
Distribution Mains	P-8023	COV	Read Ave.	6	Cast iron	357	127	2.58 out of 5	\$345	\$123,165	
Distribution Mains	P-8025	COV	Read Ave.	6	Cast iron	243	127	2.58 out of 5	\$345	\$83,835	
Distribution Mains	P-8027	COV	Read Ave.	6	Cast iron	202	127	2.58 out of 5	\$345	\$69,690	
Distribution Mains	P-8029	COV	Read Ave.	6	Cast iron	234	127	2.58 out of 5	\$345	\$80,730	
Distribution Mains	P-8031	COV	Read Ave.	6	Cast iron	171	127	2.58 out of 5	\$345	\$58,995	
Distribution Mains	P-8032	COV	Read Ave.	6	Cast iron	66	127	2.58 out of 5	\$345	\$22,770	
Distribution Mains	P-8036	COV	Read Ave.	6	Cast iron	154	127	2.58 out of 5	\$345	\$53,130	
Distribution Mains	P-8038	COV	Read Ave.	6	Cast iron	378	127	2.58 out of 5	\$345	\$130,410	
Distribution Mains	P-8039	COV	Read Ave.	6	Cast iron	950	127	2.58 out of 5	\$345	\$327,750	
Distribution Mains	P-8043	COV	Read Ave.	6	Cast iron	1,736	127	2.58 out of 5	\$345	\$598,920	
Distribution Mains	P-8848	COV	Read Ave.	6	Asbestos Cement	211	70	2.58 out of 5	\$345	\$72,795	
Distribution Mains	P-9054	COV	Read Ave.	6	Cast iron	317	127	2.58 out of 5	\$345	\$109,365	
Distribution Mains	P-9055	COV	Read Ave.	6	Cast iron	359	127	2.58 out of 5	\$345	\$123,855	
Distribution Mains	P-9060	COV	Read Ave.	6	Cast iron	71	127	2.58 out of 5	\$345	\$24,495	
Distribution Mains	P-9062	COV	Read Ave.	6	Cast iron	66	127	2.58 out of 5	\$345	\$22,770	
Distribution Mains	P-9066	COV	Read Ave.	6	Cast iron	228	127	2.58 out of 5	\$345	\$78,660	
Distribution Mains	P-9068	COV	Read Ave.	6	Cast iron	109	127	2.58 out of 5	\$345	\$37,605	
Transmission Mains	P-8045	COV	Read Ave.	16	Asbestos Cement	381	70	1.87 out of 5	\$345	\$131,445	
Transmission Mains	P-8047	COV	Read Ave.	16	Asbestos Cement	453	70	1.87 out of 5	\$345	\$156,285	
Transmission Mains	P-8056	COV	Read Ave.	16	Asbestos Cement	98	70	1.87 out of 5	\$345	\$33,810	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-8847	COV	Read Ave.	16	Asbestos Cement	207	70	1.87 out of 5	\$345	\$71,415	
Transmission Mains	P-7180	COV	Read School House Rd.	20	Ductile Iron	173	3	0 out of 5	N/A	\$0	
Transmission Mains	P-7181	COV	Read School House Rd.	20	Ductile Iron	2,073	3	0 out of 5	N/A	\$0	
Transmission Mains	P-8785	COV	Read School House Rd.	20	Ductile Iron	3,371	3	0 out of 5	N/A	\$0	
Transmission Mains	P-8786	COV	Read School House Rd. Tank	20	Ductile Iron	362	7	0 out of 5	N/A	\$0	
Distribution Mains	P-8107	COV	Rebecca St.	6	Asbestos Cement	1,064	53	2.43 out of 5	\$345	\$367,080	
Distribution Mains	P-8855	COV	Rebecca St.	6	Ductile Iron	27	10	0.71 out of 5	\$345	\$9,315	
Distribution Mains	P-8854	COV	Rebecca St.	8	Ductile Iron	28	10	0 out of 5	N/A	\$0	
Distribution Mains	P-7351	COV	Red Barn Ct.	8	Ductile Iron	441	19	0 out of 5	N/A	\$0	
Distribution Mains	P-7352	COV	Red Barn Ct.	8	Ductile Iron	138	19	0 out of 5	N/A	\$0	
Distribution Mains	P-7089	COV	Red Cedar Dr.	6	Asbestos Cement	247	38	2.29 out of 5	\$345	\$85,215	
Distribution Mains	P-8952	COV	Red Cedar Dr. Easement	6	Ductile Iron	82	24	0.86 out of 5	\$345	\$28,290	
Distribution Mains	P-8363	COV	Red Cedar Dr. Easement	8	Ductile Iron	375	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7044	COV	Red Maple Rd.	8	Asbestos Cement	540	52	1.72 out of 5	\$345	\$186,300	
Distribution Mains	P-7045	COV	Red Maple Rd.	8	Asbestos Cement	286	52	1.72 out of 5	\$345	\$98,670	
Distribution Mains	P-7893	COV	Red Oak Dr.	8	Asbestos Cement	404	34	1.58 out of 5	\$345	\$139,380	
Distribution Mains	P-7895	COV	Red Oak Dr.	8	Asbestos Cement	351	34	1.58 out of 5	\$345	\$121,095	
Distribution Mains	P-7898	COV	Red Oak Dr.	8	Asbestos Cement	367	34	1.58 out of 5	\$345	\$126,615	
Distribution Mains	P-7901	COV	Red Oak Dr.	8	Asbestos Cement	206	34	1.58 out of 5	\$345	\$71,070	
Distribution Mains	P-7902	COV	Red Oak Dr.	8	Asbestos Cement	218	34	1.58 out of 5	\$345	\$75,210	
Distribution Mains	P-7903	COV	Red Oak Dr.	8	Asbestos Cement	772	34	1.58 out of 5	\$345	\$266,340	
Distribution Mains	P-8875	COV	Red Oak Dr.	8	Asbestos Cement	661	34	1.58 out of 5	\$345	\$228,045	
Distribution Mains	P-7819	COV	Reddington St.	6	Asbestos Cement	951	39	2.29 out of 5	\$345	\$328,095	
Distribution Mains	P-8947	COV	Regal Wood Dr.	8	Ductile Iron	39	22	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7117	COV	Regal Wood Dr.	8	Ductile Iron	410	15	0 out of 5	N/A	\$0	
Distribution Mains	P-7125	COV	Regal Wood Dr.	8	Ductile Iron	392	13	0 out of 5	N/A	\$0	
Distribution Mains	P-7126	COV	Regal Wood Dr.	8	Ductile Iron	789	15	0 out of 5	N/A	\$0	
Distribution Mains	P-8365	COV	Regal Wood Dr.	8	Ductile Iron	150	15	0 out of 5	N/A	\$0	
Distribution Mains	P-8917	COV	Regent St.	6	Ductile Iron	662	24	0.86 out of 5	\$345	\$228,390	
Distribution Mains	P-8970	COV	Regis St.	6	Asbestos Cement	143	58	2.43 out of 5	\$345	\$49,335	
Distribution Mains	P-8146	COV	Rejane St.	6	Asbestos Cement	590	63	2.58 out of 5	\$345	\$203,550	
Distribution Mains	P-8147	COV	Rejane St.	6	Asbestos Cement	170	63	2.58 out of 5	\$345	\$58,650	
Distribution Mains	P-7345	COV	Remington Farm Dr.	8	Ductile Iron	1,642	19	0 out of 5	N/A	\$0	
Distribution Mains	P-7347	COV	Remington Farm Dr.	8	Ductile Iron	1,249	19	0 out of 5	N/A	\$0	
Distribution Mains	P-7348	COV	Remington Farm Dr.	8	Ductile Iron	139	19	0 out of 5	N/A	\$0	
Distribution Mains	P-7686	COV	Reno Ct.	6	Asbestos Cement	208	45	2.43 out of 5	\$345	\$71,760	
Distribution Mains	P-7156	COV	Reservoir Rd.	8	Asbestos Cement	318	49	1.72 out of 5	\$345	\$109,710	
Distribution Mains	P-7158	COV	Reservoir Rd.	8	Asbestos Cement	519	49	1.72 out of 5	\$345	\$179,055	
Distribution Mains	P-8349	COV	Reservoir Rd.	8	Asbestos Cement	108	49	1.72 out of 5	\$345	\$37,260	
Distribution Mains	P-8353	COV	Reservoir Rd.	8	Asbestos Cement	622	49	1.72 out of 5	\$345	\$214,590	
Distribution Mains	P-8356	COV	Reservoir Rd.	8	Asbestos Cement	90	49	1.72 out of 5	\$345	\$31,050	
Distribution Mains	P-8359	COV	Reservoir Rd.	8	Asbestos Cement	157	49	1.72 out of 5	\$345	\$54,165	
Transmission Mains	P-7138	COV	Reservoir Rd.	12	PVC	373	26	0.44 out of 5	\$345	\$128,685	
Transmission Mains	P-7153	COV	Reservoir Rd.	12	PVC	952	27	0.44 out of 5	\$345	\$328,440	
Transmission Mains	P-7155	COV	Reservoir Rd.	12	PVC	318	26	0.44 out of 5	\$345	\$109,710	
Transmission Mains	P-8350	COV	Reservoir Rd.	12	PVC	111	27	0.44 out of 5	\$345	\$38,295	
Transmission Mains	P-8354	COV	Reservoir Rd.	12	PVC	608	27	0.44 out of 5	\$345	\$209,760	
Transmission Mains	P-8355	COV	Reservoir Rd.	12	PVC	145	27	0.44 out of 5	\$345	\$50,025	
Transmission Mains	P-7129	COV	Reservoir Rd.	12	Ductile Iron	1,797	21	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7137	COV	Reservoir Rd.	12	Ductile Iron	1,097	21	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7127	COV	Reservoir Rd.	8	Ductile Iron	370	13	0 out of 5	N/A	\$0	
Distribution Mains	P-7128	COV	Reservoir Rd.	8	Ductile Iron	1,186	18	0 out of 5	N/A	\$0	
Distribution Mains	P-8864	COV	Richard Ct.	1.5	Galvanized iron	34	127	3.59 out of 5	\$345	\$11,730	
Distribution Mains	P-8865	COV	Richard Ct.	1.5	Galvanized iron	118	127	3.59 out of 5	\$345	\$40,710	
Distribution Mains	P-8863	COV	Richard Ct. Easement	1.5	Galvanized iron	175	127	3.59 out of 5	\$345	\$60,375	
Distribution Mains	P-8301	COV	Ridge Ave.	8	Ductile Iron	208	14	0 out of 5	N/A	\$0	
Distribution Mains	P-7513	COV	Robbins Dr.	6	Asbestos Cement	334	65	2.58 out of 5	\$345	\$115,230	
Distribution Mains	P-7514	COV	Robbins Dr.	6	Asbestos Cement	512	65	2.58 out of 5	\$345	\$176,640	
Distribution Mains	P-8140	COV	Rosebud St.	6	Asbestos Cement	237	53	2.43 out of 5	\$345	\$81,765	
Distribution Mains	P-8062	COV	Rosella St.	6	Ductile Iron	519	22	0.86 out of 5	\$345	\$179,055	
Distribution Mains	P-7487	COV	Rosemary St.	6	Asbestos Cement	499	52	2.43 out of 5	\$345	\$172,155	
Transmission Mains	P-8195	COV	Rosemary St.	12	Ductile Iron	445	26	0.15 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-7910	COV	Rosewood Ct.	6	Asbestos Cement	312	33	3 out of 5	\$345	\$107,640	
Distribution Mains	P-8414	COV	Ross Ct.	8	Ductile Iron	325	9	0 out of 5	N/A	\$0	
Distribution Mains	P-8212	COV	Roundway Dr.	8	Ductile Iron	218	3	0 out of 5	N/A	\$0	
Distribution Mains	P-8214	COV	Roundway Dr.	8	Ductile Iron	367	3	0 out of 5	N/A	\$0	
Distribution Mains	P-9070	COV	Roundway Dr.	8	Ductile Iron	73	3	0 out of 5	N/A	\$0	
Distribution Mains	P-7023	COV	Rustic Way	8	Asbestos Cement	389	35	1.58 out of 5	\$345	\$134,205	
Distribution Mains	P-8315	COV	Salvas Ave.	8	Ductile Iron	671	11	0 out of 5	N/A	\$0	
Distribution Mains	P-7590	COV	Sand St.	6	Asbestos Cement	185	51	2.43 out of 5	\$345	\$63,825	
Distribution Mains	P-7941	COV	Sandalwood Ct.	6	Asbestos Cement	320	48	2.43 out of 5	\$345	\$110,400	
Distribution Mains	P-7942	COV	Sandalwood Ct.	6	Asbestos Cement	132	48	2.43 out of 5	\$345	\$45,540	
Distribution Mains	P-8381	COV	Sandlewood Ct.	6	Asbestos Cement	408	48	2.43 out of 5	\$345	\$140,760	
Distribution Mains	P-8382	COV	Sandlewood Ct.	6	Asbestos Cement	131	48	2.43 out of 5	\$345	\$45,195	
Distribution Mains	P-8383	COV	Sandlewood Ct.	6	Asbestos Cement	171	48	2.43 out of 5	\$345	\$58,995	
Transmission Mains	P-7558	COV	Sandy Bottom Rd.	16	Cast iron	342	124	1.87 out of 5	\$345	\$117,990	
Distribution Mains	P-7843	COV	Sandy Bottom Rd.	8	Asbestos Cement	432	49	1.72 out of 5	\$345	\$149,040	IFR 2014A
Distribution Mains	P-8472	COV	Sandy Bottom Rd.	8	Asbestos Cement	1,215	49	1.72 out of 5	\$345	\$419,175	IFR 2014A
Transmission Mains	P-8930	COV	Sandy Bottom Rd.	16	Ductile Iron	142	49	0.29 out of 5	N/A	\$0	
Distribution Mains	P-8473	COV	Sandy Bottom Rd.	8	Ductile Iron	111	15	0 out of 5	N/A	\$0	
Distribution Mains	P-8928	COV	Sandy Bottom Rd.	8	Ductile Iron	26	3	0 out of 5	N/A	\$0	
Transmission Mains	P-8929	COV	Sandy Bottom Rd.	16	Ductile Iron	373	3	0 out of 5	N/A	\$0	
Distribution Mains	P-8362	COV	School Access Rd.	8	Asbestos Cement	546	40	1.72 out of 5	\$345	\$188,370	
Distribution Mains	P-7152	COV	School Access Rd.	8	Ductile Iron	590	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8360	COV	School Access Rd.	8	Ductile Iron	469	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7228	COV	Second St.	6	Asbestos Cement	216	60	3.29 out of 5	\$345	\$74,520	
Distribution Mains	P-7725	COV	Seneca St.	8	Ductile Iron	186	9	0 out of 5	N/A	\$0	
Distribution Mains	P-8765	COV	Seneca St.	8	Ductile Iron	506	9	0 out of 5	N/A	\$0	
Distribution Mains	P-7104	COV	Sharon Dr.	8	Ductile Iron	3,066	21	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8284	COV	Sharp St.	6	Asbestos Cement	150	51	2.43 out of 5	\$345	\$51,750	
Distribution Mains	P-7836	COV	Sheltra Ave.	8	Asbestos Cement	1,382	49	2.43 out of 5	\$345	\$476,790	
Distribution Mains	P-8285	COV	Sheltra Ave.	8	PVC	762	29	0.44 out of 5	\$345	\$262,890	
Distribution Mains	P-7381	COV	Sheri Dr.	8	Ductile Iron	126	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7382	COV	Sheri Dr.	8	Ductile Iron	414	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7383	COV	Sheri Dr.	8	Ductile Iron	255	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7009	COV	Sherwood Valley Ln.	12	Asbestos Cement	145	32	1.58 out of 5	\$345	\$50,025	
Distribution Mains	P-8040	COV	Shippee Ave.	8	Cast iron	288	125	1.87 out of 5	\$345	\$99,360	
Distribution Mains	P-7374	COV	Short Way Dr.	6	Asbestos Cement	301	43	2.43 out of 5	\$345	\$103,845	
Distribution Mains	P-7359	COV	Silo Ln.	8	Ductile Iron	205	19	0 out of 5	N/A	\$0	
Distribution Mains	P-7105	COV	Silver Maple Dr.	8	Asbestos Cement	306	36	1.58 out of 5	\$345	\$105,570	
Distribution Mains	P-7108	COV	Silver Maple Dr.	8	Asbestos Cement	640	36	1.58 out of 5	\$345	\$220,800	
Distribution Mains	P-7113	COV	Silver Maple Dr.	8	Asbestos Cement	170	36	1.58 out of 5	\$345	\$58,650	
Distribution Mains	P-7112	COV	Silver Maple Dr.	8	Ductile Iron	219	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7118	COV	Silver Maple Dr.	8	Ductile Iron	437	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7121	COV	Silver Maple Dr.	8	Ductile Iron	343	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7749	COV	Sooner Ln.	8	Ductile Iron	330	22	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7710	COV	South Glen Dr.	6	Asbestos Cement	845	55	3.14 out of 5	\$345	\$291,525	
Distribution Mains	P-7511	COV	South Main St.	8	Asbestos Cement	249	66	1.87 out of 5	\$345	\$85,905	
Distribution Mains	P-7517	COV	South Main St.	8	Asbestos Cement	1,253	66	1.87 out of 5	\$345	\$432,285	
Distribution Mains	P-7523	COV	South Main St.	8	Asbestos Cement	188	66	1.87 out of 5	\$345	\$64,860	
Distribution Mains	P-7524	COV	South Main St.	8	Asbestos Cement	370	66	1.87 out of 5	\$345	\$127,650	
Distribution Mains	P-7525	COV	South Main St.	8	Asbestos Cement	241	66	1.87 out of 5	\$345	\$83,145	
Distribution Mains	P-7526	COV	South Main St.	8	Asbestos Cement	492	66	1.87 out of 5	\$345	\$169,740	
Distribution Mains	P-7534	COV	South Main St.	8	Asbestos Cement	391	66	1.87 out of 5	\$345	\$134,895	
Transmission Mains	P-7535	COV	South Main St.	16	Cast iron	489	124	1.87 out of 5	\$345	\$168,705	
Transmission Mains	P-7536	COV	South Main St.	16	Cast iron	128	124	1.87 out of 5	\$345	\$44,160	
Transmission Mains	P-7537	COV	South Main St.	16	Cast iron	343	124	1.87 out of 5	\$345	\$118,335	
Distribution Mains	P-7550	COV	South Main St.	8	Asbestos Cement	274	66	1.87 out of 5	\$345	\$94,530	
Distribution Mains	P-7551	COV	South Main St.	8	Asbestos Cement	206	66	1.87 out of 5	\$345	\$71,070	
Transmission Mains	P-7586	COV	South Main St.	16	Cast iron	271	124	1.87 out of 5	\$345	\$93,495	
Transmission Mains	P-8933	COV	South Main St.	16	Cast iron	37	124	1.87 out of 5	\$345	\$12,765	
Transmission Mains	P-7931	COV	South Pond Dr.	12	Ductile Iron	641	16	0 out of 5	N/A	\$0	
Distribution Mains	P-7932	COV	South Pond Dr.	8	Ductile Iron	1,182	16	0 out of 5	N/A	\$0	
Distribution Mains	P-7934	COV	South Pond Dr.	8	Ductile Iron	1,009	16	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-8852	COV	South Pond Dr.	24	Ductile Iron	42	10	0 out of 5	N/A	\$0	
Distribution Mains	P-8016	COV	South St.	4	Cast iron	262	124	3.3 out of 5	\$345	\$90,390	
Distribution Mains	P-8015	COV	South St.	6	Cast iron	583	124	2.58 out of 5	\$345	\$201,135	
Distribution Mains	P-7561	COV	Spencer St.	6	Cast iron	402	124	2.58 out of 5	\$345	\$138,690	
Distribution Mains	P-7915	COV	Spencer St.	6	Asbestos Cement	99	69	2.58 out of 5	\$345	\$34,155	
Distribution Mains	P-9032	COV	St. Vincent DePaul St.	6	Cast iron	538	75	2.29 out of 5	\$345	\$185,610	
Transmission Mains	P-7845	COV	Station St.	12	Asbestos Cement	76	73	2.58 out of 5	\$345	\$26,220	
Distribution Mains	P-7262	COV	Station St.	8	Asbestos Cement	548	51	2.43 out of 5	\$345	\$189,060	
Transmission Mains	P-7261	COV	Station St.	12	Asbestos Cement	118	73	1.87 out of 5	\$345	\$40,710	
Distribution Mains	P-7269	COV	Station St.	8	Asbestos Cement	423	51	1.72 out of 5	\$345	\$145,935	
Distribution Mains	P-7343	COV	Station St.	8	Asbestos Cement	1,867	51	1.72 out of 5	\$345	\$644,115	
Distribution Mains	P-8324	COV	Station St.	8	Asbestos Cement	2,362	51	1.72 out of 5	\$345	\$814,890	
Distribution Mains	P-8325	COV	Station St.	8	Asbestos Cement	1,026	51	1.72 out of 5	\$345	\$353,970	
Distribution Mains	P-8823	COV	Station St.	8	Asbestos Cement	754	51	1.72 out of 5	\$345	\$260,130	
Distribution Mains	P-8824	COV	Station St.	8	Asbestos Cement	437	51	1.72 out of 5	\$345	\$150,765	
Distribution Mains	P-8914	COV	Station St.	8	Asbestos Cement	300	51	1.72 out of 5	\$345	\$103,500	
Distribution Mains	P-7420	COV	Steere Ln.	6	Asbestos Cement	89	48	2.43 out of 5	\$345	\$30,705	
Distribution Mains	P-7421	COV	Steere Ln.	6	Asbestos Cement	230	48	2.43 out of 5	\$345	\$79,350	
Distribution Mains	P-7530	COV	Stone St.	2	Cast iron	369	74	3.01 out of 5	\$345	\$127,305	
Distribution Mains	P-7529	COV	Stone St.	6	Cast iron	315	74	2.29 out of 5	\$345	\$108,675	
Distribution Mains	P-8321	COV	Stone St.	6	Cast iron	94	74	2.29 out of 5	\$345	\$32,430	
Distribution Mains	P-8936	COV	Stone St.	6	Cast iron	134	74	2.29 out of 5	\$345	\$46,230	
Distribution Mains	P-7215	COV	Stoney Hill Cir.	8	Ductile Iron	875	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7217	COV	Stoney Hill Cir.	8	Ductile Iron	375	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7450	COV	Stratford Dr.	8	Ductile Iron	428	20	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7073	COV	Sugar Maple Dr.	12	Ductile Iron	367	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7075	COV	Sugar Maple Dr.	12	Ductile Iron	560	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7083	COV	Sugar Maple Dr.	12	Ductile Iron	431	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7084	COV	Sugar Maple Dr.	12	Ductile Iron	390	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7085	COV	Sugar Maple Dr.	12	Ductile Iron	389	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7087	COV	Sugar Maple Dr.	12	Ductile Iron	265	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7532	COV	Sunapee Ct.	6	Asbestos Cement	186	57	2.43 out of 5	\$345	\$64,170	
Distribution Mains	P-7533	COV	Sunapee Ct.	6	Asbestos Cement	613	57	2.43 out of 5	\$345	\$211,485	
Distribution Mains	P-7914	COV	Sunrise Ave.	6	Asbestos Cement	89	61	2.58 out of 5	\$345	\$30,705	
Distribution Mains	P-8979	COV	Sunset Ave.	6	Asbestos Cement	186	60	2.58 out of 5	\$345	\$64,170	
Distribution Mains	P-8987	COV	Sunset Ave.	2	Copper	274	74	2.44 out of 5	\$345	\$94,530	
Distribution Mains	P-9023	COV	Sweet Fern Ln.	8	Ductile Iron	1,300	6	0 out of 5	N/A	\$0	
Distribution Mains	P-7295	COV	Sweetwater Dr.	8	Asbestos Cement	470	36	1.58 out of 5	\$345	\$162,150	
Distribution Mains	P-7296	COV	Sweetwater Dr.	8	Asbestos Cement	1,116	36	1.58 out of 5	\$345	\$385,020	
Distribution Mains	P-7449	COV	Sycamore Dr.	8	Ductile Iron	458	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7451	COV	Sycamore Dr.	8	Ductile Iron	329	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7453	COV	Sycamore Dr.	8	Ductile Iron	428	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-8965	COV	Sycamore Dr.	8	Ductile Iron	38	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7448	COV	Sycamore Dr. Easement	8	Ductile Iron	366	20	0.15 out of 5	N/A	\$0	
Transmission Mains	P-9025	COV	Tafford Park Dr.	12	Ductile Iron	47	6	0 out of 5	N/A	\$0	
Distribution Mains	P-7831	COV	Taft St.	6	Cast iron	427	127	2.58 out of 5	\$345	\$147,315	
Distribution Mains	P-7832	COV	Taft St.	6	Cast iron	230	127	2.58 out of 5	\$345	\$79,350	
Distribution Mains	P-7834	COV	Taft St.	6	Asbestos Cement	567	49	2.43 out of 5	\$345	\$195,615	
Distribution Mains	P-7119	COV	Tamarack Tr.	8	Ductile Iron	893	22	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7297	COV	Teakwood Dr. East	8	Asbestos Cement	424	35	1.58 out of 5	\$345	\$146,280	
Distribution Mains	P-7298	COV	Teakwood Dr. East	8	Asbestos Cement	156	35	1.58 out of 5	\$345	\$53,820	
Distribution Mains	P-7313	COV	Teakwood Dr. East	8	Asbestos Cement	455	35	1.58 out of 5	\$345	\$156,975	
Distribution Mains	P-7307	COV	Teakwood Dr. West	8	Asbestos Cement	250	35	1.58 out of 5	\$345	\$86,250	
Distribution Mains	P-7308	COV	Teakwood Dr. West	8	Asbestos Cement	460	35	1.58 out of 5	\$345	\$158,700	
Distribution Mains	P-7309	COV	Teakwood Dr. West	8	Asbestos Cement	147	35	1.58 out of 5	\$345	\$50,715	
Distribution Mains	P-7267	COV	Tero Dr.	6	Asbestos Cement	579	39	2.29 out of 5	\$345	\$199,755	
Distribution Mains	P-8134	COV	Terrace Ave.	4	Cast iron	222	114	3.3 out of 5	\$345	\$76,590	
Distribution Mains	P-7195	COV	Thompson Dr.	8	Asbestos Cement	554	40	1.72 out of 5	\$345	\$191,130	
Distribution Mains	P-8163	COV	Tiffany Rd.	8	Asbestos Cement	240	38	1.58 out of 5	\$345	\$82,800	
Distribution Mains	P-8164	COV	Tiffany Rd.	8	Asbestos Cement	254	38	1.58 out of 5	\$345	\$87,630	
Distribution Mains	P-8192	COV	Tiffany Rd.	8	PVC	1,378	27	0.44 out of 5	\$345	\$475,410	
Transmission Mains	P-8167	COV	Tiffany Rd.	12	Ductile Iron	163	6	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-8712	COV	Tiffany Rd.	12	Ductile Iron	944	6	0 out of 5	N/A	\$0	
Transmission Mains	P-9026	COV	Tiffany Rd.	12	Ductile Iron	23	6	0 out of 5	N/A	\$0	
Distribution Mains	P-9027	COV	Tiffany Rd.	8	Ductile Iron	27	6	0 out of 5	N/A	\$0	
Distribution Mains	P-8401	COV	Timber Tr.	8	Ductile Iron	300	4	0 out of 5	N/A	\$0	
Distribution Mains	P-8402	COV	Timber Tr.	8	Ductile Iron	515	4	0 out of 5	N/A	\$0	
Distribution Mains	P-8403	COV	Timber Tr.	8	Ductile Iron	515	4	0 out of 5	N/A	\$0	
Distribution Mains	P-8405	COV	Timber Tr.	8	Ductile Iron	230	4	0 out of 5	N/A	\$0	
Distribution Mains	P-8513	COV	Tiogue Ave.	8	Asbestos Cement	867	66	2.58 out of 5	\$345	\$299,115	
Transmission Mains	P-7507	COV	Tiogue Ave.	12	Asbestos Cement	1,626	52	2.43 out of 5	\$345	\$560,970	
Distribution Mains	P-7496	COV	Tiogue Ave.	8	Asbestos Cement	843	66	1.87 out of 5	\$345	\$290,835	
Distribution Mains	P-7500	COV	Tiogue Ave.	8	Asbestos Cement	133	66	1.87 out of 5	\$345	\$45,885	
Transmission Mains	P-7562	COV	Tiogue Ave.	12	Asbestos Cement	268	65	1.87 out of 5	\$345	\$92,460	
Transmission Mains	P-7563	COV	Tiogue Ave.	12	Asbestos Cement	2,299	65	1.87 out of 5	\$345	\$793,155	
Transmission Mains	P-7564	COV	Tiogue Ave.	12	Asbestos Cement	345	65	1.87 out of 5	\$345	\$119,025	
Transmission Mains	P-7743	COV	Tiogue Ave.	12	Asbestos Cement	721	65	1.87 out of 5	\$345	\$248,745	
Transmission Mains	P-7744	COV	Tiogue Ave.	12	Asbestos Cement	52	65	1.87 out of 5	\$345	\$17,940	
Transmission Mains	P-7745	COV	Tiogue Ave.	12	Asbestos Cement	134	65	1.87 out of 5	\$345	\$46,230	
Transmission Mains	P-7751	COV	Tiogue Ave.	12	Asbestos Cement	917	65	1.87 out of 5	\$345	\$316,365	
Transmission Mains	P-8526	COV	Tiogue Ave.	12	Asbestos Cement	115	65	1.87 out of 5	\$345	\$39,675	
Transmission Mains	P-9005	COV	Tiogue Ave.	12	Asbestos Cement	467	65	1.87 out of 5	\$345	\$161,115	
Distribution Mains	P-7502	COV	Tiogue Ave.	8	Asbestos Cement	49	52	1.72 out of 5	\$345	\$16,905	
Transmission Mains	P-7508	COV	Tiogue Ave.	12	Asbestos Cement	239	52	1.72 out of 5	\$345	\$82,455	
Transmission Mains	P-7509	COV	Tiogue Ave.	12	Asbestos Cement	741	52	1.72 out of 5	\$345	\$255,645	
Transmission Mains	P-7510	COV	Tiogue Ave.	12	Asbestos Cement	1,078	52	1.72 out of 5	\$345	\$371,910	
Transmission Mains	P-7754	COV	Tiogue Ave.	12	Asbestos Cement	173	49	1.72 out of 5	\$345	\$59,685	
Transmission Mains	P-7755	COV	Tiogue Ave.	12	Asbestos Cement	368	49	1.72 out of 5	\$345	\$126,960	
Transmission Mains	P-7768	COV	Tiogue Ave.	12	Asbestos Cement	373	49	1.72 out of 5	\$345	\$128,685	
Transmission Mains	P-7769	COV	Tiogue Ave.	12	Asbestos Cement	134	49	1.72 out of 5	\$345	\$46,230	
Transmission Mains	P-7770	COV	Tiogue Ave.	12	Asbestos Cement	238	49	1.72 out of 5	\$345	\$82,110	
Transmission Mains	P-8943	COV	Tiogue Ave.	12	Asbestos Cement	399	52	1.72 out of 5	\$345	\$137,655	
Transmission Mains	P-9018	COV	Tiogue Ave.	12	Asbestos Cement	287	49	1.72 out of 5	\$345	\$99,015	
Transmission Mains	P-7160	COV	Tiogue Ave.	12	Ductile Iron	787	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8748	COV	Tiogue Ave.	12	Ductile Iron	375	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7503	COV	Tiogue Ave.	8	Ductile Iron	53	19	0 out of 5	N/A	\$0	
Transmission Mains	P-7504	COV	Tiogue Ave.	12	Ductile Iron	464	14	0 out of 5	N/A	\$0	
Transmission Mains	P-7505	COV	Tiogue Ave.	12	Ductile Iron	89	14	0 out of 5	N/A	\$0	
Transmission Mains	P-7506	COV	Tiogue Ave.	12	Ductile Iron	44	14	0 out of 5	N/A	\$0	
Transmission Mains	P-7608	COV	Tiogue Ave.	20	Ductile Iron	414	14	0 out of 5	N/A	\$0	
Transmission Mains	P-7609	COV	Tiogue Ave.	20	Ductile Iron	265	14	0 out of 5	N/A	\$0	
Transmission Mains	P-7714	COV	Tiogue Ave.	16	Ductile Iron	324	14	0 out of 5	N/A	\$0	
Transmission Mains	P-7715	COV	Tiogue Ave.	20	Ductile Iron	1,796	14	0 out of 5	N/A	\$0	
Transmission Mains	P-7717	COV	Tiogue Ave.	12	Ductile Iron	848	14	0 out of 5	N/A	\$0	
Transmission Mains	P-7718	COV	Tiogue Ave.	12	Ductile Iron	96	14	0 out of 5	N/A	\$0	
Transmission Mains	P-7732	COV	Tiogue Ave.	12	Ductile Iron	36	14	0 out of 5	N/A	\$0	
Transmission Mains	P-7753	COV	Tiogue Ave.	12	Ductile Iron	108	14	0 out of 5	N/A	\$0	
Transmission Mains	P-8293	COV	Tiogue Ave.	16	Ductile Iron	204	14	0 out of 5	N/A	\$0	
Transmission Mains	P-8294	COV	Tiogue Ave.	16	Ductile Iron	177	14	0 out of 5	N/A	\$0	
Transmission Mains	P-8296	COV	Tiogue Ave.	16	Ductile Iron	2,015	14	0 out of 5	N/A	\$0	
Distribution Mains	P-8298	COV	Tiogue Ave.	8	Ductile Iron	747	19	0 out of 5	N/A	\$0	
Transmission Mains	P-8425	COV	Tiogue Ave.	12	Ductile Iron	948	14	0 out of 5	N/A	\$0	
Transmission Mains	P-8475	COV	Tiogue Ave.	12	Ductile Iron	1,509	14	0 out of 5	N/A	\$0	
Transmission Mains	P-8487	COV	Tiogue Ave.	12	Ductile Iron	199	14	0 out of 5	N/A	\$0	
Transmission Mains	P-8715	COV	Tiogue Ave.	12	Ductile Iron	1,485	6	0 out of 5	N/A	\$0	
Transmission Mains	P-8718	COV	Tiogue Ave.	12	Ductile Iron	200	6	0 out of 5	N/A	\$0	
Transmission Mains	P-8719	COV	Tiogue Ave.	12	Ductile Iron	200	6	0 out of 5	N/A	\$0	
Transmission Mains	P-8720	COV	Tiogue Ave.	12	Ductile Iron	244	6	0 out of 5	N/A	\$0	
Transmission Mains	P-8721	COV	Tiogue Ave.	12	Ductile Iron	564	14	0 out of 5	N/A	\$0	
Transmission Mains	P-8946	COV	Tiogue Ave.	12	Ductile Iron	345	14	0 out of 5	N/A	\$0	
Transmission Mains	P-9003	COV	Tiogue Ave.	16	Ductile Iron	316	14	0 out of 5	N/A	\$0	
Transmission Mains	P-9004	COV	Tiogue Ave.	16	Ductile Iron	115	14	0 out of 5	N/A	\$0	
Transmission Mains	P-9006	COV	Tiogue Ave.	16	Ductile Iron	504	14	0 out of 5	N/A	\$0	
Transmission Mains	P-7730	COV	Tiogue Tank	12	Asbestos Cement	2	61	1.87 out of 5	\$345	\$690	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-7731	COV	Tiogou Tank	12	Asbestos Cement	72	61	1.87 out of 5	\$345	\$24,840	
Transmission Mains	P-8485	COV	Tiogou Tank	12	Asbestos Cement	8	61	1.87 out of 5	\$345	\$2,760	
Distribution Mains	P-8717	COV	Tiogou Tank Booster PS	8	Ductile Iron	151	9	0 out of 5	N/A	\$0	
Distribution Mains	P-8844	COV	Tobin St.	6	Cast iron	99	124	2.58 out of 5	\$345	\$34,155	
Distribution Mains	P-7572	COV	Tobin St.	6	Ductile Iron	191	25	0.86 out of 5	\$345	\$65,895	
Distribution Mains	P-8165	COV	Trafford Park Dr.	8	Asbestos Cement	1,025	37	1.58 out of 5	\$345	\$353,625	
Distribution Mains	P-7678	COV	Tulip Rd.	6	Asbestos Cement	439	51	2.43 out of 5	\$345	\$151,455	
Distribution Mains	P-7837	COV	Turcotte St.	8	PVC	319	27	0.44 out of 5	\$345	\$110,055	
Distribution Mains	P-7652	COV	Twin Lakes Ave.	8	Ductile Iron	646	13	0 out of 5	N/A	\$0	
Distribution Mains	P-7654	COV	Twin Lakes Ave.	8	Ductile Iron	178	13	0 out of 5	N/A	\$0	
Distribution Mains	P-7656	COV	Twin Lakes Ave.	8	Ductile Iron	179	13	0 out of 5	N/A	\$0	
Distribution Mains	P-9038	COV	Union St.	1	Copper	114	81	2.58 out of 5	\$345	\$39,330	
Distribution Mains	P-7662	COV	Vale St.	2	Copper	468	78	2.44 out of 5	\$345	\$161,460	
Distribution Mains	P-7293	COV	Valley Crest Rd.	6	Asbestos Cement	760	55	2.43 out of 5	\$345	\$262,200	
Distribution Mains	P-7288	COV	Valley Crest Rd.	8	Asbestos Cement	227	54	1.72 out of 5	\$345	\$78,315	
Distribution Mains	P-7289	COV	Valley Crest Rd.	8	Asbestos Cement	228	54	1.72 out of 5	\$345	\$78,660	
Distribution Mains	P-8138	COV	Valrene St.	6	Asbestos Cement	469	47	2.43 out of 5	\$345	\$161,805	
Distribution Mains	P-8139	COV	Valrene St.	6	Asbestos Cement	56	47	2.43 out of 5	\$345	\$19,320	
Distribution Mains	P-7799	COV	Vanderbilt Ter.	6	Asbestos Cement	458	38	2.29 out of 5	\$345	\$158,010	
Distribution Mains	P-7804	COV	Vanderbilt Ter.	6	Asbestos Cement	494	38	2.29 out of 5	\$345	\$170,430	
Distribution Mains	P-7673	COV	Vera Rd.	6	Asbestos Cement	575	51	2.43 out of 5	\$345	\$198,375	
Distribution Mains	P-8975	COV	Vera Rd.	6	Asbestos Cement	338	51	2.43 out of 5	\$345	\$116,610	
Distribution Mains	P-7102	COV	Veronica Ct.	6	Asbestos Cement	300	39	2.29 out of 5	\$345	\$103,500	
Distribution Mains	P-7705	COV	View Rd.	2	Copper	351	55	2.29 out of 5	\$345	\$121,095	
Distribution Mains	P-7370	COV	Viola St.	6	Asbestos Cement	372	46	2.43 out of 5	\$345	\$128,340	
Distribution Mains	P-7371	COV	Viola St.	6	Asbestos Cement	310	46	2.43 out of 5	\$345	\$106,950	
Distribution Mains	P-7372	COV	Viola St.	6	Asbestos Cement	258	46	2.43 out of 5	\$345	\$89,010	
Distribution Mains	P-7373	COV	Viola St.	6	Asbestos Cement	253	46	2.43 out of 5	\$345	\$87,285	
Transmission Mains	P-7186	COV	Walker Ln.	12	Ductile Iron	3,121	20	0.15 out of 5	N/A	\$0	
Transmission Mains	P-7187	COV	Walker Ln.	12	Ductile Iron	813	20	0.15 out of 5	N/A	\$0	
Transmission Mains	P-8896	COV	Walker Ln.	12	Ductile Iron	30	3	0 out of 5	N/A	\$0	
Distribution Mains	P-7320	COV	Walnut Hill Rd.	8	Asbestos Cement	541	49	1.72 out of 5	\$345	\$186,645	
Transmission Mains	P-7962	COV	Washington St.	12	Cast iron	638	127	2.58 out of 5	\$345	\$220,110	
Transmission Mains	P-7848	COV	Washington St.	16	Cast iron	871	124	1.87 out of 5	\$345	\$300,495	
Transmission Mains	P-7865	COV	Washington St.	12	Cast iron	238	127	1.87 out of 5	\$345	\$82,110	
Transmission Mains	P-7964	COV	Washington St.	12	Asbestos Cement	910	70	1.87 out of 5	\$345	\$313,950	
Transmission Mains	P-7965	COV	Washington St.	12	Cast iron	162	127	1.87 out of 5	\$345	\$55,890	
Transmission Mains	P-8009	COV	Washington St.	12	Cast iron	694	127	1.87 out of 5	\$345	\$239,430	
Transmission Mains	P-8010	COV	Washington St.	12	Cast iron	121	127	1.87 out of 5	\$345	\$41,745	
Transmission Mains	P-8011	COV	Washington St.	12	Cast iron	407	127	1.87 out of 5	\$345	\$140,415	
Transmission Mains	P-8020	COV	Washington St.	12	Cast iron	249	127	1.87 out of 5	\$345	\$85,905	
Transmission Mains	P-8022	COV	Washington St.	12	Cast iron	458	127	1.87 out of 5	\$345	\$158,010	
Transmission Mains	P-8243	COV	Washington St.	16	Cast iron	99	124	1.87 out of 5	\$345	\$34,155	
Transmission Mains	P-8244	COV	Washington St.	16	Cast iron	175	128	1.87 out of 5	\$345	\$60,375	
Transmission Mains	P-8246	COV	Washington St.	16	Cast iron	1,089	128	1.87 out of 5	\$345	\$375,705	
Transmission Mains	P-8287	COV	Washington St.	12	Cast iron	226	127	1.87 out of 5	\$345	\$77,970	
Transmission Mains	P-8288	COV	Washington St.	12	Cast iron	100	127	1.87 out of 5	\$345	\$34,500	
Transmission Mains	P-8290	COV	Washington St.	16	Cast iron	46	127	1.87 out of 5	\$345	\$15,870	
Transmission Mains	P-8291	COV	Washington St.	16	Cast iron	545	127	1.87 out of 5	\$345	\$188,025	
Transmission Mains	P-8762	COV	Washington St.	12	Cast iron	292	127	1.87 out of 5	\$345	\$100,740	
Transmission Mains	P-8775	COV	Washington St.	12	Cast iron	1,243	127	1.87 out of 5	\$345	\$428,835	
Transmission Mains	P-8777	COV	Washington St.	12	Asbestos Cement	459	70	1.87 out of 5	\$345	\$158,355	
Transmission Mains	P-9029	COV	Washington St.	12	Cast iron	56	127	1.87 out of 5	\$345	\$19,320	
Transmission Mains	P-9045	COV	Washington St.	12	Cast iron	598	127	1.87 out of 5	\$345	\$206,310	
Transmission Mains	P-7860	COV	Washington St.	12	Ductile Iron	1,132	10	0 out of 5	N/A	\$0	
Distribution Mains	P-7311	COV	Watercress Ct.	8	Asbestos Cement	137	35	2.29 out of 5	\$345	\$47,265	
Distribution Mains	P-7300	COV	Watercress Ct.	8	Asbestos Cement	615	35	1.58 out of 5	\$345	\$212,175	
Distribution Mains	P-7301	COV	Watercress Ct.	8	Asbestos Cement	468	35	1.58 out of 5	\$345	\$161,460	
Distribution Mains	P-7312	COV	Watercress Ct.	8	Asbestos Cement	897	35	1.58 out of 5	\$345	\$309,465	
Distribution Mains	P-7567	COV	Wendell St.	6	Asbestos Cement	254	60	2.58 out of 5	\$345	\$87,630	
Distribution Mains	P-7568	COV	Wendell St.	6	Asbestos Cement	248	60	2.58 out of 5	\$345	\$85,560	
Distribution Mains	P-8152	COV	Wendy Dr.	8	Asbestos Cement	186	41	1.72 out of 5	\$345	\$64,170	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-8157	COV	Wendy Dr.	8	Asbestos Cement	171	41	1.72 out of 5	\$345	\$58,995	
Distribution Mains	P-8158	COV	Wendy Dr.	8	Asbestos Cement	417	41	1.72 out of 5	\$345	\$143,865	
Distribution Mains	P-7815	COV	Wesleyan Ave.	6	Asbestos Cement	275	47	2.43 out of 5	\$345	\$94,875	
Distribution Mains	P-7817	COV	Wesleyan Ave.	6	Asbestos Cement	589	47	2.43 out of 5	\$345	\$203,205	
Distribution Mains	P-7798	COV	Wesleyan Ave.	8	Asbestos Cement	252	47	1.72 out of 5	\$345	\$86,940	
Distribution Mains	P-7806	COV	Wesleyan Ave.	8	Asbestos Cement	1,333	47	1.72 out of 5	\$345	\$459,885	
Distribution Mains	P-7628	COV	West Lake Dr.	6	Asbestos Cement	412	53	2.43 out of 5	\$345	\$142,140	
Distribution Mains	P-8309	COV	West Shore Dr.	6	Asbestos Cement	210	60	2.58 out of 5	\$345	\$72,450	
Distribution Mains	P-7661	COV	West Shore Dr.	1	Copper	230	78	2.44 out of 5	\$345	\$79,350	
Distribution Mains	P-8994	COV	West Shore Dr.	1	Copper	209	60	2.44 out of 5	\$345	\$72,105	
Distribution Mains	P-7689	COV	West Shore Dr.	6	Asbestos Cement	413	48	2.43 out of 5	\$345	\$142,485	
Distribution Mains	P-8993	COV	West Shore Dr.	6	Ductile Iron	42	13	0.71 out of 5	\$345	\$14,490	
Distribution Mains	P-8996	COV	West Shore Dr.	8	Ductile Iron	33	6	0 out of 5	N/A	\$0	
Distribution Mains	P-8997	COV	West Shore Dr.	8	Ductile Iron	27	6	0 out of 5	N/A	\$0	
Distribution Mains	P-7056	COV	West View Dr.	8	Asbestos Cement	318	41	1.72 out of 5	\$345	\$109,710	
Distribution Mains	P-7057	COV	West View Dr.	8	Asbestos Cement	334	41	1.72 out of 5	\$345	\$115,230	
Distribution Mains	P-7058	COV	West View Dr.	8	Asbestos Cement	265	41	1.72 out of 5	\$345	\$91,425	
Distribution Mains	P-7067	COV	West View Dr.	8	Asbestos Cement	512	41	1.72 out of 5	\$345	\$176,640	
Distribution Mains	P-7066	COV	West View Dr.	8	Asbestos Cement	872	27	1.58 out of 5	\$345	\$300,840	
Distribution Mains	P-7131	COV	White Oak Ct.	8	Ductile Iron	403	15	0 out of 5	N/A	\$0	
Distribution Mains	P-7132	COV	White Oak Ct.	8	Ductile Iron	462	15	0 out of 5	N/A	\$0	
Distribution Mains	P-7133	COV	White Oak Ct.	8	Ductile Iron	173	15	0 out of 5	N/A	\$0	
Distribution Mains	P-7904	COV	White Pine Rd.	8	Asbestos Cement	748	34	1.58 out of 5	\$345	\$258,060	
Distribution Mains	P-7906	COV	White Pine Rd.	8	Asbestos Cement	415	34	1.58 out of 5	\$345	\$143,175	
Distribution Mains	P-7321	COV	White Rock Dr.	8	Asbestos Cement	168	49	1.72 out of 5	\$345	\$57,960	
Distribution Mains	P-7322	COV	White Rock Dr.	8	Asbestos Cement	787	49	1.72 out of 5	\$345	\$271,515	
Distribution Mains	P-7881	COV	White Rock Dr.	8	Asbestos Cement	580	49	1.72 out of 5	\$345	\$200,100	
Distribution Mains	P-8220	COV	White Rock Dr.	8	Asbestos Cement	102	49	1.72 out of 5	\$345	\$35,190	
Distribution Mains	P-8018	COV	Whitford St.	8	Ductile Iron	350	11	0 out of 5	N/A	\$0	
Distribution Mains	P-8764	COV	Whitford St.	8	Ductile Iron	464	11	0 out of 5	N/A	\$0	
Distribution Mains	P-7565	COV	Whitman St.	6	Asbestos Cement	415	45	2.43 out of 5	\$345	\$143,175	
Distribution Mains	P-8160	COV	Whittier Dr.	8	Asbestos Cement	442	41	1.72 out of 5	\$345	\$152,490	
Distribution Mains	P-8161	COV	Whittier Dr.	8	Asbestos Cement	174	41	1.72 out of 5	\$345	\$60,030	
Distribution Mains	P-7356	COV	Wildflower Dr.	8	Ductile Iron	772	19	0 out of 5	N/A	\$0	
Distribution Mains	P-7549	COV	Wildwood St.	6	Asbestos Cement	199	64	2.58 out of 5	\$345	\$68,655	
Distribution Mains	P-7559	COV	Williams St.	2	Galvanized iron	451	82	3.44 out of 5	\$345	\$155,595	
Distribution Mains	P-7560	COV	Williams St.	6	Asbestos Cement	464	64	2.58 out of 5	\$345	\$160,080	
Distribution Mains	P-8033	COV	Willow St.	6	Cast iron	311	119	2.58 out of 5	\$345	\$107,295	
Distribution Mains	P-8203	COV	Windsor Park Dr.	8	Ductile Iron	659	3	0 out of 5	N/A	\$0	
Distribution Mains	P-8204	COV	Windsor Park Dr.	8	Ductile Iron	240	3	0 out of 5	N/A	\$0	
Distribution Mains	P-8206	COV	Windsor Park Dr.	8	Ductile Iron	226	3	0 out of 5	N/A	\$0	
Distribution Mains	P-8207	COV	Windsor Park Dr.	8	Ductile Iron	277	3	0 out of 5	N/A	\$0	
Distribution Mains	P-8209	COV	Windsor Park Dr.	8	Ductile Iron	281	3	0 out of 5	N/A	\$0	
Distribution Mains	P-8210	COV	Windsor Park Dr.	8	Ductile Iron	263	3	0 out of 5	N/A	\$0	
Distribution Mains	P-8213	COV	Windsor Park Dr.	8	Ductile Iron	557	3	0 out of 5	N/A	\$0	
Distribution Mains	P-7068	COV	Winterberry Dr.	6	Asbestos Cement	603	41	2.43 out of 5	\$345	\$208,035	
Distribution Mains	P-7070	COV	Winterberry Dr.	6	Asbestos Cement	457	41	2.43 out of 5	\$345	\$157,665	
Distribution Mains	P-7896	COV	Wintergreen Ct.	6	Asbestos Cement	243	33	2.29 out of 5	\$345	\$83,835	
Distribution Mains	P-7011	COV	Wisteria Dr.	8	Asbestos Cement	1,645	52	1.72 out of 5	\$345	\$567,525	
Distribution Mains	P-7017	COV	Wisteria Dr.	8	Asbestos Cement	367	52	1.72 out of 5	\$345	\$126,615	
Distribution Mains	P-7025	COV	Wisteria Dr.	8	Asbestos Cement	471	52	1.72 out of 5	\$345	\$162,495	
Distribution Mains	P-7026	COV	Wisteria Dr.	8	Asbestos Cement	341	52	1.72 out of 5	\$345	\$117,645	
Distribution Mains	P-7030	COV	Wisteria Dr.	8	Asbestos Cement	699	52	1.72 out of 5	\$345	\$241,155	
Distribution Mains	P-7037	COV	Wisteria Dr.	8	Asbestos Cement	630	52	1.72 out of 5	\$345	\$217,350	
Distribution Mains	P-7039	COV	Wisteria Dr.	8	Asbestos Cement	509	52	1.72 out of 5	\$345	\$175,605	
Distribution Mains	P-7040	COV	Wisteria Dr.	8	Asbestos Cement	226	52	1.72 out of 5	\$345	\$77,970	
Distribution Mains	P-7041	COV	Wisteria Dr.	8	Asbestos Cement	218	52	1.72 out of 5	\$345	\$75,210	
Distribution Mains	P-7054	COV	Wisteria Dr.	8	Asbestos Cement	449	52	1.72 out of 5	\$345	\$154,905	
Distribution Mains	P-7055	COV	Wisteria Dr.	8	Asbestos Cement	438	52	1.72 out of 5	\$345	\$151,110	
Transmission Mains	P-8932	COV	Woburn St.	16	Cast iron	282	124	1.87 out of 5	\$345	\$97,290	
Distribution Mains	P-7082	COV	Wolfe Ct.	6	Ductile Iron	230	24	0.86 out of 5	\$345	\$79,350	
Distribution Mains	P-7012	COV	Wood Cove Dr.	8	Asbestos Cement	651	46	1.72 out of 5	\$345	\$224,595	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-7013	COV	Wood Cove Dr.	8	Asbestos Cement	895	46	1.72 out of 5	\$345	\$308,775	
Distribution Mains	P-7015	COV	Wood Cove Dr.	8	Asbestos Cement	1,406	46	1.72 out of 5	\$345	\$485,070	
Distribution Mains	P-7029	COV	Wood Cove Dr.	8	Asbestos Cement	433	46	1.72 out of 5	\$345	\$149,385	
Distribution Mains	P-7033	COV	Wood Cove Dr.	8	Asbestos Cement	244	46	1.72 out of 5	\$345	\$84,180	
Distribution Mains	P-7047	COV	Wood Cove Dr.	8	Asbestos Cement	264	46	1.72 out of 5	\$345	\$91,080	
Distribution Mains	P-7049	COV	Wood Cove Dr.	8	Asbestos Cement	833	46	1.72 out of 5	\$345	\$287,385	
Distribution Mains	P-7051	COV	Wood Cove Dr.	8	Asbestos Cement	674	46	1.72 out of 5	\$345	\$232,530	
Distribution Mains	P-7052	COV	Wood Cove Dr.	8	Asbestos Cement	180	46	1.72 out of 5	\$345	\$62,100	
Distribution Mains	P-7079	COV	Wood Cove Dr.	8	Asbestos Cement	471	46	1.72 out of 5	\$345	\$162,495	
Distribution Mains	P-7088	COV	Wood Cove Dr.	8	Asbestos Cement	1,139	46	1.72 out of 5	\$345	\$392,955	
Distribution Mains	P-7090	COV	Wood Cove Dr.	8	Asbestos Cement	615	46	1.72 out of 5	\$345	\$212,175	
Distribution Mains	P-8961	COV	Wood Cove Dr.	6	Ductile Iron	27	8	0.71 out of 5	\$345	\$9,315	
Distribution Mains	P-8960	COV	Wood Cove Dr.	8	Ductile Iron	31	8	0 out of 5	N/A	\$0	
Transmission Mains	P-7553	COV	Wood St.	16	Cast iron	135	124	1.87 out of 5	\$345	\$46,575	
Transmission Mains	P-7555	COV	Wood St.	16	Cast iron	823	124	1.87 out of 5	\$345	\$283,935	
Transmission Mains	P-7557	COV	Wood St.	16	Cast iron	434	124	1.87 out of 5	\$345	\$149,730	
Transmission Mains	P-8931	COV	Wood St.	16	Cast iron	786	124	1.87 out of 5	\$345	\$271,170	
Distribution Mains	P-7547	COV	Woodland Ave.	6	Asbestos Cement	594	64	2.58 out of 5	\$345	\$204,930	
Distribution Mains	P-7548	COV	Woodland Ave.	6	Asbestos Cement	241	64	2.58 out of 5	\$345	\$83,145	
Distribution Mains	P-8067	COV	Woodmist Cir.	8	Ductile Iron	1,142	13	0 out of 5	N/A	\$0	
Distribution Mains	P-8068	COV	Woodmist Cir.	8	Ductile Iron	496	13	0 out of 5	N/A	\$0	
Distribution Mains	P-8069	COV	Woodmist Cir.	8	Ductile Iron	1,384	13	0 out of 5	N/A	\$0	
Distribution Mains	P-7522	COV	Woodside Ave.	6	Cast iron	260	75	2.29 out of 5	\$345	\$89,700	
Distribution Mains	P-7780	COV	Yale Dr.	6	Asbestos Cement	607	55	2.43 out of 5	\$345	\$209,415	
Distribution Mains	P-7791	COV	Yale Dr.	6	Asbestos Cement	724	55	2.43 out of 5	\$345	\$249,780	
Distribution Mains	P-7792	COV	Yale Dr.	6	Asbestos Cement	183	55	2.43 out of 5	\$345	\$63,135	
Distribution Mains	P-9063	COV	Yates Ave.	1	Copper	343	127	2.73 out of 5	\$345	\$118,335	
Distribution Mains	P-7982	COV	Yates Ave.	6	Asbestos Cement	234	65	2.58 out of 5	\$345	\$80,730	
Distribution Mains	P-7983	COV	Yates Ave.	6	Asbestos Cement	481	65	2.58 out of 5	\$345	\$165,945	
Distribution Mains	P-8076	COV	Yeaton St.	8	Ductile Iron	521	3	0 out of 5	N/A	\$0	
Distribution Mains	P-7601	COV	York Dr.	8	Asbestos Cement	473	48	1.72 out of 5	\$345	\$163,185	
Distribution Mains	P-7621	COV	York Dr.	8	Asbestos Cement	774	48	1.72 out of 5	\$345	\$267,030	
Distribution Mains	P-7626	COV	York Dr.	8	Asbestos Cement	1,503	48	1.72 out of 5	\$345	\$518,535	
Distribution Mains	P-8048	COV	Youngs Ave.	8	Asbestos Cement	188	58	1.72 out of 5	\$345	\$64,860	
Distribution Mains	P-8050	COV	Youngs Ave.	8	Asbestos Cement	648	58	1.72 out of 5	\$345	\$223,560	
Distribution Mains	P-5026	CRA	Allard St.	8	Ductile Iron	598	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5027	CRA	Allard St.	8	Ductile Iron	150	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5140	CRA	Allard St.	8	Ductile Iron	150	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5042	CRA	Amanda Ct.	8	Ductile Iron	239	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5030	CRA	Amanda St.	8	Ductile Iron	224	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5039	CRA	Amanda St.	8	Ductile Iron	1,002	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5040	CRA	Amanda St.	8	Ductile Iron	236	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5041	CRA	Amanda St.	8	Ductile Iron	90	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5169	CRA	Amanda St.	8	Ductile Iron	172	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5003	CRA	Angell Ave.	8	Ductile Iron	451	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5005	CRA	Angell Ave.	8	Ductile Iron	457	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5006	CRA	Angell Ave.	8	Ductile Iron	228	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5015	CRA	Angell Ave.	8	Ductile Iron	272	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5153	CRA	Angell Ave.	8	Ductile Iron	218	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5096	CRA	Bald Hill Rd.	6	Asbestos Cement	54	46	2.43 out of 5	\$345	\$18,630	
Distribution Mains	P-5097	CRA	Bald Hill Rd.	6	Asbestos Cement	462	46	2.43 out of 5	\$345	\$159,390	
Distribution Mains	P-5099	CRA	Bald Hill Rd.	6	Asbestos Cement	324	46	2.43 out of 5	\$345	\$111,780	
Distribution Mains	P-5100	CRA	Bald Hill Rd.	6	Asbestos Cement	252	46	2.43 out of 5	\$345	\$86,940	
Distribution Mains	P-5094	CRA	Bald Hill Rd.	10	Asbestos Cement	244	46	1.72 out of 5	\$345	\$84,180	
Distribution Mains	P-5095	CRA	Bald Hill Rd.	10	Asbestos Cement	460	46	1.72 out of 5	\$345	\$158,700	
Distribution Mains	P-5101	CRA	Bald Hill Rd.	10	Asbestos Cement	731	46	1.72 out of 5	\$345	\$252,195	
Distribution Mains	P-5102	CRA	Bald Hill Rd.	8	Asbestos Cement	359	46	1.72 out of 5	\$345	\$123,855	
Distribution Mains	P-5154	CRA	Bald Hill Rd.	8	Asbestos Cement	181	46	1.72 out of 5	\$345	\$62,445	
Distribution Mains	P-5033	CRA	Benjamin St.	8	Ductile Iron	266	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5034	CRA	Benjamin St.	8	Ductile Iron	225	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5168	CRA	Benjamin St.	8	Ductile Iron	24	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5072	CRA	Brianwood Rd.	6	Asbestos Cement	66	57	2.43 out of 5	\$345	\$22,770	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-5078	CRA	Briarwood Rd.	6	Asbestos Cement	79	57	2.43 out of 5	\$345	\$27,255	
Distribution Mains	P-5079	CRA	Briarwood Rd.	6	Asbestos Cement	192	57	2.43 out of 5	\$345	\$66,240	
Distribution Mains	P-5074	CRA	Brookfield Dr.	6	Asbestos Cement	312	59	2.43 out of 5	\$345	\$107,640	
Distribution Mains	P-5080	CRA	Brookfield Dr.	6	Asbestos Cement	961	59	2.43 out of 5	\$345	\$331,545	
Distribution Mains	P-5081	CRA	Burdick Dr.	8	Asbestos Cement	219	44	1.72 out of 5	\$345	\$75,555	
Distribution Mains	P-5083	CRA	Burdick Dr.	8	Asbestos Cement	259	44	1.72 out of 5	\$345	\$89,355	
Distribution Mains	P-5085	CRA	Burdick Dr.	8	Asbestos Cement	261	44	1.72 out of 5	\$345	\$90,045	
Distribution Mains	P-5089	CRA	Burdick Dr.	8	Asbestos Cement	652	44	1.72 out of 5	\$345	\$224,940	
Distribution Mains	P-5090	CRA	Burdick Dr.	8	Asbestos Cement	278	44	1.72 out of 5	\$345	\$95,910	
Distribution Mains	P-5092	CRA	Burdick Dr.	8	Asbestos Cement	1,167	44	1.72 out of 5	\$345	\$402,615	
Distribution Mains	P-5110	CRA	Candle Dr.	8	Asbestos Cement	412	37	1.58 out of 5	\$345	\$142,140	
Distribution Mains	P-5049	CRA	Capeway Rd.	6	Asbestos Cement	197	65	2.58 out of 5	\$345	\$67,965	
Distribution Mains	P-5109	CRA	Carriage Dr.	8	Asbestos Cement	256	39	1.58 out of 5	\$345	\$88,320	
Distribution Mains	P-5111	CRA	Carriage Dr.	8	Asbestos Cement	260	39	1.58 out of 5	\$345	\$89,700	
Distribution Mains	P-5113	CRA	Carriage Dr.	8	Asbestos Cement	174	39	1.58 out of 5	\$345	\$60,030	
Distribution Mains	P-5115	CRA	Chapel Dr.	6	PVC	231	26	1.15 out of 5	\$345	\$79,695	
Distribution Mains	P-5032	CRA	Ellison St.	8	Ductile Iron	276	12	0 out of 5	N/A	\$0	
Distribution Mains	P-5038	CRA	Ellison St.	8	Ductile Iron	1,239	12	0 out of 5	N/A	\$0	
Distribution Mains	P-5036	CRA	Esther St.	8	Ductile Iron	226	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5019	CRA	Exchange St.	8	Ductile Iron	290	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5057	CRA	Fairway Dr.	8	Ductile Iron	162	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5060	CRA	Fairway Dr.	8	Ductile Iron	506	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5061	CRA	Fairway Dr.	8	Ductile Iron	135	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5022	CRA	Fruit St.	8	Ductile Iron	210	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5162	CRA	Fruit St.	8	Ductile Iron	31	12	0 out of 5	N/A	\$0	
Distribution Mains	P-5163	CRA	Fruit St.	8	Ductile Iron	104	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5075	CRA	Gaunt Dr.	6	Asbestos Cement	240	60	2.58 out of 5	\$345	\$82,800	
Distribution Mains	P-5187	CRA	Gaunt Dr.	6	Ductile Iron	12	1	0.71 out of 5	\$345	\$4,140	
Distribution Mains	P-5076	CRA	Gaunt Dr.	8	Ductile Iron	61	1	0 out of 5	N/A	\$0	
Distribution Mains	P-5059	CRA	Green Ct.	8	Ductile Iron	337	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5105	CRA	Greenview Rd.	8	Asbestos Cement	241	39	1.58 out of 5	\$345	\$83,145	
Distribution Mains	P-5118	CRA	Greenview Rd.	8	Asbestos Cement	391	39	1.58 out of 5	\$345	\$134,895	
Distribution Mains	P-5185	CRA	Hagen Ave.	8	Ductile Iron	88	41	0.29 out of 5	N/A	\$0	
Distribution Mains	P-5058	CRA	Hagen Ave.	8	Ductile Iron	270	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5142	CRA	Hall Ave.	6	PVC	140	29	1.15 out of 5	\$345	\$48,300	
Distribution Mains	P-5123	CRA	Hall Ave.	6	Ductile Iron	263	2	0.71 out of 5	\$345	\$90,735	
Distribution Mains	P-5195	CRA	Hall Ave.	8	Ductile Iron	312	2	0 out of 5	N/A	\$0	
Distribution Mains	P-5112	CRA	Hardpoint Rd.	8	Asbestos Cement	432	38	1.58 out of 5	\$345	\$149,040	
Distribution Mains	P-5007	CRA	Harrison Ave.	8	Ductile Iron	223	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5008	CRA	Harrison Ave.	8	Ductile Iron	248	11	0 out of 5	N/A	\$0	
Transmission Mains	P-5121	CRA	Hope Rd.	12	Ductile Iron	511	2	0 out of 5	N/A	\$0	
Distribution Mains	P-5122	CRA	Hope Rd.	8	Ductile Iron	554	2	0 out of 5	N/A	\$0	
Distribution Mains	P-5124	CRA	Hope Rd.	8	Ductile Iron	870	2	0 out of 5	N/A	\$0	
Distribution Mains	P-5127	CRA	Hope Rd.	8	Ductile Iron	125	2	0 out of 5	N/A	\$0	
Distribution Mains	P-5128	CRA	Hope Rd.	8	Ductile Iron	349	2	0 out of 5	N/A	\$0	
Distribution Mains	P-5129	CRA	Hope Rd.	8	Ductile Iron	580	2	0 out of 5	N/A	\$0	
Distribution Mains	P-5130	CRA	Hope Rd. PS	3	Ductile Iron	161	15	1.43 out of 5	\$345	\$55,545	
Distribution Mains	P-5143	CRA	Hope Rd. PS	3	Ductile Iron	124	15	1.43 out of 5	\$345	\$42,780	
Distribution Mains	P-5144	CRA	Hope Rd. PS	3	Ductile Iron	161	15	1.43 out of 5	\$345	\$55,545	
Distribution Mains	P-5009	CRA	Lincoln Park Ave.	6	Asbestos Cement	1,127	43	3.14 out of 5	\$345	\$388,815	
Distribution Mains	P-5159	CRA	Lincoln Park Ave.	8	Ductile Iron	242	10	0.71 out of 5	\$345	\$83,490	
Distribution Mains	P-5126	CRA	Lippitt Ave.	6	Asbestos Cement	1,215	39	2.29 out of 5	\$345	\$419,175	
Transmission Mains	P-5194	CRA	Locust Ct.	12	Cast iron	353	128	1.87 out of 5	\$345	\$121,785	
Distribution Mains	P-5029	CRA	Loring St.	8	Ductile Iron	238	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5031	CRA	Loring St.	8	Ductile Iron	250	4	0 out of 5	N/A	\$0	
Transmission Mains	P-5192	CRA	Main St.	12	Cast iron	352	128	1.87 out of 5	\$345	\$121,440	
Transmission Mains	P-5193	CRA	Main St.	12	Cast iron	968	128	1.87 out of 5	\$345	\$333,960	
Distribution Mains	P-5125	CRA	Main St.	8	Ductile Iron	1,693	1	0 out of 5	N/A	\$0	
Distribution Mains	P-5077	CRA	Manor Rd.	6	Asbestos Cement	807	60	2.58 out of 5	\$345	\$278,415	
Distribution Mains	P-5098	CRA	Moon Ave.	6	Cast iron	170	86	2.43 out of 5	\$345	\$58,650	
Distribution Mains	P-5191	CRA	New London Ave.	6	Asbestos Cement	161	60	2.58 out of 5	\$345	\$55,545	
Distribution Mains	P-5156	CRA	New London Ave.	10	Cast iron	130	86	1.72 out of 5	\$345	\$44,850	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-5186	CRA	New London Ave.	10	Cast iron	40	86	1.72 out of 5	\$345	\$13,800	
Distribution Mains	P-5190	CRA	New London Ave.	6	Ductile Iron	32	10	0.71 out of 5	\$345	\$11,040	
Transmission Mains	P-5062	CRA	New London Ave.	12	Ductile Iron	1,031	11	0 out of 5	N/A	\$0	
Transmission Mains	P-5103	CRA	New London Ave.	12	Ductile Iron	588	11	0 out of 5	N/A	\$0	
Transmission Mains	P-5188	CRA	New London Ave.	12	Ductile Iron	466	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5189	CRA	New London Ave.	8	Ductile Iron	30	10	0 out of 5	N/A	\$0	
Distribution Mains	P-5138	CRA	Normandy Dr.	6	Asbestos Cement	764	64	2.58 out of 5	\$345	\$263,580	
Distribution Mains	P-5182	CRA	Normandy Dr.	6	Asbestos Cement	275	64	2.58 out of 5	\$345	\$94,875	
Distribution Mains	P-5183	CRA	Normandy Dr.	6	Asbestos Cement	164	64	2.58 out of 5	\$345	\$56,580	
Distribution Mains	P-5184	CRA	Normandy Dr.	1	Copper	156	64	2.44 out of 5	\$345	\$53,820	
Transmission Mains	P-5054	CRA	Oaklawn Ave.	12	Cast iron	315	86	1.72 out of 5	\$345	\$108,675	
Distribution Mains	P-5093	CRA	Oaklawn Ave.	10	Cast iron	402	86	1.72 out of 5	\$345	\$138,690	
Transmission Mains	P-5155	CRA	Oaklawn Ave.	12	Cast iron	894	86	1.72 out of 5	\$345	\$308,430	
Transmission Mains	P-5045	CRA	Oaklawn Ave.	12	Ductile Iron	224	12	0 out of 5	N/A	\$0	
Transmission Mains	P-5050	CRA	Oaklawn Ave.	12	Ductile Iron	776	12	0 out of 5	N/A	\$0	
Transmission Mains	P-5052	CRA	Oaklawn Ave.	12	Ductile Iron	258	12	0 out of 5	N/A	\$0	
Transmission Mains	P-5055	CRA	Oaklawn Ave.	12	Ductile Iron	1,530	11	0 out of 5	N/A	\$0	
Transmission Mains	P-5056	CRA	Oaklawn Ave.	12	Ductile Iron	255	11	0 out of 5	N/A	\$0	
Transmission Mains	P-5139	CRA	Oaklawn Ave.	12	Ductile Iron	273	11	0 out of 5	N/A	\$0	
Transmission Mains	P-5173	CRA	Oaklawn Ave.	12	Ductile Iron	338	12	0 out of 5	N/A	\$0	
Transmission Mains	P-5177	CRA	Oaklawn Ave.	12	Ductile Iron	92	12	0 out of 5	N/A	\$0	
Distribution Mains	P-5136	CRA	Oaklawn Master Meter	8	Ductile Iron	30	10	0 out of 5	N/A	\$0	
Transmission Mains	P-5137	CRA	Oaklawn Master Meter	12	Ductile Iron	67	12	0 out of 5	N/A	\$0	
Transmission Mains	P-5174	CRA	Oaklawn Master Meter	12	Ductile Iron	48	10	0 out of 5	N/A	\$0	
Distribution Mains	P-5175	CRA	Oaklawn Master Meter	8	Ductile Iron	41	10	0 out of 5	N/A	\$0	
Distribution Mains	P-5179	CRA	Old Spring Rd.	1.5	Copper	141	86	2.58 out of 5	\$345	\$48,645	
Distribution Mains	P-5180	CRA	Old Spring Rd.	1.5	Copper	132	86	2.58 out of 5	\$345	\$45,540	
Distribution Mains	P-5181	CRA	Old Spring Rd.	1.5	Copper	96	86	2.58 out of 5	\$345	\$33,120	
Transmission Mains	P-5046	CRA	Old Spring Rd.	12	Cast iron	562	86	1.72 out of 5	\$345	\$193,890	
Transmission Mains	P-5048	CRA	Old Spring Rd.	12	Cast iron	508	86	1.72 out of 5	\$345	\$175,260	
Transmission Mains	P-5176	CRA	Old Spring Rd.	12	Cast iron	49	86	1.72 out of 5	\$345	\$16,905	
Transmission Mains	P-5178	CRA	Old Spring Rd.	12	Cast iron	232	86	1.72 out of 5	\$345	\$80,040	
Distribution Mains	P-5010	CRA	Olive St.	8	Ductile Iron	224	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5150	CRA	Olive St.	8	Ductile Iron	249	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5067	CRA	Ontario Ave.	6	Asbestos Cement	243	55	2.43 out of 5	\$345	\$83,835	
Distribution Mains	P-5082	CRA	Ontario Ave.	6	Asbestos Cement	270	44	2.43 out of 5	\$345	\$93,150	
Distribution Mains	P-5001	CRA	Oriole Ave.	8	Ductile Iron	249	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5002	CRA	Oriole Ave.	8	Ductile Iron	239	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5004	CRA	Oriole Ave.	8	Ductile Iron	241	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5084	CRA	Rainbow Rd.	6	Asbestos Cement	188	43	2.43 out of 5	\$345	\$64,860	
Distribution Mains	P-5114	CRA	Red Barn Ct.	8	Asbestos Cement	312	37	1.58 out of 5	\$345	\$107,640	
Distribution Mains	P-5116	CRA	Red Barn Ct.	8	Asbestos Cement	144	37	1.58 out of 5	\$345	\$49,680	
Distribution Mains	P-5117	CRA	Red Barn Ct.	8	Asbestos Cement	183	37	1.58 out of 5	\$345	\$63,135	
Distribution Mains	P-5091	CRA	Redfern Dr.	8	Ductile Iron	92	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5172	CRA	Redfern Dr.	8	Ductile Iron	137	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5016	CRA	Searle Ave.	8	Ductile Iron	253	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5018	CRA	Searle Ave.	8	Ductile Iron	343	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5151	CRA	Searle Ave.	8	Ductile Iron	313	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5160	CRA	Searle Ave.	8	Ductile Iron	281	10	0 out of 5	N/A	\$0	
Transmission Mains	P-5119	CRA	Seven Mile Rd.	12	Ductile Iron	45	15	0 out of 5	N/A	\$0	
Transmission Mains	P-5120	CRA	Seven Mile Rd.	16	Ductile Iron	1,200	15	0 out of 5	N/A	\$0	
Transmission Mains	P-5196	CRA	Seven Mile Rd.	16	Ductile Iron	321	15	0 out of 5	N/A	\$0	
Transmission Mains	P-5197	CRA	Seven Mile Rd.	16	Ductile Iron	2,236	15	0 out of 5	N/A	\$0	
Transmission Mains	P-5198	CRA	Seven Mile Rd.	16	Ductile Iron	28	2	0 out of 5	N/A	\$0	
Transmission Mains	P-5133	CRA	Seven Mile Rd. Tanks	16	Ductile Iron	162	15	0 out of 5	N/A	\$0	
Distribution Mains	P-5104	CRA	Southview Ter.	8	Asbestos Cement	354	34	1.58 out of 5	\$345	\$122,130	
Distribution Mains	P-5167	CRA	Stoneham Ct.	6	Asbestos Cement	68	75	2.58 out of 5	\$345	\$23,460	
Distribution Mains	P-5166	CRA	Stoneham Ct.	8	Ductile Iron	40	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5023	CRA	Stoneham St.	8	Ductile Iron	549	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5087	CRA	Sunkist Cir.	8	Asbestos Cement	95	43	1.72 out of 5	\$345	\$32,775	
Distribution Mains	P-5086	CRA	Sunrise Dr.	8	Asbestos Cement	311	42	1.72 out of 5	\$345	\$107,295	
Distribution Mains	P-5088	CRA	Sunrise Dr.	8	Asbestos Cement	305	42	1.72 out of 5	\$345	\$105,225	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-5011	CRA	Turner Ave.	8	Ductile Iron	449	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5012	CRA	Turner Ave.	8	Ductile Iron	449	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5014	CRA	Turner Ave.	8	Ductile Iron	485	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5000	CRA	Turner Ave.	8	Ductile Iron	445	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5106	CRA	Verdant Dr.	8	Asbestos Cement	357	38	1.58 out of 5	\$345	\$123,165	
Distribution Mains	P-5107	CRA	Verdant Dr.	8	Asbestos Cement	265	38	1.58 out of 5	\$345	\$91,425	
Distribution Mains	P-5108	CRA	Verdant Dr.	8	Asbestos Cement	589	38	1.58 out of 5	\$345	\$203,205	
Distribution Mains	P-5068	CRA	Versailles St.	6	Asbestos Cement	271	45	2.43 out of 5	\$345	\$93,495	
Distribution Mains	P-5069	CRA	Versailles St.	6	Asbestos Cement	477	45	2.43 out of 5	\$345	\$164,565	
Distribution Mains	P-5070	CRA	Versailles St.	6	Asbestos Cement	473	45	2.43 out of 5	\$345	\$163,185	
Distribution Mains	P-5071	CRA	Versailles St.	6	Asbestos Cement	53	45	2.43 out of 5	\$345	\$18,285	
Distribution Mains	P-5013	CRA	Vinton Ave.	8	Ductile Iron	711	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5148	CRA	Vinton Ave.	8	Ductile Iron	444	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5149	CRA	Vinton Ave.	8	Ductile Iron	449	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5064	CRA	Warfield Ave.	6	Asbestos Cement	190	61	2.58 out of 5	\$345	\$65,550	
Distribution Mains	P-5065	CRA	Warfield Ave.	6	Asbestos Cement	111	61	2.58 out of 5	\$345	\$38,295	
Distribution Mains	P-5063	CRA	Warfield Ave.	6	Cast iron	227	78	2.29 out of 5	\$345	\$78,315	
Distribution Mains	P-5024	CRA	Warren Ave.	8	Asbestos Cement	32	75	1.87 out of 5	\$345	\$11,040	
Distribution Mains	P-5025	CRA	Warren Ave.	8	Ductile Iron	354	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5028	CRA	Warren Ave.	8	Ductile Iron	246	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5035	CRA	Warren Ave.	8	Ductile Iron	224	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5037	CRA	Warren Ave.	8	Ductile Iron	846	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5141	CRA	Warren Ave.	8	Ductile Iron	95	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5164	CRA	Warren Ave.	8	Ductile Iron	227	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5165	CRA	Warren Ave.	8	Ductile Iron	19	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5170	CRA	Warren Ave.	8	Ductile Iron	211	4	0 out of 5	N/A	\$0	
Distribution Mains	P-5171	CRA	Warren Ct.	6	Ductile Iron	162	4	0.71 out of 5	\$345	\$55,890	
Distribution Mains	P-5053	CRA	Westbrook Rd.	8	Ductile Iron	269	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5017	CRA	Wheelock Ave.	8	Ductile Iron	212	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5152	CRA	Wheelock Ave.	8	Ductile Iron	337	11	0 out of 5	N/A	\$0	
Transmission Mains	P-5020	CRA	Wilbur Ave.	12	Ductile Iron	513	12	0 out of 5	N/A	\$0	
Transmission Mains	P-5021	CRA	Wilbur Ave.	12	Ductile Iron	254	12	0 out of 5	N/A	\$0	
Transmission Mains	P-5043	CRA	Wilbur Ave.	12	Ductile Iron	428	12	0 out of 5	N/A	\$0	
Distribution Mains	P-5161	CRA	Wilbur Ave.	8	Ductile Iron	242	12	0 out of 5	N/A	\$0	
Distribution Mains	P-5051	CRA	Willow Dr.	8	Ductile Iron	221	11	0 out of 5	N/A	\$0	
Distribution Mains	P-5066	CRA	Woodlawn Dr.	6	Asbestos Cement	794	60	2.58 out of 5	\$345	\$273,930	
Distribution Mains	P-5073	CRA	Woodlawn Dr.	6	Asbestos Cement	508	60	2.58 out of 5	\$345	\$175,260	
Distribution Mains	P-4101	EG	Adirondack Dr.	8	Asbestos Cement	447	38	1.58 out of 5	\$345	\$154,215	
Distribution Mains	P-4102	EG	Adirondack Dr.	8	Asbestos Cement	725	38	1.58 out of 5	\$345	\$250,125	
Distribution Mains	P-4103	EG	Adirondack Dr.	8	Asbestos Cement	539	38	1.58 out of 5	\$345	\$185,955	
Distribution Mains	P-4090	EG	Adirondack Dr.	8	Ductile Iron	269	33	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4094	EG	Adirondack Dr.	8	Ductile Iron	460	33	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4095	EG	Adirondack Dr.	8	Ductile Iron	1,463	33	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4097	EG	Adirondack Dr.	8	Ductile Iron	699	33	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4448	EG	Alder Ct.	6	Asbestos Cement	218	43	2.43 out of 5	\$345	\$75,210	
Distribution Mains	P-4358	EG	Allen Dr.	6	Asbestos Cement	415	46	2.43 out of 5	\$345	\$143,175	
Distribution Mains	P-4374	EG	Allen Dr.	6	Asbestos Cement	250	46	2.43 out of 5	\$345	\$86,250	
Distribution Mains	P-4379	EG	Allen Dr.	6	Asbestos Cement	448	46	2.43 out of 5	\$345	\$154,560	
Distribution Mains	P-4380	EG	Allen Dr.	6	Asbestos Cement	424	46	2.43 out of 5	\$345	\$146,280	
Distribution Mains	P-4480	EG	Apple Tree Ct.	6	Asbestos Cement	331	43	3.14 out of 5	\$345	\$114,195	
Distribution Mains	P-4051	EG	Arbor Way	8	Asbestos Cement	609	42	1.72 out of 5	\$345	\$210,105	
Distribution Mains	P-4714	EG	Arrowhead Dr.	8	Asbestos Cement	992	41	1.72 out of 5	\$345	\$342,240	
Distribution Mains	P-4715	EG	Arrowhead Dr.	8	Ductile Iron	150	17	0 out of 5	N/A	\$0	
Distribution Mains	P-4718	EG	Arrowhead Dr.	8	Ductile Iron	72	17	0 out of 5	N/A	\$0	
Distribution Mains	P-4704	EG	Ashbrook Run	8	Ductile Iron	487	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4369	EG	Atherton Rd.	6	Asbestos Cement	979	57	3.14 out of 5	\$345	\$337,755	
Distribution Mains	P-4334	EG	Avenger Dr.	6	Asbestos Cement	274	45	2.43 out of 5	\$345	\$94,530	
Distribution Mains	P-4193	EG	Ayrault Rd.	8	Ductile Iron	126	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4196	EG	Ayrault Rd.	8	Ductile Iron	234	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4445	EG	Balsam Dr.	6	Asbestos Cement	1,161	45	2.43 out of 5	\$345	\$400,545	
Distribution Mains	P-4446	EG	Balsam Dr.	6	Asbestos Cement	218	45	2.43 out of 5	\$345	\$75,210	
Distribution Mains	P-4451	EG	Barrows Dr.	6	Asbestos Cement	664	53	2.43 out of 5	\$345	\$229,080	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-4979	EG	Barrows Dr.	6	Asbestos Cement	81	53	2.43 out of 5	\$345	\$27,945	
Distribution Mains	P-4427	EG	Bayberry Dr.	6	Asbestos Cement	1,145	45	2.43 out of 5	\$345	\$395,025	
Distribution Mains	P-4004	EG	Bear Swamp Rd.	8	Asbestos Cement	822	36	1.58 out of 5	\$345	\$283,590	
Transmission Mains	P-4005	EG	Bear Swamp Rd. Easement	12	Ductile Iron	440	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4815	EG	Beechcrest Rd.	8	Ductile Iron	800	9	0 out of 5	N/A	\$0	
Distribution Mains	P-4878	EG	Beechcrest Rd.	8	Ductile Iron	117	9	0 out of 5	N/A	\$0	
Distribution Mains	P-4649	EG	Bennett St.	8	Ductile Iron	241	14	0 out of 5	N/A	\$0	
Transmission Mains	P-4621	EG	Bicknell Ave.	12	Ductile Iron	357	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4898	EG	Bicknell Ave.	8	Ductile Iron	19	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4418	EG	Birchwood Way	6	Asbestos Cement	363	45	2.43 out of 5	\$345	\$125,235	
Distribution Mains	P-4423	EG	Birchwood Way	6	Asbestos Cement	288	45	2.43 out of 5	\$345	\$99,360	
Distribution Mains	P-4424	EG	Birchwood Way	6	Asbestos Cement	260	45	2.43 out of 5	\$345	\$89,700	
Distribution Mains	P-4450	EG	Blueberry Dr.	6	Asbestos Cement	1,032	53	2.43 out of 5	\$345	\$356,040	
Distribution Mains	P-4452	EG	Blueberry Dr.	6	Asbestos Cement	567	53	2.43 out of 5	\$345	\$195,615	
Distribution Mains	P-40033	EG	Bond St.	1	Copper	320	45	2.29 out of 5	\$345	\$110,400	
Transmission Mains	P-4879	EG	Boulder Way	20	Ductile Iron	632	31	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4992	EG	Boulder Way	20	Ductile Iron	1,219	31	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4329	EG	Bow St.	8	Asbestos Cement	2,038	45	2.43 out of 5	\$345	\$703,110	
Distribution Mains	P-4330	EG	Bow St.	8	Asbestos Cement	396	45	1.72 out of 5	\$345	\$136,620	
Distribution Mains	P-4301	EG	Boxwood Dr.	6	Asbestos Cement	981	46	3.14 out of 5	\$345	\$338,445	
Distribution Mains	P-4568	EG	Brayton St.	8	Ductile Iron	853	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4597	EG	Bridge St.	8	Ductile Iron	218	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4693	EG	Bridge St.	8	Ductile Iron	242	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4517	EG	Brisas Cir.	8	Asbestos Cement	370	47	1.72 out of 5	\$345	\$127,650	
Distribution Mains	P-4518	EG	Brisas Cir.	8	Asbestos Cement	690	47	1.72 out of 5	\$345	\$238,050	
Distribution Mains	P-4519	EG	Brisas Cir.	8	Asbestos Cement	157	47	1.72 out of 5	\$345	\$54,165	
Distribution Mains	P-4520	EG	Brisas Cir.	8	Asbestos Cement	782	47	1.72 out of 5	\$345	\$269,790	
Distribution Mains	P-4151	EG	Brookfield Ct.	8	Ductile Iron	628	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4509	EG	Brookside Dr.	6	Asbestos Cement	503	64	3.29 out of 5	\$345	\$173,535	
Distribution Mains	P-4508	EG	Brookside Dr.	6	Asbestos Cement	735	64	2.58 out of 5	\$345	\$253,575	
Distribution Mains	P-4349	EG	Bunker Hill Ln.	8	Asbestos Cement	590	50	1.72 out of 5	\$345	\$203,550	
Distribution Mains	P-4201	EG	Canonicus Tr.	8	Ductile Iron	549	15	0 out of 5	N/A	\$0	
Distribution Mains	P-4205	EG	Canonicus Tr.	8	Ductile Iron	503	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4049	EG	Cardinal Ln.	8	Asbestos Cement	711	42	2.43 out of 5	\$345	\$245,295	
Distribution Mains	P-4047	EG	Cardinal Ln.	8	Asbestos Cement	397	42	1.72 out of 5	\$345	\$136,965	
Distribution Mains	P-4068	EG	Cardinal Ln. Easement	8	Asbestos Cement	253	42	1.72 out of 5	\$345	\$87,285	
Transmission Mains	P-40043	EG	Carrs Pond Rd.	20	Ductile Iron	22	13	0 out of 5	N/A	\$0	
Transmission Mains	P-40044	EG	Carrs Pond Rd.	16	Ductile Iron	41	13	0 out of 5	N/A	\$0	
Distribution Mains	P-4096	EG	Cartier Ct.	6	Ductile Iron	412	28	0.86 out of 5	\$345	\$142,140	
Distribution Mains	P-4650	EG	Castle St.	8	Ductile Iron	236	14	0 out of 5	N/A	\$0	
Distribution Mains	P-4654	EG	Castle St.	8	Ductile Iron	332	14	0 out of 5	N/A	\$0	
Distribution Mains	P-4091	EG	Cavalier Dr.	8	Ductile Iron	851	33	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4093	EG	Cavalier Dr.	8	Ductile Iron	1,113	33	0.15 out of 5	N/A	\$0	
Distribution Mains	P-40030	EG	Cedar Ave.	8	Asbestos Cement	1,128	48	1.72 out of 5	\$345	\$389,160	
Distribution Mains	P-4437	EG	Cedar Ave.	8	Asbestos Cement	494	48	1.72 out of 5	\$345	\$170,430	
Distribution Mains	P-4499	EG	Cedar Ave.	8	Asbestos Cement	626	48	1.72 out of 5	\$345	\$215,970	
Distribution Mains	P-4501	EG	Cedar Ave.	8	Asbestos Cement	1,097	48	1.72 out of 5	\$345	\$378,465	
Distribution Mains	P-4524	EG	Cedar Ave.	8	Asbestos Cement	686	48	1.72 out of 5	\$345	\$236,670	
Distribution Mains	P-4503	EG	Cedar Ave.	8	Ductile Iron	813	35	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4523	EG	Cedar Ave.	8	Ductile Iron	1,633	35	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4696	EG	Cedar Ave.	8	Ductile Iron	260	18	0 out of 5	N/A	\$0	
Distribution Mains	P-4041	EG	Chestnut Dr.	8	Asbestos Cement	353	46	1.72 out of 5	\$345	\$121,785	
Distribution Mains	P-4055	EG	Chestnut Dr.	8	Asbestos Cement	155	46	1.72 out of 5	\$345	\$53,475	
Distribution Mains	P-4257	EG	Chestnut Dr.	8	Asbestos Cement	628	46	1.72 out of 5	\$345	\$216,660	
Distribution Mains	P-4258	EG	Chestnut Dr.	8	Asbestos Cement	431	46	1.72 out of 5	\$345	\$148,695	
Distribution Mains	P-4261	EG	Chestnut Dr.	8	Asbestos Cement	1,120	46	1.72 out of 5	\$345	\$386,400	
Distribution Mains	P-4270	EG	Chestnut Dr.	8	Asbestos Cement	541	46	1.72 out of 5	\$345	\$186,645	
Distribution Mains	P-4271	EG	Chestnut Dr.	8	Asbestos Cement	432	46	1.72 out of 5	\$345	\$149,040	
Distribution Mains	P-4161	EG	Chief Botelho Ct.	8	Ductile Iron	410	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4569	EG	Church St.	8	Ductile Iron	275	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4570	EG	Church St.	8	Ductile Iron	245	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4684	EG	Church St.	8	Ductile Iron	305	12	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-4686	EG	Church St.	8	Ductile Iron	754	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4688	EG	Church St.	8	Ductile Iron	297	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4965	EG	Church St.	8	Ductile Iron	37	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4477	EG	Cindyann Dr.	8	Asbestos Cement	867	51	2.43 out of 5	\$345	\$299,115	
Distribution Mains	P-4345	EG	Cindyann Dr.	8	Asbestos Cement	498	51	1.72 out of 5	\$345	\$171,810	
Distribution Mains	P-4387	EG	Cindyann Dr.	8	Asbestos Cement	1,005	51	1.72 out of 5	\$345	\$346,725	
Distribution Mains	P-4388	EG	Cindyann Dr.	8	Asbestos Cement	1,795	51	1.72 out of 5	\$345	\$619,275	
Distribution Mains	P-4479	EG	Cindyann Dr.	8	Asbestos Cement	145	51	1.72 out of 5	\$345	\$50,025	
Distribution Mains	P-4481	EG	Cindyann Dr.	8	Asbestos Cement	253	51	1.72 out of 5	\$345	\$87,285	
Distribution Mains	P-4482	EG	Cindyann Dr.	8	Asbestos Cement	405	51	1.72 out of 5	\$345	\$139,725	
Distribution Mains	P-4980	EG	Cindyann Dr.	8	Asbestos Cement	202	51	1.72 out of 5	\$345	\$69,690	
Distribution Mains	P-4982	EG	Cindyann Dr.	8	Asbestos Cement	704	51	1.72 out of 5	\$345	\$242,880	
Transmission Mains	P-4149	EG	Clauson Ct. Easement	16	Ductile Iron	1,902	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4117	EG	Clemente Dr.	6	Asbestos Cement	505	51	2.43 out of 5	\$345	\$174,225	
Distribution Mains	P-4142	EG	Clemente Dr.	6	Asbestos Cement	327	51	2.43 out of 5	\$345	\$112,815	
Transmission Mains	P-4591	EG	Cliff St.	12	Ductile Iron	455	18	0 out of 5	N/A	\$0	
Distribution Mains	P-4485	EG	Clover Hill Ct.	6	Asbestos Cement	157	38	2.29 out of 5	\$345	\$54,165	
Distribution Mains	P-4430	EG	Coddington Ct.	6	Asbestos Cement	185	44	2.43 out of 5	\$345	\$63,825	
Distribution Mains	P-40031	EG	Cole Jr. High School	8	Asbestos Cement	28	48	1.72 out of 5	\$345	\$9,660	
Distribution Mains	P-4203	EG	Cononchet Tr.	8	Ductile Iron	337	3	0 out of 5	N/A	\$0	
Distribution Mains	P-40023	EG	Cora St.	6	Ductile Iron	19	15	0.71 out of 5	\$345	\$6,555	
Distribution Mains	P-40025	EG	Cora St.	6	Ductile Iron	40	15	0.71 out of 5	\$345	\$13,800	
Distribution Mains	P-4404	EG	Cora St.	8	Ductile Iron	855	15	0 out of 5	N/A	\$0	
Distribution Mains	P-4405	EG	Cora St.	8	Ductile Iron	342	15	0 out of 5	N/A	\$0	
Distribution Mains	P-4163	EG	Corr Way	8	Ductile Iron	551	21	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4433	EG	Country Ct.	6	Asbestos Cement	148	44	2.43 out of 5	\$345	\$51,060	
Distribution Mains	P-4804	EG	Courthouse Ln.	6	Ductile Iron	175	19	0.71 out of 5	\$345	\$60,375	
Distribution Mains	P-4340	EG	Crest Ridge Dr.	8	Asbestos Cement	880	45	2.43 out of 5	\$345	\$303,600	
Distribution Mains	P-4341	EG	Crest Ridge Dr.	8	Asbestos Cement	516	45	1.72 out of 5	\$345	\$178,020	
Distribution Mains	P-4990	EG	Crest Ridge Dr.	8	Asbestos Cement	118	45	1.72 out of 5	\$345	\$40,710	
Distribution Mains	P-4459	EG	Cresthill Dr.	6	Asbestos Cement	613	56	2.43 out of 5	\$345	\$211,485	
Distribution Mains	P-4461	EG	Cresthill Dr.	6	Asbestos Cement	366	56	2.43 out of 5	\$345	\$126,270	
Distribution Mains	P-4660	EG	Crompton Ave.	6	Ductile Iron	1,530	27	0.86 out of 5	\$345	\$527,850	
Distribution Mains	P-4930	EG	Crompton Ave.	6	Ductile Iron	105	27	0.86 out of 5	\$345	\$36,225	
Transmission Mains	P-4184	EG	Crompton Rd.	16	Ductile Iron	209	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4185	EG	Crompton Rd.	16	Ductile Iron	3,115	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4673	EG	Crompton Rd.	16	Ductile Iron	270	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4619	EG	Crop St.	12	Ductile Iron	247	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4415	EG	Crossways Rd.	6	Asbestos Cement	170	55	2.43 out of 5	\$345	\$58,650	
Distribution Mains	P-4393	EG	Crossways Rd.	6	Ductile Iron	79	17	0.71 out of 5	\$345	\$27,255	
Distribution Mains	P-4700	EG	Crossways Rd.	6	Ductile Iron	261	17	0.71 out of 5	\$345	\$90,045	
Distribution Mains	P-4122	EG	Crystal Ct.	6	Asbestos Cement	137	39	2.29 out of 5	\$345	\$47,265	
Distribution Mains	P-4121	EG	Crystal Dr.	8	Asbestos Cement	943	39	1.58 out of 5	\$345	\$325,335	
Distribution Mains	P-4123	EG	Crystal Dr.	8	Asbestos Cement	644	39	1.58 out of 5	\$345	\$222,180	
Distribution Mains	P-4256	EG	Cypruss Ct.	6	Asbestos Cement	359	46	2.43 out of 5	\$345	\$123,855	
Distribution Mains	P-4456	EG	Dalehill Dr.	6	Asbestos Cement	458	54	3.86 out of 5	\$345	\$158,010	
Distribution Mains	P-4453	EG	Dalehill Dr.	6	Asbestos Cement	403	54	2.43 out of 5	\$345	\$139,035	
Distribution Mains	P-4455	EG	Dalehill Dr.	8	Asbestos Cement	196	54	1.72 out of 5	\$345	\$67,620	
Distribution Mains	P-4462	EG	Dalehill Dr.	8	Asbestos Cement	438	54	1.72 out of 5	\$345	\$151,110	
Distribution Mains	P-4502	EG	Dalehill Dr.	8	Asbestos Cement	594	54	1.72 out of 5	\$345	\$204,930	
Distribution Mains	P-4136	EG	Darl Ct.	8	PVC	339	28	0.44 out of 5	\$345	\$116,955	
Distribution Mains	P-4607	EG	Dedford St.	6	Asbestos Cement	141	44	2.43 out of 5	\$345	\$48,645	
Distribution Mains	P-4470	EG	Deep Meadow Ln.	8	Ductile Iron	220	14	0 out of 5	N/A	\$0	
Distribution Mains	P-4037	EG	Deerfield Dr	8	Asbestos Cement	564	40	1.72 out of 5	\$345	\$194,580	
Distribution Mains	P-4039	EG	Deerfield Dr.	8	Asbestos Cement	581	40	1.72 out of 5	\$345	\$200,445	
Distribution Mains	P-4022	EG	Deerfield Dr.	8	PVC	803	27	0.44 out of 5	\$345	\$277,035	
Distribution Mains	P-4033	EG	Deerfield Dr.	8	PVC	528	27	0.44 out of 5	\$345	\$182,160	
Distribution Mains	P-4035	EG	Deerfield Dr.	8	PVC	642	27	0.44 out of 5	\$345	\$221,490	
Distribution Mains	P-4036	EG	Deerfield Dr.	8	PVC	690	27	0.44 out of 5	\$345	\$238,050	
Distribution Mains	P-4331	EG	Devon Pl.	6	Asbestos Cement	696	45	2.43 out of 5	\$345	\$240,120	
Transmission Mains	P-4180	EG	Division Rd.	12	Asbestos Cement	40	57	1.72 out of 5	\$345	\$13,800	
Transmission Mains	P-4705	EG	Division Rd.	12	Asbestos Cement	328	43	1.72 out of 5	\$345	\$113,160	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-4706	EG	Division Rd.	12	Asbestos Cement	3,590	43	1.72 out of 5	\$345	\$1,238,550	
Transmission Mains	P-4780	EG	Division Rd.	12	Asbestos Cement	602	43	1.72 out of 5	\$345	\$207,690	
Transmission Mains	P-4168	EG	Division Rd.	16	Ductile Iron	2,179	19	0 out of 5	N/A	\$0	
Transmission Mains	P-4754	EG	Division Rd.	16	Ductile Iron	1,276	19	0 out of 5	N/A	\$0	
Transmission Mains	P-4756	EG	Division Rd.	16	Ductile Iron	376	8	0 out of 5	N/A	\$0	
Transmission Mains	P-4849	EG	Division Rd.	16	Ductile Iron	261	8	0 out of 5	N/A	\$0	
Transmission Mains	P-4881	EG	Division Rd.	16	Ductile Iron	534	8	0 out of 5	N/A	\$0	
Transmission Mains	P-4882	EG	Division Rd.	16	Ductile Iron	201	8	0 out of 5	N/A	\$0	
Distribution Mains	P-4539	EG	Division St.	4	Cast iron	327	124	3.3 out of 5	\$345	\$112,815	
Distribution Mains	P-4885	EG	Division St.	2	Cast iron	327	124	3.3 out of 5	\$345	\$112,815	
Distribution Mains	P-4550	EG	Division St.	6	Cast iron	741	128	2.58 out of 5	\$345	\$255,645	
Distribution Mains	P-4893	EG	Division St.	6	Cast iron	205	124	2.58 out of 5	\$345	\$70,725	
Transmission Mains	P-4674	EG	Division St.	12	Asbestos Cement	3,633	57	2.43 out of 5	\$345	\$1,253,385	
Distribution Mains	P-4560	EG	Division St.	8	Cast iron	405	124	1.87 out of 5	\$345	\$139,725	
Distribution Mains	P-4561	EG	Division St.	8	Cast iron	58	124	1.87 out of 5	\$345	\$20,010	
Distribution Mains	P-4562	EG	Division St.	8	Cast iron	267	124	1.87 out of 5	\$345	\$92,115	
Distribution Mains	P-4563	EG	Division St.	8	Cast iron	273	124	1.87 out of 5	\$345	\$94,185	
Distribution Mains	P-4564	EG	Division St.	8	Cast iron	239	124	1.87 out of 5	\$345	\$82,455	
Distribution Mains	P-4567	EG	Division St.	8	Cast iron	256	124	1.87 out of 5	\$345	\$88,320	
Distribution Mains	P-4713	EG	Division St.	8	Cast iron	315	124	1.87 out of 5	\$345	\$108,675	
Transmission Mains	P-4463	EG	Division St.	12	Asbestos Cement	555	57	1.72 out of 5	\$345	\$191,475	
Transmission Mains	P-4465	EG	Division St.	12	Asbestos Cement	564	57	1.72 out of 5	\$345	\$194,580	
Transmission Mains	P-4466	EG	Division St.	12	Asbestos Cement	439	57	1.72 out of 5	\$345	\$151,455	
Transmission Mains	P-4497	EG	Division St.	12	Asbestos Cement	603	57	1.72 out of 5	\$345	\$208,035	
Transmission Mains	P-4498	EG	Division St.	12	Asbestos Cement	530	57	1.72 out of 5	\$345	\$182,850	
Transmission Mains	P-4521	EG	Division St.	12	Asbestos Cement	1,082	57	1.72 out of 5	\$345	\$373,290	
Transmission Mains	P-4526	EG	Division St.	12	Asbestos Cement	809	57	1.72 out of 5	\$345	\$279,105	
Transmission Mains	P-4536	EG	Division St.	12	Asbestos Cement	162	57	1.72 out of 5	\$345	\$55,890	
Transmission Mains	P-4537	EG	Division St.	12	Asbestos Cement	117	57	1.72 out of 5	\$345	\$40,365	
Transmission Mains	P-4538	EG	Division St.	12	Asbestos Cement	686	57	1.72 out of 5	\$345	\$236,670	
Transmission Mains	P-4551	EG	Division St.	12	Asbestos Cement	86	57	1.72 out of 5	\$345	\$29,670	
Transmission Mains	P-4558	EG	Division St.	12	Asbestos Cement	121	57	1.72 out of 5	\$345	\$41,745	
Transmission Mains	P-4559	EG	Division St.	12	Asbestos Cement	250	57	1.72 out of 5	\$345	\$86,250	
Transmission Mains	P-4583	EG	Division St.	12	Asbestos Cement	1,469	57	1.72 out of 5	\$345	\$506,805	
Transmission Mains	P-4602	EG	Division St.	12	Asbestos Cement	486	57	1.72 out of 5	\$345	\$167,670	
Transmission Mains	P-4676	EG	Division St.	12	Asbestos Cement	227	57	1.72 out of 5	\$345	\$78,315	
Transmission Mains	P-4678	EG	Division St.	12	Asbestos Cement	85	57	1.72 out of 5	\$345	\$29,325	
Transmission Mains	P-4701	EG	Division St.	12	Asbestos Cement	778	57	1.72 out of 5	\$345	\$268,410	
Transmission Mains	P-4702	EG	Division St.	12	Asbestos Cement	288	57	1.72 out of 5	\$345	\$99,360	
Distribution Mains	P-4886	EG	Division St.	8	Asbestos Cement	281	57	1.72 out of 5	\$345	\$96,945	
Distribution Mains	P-4894	EG	Division St.	6	Ductile Iron	20	3	0.71 out of 5	\$345	\$6,900	
Transmission Mains	P-4565	EG	Division St.	12	Ductile Iron	228	3	0 out of 5	N/A	\$0	
Transmission Mains	P-4566	EG	Division St.	12	Ductile Iron	243	3	0 out of 5	N/A	\$0	
Transmission Mains	P-4758	EG	Division St.	16	Ductile Iron	170	8	0 out of 5	N/A	\$0	
Distribution Mains	P-4887	EG	Division St.	8	Ductile Iron	24	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4888	EG	Division St.	8	Ductile Iron	23	3	0 out of 5	N/A	\$0	
Transmission Mains	P-4891	EG	Division St.	16	Ductile Iron	32	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4895	EG	Division St.	8	Ductile Iron	17	3	0 out of 5	N/A	\$0	
Transmission Mains	P-4897	EG	Division St.	12	Ductile Iron	22	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4495	EG	Division St. PRV	8	Ductile Iron	208	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4675	EG	Division St. PRV	8	Ductile Iron	105	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4324	EG	Dowling Dr.	8	Asbestos Cement	1,421	45	1.72 out of 5	\$345	\$490,245	
Distribution Mains	P-4616	EG	Duke St.	8	Ductile Iron	376	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4627	EG	Duke St.	8	Ductile Iron	133	14	0 out of 5	N/A	\$0	
Distribution Mains	P-4628	EG	Duke St.	8	Ductile Iron	405	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4644	EG	Duke St.	8	Ductile Iron	402	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4646	EG	Duke St.	8	Ductile Iron	329	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4904	EG	Duke St.	8	Ductile Iron	256	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4034	EG	Eagle Ln.	8	PVC	354	27	0.44 out of 5	\$345	\$122,130	
Distribution Mains	P-4252	EG	Edward Dr.	6	Asbestos Cement	511	51	2.43 out of 5	\$345	\$176,295	
Transmission Mains	P-4236	EG	EG Well	12	Ductile Iron	283	17	0 out of 5	N/A	\$0	
Transmission Mains	P-4237	EG	EG Well	12	Ductile Iron	20	17	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-4238	EG	EG Well	12	Ductile Iron	20	17	0 out of 5	N/A	\$0	
Distribution Mains	P-4553	EG	Eldredge Ave.	8	Ductile Iron	322	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4683	EG	Eldredge Ave.	8	Ductile Iron	496	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4372	EG	Eugene St.	6	Asbestos Cement	923	46	2.43 out of 5	\$345	\$318,435	
Transmission Mains	P-4229	EG	Eugene St.	20	Asbestos Cement	1,186	50	1.72 out of 5	\$345	\$409,170	
Distribution Mains	P-4629	EG	Exchange St.	8	Ductile Iron	430	14	0 out of 5	N/A	\$0	
Distribution Mains	P-4098	EG	Ezechial Carrie Rd.	8	PVC	1,183	30	0.44 out of 5	\$345	\$408,135	
Distribution Mains	P-4335	EG	Fairfield Ave.	6	Ductile Iron	201	16	0.71 out of 5	\$345	\$69,345	
Distribution Mains	P-4342	EG	Fairfield Ave.	6	Ductile Iron	216	16	0.71 out of 5	\$345	\$74,520	
Distribution Mains	P-4348	EG	Fairfield Ave.	6	Ductile Iron	195	16	0.71 out of 5	\$345	\$67,275	
Distribution Mains	P-4350	EG	Fairfield Ave.	6	Ductile Iron	183	16	0.71 out of 5	\$345	\$63,135	
Distribution Mains	P-4038	EG	Falcon Cir.	8	Asbestos Cement	2,055	40	1.72 out of 5	\$345	\$708,975	
Distribution Mains	P-4338	EG	Farifield Ave.	6	Ductile Iron	194	16	0.71 out of 5	\$345	\$66,930	
Distribution Mains	P-4133	EG	Fernwood Dr.	6	Ductile Iron	256	31	0.86 out of 5	\$345	\$88,320	
Transmission Mains	P-4132	EG	Fernwood Dr.	20	Ductile Iron	1,344	31	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4134	EG	Fernwood Dr.	20	Ductile Iron	955	31	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4994	EG	Fernwood Dr.	20	Ductile Iron	205	31	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4468	EG	Field Stone Dr.	6	Ductile Iron	355	14	0.71 out of 5	\$345	\$122,475	
Distribution Mains	P-4946	EG	Fifth Ave.	6	Asbestos Cement	242	46	2.43 out of 5	\$345	\$83,490	
Distribution Mains	P-4666	EG	Fifth St.	6	PVC	340	31	1.15 out of 5	\$345	\$117,300	
Distribution Mains	P-4532	EG	First Ave.	6	Cast iron	310	128	2.58 out of 5	\$345	\$106,950	
Distribution Mains	P-4585	EG	First Ave.	6	Cast iron	204	128	2.58 out of 5	\$345	\$70,380	
Distribution Mains	P-4586	EG	First Ave.	6	Cast iron	241	128	2.58 out of 5	\$345	\$83,145	
Distribution Mains	P-4588	EG	First Ave.	6	Cast iron	222	128	2.58 out of 5	\$345	\$76,590	
Distribution Mains	P-4590	EG	First Ave.	6	Cast iron	747	128	2.58 out of 5	\$345	\$257,715	
Distribution Mains	P-4593	EG	First Ave.	6	Cast iron	260	128	2.58 out of 5	\$345	\$89,700	
Distribution Mains	P-4681	EG	First Ave.	6	Cast iron	216	128	2.58 out of 5	\$345	\$74,520	
Distribution Mains	P-4514	EG	First Ave.	8	Asbestos Cement	274	47	1.72 out of 5	\$345	\$94,530	
Distribution Mains	P-4515	EG	First Ave.	8	Asbestos Cement	445	47	1.72 out of 5	\$345	\$153,525	
Distribution Mains	P-4516	EG	First Ave.	8	Asbestos Cement	13	47	1.72 out of 5	\$345	\$4,485	
Distribution Mains	P-4703	EG	First Ave.	8	Asbestos Cement	396	47	1.72 out of 5	\$345	\$136,620	
Transmission Mains	P-4662	EG	First Ave.	12	Ductile Iron	80	18	0 out of 5	N/A	\$0	
Transmission Mains	P-4940	EG	First Ave.	12	Ductile Iron	61	18	0 out of 5	N/A	\$0	
Distribution Mains	P-4969	EG	First Ave.	8	Ductile Iron	21	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4970	EG	First Ave.	8	Ductile Iron	20	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4280	EG	Flinstone Ct.	6	Asbestos Cement	361	46	2.43 out of 5	\$345	\$124,545	
Distribution Mains	P-4664	EG	Fourth Ave.	6	Asbestos Cement	254	63	2.58 out of 5	\$345	\$87,630	
Distribution Mains	P-4941	EG	Fourth Ave.	6	PVC	744	31	1.15 out of 5	\$345	\$256,680	
Distribution Mains	P-4944	EG	Fourth St.	6	Asbestos Cement	265	63	2.58 out of 5	\$345	\$91,425	
Distribution Mains	P-4945	EG	Fourth St.	6	Asbestos Cement	180	63	2.58 out of 5	\$345	\$62,100	
Distribution Mains	P-4171	EG	Fox Run	8	Asbestos Cement	581	34	1.58 out of 5	\$345	\$200,445	
Distribution Mains	P-4172	EG	Fox Run	8	Asbestos Cement	1,598	34	1.58 out of 5	\$345	\$551,310	
Distribution Mains	P-4057	EG	Franklin Rd.	8	Asbestos Cement	712	46	1.72 out of 5	\$345	\$245,640	
Distribution Mains	P-4072	EG	Frederick T. Miller Way	8	Ductile Iron	382	14	0 out of 5	N/A	\$0	
Transmission Mains	P-40005	EG	Frenchtown Rd.	20	Asbestos Cement	508	44	1.72 out of 5	\$345	\$175,260	
Transmission Mains	P-40019	EG	Frenchtown Rd.	12	Asbestos Cement	363	50	1.72 out of 5	\$345	\$125,235	
Transmission Mains	P-4002	EG	Frenchtown Rd.	16	Asbestos Cement	447	44	1.72 out of 5	\$345	\$154,215	
Transmission Mains	P-4003	EG	Frenchtown Rd.	16	Asbestos Cement	741	44	1.72 out of 5	\$345	\$255,645	
Transmission Mains	P-4060	EG	Frenchtown Rd.	16	Asbestos Cement	524	44	1.72 out of 5	\$345	\$180,780	
Transmission Mains	P-4061	EG	Frenchtown Rd.	12	Asbestos Cement	106	50	1.72 out of 5	\$345	\$36,570	
Transmission Mains	P-4075	EG	Frenchtown Rd.	20	Asbestos Cement	1,808	44	1.72 out of 5	\$345	\$623,760	
Transmission Mains	P-4104	EG	Frenchtown Rd.	12	Asbestos Cement	423	50	1.72 out of 5	\$345	\$145,935	
Transmission Mains	P-4105	EG	Frenchtown Rd.	12	Asbestos Cement	254	50	1.72 out of 5	\$345	\$87,630	
Transmission Mains	P-4113	EG	Frenchtown Rd.	12	Asbestos Cement	464	44	1.72 out of 5	\$345	\$160,080	
Transmission Mains	P-4114	EG	Frenchtown Rd.	12	Asbestos Cement	1,238	50	1.72 out of 5	\$345	\$427,110	
Transmission Mains	P-4721	EG	Frenchtown Rd.	20	Asbestos Cement	1,434	44	1.72 out of 5	\$345	\$494,730	
Transmission Mains	P-4722	EG	Frenchtown Rd.	20	Asbestos Cement	599	44	1.72 out of 5	\$345	\$206,655	
Transmission Mains	P-4728	EG	Frenchtown Rd.	12	Asbestos Cement	1,219	50	1.72 out of 5	\$345	\$420,555	
Transmission Mains	P-4732	EG	Frenchtown Rd.	12	Asbestos Cement	157	50	1.72 out of 5	\$345	\$54,165	
Transmission Mains	P-4733	EG	Frenchtown Rd.	12	Asbestos Cement	349	50	1.72 out of 5	\$345	\$120,405	
Transmission Mains	P-4855	EG	Frenchtown Rd.	12	Asbestos Cement	5,331	50	1.72 out of 5	\$345	\$1,839,195	
Transmission Mains	P-4859	EG	Frenchtown Rd.	12	Asbestos Cement	878	50	1.72 out of 5	\$345	\$302,910	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-40002	EG	Frenchtown Rd.	12	Ductile Iron	50	15	0 out of 5	N/A	\$0	
Distribution Mains	P-40003	EG	Frenchtown Rd.	8	Ductile Iron	488	10	0 out of 5	N/A	\$0	
Transmission Mains	P-4001	EG	Frenchtown Rd.	16	Ductile Iron	2,082	12	0 out of 5	N/A	\$0	
Transmission Mains	P-4056	EG	Frenchtown Rd.	12	Ductile Iron	482	15	0 out of 5	N/A	\$0	
Transmission Mains	P-4062	EG	Frenchtown Rd.	12	Ductile Iron	7	15	0 out of 5	N/A	\$0	
Transmission Mains	P-4063	EG	Frenchtown Rd.	12	Ductile Iron	18	15	0 out of 5	N/A	\$0	
Transmission Mains	P-4069	EG	Frenchtown Rd.	12	Ductile Iron	1,277	15	0 out of 5	N/A	\$0	
Transmission Mains	P-4730	EG	Frenchtown Rd.	16	Ductile Iron	632	16	0 out of 5	N/A	\$0	
Transmission Mains	P-4731	EG	Frenchtown Rd.	16	Ductile Iron	6,840	16	0 out of 5	N/A	\$0	
Transmission Mains	P-4843	EG	Frenchtown Rd.	12	Ductile Iron	370	15	0 out of 5	N/A	\$0	
Transmission Mains	P-4066	EG	Frenchtown Rd. Tank	16	Asbestos Cement	272	44	1.72 out of 5	\$345	\$93,840	
Distribution Mains	P-4065	EG	Frenchtown Rd. Tank	8	Ductile Iron	56	15	0 out of 5	N/A	\$0	
Transmission Mains	P-4064	EG	Frenchtown Rd. Tank Easemen	20	Asbestos Cement	588	44	1.72 out of 5	\$345	\$202,860	
Distribution Mains	P-4058	EG	Frenchtown Rd. Tank Easemen	8	Asbestos Cement	76	37	1.58 out of 5	\$345	\$26,220	
Transmission Mains	P-4059	EG	Frenchtown Rd. Tank Easemen	12	Ductile Iron	675	15	0 out of 5	N/A	\$0	
Distribution Mains	P-4377	EG	Friendly Rd.	6	Ductile Iron	444	26	0.86 out of 5	\$345	\$153,180	
Distribution Mains	P-4414	EG	Friendly Rd.	6	Ductile Iron	519	26	0.86 out of 5	\$345	\$179,055	
Distribution Mains	P-4579	EG	Friendship St.	4	Cast iron	247	128	3.3 out of 5	\$345	\$85,215	
Distribution Mains	P-4577	EG	Friendship St.	6	Asbestos Cement	243	64	3.29 out of 5	\$345	\$83,835	
Distribution Mains	P-4958	EG	Friendship St.	1	Copper	142	64	2.44 out of 5	\$345	\$48,990	
Transmission Mains	P-4592	EG	Friendship St.	12	Ductile Iron	245	18	0 out of 5	N/A	\$0	
Transmission Mains	P-4947	EG	Friendship St.	12	Ductile Iron	499	18	0 out of 5	N/A	\$0	
Distribution Mains	P-4460	EG	Gladridge Dr.	6	Asbestos Cement	349	56	2.43 out of 5	\$345	\$120,405	
Distribution Mains	P-4396	EG	Glenn Dr.	6	Asbestos Cement	1,161	54	2.43 out of 5	\$345	\$400,545	
Distribution Mains	P-40027	EG	Glenn Dr.	8	Ductile Iron	29	13	0 out of 5	N/A	\$0	
Distribution Mains	P-4365	EG	Gould Pl.	6	Asbestos Cement	746	56	2.43 out of 5	\$345	\$257,370	
Distribution Mains	P-4723	EG	Graham Way	8	Ductile Iron	828	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4725	EG	Graham Way	8	Ductile Iron	467	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4260	EG	Grandview Dr.	6	Asbestos Cement	406	46	2.43 out of 5	\$345	\$140,070	
Distribution Mains	P-4268	EG	Grandview Dr.	6	Asbestos Cement	647	53	2.43 out of 5	\$345	\$223,215	
Distribution Mains	P-4274	EG	Grandview Dr.	6	Asbestos Cement	309	46	2.43 out of 5	\$345	\$106,605	
Distribution Mains	P-4287	EG	Grandview Dr.	6	Asbestos Cement	243	53	2.43 out of 5	\$345	\$83,835	
Distribution Mains	P-4288	EG	Grandview Dr.	6	Asbestos Cement	479	53	2.43 out of 5	\$345	\$165,255	
Distribution Mains	P-4316	EG	Grandview Dr.	6	Asbestos Cement	735	46	2.43 out of 5	\$345	\$253,575	
Distribution Mains	P-4317	EG	Grandview Dr.	6	Asbestos Cement	384	46	2.43 out of 5	\$345	\$132,480	
Distribution Mains	P-4402	EG	Grandview Dr.	6	Asbestos Cement	239	46	2.43 out of 5	\$345	\$82,455	
Distribution Mains	P-4403	EG	Grandview Dr.	6	Asbestos Cement	145	46	2.43 out of 5	\$345	\$50,025	
Transmission Mains	P-4228	EG	Grandview Dr.	20	Asbestos Cement	115	50	1.72 out of 5	\$345	\$39,675	
Distribution Mains	P-4127	EG	Granite Dr.	6	Asbestos Cement	407	39	2.29 out of 5	\$345	\$140,415	
Distribution Mains	P-4129	EG	Granite Dr.	6	Asbestos Cement	843	39	2.29 out of 5	\$345	\$290,835	
Distribution Mains	P-40029	EG	Grasslands Rd.	8	Cast iron	116	77	1.58 out of 5	\$345	\$40,020	
Distribution Mains	P-4375	EG	Grasslands Rd.	6	Ductile Iron	326	26	0.86 out of 5	\$345	\$112,470	
Distribution Mains	P-4391	EG	Great Rd.	8	Asbestos Cement	822	45	1.72 out of 5	\$345	\$283,590	
Distribution Mains	P-4987	EG	Great Rd.	8	Asbestos Cement	631	45	1.72 out of 5	\$345	\$217,695	
Distribution Mains	P-4988	EG	Great Rd.	8	Asbestos Cement	307	45	1.72 out of 5	\$345	\$105,915	
Distribution Mains	P-4989	EG	Great Rd.	8	Asbestos Cement	363	45	1.72 out of 5	\$345	\$125,235	
Distribution Mains	P-4464	EG	Green Bush Rd.	8	Ductile Iron	134	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4599	EG	Greene St.	8	Ductile Iron	328	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4600	EG	Greene St.	8	Ductile Iron	402	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4850	EG	Greene St.	8	Ductile Iron	118	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4851	EG	Greene St.	8	Ductile Iron	167	12	0 out of 5	N/A	\$0	
Distribution Mains	P-40037	EG	Greenwich Blvd.	1.5	Galvanized iron	391	36	3.72 out of 5	\$345	\$134,895	
Distribution Mains	P-4483	EG	Greenwich Blvd.	2	PVC	307	44	2.72 out of 5	\$345	\$105,915	
Distribution Mains	P-4410	EG	Greenwich Blvd.	2	PVC	151	36	1.87 out of 5	\$345	\$52,095	
Distribution Mains	P-4266	EG	Hamilton Dr.	6	Asbestos Cement	2,056	46	2.43 out of 5	\$345	\$709,320	
Distribution Mains	P-4363	EG	Hanaford Dr.	6	Asbestos Cement	439	46	2.43 out of 5	\$345	\$151,455	
Distribution Mains	P-4364	EG	Hanaford Dr.	6	Asbestos Cement	199	46	2.43 out of 5	\$345	\$68,655	
Distribution Mains	P-4366	EG	Hanaford Dr.	6	Asbestos Cement	883	46	2.43 out of 5	\$345	\$304,635	
Distribution Mains	P-4535	EG	Harwood Rd.	6	Cast iron	1,033	82	2.43 out of 5	\$345	\$356,385	
Distribution Mains	P-4447	EG	Hemlock Dr.	8	Asbestos Cement	445	45	1.72 out of 5	\$345	\$153,525	
Distribution Mains	P-4449	EG	Hemlock Dr.	8	Asbestos Cement	774	45	1.72 out of 5	\$345	\$267,030	
Distribution Mains	P-4458	EG	Hemlock Dr.	8	Asbestos Cement	1,562	45	1.72 out of 5	\$345	\$538,890	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-4295	EG	Hickory Dr.	8	Asbestos Cement	409	46	1.72 out of 5	\$345	\$141,105	
Distribution Mains	P-4299	EG	Hickory Dr.	8	Asbestos Cement	192	46	1.72 out of 5	\$345	\$66,240	
Distribution Mains	P-4300	EG	Hickory Dr.	8	Asbestos Cement	269	46	1.72 out of 5	\$345	\$92,805	
Distribution Mains	P-4809	EG	Hidden Ln.	8	Ductile Iron	690	9	0 out of 5	N/A	\$0	
Distribution Mains	P-4810	EG	Hidden Ln.	8	Ductile Iron	185	9	0 out of 5	N/A	\$0	
Distribution Mains	P-4811	EG	Hidden Ln.	8	Ductile Iron	425	9	0 out of 5	N/A	\$0	
Distribution Mains	P-40004	EG	High Hawk Rd.	8	Asbestos Cement	64	44	1.72 out of 5	\$345	\$22,080	
Distribution Mains	P-40006	EG	High Hawk Rd.	8	Asbestos Cement	26	44	1.72 out of 5	\$345	\$8,970	
Distribution Mains	P-4042	EG	High Hawk Rd.	8	Asbestos Cement	1,428	44	1.72 out of 5	\$345	\$492,660	
Distribution Mains	P-4046	EG	High Hawk Rd.	8	Asbestos Cement	147	44	1.72 out of 5	\$345	\$50,715	
Distribution Mains	P-4050	EG	High Hawk Rd.	8	Asbestos Cement	512	44	1.72 out of 5	\$345	\$176,640	
Distribution Mains	P-4052	EG	High Hawk Rd.	8	Asbestos Cement	424	44	1.72 out of 5	\$345	\$146,280	
Distribution Mains	P-4053	EG	High Hawk Rd.	8	Asbestos Cement	1,945	44	1.72 out of 5	\$345	\$671,025	
Transmission Mains	P-4018	EG	High Hawk Rd.	12	PVC	462	28	0.44 out of 5	\$345	\$159,390	
Transmission Mains	P-4019	EG	High Hawk Rd.	12	PVC	383	28	0.44 out of 5	\$345	\$132,135	
Transmission Mains	P-4023	EG	High Hawk Rd.	12	PVC	332	28	0.44 out of 5	\$345	\$114,540	
Transmission Mains	P-4029	EG	High Hawk Rd.	12	PVC	205	28	0.44 out of 5	\$345	\$70,725	
Transmission Mains	P-4040	EG	High Hawk Rd.	12	PVC	741	28	0.44 out of 5	\$345	\$255,645	
Distribution Mains	P-4995	EG	Hill Ct.	6	Ductile Iron	535	22	0.86 out of 5	\$345	\$184,575	
Distribution Mains	P-4217	EG	Holly Hill Ct.	6	Asbestos Cement	166	46	2.43 out of 5	\$345	\$57,270	
Distribution Mains	P-4991	EG	Holly Hill Ct.	8	Asbestos Cement	144	46	1.72 out of 5	\$345	\$49,680	
Distribution Mains	P-4500	EG	Howland Farm Rd.	8	Ductile Iron	1,764	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4373	EG	Howland Rd.	8	Asbestos Cement	1,990	52	1.72 out of 5	\$345	\$686,550	
Distribution Mains	P-4454	EG	Howland Rd.	8	Asbestos Cement	285	52	1.72 out of 5	\$345	\$98,325	
Distribution Mains	P-4487	EG	Howland Rd.	8	Asbestos Cement	169	52	1.72 out of 5	\$345	\$58,305	
Distribution Mains	P-4488	EG	Howland Rd.	8	Asbestos Cement	561	52	1.72 out of 5	\$345	\$193,545	
Distribution Mains	P-4978	EG	Howland Rd.	8	Asbestos Cement	1,214	52	1.72 out of 5	\$345	\$418,830	
Distribution Mains	P-4376	EG	Howland Rd.	8	Ductile Iron	348	37	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4381	EG	Howland Rd.	8	Ductile Iron	456	37	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4382	EG	Howland Rd.	8	Ductile Iron	306	37	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4828	EG	Hoyer Ct.	8	Ductile Iron	405	9	0 out of 5	N/A	\$0	
Distribution Mains	P-4106	EG	Hugenot Dr.	8	Asbestos Cement	565	38	1.58 out of 5	\$345	\$194,925	
Distribution Mains	P-4107	EG	Hugenot Dr.	8	Asbestos Cement	586	39	1.58 out of 5	\$345	\$202,170	
Distribution Mains	P-4099	EG	Huling Ln.	8	Ductile Iron	440	30	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4100	EG	Huling Ln.	8	Ductile Iron	633	30	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4008	EG	Hunters Crossing Rd.	12	Ductile Iron	781	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4977	EG	Hutchins Ct.	6	Asbestos Cement	253	64	2.58 out of 5	\$345	\$87,285	
Distribution Mains	P-4543	EG	Hyland Ave.	8	Ductile Iron	484	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4679	EG	Hyland Ave.	8	Ductile Iron	310	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4471	EG	Ivy Garden Way	6	Ductile Iron	199	14	0.71 out of 5	\$345	\$68,655	
Distribution Mains	P-4557	EG	James St.	8	Ductile Iron	206	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4251	EG	Jefferson Dr.	8	Asbestos Cement	1,753	46	1.72 out of 5	\$345	\$604,785	
Distribution Mains	P-4109	EG	Jodie Beth Cir.	8	Asbestos Cement	1,370	41	1.72 out of 5	\$345	\$472,650	
Distribution Mains	P-4111	EG	Jodie Beth Cir.	8	Ductile Iron	674	19	0 out of 5	N/A	\$0	
Distribution Mains	P-4386	EG	John Alden Rd.	6	Asbestos Cement	230	44	2.43 out of 5	\$345	\$79,350	
Distribution Mains	P-4826	EG	Judge Torres Ln.	8	Ductile Iron	385	9	0 out of 5	N/A	\$0	
Distribution Mains	P-4827	EG	Judge Torres Ln.	8	Ductile Iron	665	9	0 out of 5	N/A	\$0	
Transmission Mains	P-4006	EG	Juniper Rd.	12	Ductile Iron	731	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4007	EG	Juniper Rd.	12	Ductile Iron	520	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4009	EG	Juniper Rd.	12	Ductile Iron	843	22	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4011	EG	Juniper Rd.	12	Ductile Iron	373	22	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4013	EG	Juniper Rd.	8	Ductile Iron	302	22	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4512	EG	Kenson Dr.	6	Asbestos Cement	477	64	2.58 out of 5	\$345	\$164,565	
Distribution Mains	P-4976	EG	Kenson Dr.	6	Asbestos Cement	594	64	2.58 out of 5	\$345	\$204,930	
Distribution Mains	P-4352	EG	Kent Dr.	6	Asbestos Cement	1,005	46	3.14 out of 5	\$345	\$346,725	
Distribution Mains	P-4361	EG	Kent Dr.	6	Asbestos Cement	346	46	2.43 out of 5	\$345	\$119,370	
Distribution Mains	P-4362	EG	Kent Dr.	6	Asbestos Cement	1,181	46	2.43 out of 5	\$345	\$407,445	
Distribution Mains	P-4389	EG	Kent Dr.	8	Asbestos Cement	920	46	1.72 out of 5	\$345	\$317,400	
Distribution Mains	P-4390	EG	Kent Dr.	8	Asbestos Cement	474	46	1.72 out of 5	\$345	\$163,530	
Distribution Mains	P-4984	EG	Kent Dr.	8	Asbestos Cement	262	46	1.72 out of 5	\$345	\$90,390	
Distribution Mains	P-4986	EG	Kent Dr.	8	Asbestos Cement	22	46	1.72 out of 5	\$345	\$7,590	
Distribution Mains	P-4531	EG	Kenyon Ave.	8	Asbestos Cement	1,071	65	3.3 out of 5	\$345	\$369,495	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-4540	EG	Kenyon Ave.	6	Cast iron	179	128	2.58 out of 5	\$345	\$61,755	
Distribution Mains	P-4542	EG	Kenyon Ave.	6	Cast iron	264	128	2.58 out of 5	\$345	\$91,080	
Distribution Mains	P-4544	EG	Kenyon Ave.	6	Cast iron	319	128	2.58 out of 5	\$345	\$110,055	
Distribution Mains	P-4545	EG	Kenyon Ave.	6	Cast iron	231	128	2.58 out of 5	\$345	\$79,695	
Distribution Mains	P-4549	EG	Kenyon Ave.	6	Cast iron	597	128	2.58 out of 5	\$345	\$205,965	
Distribution Mains	P-4527	EG	Kenyon Ave.	8	Asbestos Cement	880	65	1.87 out of 5	\$345	\$303,600	
Transmission Mains	P-4234	EG	Kenyon Ave.	20	Asbestos Cement	2,350	50	1.72 out of 5	\$345	\$810,750	
Transmission Mains	P-4235	EG	Kenyon Ave.	20	Asbestos Cement	1,528	50	1.72 out of 5	\$345	\$527,160	
Distribution Mains	P-4972	EG	Kenyon Ave.	8	Ductile Iron	22	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4973	EG	Kenyon Ave.	8	Ductile Iron	21	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4974	EG	Kenyon Ave.	8	Ductile Iron	24	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4975	EG	Kenyon Ave.	8	Ductile Iron	22	12	0 out of 5	N/A	\$0	
Transmission Mains	P-40009	EG	King Phillip Tr.	12	Asbestos Cement	46	51	1.72 out of 5	\$345	\$15,870	
Distribution Mains	P-40010	EG	King Phillip Tr.	8	Asbestos Cement	29	44	1.72 out of 5	\$345	\$10,005	
Distribution Mains	P-40011	EG	King Phillip Tr.	8	Ductile Iron	98	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4200	EG	King Phillip Tr.	8	Ductile Iron	324	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4202	EG	King Phillip Tr.	8	Ductile Iron	195	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4211	EG	King Phillip Tr.	8	Ductile Iron	263	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4613	EG	King St.	6	Cast iron	256	128	2.58 out of 5	\$345	\$88,320	
Distribution Mains	P-4615	EG	King St.	6	Cast iron	196	128	2.58 out of 5	\$345	\$67,620	
Distribution Mains	P-4617	EG	King St.	6	Cast iron	78	128	2.58 out of 5	\$345	\$26,910	
Distribution Mains	P-4618	EG	King St.	6	Cast iron	130	128	2.58 out of 5	\$345	\$44,850	
Distribution Mains	P-4910	EG	King St.	8	Cast iron	24	128	1.87 out of 5	\$345	\$8,280	
Distribution Mains	P-4622	EG	King St.	6	Ductile Iron	314	27	0.86 out of 5	\$345	\$108,330	
Distribution Mains	P-4901	EG	King St.	6	Ductile Iron	85	27	0.86 out of 5	\$345	\$29,325	
Distribution Mains	P-4902	EG	King St.	6	Ductile Iron	70	27	0.86 out of 5	\$345	\$24,150	
Distribution Mains	P-4900	EG	King St.	6	Ductile Iron	49	3	0.71 out of 5	\$345	\$16,905	
Distribution Mains	P-4907	EG	King St.	6	Ductile Iron	20	3	0.71 out of 5	\$345	\$6,900	
Distribution Mains	P-4909	EG	King St.	6	Ductile Iron	24	11	0.71 out of 5	\$345	\$8,280	
Distribution Mains	P-4906	EG	King St.	8	Ductile Iron	23	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4908	EG	King St.	8	Ductile Iron	19	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4110	EG	Kirker Dr.	8	Asbestos Cement	949	41	1.72 out of 5	\$345	\$327,405	
Distribution Mains	P-4528	EG	Knollwood Ave.	6	Asbestos Cement	1,275	64	2.58 out of 5	\$345	\$439,875	
Distribution Mains	P-4529	EG	Knollwood Ave.	6	Asbestos Cement	854	64	2.58 out of 5	\$345	\$294,630	
Distribution Mains	P-4422	EG	Lafayette Dr.	6	Asbestos Cement	1,090	45	2.43 out of 5	\$345	\$376,050	
Distribution Mains	P-4419	EG	Landover Dr.	6	Asbestos Cement	315	55	2.43 out of 5	\$345	\$108,675	
Distribution Mains	P-4421	EG	Landover Dr.	6	Asbestos Cement	270	55	2.43 out of 5	\$345	\$93,150	
Distribution Mains	P-4326	EG	Larch Rd.	6	Asbestos Cement	424	45	2.43 out of 5	\$345	\$146,280	
Distribution Mains	P-4327	EG	Larch Rd.	6	Asbestos Cement	1,021	45	2.43 out of 5	\$345	\$352,245	
Distribution Mains	P-4304	EG	Laurel Hill Rd.	6	Asbestos Cement	699	54	2.43 out of 5	\$345	\$241,155	
Distribution Mains	P-4309	EG	Laurel Hill Rd.	6	Asbestos Cement	193	55	2.43 out of 5	\$345	\$66,585	
Distribution Mains	P-4310	EG	Laurel Hill Rd.	6	Asbestos Cement	923	55	2.43 out of 5	\$345	\$318,435	
Distribution Mains	P-40016	EG	Laurel Ln.	8	Ductile Iron	262	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4086	EG	Laurel Wood Dr.	8	Ductile Iron	809	19	0 out of 5	N/A	\$0	
Distribution Mains	P-4087	EG	Laurel Wood Dr.	8	Ductile Iron	985	19	0 out of 5	N/A	\$0	
Distribution Mains	P-4088	EG	Laurel Wood Dr.	8	Ductile Iron	1,236	19	0 out of 5	N/A	\$0	
Distribution Mains	P-4089	EG	Laurel Wood Dr. Easement	8	Ductile Iron	420	19	0 out of 5	N/A	\$0	
Distribution Mains	P-4436	EG	Le Baron Dr.	6	Asbestos Cement	166	60	2.58 out of 5	\$345	\$57,270	
Distribution Mains	P-40028	EG	Le Baron Dr.	6	Asbestos Cement	134	46	2.43 out of 5	\$345	\$46,230	
Distribution Mains	P-4420	EG	Le Baron Dr.	6	Asbestos Cement	183	46	2.43 out of 5	\$345	\$63,135	
Distribution Mains	P-4425	EG	Le Baron Dr.	6	Asbestos Cement	72	46	2.43 out of 5	\$345	\$24,840	
Distribution Mains	P-4426	EG	Le Baron Dr.	6	Asbestos Cement	279	46	2.43 out of 5	\$345	\$96,255	
Distribution Mains	P-4438	EG	Le Baron Dr.	6	Asbestos Cement	177	46	2.43 out of 5	\$345	\$61,065	
Transmission Mains	P-4232	EG	Le Baron Dr.	20	Asbestos Cement	1,048	50	1.72 out of 5	\$345	\$361,560	
Distribution Mains	P-4541	EG	Ledge Rd.	8	Ductile Iron	672	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4154	EG	Lenihan Ln.	8	Ductile Iron	1,561	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4155	EG	Lenihan Ln.	8	Ductile Iron	464	9	0 out of 5	N/A	\$0	
Distribution Mains	P-4824	EG	Lenihan Ln.	8	Ductile Iron	484	12	0 out of 5	N/A	\$0	
Distribution Mains	P-40035	EG	Liberty St.	10	Cast iron	349	128	1.87 out of 5	\$345	\$120,405	
Distribution Mains	P-4604	EG	Liberty St.	8	Ductile Iron	433	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4950	EG	Liberty St.	8	Ductile Iron	276	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4953	EG	Liberty St.	8	Ductile Iron	51	12	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-4351	EG	Lillian St.	6	Asbestos Cement	473	52	2.43 out of 5	\$345	\$163,185	
Distribution Mains	P-4428	EG	Lillibridge Dr.	6	Asbestos Cement	586	52	2.43 out of 5	\$345	\$202,170	
Distribution Mains	P-4128	EG	Limerock Dr.	6	Asbestos Cement	1,002	37	2.29 out of 5	\$345	\$345,690	
Distribution Mains	P-4691	EG	Lincoln St.	8	Ductile Iron	587	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4648	EG	Lion St.	8	Ductile Iron	174	14	0 out of 5	N/A	\$0	
Distribution Mains	P-4653	EG	Lion St.	8	Ductile Iron	221	14	0 out of 5	N/A	\$0	
Distribution Mains	P-4277	EG	Locus Dr.	6	Asbestos Cement	778	46	2.43 out of 5	\$345	\$268,410	
Distribution Mains	P-4635	EG	London St.	6	Cast iron	266	128	2.58 out of 5	\$345	\$91,770	
Distribution Mains	P-4929	EG	London St.	6	Cast iron	36	128	2.58 out of 5	\$345	\$12,420	
Transmission Mains	P-4634	EG	London St.	12	Asbestos Cement	43	55	1.72 out of 5	\$345	\$14,835	
Distribution Mains	P-4647	EG	London St.	6	Ductile Iron	136	27	0.86 out of 5	\$345	\$46,920	
Distribution Mains	P-4643	EG	London St.	6	Ductile Iron	136	3	0.71 out of 5	\$345	\$46,920	
Distribution Mains	P-4636	EG	London St.	8	Ductile Iron	63	3	0 out of 5	N/A	\$0	
Transmission Mains	P-4638	EG	London St.	12	Ductile Iron	256	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4642	EG	London St.	8	Ductile Iron	163	3	0 out of 5	N/A	\$0	
Transmission Mains	P-4926	EG	London St.	12	Ductile Iron	22	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4645	EG	Long St.	8	Ductile Iron	244	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4651	EG	Long St.	8	Ductile Iron	149	14	0 out of 5	N/A	\$0	
Distribution Mains	P-4652	EG	Long St.	8	Ductile Iron	278	14	0 out of 5	N/A	\$0	
Distribution Mains	P-4000	EG	Longmeadow Dr.	8	Ductile Iron	1,633	11	0 out of 5	N/A	\$0	
Distribution Mains	P-4829	EG	Lovegreen Ln.	8	Ductile Iron	390	9	0 out of 5	N/A	\$0	
Distribution Mains	P-4135	EG	Lynn Cir.	8	PVC	2,221	28	0.44 out of 5	\$345	\$766,245	
Distribution Mains	P-4137	EG	Lynn Cir.	8	PVC	145	28	0.44 out of 5	\$345	\$50,025	
Distribution Mains	P-4279	EG	Main St.	10	Cast iron	451	128	1.87 out of 5	\$345	\$155,595	
Distribution Mains	P-4594	EG	Main St.	10	Cast iron	430	128	1.87 out of 5	\$345	\$148,350	
Distribution Mains	P-4598	EG	Main St.	10	Cast iron	172	128	1.87 out of 5	\$345	\$59,340	
Distribution Mains	P-4612	EG	Main St.	8	Cast iron	598	128	1.87 out of 5	\$345	\$206,310	
Distribution Mains	P-4623	EG	Main St.	8	Cast iron	305	128	1.87 out of 5	\$345	\$105,225	
Distribution Mains	P-4633	EG	Main St.	8	Cast iron	197	128	1.87 out of 5	\$345	\$67,965	
Distribution Mains	P-4641	EG	Main St.	10	Cast iron	308	128	1.87 out of 5	\$345	\$106,260	
Distribution Mains	P-4657	EG	Main St.	10	Cast iron	296	128	1.87 out of 5	\$345	\$102,120	
Distribution Mains	P-4687	EG	Main St.	8	Cast iron	205	128	1.87 out of 5	\$345	\$70,725	
Distribution Mains	P-4689	EG	Main St.	8	Cast iron	526	128	1.87 out of 5	\$345	\$181,470	
Distribution Mains	P-4692	EG	Main St.	10	Cast iron	235	128	1.87 out of 5	\$345	\$81,075	
Distribution Mains	P-4892	EG	Main St.	8	Cast iron	23	128	1.87 out of 5	\$345	\$7,935	
Distribution Mains	P-4924	EG	Main St.	10	Cast iron	50	128	1.87 out of 5	\$345	\$17,250	
Distribution Mains	P-4939	EG	Main St.	10	Cast iron	72	128	1.87 out of 5	\$345	\$24,840	
Distribution Mains	P-40036	EG	Main St.	10	Ductile Iron	343	18	0 out of 5	N/A	\$0	
Distribution Mains	P-4263	EG	Main St.	10	Ductile Iron	359	18	0 out of 5	N/A	\$0	
Distribution Mains	P-4321	EG	Main St.	10	Ductile Iron	1,300	18	0 out of 5	N/A	\$0	
Distribution Mains	P-4911	EG	Main St.	10	Ductile Iron	22	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4931	EG	Main St.	10	Ductile Iron	23	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4932	EG	Main St.	10	Ductile Iron	20	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4935	EG	Main St.	10	Ductile Iron	31	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4936	EG	Main St.	10	Ductile Iron	24	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4937	EG	Main St.	10	Ductile Iron	21	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4949	EG	Main St.	10	Ductile Iron	20	12	0 out of 5	N/A	\$0	
Transmission Mains	P-4010	EG	Mallard Way	12	Ductile Iron	725	22	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4290	EG	Maplewood Dr.	8	Asbestos Cement	785	54	1.72 out of 5	\$345	\$270,825	
Distribution Mains	P-4394	EG	Maplewood Dr.	8	Asbestos Cement	477	54	1.72 out of 5	\$345	\$164,565	
Distribution Mains	P-4395	EG	Maplewood Dr.	8	Asbestos Cement	996	54	1.72 out of 5	\$345	\$343,620	
Distribution Mains	P-4610	EG	Marion St.	4	Cast iron	431	128	3.3 out of 5	\$345	\$148,695	
Distribution Mains	P-4918	EG	Marion St.	4	Cast iron	174	128	3.3 out of 5	\$345	\$60,030	
Transmission Mains	P-4614	EG	Marlborough St.	12	Asbestos Cement	629	58	1.72 out of 5	\$345	\$217,005	
Transmission Mains	P-4625	EG	Marlborough St.	12	Asbestos Cement	529	58	1.72 out of 5	\$345	\$182,505	
Transmission Mains	P-4639	EG	Marlborough St.	12	Asbestos Cement	376	58	1.72 out of 5	\$345	\$129,720	
Transmission Mains	P-4640	EG	Marlborough St.	12	Asbestos Cement	301	58	1.72 out of 5	\$345	\$103,845	
Distribution Mains	P-4596	EG	Marlborough St.	8	Ductile Iron	280	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4656	EG	Marlborough St.	8	Ductile Iron	572	11	0 out of 5	N/A	\$0	
Distribution Mains	P-4659	EG	Marlborough St.	8	Ductile Iron	356	11	0 out of 5	N/A	\$0	
Distribution Mains	P-4695	EG	Marlborough St.	8	Ductile Iron	290	12	0 out of 5	N/A	\$0	
Transmission Mains	P-4927	EG	Marlborough St.	12	Ductile Iron	24	12	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-4928	EG	Marlborough St.	12	Ductile Iron	25	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4139	EG	Mawney Brook Dr.	8	Ductile Iron	585	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4578	EG	Mawney St.	4	Cast iron	842	128	3.3 out of 5	\$345	\$290,490	
Distribution Mains	P-4587	EG	Mawney St.	4	Cast iron	441	128	3.3 out of 5	\$345	\$152,145	
Distribution Mains	P-4356	EG	Mayflower Dr.	6	Asbestos Cement	528	45	2.43 out of 5	\$345	\$182,160	
Distribution Mains	P-4357	EG	Mayflower Dr.	6	Asbestos Cement	174	45	2.43 out of 5	\$345	\$60,030	
Distribution Mains	P-4384	EG	Mayflower Dr.	6	Asbestos Cement	452	45	2.43 out of 5	\$345	\$155,940	
Distribution Mains	P-4385	EG	Mayflower Dr.	6	Asbestos Cement	440	45	2.43 out of 5	\$345	\$151,800	
Distribution Mains	P-4273	EG	McGraw Ct.	6	Ductile Iron	276	23	0.86 out of 5	\$345	\$95,220	
Distribution Mains	P-4144	EG	McPartland Way	8	Ductile Iron	714	11	0 out of 5	N/A	\$0	
Distribution Mains	P-4145	EG	McPartland Way	8	Ductile Iron	1,310	11	0 out of 5	N/A	\$0	
Distribution Mains	P-4146	EG	McPartland Way	8	Ductile Iron	428	11	0 out of 5	N/A	\$0	
Distribution Mains	P-40020	EG	Meadowbrook Rd.	6	PVC	1,027	50	1.29 out of 5	\$345	\$354,315	
Distribution Mains	P-40021	EG	Meadowbrook Rd.	6	PVC	25	50	1.29 out of 5	\$345	\$8,625	
Distribution Mains	P-40022	EG	Meadowbrook Rd.	6	Ductile Iron	129	50	1 out of 5	\$345	\$44,505	
Transmission Mains	P-4118	EG	Middle Rd.	12	Asbestos Cement	1,087	41	1.72 out of 5	\$345	\$375,015	
Transmission Mains	P-4212	EG	Middle Rd.	12	Asbestos Cement	1,892	52	1.72 out of 5	\$345	\$652,740	
Transmission Mains	P-4233	EG	Middle Rd.	20	Asbestos Cement	1,660	50	1.72 out of 5	\$345	\$572,700	
Transmission Mains	P-4336	EG	Middle Rd.	12	Asbestos Cement	578	52	1.72 out of 5	\$345	\$199,410	
Transmission Mains	P-4343	EG	Middle Rd.	12	Asbestos Cement	218	52	1.72 out of 5	\$345	\$75,210	
Transmission Mains	P-4344	EG	Middle Rd.	12	Asbestos Cement	481	52	1.72 out of 5	\$345	\$165,945	
Transmission Mains	P-4727	EG	Middle Rd.	12	Asbestos Cement	800	41	1.72 out of 5	\$345	\$276,000	
Transmission Mains	P-4116	EG	Middle Rd.	20	Ductile Iron	1,147	31	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4130	EG	Middle Rd.	20	Ductile Iron	2	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4138	EG	Middle Rd.	16	Ductile Iron	870	20	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4158	EG	Middle Rd.	16	Ductile Iron	325	21	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4371	EG	Middle Rd.	8	Ductile Iron	1,308	27	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4398	EG	Middle Rd.	8	Ductile Iron	375	27	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4444	EG	Middle Rd.	8	Ductile Iron	860	27	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4525	EG	Middle Rd.	8	Ductile Iron	1,467	27	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4719	EG	Middle Rd.	20	Ductile Iron	20	31	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4720	EG	Middle Rd.	12	Ductile Iron	20	31	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4726	EG	Middle Rd.	12	Ductile Iron	2,182	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4140	EG	Middle Rd.	16	Ductile Iron	246	9	0 out of 5	N/A	\$0	
Transmission Mains	P-4143	EG	Middle Rd.	16	Ductile Iron	509	11	0 out of 5	N/A	\$0	
Transmission Mains	P-4147	EG	Middle Rd.	16	Ductile Iron	756	12	0 out of 5	N/A	\$0	
Transmission Mains	P-4148	EG	Middle Rd.	16	Ductile Iron	567	12	0 out of 5	N/A	\$0	
Transmission Mains	P-4157	EG	Middle Rd.	16	Ductile Iron	1,084	13	0 out of 5	N/A	\$0	
Distribution Mains	P-4337	EG	Middle Rd.	8	Ductile Iron	62	13	0 out of 5	N/A	\$0	
Distribution Mains	P-4339	EG	Middle Rd.	8	Ductile Iron	318	13	0 out of 5	N/A	\$0	
Distribution Mains	P-4367	EG	Middle Rd.	8	Ductile Iron	87	13	0 out of 5	N/A	\$0	
Distribution Mains	P-4368	EG	Middle Rd.	8	Ductile Iron	964	13	0 out of 5	N/A	\$0	
Distribution Mains	P-4392	EG	Middle Rd.	8	Ductile Iron	323	13	0 out of 5	N/A	\$0	
Distribution Mains	P-4397	EG	Middle Rd.	8	Ductile Iron	405	13	0 out of 5	N/A	\$0	
Transmission Mains	P-4671	EG	Middle Rd.	12	Steel	280	13	0 out of 5	N/A	\$0	
Transmission Mains	P-4806	EG	Middle Rd.	16	Ductile Iron	1,085	9	0 out of 5	N/A	\$0	
Transmission Mains	P-4807	EG	Middle Rd.	12	Ductile Iron	964	9	0 out of 5	N/A	\$0	
Distribution Mains	P-4224	EG	Middle Rd. PRV	8	Ductile Iron	161	13	0 out of 5	N/A	\$0	
Distribution Mains	P-4672	EG	Middle Rd. PRV	8	Ductile Iron	230	13	0 out of 5	N/A	\$0	
Distribution Mains	P-4440	EG	Midlands Dr.	6	Asbestos Cement	527	40	2.43 out of 5	\$345	\$181,815	
Transmission Mains	P-4160	EG	Miss Fry Dr.	16	Ductile Iron	591	21	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4162	EG	Miss Fry Dr.	16	Ductile Iron	971	21	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4167	EG	Miss Fry Dr.	16	Ductile Iron	1,326	21	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4275	EG	Misty Oak Dr.	8	Asbestos Cement	274	49	1.72 out of 5	\$345	\$94,530	
Distribution Mains	P-4281	EG	Misty Oak Dr.	8	PVC	492	30	0.44 out of 5	\$345	\$169,740	
Distribution Mains	P-4282	EG	Misty Oak Dr.	8	PVC	497	30	0.44 out of 5	\$345	\$171,465	
Distribution Mains	P-4108	EG	Monroe Dr.	6	Asbestos Cement	509	39	2.29 out of 5	\$345	\$175,605	
Distribution Mains	P-4919	EG	Montrose St.	4	Cast iron	272	128	3.3 out of 5	\$345	\$93,840	
Transmission Mains	P-40040	EG	Moosehorn Rd.	16	Ductile Iron	86	21	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4159	EG	Moosehorn Rd.	16	Ductile Iron	1,380	21	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4983	EG	Moss Ln.	8	Asbestos Cement	275	30	1.58 out of 5	\$345	\$94,875	
Distribution Mains	P-4283	EG	Mullberry Ct.	6	PVC	182	30	1.15 out of 5	\$345	\$62,790	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-4259	EG	Newcastle Dr.	8	PVC	417	36	0.44 out of 5	\$345	\$143,865	
Distribution Mains	P-4267	EG	Newcastle Dr.	8	PVC	117	36	0.44 out of 5	\$345	\$40,365	
Distribution Mains	P-4378	EG	Nichols Ln.	6	Asbestos Cement	1,039	46	2.43 out of 5	\$345	\$358,455	
Distribution Mains	P-4322	EG	North Gate Dr.	8	Asbestos Cement	245	45	1.72 out of 5	\$345	\$84,525	
Distribution Mains	P-4896	EG	North Marlborough St.	8	Ductile Iron	20	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4221	EG	Oak Dell Cir.	8	Asbestos Cement	1,136	46	1.72 out of 5	\$345	\$391,920	
Distribution Mains	P-4457	EG	Oakwood Dr.	6	Asbestos Cement	1,176	55	2.43 out of 5	\$345	\$405,720	
Distribution Mains	P-4808	EG	Old Farm Rd.	8	Ductile Iron	845	9	0 out of 5	N/A	\$0	
Distribution Mains	P-4291	EG	Old Forge Rd.	10	Ductile Iron	84	18	0 out of 5	N/A	\$0	
Distribution Mains	P-4489	EG	Old Greenwich Dr.	6	Asbestos Cement	139	42	2.43 out of 5	\$345	\$47,955	
Distribution Mains	P-4490	EG	Old Greenwich Dr.	6	Asbestos Cement	137	42	2.43 out of 5	\$345	\$47,265	
Distribution Mains	P-4491	EG	Old Greenwich Dr.	6	Asbestos Cement	182	42	2.43 out of 5	\$345	\$62,790	
Distribution Mains	P-4276	EG	Old Post Rd.	10	Cast iron	324	128	1.87 out of 5	\$345	\$111,780	
Distribution Mains	P-4285	EG	Old Post Rd.	10	Cast iron	486	128	1.87 out of 5	\$345	\$167,670	
Transmission Mains	P-4227	EG	Old Post Rd.	20	Asbestos Cement	253	50	1.72 out of 5	\$345	\$87,285	
Distribution Mains	P-4707	EG	Old Quaker Ln.	8	Ductile Iron	555	11	0 out of 5	N/A	\$0	
Distribution Mains	P-4708	EG	Old Quaker Ln.	10	Ductile Iron	174	11	0 out of 5	N/A	\$0	
Distribution Mains	P-4030	EG	Osprey Dr.	8	PVC	1,468	27	0.44 out of 5	\$345	\$506,460	
Distribution Mains	P-4031	EG	Osprey Dr.	8	PVC	420	27	0.44 out of 5	\$345	\$144,900	
Distribution Mains	P-4533	EG	Overbrook Ln.	6	Asbestos Cement	617	59	3.14 out of 5	\$345	\$212,865	
Distribution Mains	P-4534	EG	Overbrook Ln.	6	Asbestos Cement	222	59	2.43 out of 5	\$345	\$76,590	
Distribution Mains	P-4354	EG	Overfield Rd.	6	Ductile Iron	947	25	0.86 out of 5	\$345	\$326,715	
Distribution Mains	P-4355	EG	Overfield Rd.	6	Ductile Iron	333	25	0.86 out of 5	\$345	\$114,885	
Distribution Mains	P-4697	EG	Overfield Rd.	6	Ductile Iron	495	25	0.86 out of 5	\$345	\$170,775	
Distribution Mains	P-4698	EG	Overfield Rd.	6	Ductile Iron	444	25	0.86 out of 5	\$345	\$153,180	
Distribution Mains	P-4044	EG	Owl Tree Ln.	8	Ductile Iron	457	14	0 out of 5	N/A	\$0	
Distribution Mains	P-4073	EG	Pardon's Wood Ln.	8	Ductile Iron	773	21	0.15 out of 5	N/A	\$0	
Distribution Mains	P-40042	EG	Partridge Run	8	Ductile Iron	608	21	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4164	EG	Partridge Run	8	Ductile Iron	705	19	0 out of 5	N/A	\$0	
Distribution Mains	P-4967	EG	Pearl St.	1.5	Copper	88	12	2 out of 5	\$345	\$30,360	
Distribution Mains	P-4966	EG	Pearl St.	8	Ductile Iron	24	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4493	EG	Pegwin Dr.	6	Asbestos Cement	459	50	2.43 out of 5	\$345	\$158,355	
Distribution Mains	P-4494	EG	Pegwin Dr.	6	Asbestos Cement	742	50	2.43 out of 5	\$345	\$255,990	
Distribution Mains	P-4475	EG	Pegwin Dr. Easement	8	Ductile Iron	568	14	0 out of 5	N/A	\$0	
Distribution Mains	P-4190	EG	Pequot Tr.	8	Ductile Iron	283	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4191	EG	Pequot Tr.	8	Ductile Iron	131	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4194	EG	Pequot Tr.	8	Ductile Iron	916	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4199	EG	Pequot Tr.	8	Ductile Iron	722	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4204	EG	Pequot Tr.	8	Ductile Iron	122	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4206	EG	Pequot Tr.	8	Ductile Iron	350	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4353	EG	Pettine St.	1.3	Copper	445	61	2.44 out of 5	\$345	\$153,525	
Transmission Mains	P-40000	EG	Pheasant Dr.	12	PVC	442	25	0.44 out of 5	\$345	\$152,490	
Transmission Mains	P-4024	EG	Pheasant Dr.	16	Ductile Iron	1,739	21	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4026	EG	Pheasant Dr.	16	Ductile Iron	531	21	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4027	EG	Pheasant Dr. Easement	16	Ductile Iron	1,142	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4411	EG	Phillips Dr.	6	Asbestos Cement	275	44	2.43 out of 5	\$345	\$94,875	
Distribution Mains	P-4412	EG	Phillips Dr.	6	Asbestos Cement	265	44	2.43 out of 5	\$345	\$91,425	
Distribution Mains	P-4429	EG	Phillips Dr.	6	Asbestos Cement	456	44	2.43 out of 5	\$345	\$157,320	
Distribution Mains	P-4431	EG	Phillips Dr.	6	Asbestos Cement	433	44	2.43 out of 5	\$345	\$149,385	
Distribution Mains	P-4432	EG	Phillips Dr.	6	Asbestos Cement	286	44	2.43 out of 5	\$345	\$98,670	
Distribution Mains	P-4606	EG	Pierce St.	6	Cast iron	279	128	2.58 out of 5	\$345	\$96,255	
Distribution Mains	P-4608	EG	Pierce St.	6	Cast iron	230	128	2.58 out of 5	\$345	\$79,350	
Distribution Mains	P-4611	EG	Pierce St.	6	Cast iron	570	128	2.58 out of 5	\$345	\$196,650	
Distribution Mains	P-4685	EG	Pierce St.	6	Cast iron	502	128	2.58 out of 5	\$345	\$173,190	
Distribution Mains	P-4920	EG	Pierce St.	6	Cast iron	18	128	2.58 out of 5	\$345	\$6,210	
Distribution Mains	P-4925	EG	Pierce St.	6	Cast iron	313	128	2.58 out of 5	\$345	\$107,985	
Distribution Mains	P-4890	EG	Pierce St.	6	Ductile Iron	22	3	0.71 out of 5	\$345	\$7,590	
Distribution Mains	P-4921	EG	Pierce St.	6	Ductile Iron	17	12	0.71 out of 5	\$345	\$5,865	
Distribution Mains	P-4923	EG	Pierce St.	6	Ductile Iron	25	12	0.71 out of 5	\$345	\$8,625	
Distribution Mains	P-4889	EG	Pierce St.	8	Ductile Iron	23	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4922	EG	Pierce St.	8	Ductile Iron	17	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4214	EG	Pine Hill Dr.	8	Asbestos Cement	502	46	1.72 out of 5	\$345	\$173,190	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-40034	EG	Post Rd.	10	Cast iron	187	128	1.87 out of 5	\$345	\$64,515	
Distribution Mains	P-4269	EG	Post Rd.	10	Cast iron	1,358	128	1.87 out of 5	\$345	\$468,510	
Distribution Mains	P-4272	EG	Post Rd.	10	Cast iron	2,164	128	1.87 out of 5	\$345	\$746,580	
Distribution Mains	P-4736	EG	Post Rd.	10	Cast iron	1,413	128	1.87 out of 5	\$345	\$487,485	
Distribution Mains	P-4737	EG	Post Rd.	10	Cast iron	221	128	1.87 out of 5	\$345	\$76,245	
Transmission Mains	P-4226	EG	Post Rd.	20	Asbestos Cement	219	50	1.72 out of 5	\$345	\$75,555	
Transmission Mains	P-4735	EG	Post Rd.	20	Asbestos Cement	540	50	1.72 out of 5	\$345	\$186,300	
Distribution Mains	P-4740	EG	Post Rd.	6	Ductile Iron	36	18	0.71 out of 5	\$345	\$12,420	
Transmission Mains	P-4242	EG	Post Rd.	12	Ductile Iron	183	44	0.29 out of 5	N/A	\$0	
Distribution Mains	P-40032	EG	Post Rd.	10	Ductile Iron	212	18	0 out of 5	N/A	\$0	
Distribution Mains	P-4067	EG	Post Rd.	10	Ductile Iron	1,764	18	0 out of 5	N/A	\$0	
Transmission Mains	P-4239	EG	Post Rd.	16	Ductile Iron	102	17	0 out of 5	N/A	\$0	
Transmission Mains	P-4240	EG	Post Rd.	16	Ductile Iron	257	16	0 out of 5	N/A	\$0	
Transmission Mains	P-4241	EG	Post Rd.	16	Ductile Iron	842	16	0 out of 5	N/A	\$0	
Distribution Mains	P-4278	EG	Post Rd.	10	Ductile Iron	1,251	18	0 out of 5	N/A	\$0	
Distribution Mains	P-4289	EG	Post Rd.	10	Ductile Iron	413	18	0 out of 5	N/A	\$0	
Distribution Mains	P-4292	EG	Post Rd.	10	Ductile Iron	205	18	0 out of 5	N/A	\$0	
Distribution Mains	P-4294	EG	Post Rd.	10	Ductile Iron	222	18	0 out of 5	N/A	\$0	
Distribution Mains	P-4303	EG	Post Rd.	10	Ductile Iron	164	18	0 out of 5	N/A	\$0	
Distribution Mains	P-4306	EG	Post Rd.	10	Ductile Iron	640	18	0 out of 5	N/A	\$0	
Distribution Mains	P-4312	EG	Post Rd.	10	Ductile Iron	46	18	0 out of 5	N/A	\$0	
Transmission Mains	P-4435	EG	Post Rd.	12	Ductile Iron	83	17	0 out of 5	N/A	\$0	
Distribution Mains	P-4699	EG	Post Rd.	10	Ductile Iron	969	18	0 out of 5	N/A	\$0	
Transmission Mains	P-4734	EG	Post Rd.	20	Ductile Iron	730	17	0 out of 5	N/A	\$0	
Distribution Mains	P-4738	EG	Post Rd.	10	Ductile Iron	620	18	0 out of 5	N/A	\$0	
Distribution Mains	P-4739	EG	Post Rd.	10	Ductile Iron	276	18	0 out of 5	N/A	\$0	
Distribution Mains	P-4865	EG	Post Rd.	10	Ductile Iron	661	18	0 out of 5	N/A	\$0	
Distribution Mains	P-4243	EG	Post Rd. PRV	8	Ductile Iron	380	17	0 out of 5	N/A	\$0	
Distribution Mains	P-4244	EG	Post Rd. PRV	8	Ductile Iron	400	17	0 out of 5	N/A	\$0	
Distribution Mains	P-4346	EG	Power St.	6	PVC	259	31	1.15 out of 5	\$345	\$89,355	
Distribution Mains	P-4504	EG	Pricewood Dr.	6	Asbestos Cement	682	56	2.43 out of 5	\$345	\$235,290	
Distribution Mains	P-4548	EG	Proctor Ave.	6	Cast iron	336	128	2.58 out of 5	\$345	\$115,920	
Distribution Mains	P-4680	EG	Proctor Ave.	8	Ductile Iron	210	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4682	EG	Proctor Ave.	8	Ductile Iron	426	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4589	EG	Prospect St.	6	Asbestos Cement	460	65	2.58 out of 5	\$345	\$158,700	
Transmission Mains	P-4580	EG	Prospect St.	12	Ductile Iron	455	18	0 out of 5	N/A	\$0	
Transmission Mains	P-4581	EG	Prospect St.	12	Ductile Iron	233	18	0 out of 5	N/A	\$0	
Transmission Mains	P-4955	EG	Prospect St.	12	Ductile Iron	292	18	0 out of 5	N/A	\$0	
Distribution Mains	P-4082	EG	Quail Ct.	8	PVC	222	35	0.44 out of 5	\$345	\$76,590	
Transmission Mains	P-4710	EG	Quaker Ln.	20	Asbestos Cement	1,470	45	1.72 out of 5	\$345	\$507,150	
Transmission Mains	P-4711	EG	Quaker Ln.	20	Asbestos Cement	767	45	1.72 out of 5	\$345	\$264,615	
Transmission Mains	P-4755	EG	Quaker Ln.	16	Ductile Iron	2,125	8	0 out of 5	N/A	\$0	
Distribution Mains	P-4624	EG	Queen St.	6	Cast iron	250	128	2.58 out of 5	\$345	\$86,250	
Distribution Mains	P-4626	EG	Queen St.	6	Cast iron	206	128	2.58 out of 5	\$345	\$71,070	
Distribution Mains	P-4630	EG	Queen St.	6	Cast iron	417	128	2.58 out of 5	\$345	\$143,865	
Distribution Mains	P-4631	EG	Queen St.	6	Asbestos Cement	319	39	2.29 out of 5	\$345	\$110,055	
Distribution Mains	P-4916	EG	Queen St.	8	Cast iron	25	128	1.87 out of 5	\$345	\$8,625	
Distribution Mains	P-4917	EG	Queen St.	8	Asbestos Cement	23	39	1.58 out of 5	\$345	\$7,935	
Distribution Mains	P-4913	EG	Queen St.	6	Ductile Iron	20	14	0.71 out of 5	\$345	\$6,900	
Distribution Mains	P-4915	EG	Queen St.	6	Ductile Iron	21	14	0.71 out of 5	\$345	\$7,245	
Distribution Mains	P-4912	EG	Queen St.	8	Ductile Iron	18	14	0 out of 5	N/A	\$0	
Distribution Mains	P-4914	EG	Queen St.	8	Ductile Iron	21	14	0 out of 5	N/A	\$0	
Distribution Mains	P-4032	EG	Rabbit Run	8	PVC	669	27	0.44 out of 5	\$345	\$230,805	
Distribution Mains	P-4156	EG	Ramano Ct.	8	Ductile Iron	396	12	0 out of 5	N/A	\$0	
Transmission Mains	P-4571	EG	Rector St.	12	Ductile Iron	86	17	0 out of 5	N/A	\$0	
Transmission Mains	P-4572	EG	Rector St.	12	Ductile Iron	418	17	0 out of 5	N/A	\$0	
Transmission Mains	P-4601	EG	Rector St.	12	Ductile Iron	759	17	0 out of 5	N/A	\$0	
Transmission Mains	P-4603	EG	Rector St.	12	Ductile Iron	187	17	0 out of 5	N/A	\$0	
Distribution Mains	P-4484	EG	Red Barn Ln.	8	Asbestos Cement	1,424	41	1.72 out of 5	\$345	\$491,280	
Distribution Mains	P-4486	EG	Red Barn Ln.	8	Asbestos Cement	509	41	1.72 out of 5	\$345	\$175,605	
Distribution Mains	P-4318	EG	Red Oak Rd.	6	Asbestos Cement	809	46	2.43 out of 5	\$345	\$279,105	
Distribution Mains	P-4434	EG	Reeds Pl.	6	Asbestos Cement	311	45	2.43 out of 5	\$345	\$107,295	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-4942	EG	Reilly Ave.	1	Copper	264	58	2.29 out of 5	\$345	\$91,080	
Distribution Mains	P-4092	EG	Remy Pl.	8	Ductile Iron	302	33	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4609	EG	Revolution St.	6	Asbestos Cement	347	70	2.58 out of 5	\$345	\$119,715	
Distribution Mains	P-4576	EG	Reynolds St.	4	Cast iron	624	128	3.3 out of 5	\$345	\$215,280	
Distribution Mains	P-4584	EG	Reynolds St.	4	Cast iron	420	128	3.3 out of 5	\$345	\$144,900	
Distribution Mains	P-4724	EG	Rhodes Way	8	Ductile Iron	329	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4187	EG	Ridge Rd.	8	Ductile Iron	220	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4188	EG	Ridge Rd.	8	Ductile Iron	246	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4439	EG	Ridgefield Dr.	8	Asbestos Cement	471	40	1.72 out of 5	\$345	\$162,495	
Distribution Mains	P-4441	EG	Ridgefield Dr.	8	Asbestos Cement	419	40	1.72 out of 5	\$345	\$144,555	
Distribution Mains	P-4443	EG	Ridgefield Dr.	8	Asbestos Cement	412	40	1.72 out of 5	\$345	\$142,140	
Distribution Mains	P-4248	EG	River Farm Rd.	8	Asbestos Cement	447	46	1.72 out of 5	\$345	\$154,215	
Distribution Mains	P-4247	EG	River Farm Rd.	8	Ductile Iron	1,094	16	0 out of 5	N/A	\$0	
Distribution Mains	P-4249	EG	River Farm Rd.	8	Ductile Iron	1,598	19	0 out of 5	N/A	\$0	
Distribution Mains	P-4250	EG	River Farm Rd.	8	Ductile Iron	451	19	0 out of 5	N/A	\$0	
Distribution Mains	P-4080	EG	River Run	8	PVC	1,260	35	0.44 out of 5	\$345	\$434,700	
Distribution Mains	P-4081	EG	River Run	8	PVC	1,158	35	0.44 out of 5	\$345	\$399,510	
Distribution Mains	P-4083	EG	River Run	8	PVC	751	35	0.44 out of 5	\$345	\$259,095	
Distribution Mains	P-4084	EG	River Run	8	PVC	554	35	0.44 out of 5	\$345	\$191,130	
Distribution Mains	P-4048	EG	Robin Ct.	6	Asbestos Cement	363	42	2.43 out of 5	\$345	\$125,235	
Distribution Mains	P-4816	EG	Rock Way	8	Ductile Iron	894	9	0 out of 5	N/A	\$0	
Distribution Mains	P-4661	EG	Rocky Hollow Rd.	8	Ductile Iron	373	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4694	EG	Rocky Hollow Rd.	8	Ductile Iron	251	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4938	EG	Rocky Hollow Rd.	8	Ductile Iron	68	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4085	EG	Rosewood Ct.	8	PVC	121	35	0.44 out of 5	\$345	\$41,745	
Distribution Mains	P-4993	EG	Roundhill Ct.	6	Ductile Iron	278	30	0.86 out of 5	\$345	\$95,910	
Distribution Mains	P-4981	EG	Sally Ann Dr.	8	Asbestos Cement	227	30	1.58 out of 5	\$345	\$78,315	
Distribution Mains	P-4467	EG	Sanctuary Dr.	8	Ductile Iron	1,016	14	0 out of 5	N/A	\$0	
Distribution Mains	P-4469	EG	Sanctuary Dr.	8	Ductile Iron	312	14	0 out of 5	N/A	\$0	
Distribution Mains	P-4472	EG	Sanctuary Dr.	8	Ductile Iron	319	14	0 out of 5	N/A	\$0	
Distribution Mains	P-4473	EG	Sanctuary Dr.	8	Ductile Iron	549	14	0 out of 5	N/A	\$0	
Distribution Mains	P-4474	EG	Sanctuary Dr.	8	Ductile Iron	581	14	0 out of 5	N/A	\$0	
Distribution Mains	P-4442	EG	Sarah's Trace	8	PVC	568	25	0.44 out of 5	\$345	\$195,960	
Distribution Mains	P-4948	EG	School Ln.	1	Copper	183	18	2 out of 5	\$345	\$63,135	
Transmission Mains	P-4663	EG	Second St.	12	Ductile Iron	776	18	0 out of 5	N/A	\$0	
Transmission Mains	P-4669	EG	Second St.	12	Ductile Iron	500	18	0 out of 5	N/A	\$0	
Distribution Mains	P-4812	EG	Secret Ln.	8	Ductile Iron	350	9	0 out of 5	N/A	\$0	
Transmission Mains	P-4020	EG	Sheep Farm Dr	12	PVC	1,480	27	0.44 out of 5	\$345	\$510,600	
Transmission Mains	P-40001	EG	Sheep Farm Dr.	12	PVC	184	27	0.44 out of 5	\$345	\$63,480	
Distribution Mains	P-4021	EG	Sheep Farm Dr.	8	PVC	396	27	0.44 out of 5	\$345	\$136,620	
Transmission Mains	P-4183	EG	Shippeetown Rd.	16	Ductile Iron	1,454	19	0 out of 5	N/A	\$0	
Transmission Mains	P-4741	EG	Shippeetown Rd.	12	Ductile Iron	201	9	0 out of 5	N/A	\$0	
Transmission Mains	P-4742	EG	Shippeetown Rd.	12	Ductile Iron	2,699	9	0 out of 5	N/A	\$0	
Transmission Mains	P-4814	EG	Shippeetown Rd.	12	Ductile Iron	1,050	9	0 out of 5	N/A	\$0	
Transmission Mains	P-4996	EG	Shippeetown Rd.	12	Ductile Iron	39	9	0 out of 5	N/A	\$0	
Transmission Mains	P-4997	EG	Shippeetown Rd.	12	Ductile Iron	504	9	0 out of 5	N/A	\$0	
Transmission Mains	P-4173	EG	Signal Ridge Way	12	Asbestos Cement	323	34	1.58 out of 5	\$345	\$111,435	
Transmission Mains	P-4174	EG	Signal Ridge Way	12	Asbestos Cement	703	34	1.58 out of 5	\$345	\$242,535	
Transmission Mains	P-4176	EG	Signal Ridge Way	12	Asbestos Cement	584	34	1.58 out of 5	\$345	\$201,480	
Transmission Mains	P-4178	EG	Signal Ridge Way	12	Asbestos Cement	793	34	1.58 out of 5	\$345	\$273,585	
Transmission Mains	P-4177	EG	Signal Ridge Way	20	Ductile Iron	546	31	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4179	EG	Signal Ridge Way	20	Ductile Iron	2,423	31	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4880	EG	Signal Ridge Way	8	Ductile Iron	470	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4985	EG	Silo Ln.	8	Asbestos Cement	150	30	1.58 out of 5	\$345	\$51,750	
Distribution Mains	P-4293	EG	Silverwood Dr.	6	Asbestos Cement	254	46	2.43 out of 5	\$345	\$87,630	
Distribution Mains	P-4297	EG	Silverwood Dr.	6	Asbestos Cement	260	46	2.43 out of 5	\$345	\$89,700	
Distribution Mains	P-4298	EG	Silverwood Dr.	6	Asbestos Cement	305	46	2.43 out of 5	\$345	\$105,225	
Distribution Mains	P-40038	EG	Sixth Ave.	6	Cast iron	235	124	2.58 out of 5	\$345	\$81,075	
Distribution Mains	P-4667	EG	Sixth Ave.	6	Cast iron	236	124	2.58 out of 5	\$345	\$81,420	
Distribution Mains	P-4668	EG	Sixth Ave.	6	Cast iron	252	124	2.58 out of 5	\$345	\$86,940	
Distribution Mains	P-4943	EG	Sixth Ave.	6	Cast iron	487	124	2.58 out of 5	\$345	\$168,015	
Distribution Mains	P-4207	EG	Sixth Ave.	10	Ductile Iron	73	18	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-4670	EG	Sixth Ave.	12	Ductile Iron	198	18	0 out of 5	N/A	\$0	
Distribution Mains	P-40013	EG	Sleepy Hollow Rd.	8	Ductile Iron	319	3	0 out of 5	N/A	\$0	
Distribution Mains	P-40014	EG	Sleepy Hollow Rd.	8	Ductile Iron	253	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4198	EG	Sleepy Hollow Rd.	8	Ductile Iron	745	3	0 out of 5	N/A	\$0	
Transmission Mains	P-4743	EG	So County Tr.	12	Asbestos Cement	1,622	50	1.72 out of 5	\$345	\$559,590	
Transmission Mains	P-4115	EG	So. County Tr.	12	Asbestos Cement	5,009	50	2.43 out of 5	\$345	\$1,728,105	
Transmission Mains	P-4182	EG	So. County Tr.	12	Asbestos Cement	2,842	51	1.72 out of 5	\$345	\$980,490	
Transmission Mains	P-4186	EG	So. County Tr.	12	Asbestos Cement	1,058	51	1.72 out of 5	\$345	\$365,010	
Transmission Mains	P-4209	EG	So. County Tr.	12	Asbestos Cement	3,467	51	1.72 out of 5	\$345	\$1,196,115	
Transmission Mains	P-4210	EG	So. County Tr.	12	Asbestos Cement	391	51	1.72 out of 5	\$345	\$134,895	
Transmission Mains	P-4784	EG	So. County Tr.	12	Asbestos Cement	310	51	1.72 out of 5	\$345	\$106,950	
Transmission Mains	P-4830	EG	So. County Tr.	12	Asbestos Cement	822	51	1.72 out of 5	\$345	\$283,590	
Transmission Mains	P-4837	EG	So. County Tr.	12	Asbestos Cement	1,137	51	1.72 out of 5	\$345	\$392,265	
Transmission Mains	P-4863	EG	So. County Tr.	12	Asbestos Cement	1,226	51	1.72 out of 5	\$345	\$422,970	
Transmission Mains	P-4883	EG	So. County Tr.	12	Asbestos Cement	1,161	51	1.72 out of 5	\$345	\$400,545	
Transmission Mains	P-4208	EG	So. County Tr.	12	Ductile Iron	270	16	0 out of 5	N/A	\$0	
Distribution Mains	P-4884	EG	So. County Tr.	8	Ductile Iron	23	6	0 out of 5	N/A	\$0	
Transmission Mains	P-40026	EG	So. Pierce Rd.	20	Asbestos Cement	99	50	1.72 out of 5	\$345	\$34,155	
Transmission Mains	P-4230	EG	So. Pierce Rd.	20	Asbestos Cement	1,572	50	1.72 out of 5	\$345	\$542,340	
Distribution Mains	P-4323	EG	So. Pierce Rd.	8	Ductile Iron	57	31	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4359	EG	So. Pierce Rd.	8	Ductile Iron	250	31	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4360	EG	So. Pierce Rd.	8	Ductile Iron	255	31	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4370	EG	So. Pierce Rd.	8	Ductile Iron	209	31	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4399	EG	So. Pierce Rd.	8	Ductile Iron	1,685	31	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4409	EG	So. Pierce Rd.	8	Ductile Iron	473	31	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4952	EG	Somerset St.	1.5	Copper	249	76	2.44 out of 5	\$345	\$85,905	
Distribution Mains	P-4956	EG	Somerset St.	2	Copper	322	76	2.44 out of 5	\$345	\$111,090	
Distribution Mains	P-4951	EG	Somerset St.	6	Ductile Iron	39	12	0.71 out of 5	\$345	\$13,455	
Distribution Mains	P-4016	EG	Sonnet Dr.	8	PVC	596	27	0.44 out of 5	\$345	\$205,620	
Transmission Mains	P-40008	EG	South County Tr.	12	Asbestos Cement	716	51	1.72 out of 5	\$345	\$247,020	
Transmission Mains	P-40012	EG	South County Tr.	12	Asbestos Cement	1,572	51	1.72 out of 5	\$345	\$542,340	
Transmission Mains	P-40017	EG	South County Tr.	12	Ductile Iron	31	16	0 out of 5	N/A	\$0	
Transmission Mains	P-40018	EG	South County Tr.	12	Ductile Iron	453	2	0 out of 5	N/A	\$0	
Distribution Mains	P-4025	EG	Sparrow Ln.	8	Ductile Iron	712	21	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4999	EG	Sparrow Ln.	8	Ductile Iron	34	21	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4968	EG	Spencer Ave.	10	Cast iron	50	124	1.87 out of 5	\$345	\$17,250	
Distribution Mains	P-4998	EG	Spencer Grant Dr.	8	Ductile Iron	20	9	0 out of 5	N/A	\$0	
Distribution Mains	P-4546	EG	Spring St.	6	Cast iron	703	128	2.58 out of 5	\$345	\$242,535	
Distribution Mains	P-4547	EG	Spring St.	6	Cast iron	93	128	2.58 out of 5	\$345	\$32,085	
Distribution Mains	P-4556	EG	Spring St.	6	Cast iron	207	128	2.58 out of 5	\$345	\$71,415	
Distribution Mains	P-4573	EG	Spring St.	6	Cast iron	168	128	2.58 out of 5	\$345	\$57,960	
Distribution Mains	P-4574	EG	Spring St.	6	Cast iron	364	128	2.58 out of 5	\$345	\$125,580	
Distribution Mains	P-4575	EG	Spring St.	6	Cast iron	86	128	2.58 out of 5	\$345	\$29,670	
Distribution Mains	P-4605	EG	Spring St.	6	Cast iron	733	128	2.58 out of 5	\$345	\$252,885	
Transmission Mains	P-4957	EG	Spring St.	12	Cast iron	49	128	1.87 out of 5	\$345	\$16,905	
Transmission Mains	P-4582	EG	Spring St.	12	Ductile Iron	110	18	0 out of 5	N/A	\$0	
Distribution Mains	P-4220	EG	Spring Valley Dr.	8	Asbestos Cement	645	46	2.43 out of 5	\$345	\$222,525	
Distribution Mains	P-4222	EG	Spring Valley Dr.	8	Asbestos Cement	729	46	2.43 out of 5	\$345	\$251,505	
Distribution Mains	P-4213	EG	Spring Valley Dr.	8	Asbestos Cement	538	46	1.72 out of 5	\$345	\$185,610	
Distribution Mains	P-4215	EG	Spring Valley Dr.	8	Asbestos Cement	392	46	1.72 out of 5	\$345	\$135,240	
Distribution Mains	P-4216	EG	Spring Valley Dr.	8	Asbestos Cement	867	46	1.72 out of 5	\$345	\$299,115	
Distribution Mains	P-4219	EG	Spring Valley Dr.	8	Asbestos Cement	440	46	1.72 out of 5	\$345	\$151,800	
Distribution Mains	P-4223	EG	Spring Valley Dr.	8	Asbestos Cement	538	46	1.72 out of 5	\$345	\$185,610	
Distribution Mains	P-4043	EG	Squirrel Ln.	8	Asbestos Cement	625	42	1.72 out of 5	\$345	\$215,625	
Distribution Mains	P-4045	EG	Squirrel Ln.	8	Asbestos Cement	111	42	1.72 out of 5	\$345	\$38,295	
Distribution Mains	P-4817	EG	Squirrel Ln.	8	Ductile Iron	608	9	0 out of 5	N/A	\$0	
Distribution Mains	P-4818	EG	Squirrel Ln.	8	Ductile Iron	255	9	0 out of 5	N/A	\$0	
Distribution Mains	P-4119	EG	Stoneridge Dr.	8	Asbestos Cement	479	41	1.72 out of 5	\$345	\$165,255	
Distribution Mains	P-4120	EG	Stoneridge Dr.	8	Asbestos Cement	1,533	41	1.72 out of 5	\$345	\$528,885	
Distribution Mains	P-4125	EG	Stoneridge Dr.	8	Asbestos Cement	1,950	41	1.72 out of 5	\$345	\$672,750	
Distribution Mains	P-4124	EG	Stoneridge Dr.	8	Asbestos Cement	451	39	1.58 out of 5	\$345	\$155,595	
Transmission Mains	P-4126	EG	Stoneridge Dr.	20	Ductile Iron	548	31	0.15 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-4218	EG	Sunset Dr.	8	Asbestos Cement	1,104	46	1.72 out of 5	\$345	\$380,880	
Distribution Mains	P-4253	EG	Sycamore Dr.	8	Asbestos Cement	410	46	1.72 out of 5	\$345	\$141,450	
Distribution Mains	P-4255	EG	Sycamore Dr.	8	Asbestos Cement	459	46	1.72 out of 5	\$345	\$158,355	
Distribution Mains	P-4264	EG	Sycamore Dr.	8	Asbestos Cement	234	46	1.72 out of 5	\$345	\$80,730	
Distribution Mains	P-4265	EG	Sycamore Dr.	8	Asbestos Cement	394	46	1.72 out of 5	\$345	\$135,930	
Distribution Mains	P-4513	EG	Sylvan Dr.	6	Asbestos Cement	225	64	2.58 out of 5	\$345	\$77,625	
Distribution Mains	P-4505	EG	Sylvan Dr.	8	Asbestos Cement	279	65	1.87 out of 5	\$345	\$96,255	
Distribution Mains	P-4506	EG	Sylvan Dr.	8	Asbestos Cement	279	65	1.87 out of 5	\$345	\$96,255	
Distribution Mains	P-4510	EG	Sylvan Dr.	8	Asbestos Cement	338	65	1.87 out of 5	\$345	\$116,610	
Distribution Mains	P-4511	EG	Sylvan Dr.	8	Asbestos Cement	643	65	1.87 out of 5	\$345	\$221,835	
Distribution Mains	P-4478	EG	Tall Pine Dr.	8	Asbestos Cement	598	42	1.72 out of 5	\$345	\$206,310	
Distribution Mains	P-4476	EG	Tall Pine Dr. Easement	8	Ductile Iron	293	14	0 out of 5	N/A	\$0	
Distribution Mains	P-4325	EG	Tamarack Dr.	8	Asbestos Cement	486	45	1.72 out of 5	\$345	\$167,670	
Distribution Mains	P-4332	EG	Tamarack Dr.	8	Asbestos Cement	592	45	1.72 out of 5	\$345	\$204,240	
Distribution Mains	P-4333	EG	Tamarack Dr.	8	Asbestos Cement	1,097	45	1.72 out of 5	\$345	\$378,465	
Distribution Mains	P-4307	EG	Tanglewood Dr.	8	Asbestos Cement	409	55	2.43 out of 5	\$345	\$141,105	
Distribution Mains	P-4315	EG	Tanglewood Dr.	8	Asbestos Cement	731	55	2.43 out of 5	\$345	\$252,195	
Distribution Mains	P-4302	EG	Tanglewood Dr.	8	Asbestos Cement	906	55	1.72 out of 5	\$345	\$312,570	
Distribution Mains	P-4308	EG	Tanglewood Dr.	8	Asbestos Cement	361	55	1.72 out of 5	\$345	\$124,545	
Distribution Mains	P-4313	EG	Tanglewood Dr.	8	Asbestos Cement	389	55	1.72 out of 5	\$345	\$134,205	
Distribution Mains	P-4319	EG	Tanglewood Dr.	8	Asbestos Cement	158	55	1.72 out of 5	\$345	\$54,510	
Distribution Mains	P-4320	EG	Tanglewood Dr.	8	Asbestos Cement	228	55	1.72 out of 5	\$345	\$78,660	
Distribution Mains	P-4406	EG	Taylor Cir.	6	Asbestos Cement	239	46	2.43 out of 5	\$345	\$82,455	
Distribution Mains	P-4407	EG	Taylor Cir.	6	Asbestos Cement	168	46	2.43 out of 5	\$345	\$57,960	
Distribution Mains	P-40024	EG	Taylor Cir.	6	Ductile Iron	33	15	0.71 out of 5	\$345	\$11,385	
Distribution Mains	P-4254	EG	Teakwood Ct.	6	Asbestos Cement	383	46	2.43 out of 5	\$345	\$132,135	
Distribution Mains	P-4296	EG	Terrace Dr.	6	Asbestos Cement	1,233	46	2.43 out of 5	\$345	\$425,385	
Distribution Mains	P-40039	EG	Third St.	6	Asbestos Cement	164	64	2.58 out of 5	\$345	\$56,580	
Distribution Mains	P-4665	EG	Third St.	6	Asbestos Cement	149	64	2.58 out of 5	\$345	\$51,405	
Transmission Mains	P-4070	EG	Tillinghast Rd.	12	Ductile Iron	3,375	21	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4076	EG	Tillinghast Rd.	20	Ductile Iron	1,319	31	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4077	EG	Tillinghast Rd.	20	Ductile Iron	826	31	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4078	EG	Tillinghast Rd.	20	Ductile Iron	3,446	31	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4822	EG	Tillinghast Rd.	20	Ductile Iron	1,116	31	0.15 out of 5	N/A	\$0	
Transmission Mains	P-40007	EG	Tillinghast Rd.	12	Ductile Iron	69	17	0 out of 5	N/A	\$0	
Transmission Mains	P-4071	EG	Tillinghast Rd.	12	Ductile Iron	839	14	0 out of 5	N/A	\$0	
Transmission Mains	P-4716	EG	Tillinghast Rd.	12	Ductile Iron	134	15	0 out of 5	N/A	\$0	
Transmission Mains	P-4717	EG	Tillinghast Rd.	12	Ductile Iron	1,019	15	0 out of 5	N/A	\$0	
Transmission Mains	P-4821	EG	Tillinghast Rd.	12	Ductile Iron	1,270	15	0 out of 5	N/A	\$0	
Distribution Mains	P-4819	EG	Tina Ct.	8	Ductile Iron	310	9	0 out of 5	N/A	\$0	
Distribution Mains	P-4820	EG	Tina Ct. Easement	8	Ductile Iron	255	9	0 out of 5	N/A	\$0	
Distribution Mains	P-4823	EG	Tina Ct. Easement	8	Ductile Iron	7	9	0 out of 5	N/A	\$0	
Distribution Mains	P-4825	EG	Tina Ct. Easement	8	Ductile Iron	34	9	0 out of 5	N/A	\$0	
Distribution Mains	P-4311	EG	Tory Ln.	6	Asbestos Cement	531	55	3.14 out of 5	\$345	\$183,195	
Distribution Mains	P-4314	EG	Trappers Ln.	6	Asbestos Cement	492	55	2.43 out of 5	\$345	\$169,740	
Distribution Mains	P-4328	EG	Tucker St.	6	Asbestos Cement	510	52	2.43 out of 5	\$345	\$175,950	
Distribution Mains	P-4492	EG	Twin Pond Rd.	6	Asbestos Cement	592	49	2.43 out of 5	\$345	\$204,240	
Distribution Mains	P-4658	EG	Union St.	8	Ductile Iron	257	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4933	EG	Union St.	8	Ductile Iron	146	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4934	EG	Union St.	8	Ductile Iron	74	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4954	EG	Union St.	8	Ductile Iron	29	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4400	EG	Upland Ave.	6	Asbestos Cement	202	46	2.43 out of 5	\$345	\$69,690	
Distribution Mains	P-4401	EG	Upland Ave.	8	Ductile Iron	300	7	0 out of 5	N/A	\$0	
Distribution Mains	P-4189	EG	Valley Rd.	8	Ductile Iron	207	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4197	EG	Valley Rd.	8	Ductile Iron	942	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4507	EG	Verndale Dr.	6	Asbestos Cement	1,035	66	2.58 out of 5	\$345	\$357,075	
Distribution Mains	P-4347	EG	Victory St.	6	Asbestos Cement	217	45	2.43 out of 5	\$345	\$74,865	
Distribution Mains	P-4805	EG	Vine St.	6	Ductile Iron	175	12	0.71 out of 5	\$345	\$60,375	
Distribution Mains	P-4595	EG	Vine St.	8	Ductile Iron	272	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4408	EG	Violet Ct.	6	Asbestos Cement	147	46	2.43 out of 5	\$345	\$50,715	
Distribution Mains	P-4530	EG	Virginia Ave.	6	Asbestos Cement	758	64	2.58 out of 5	\$345	\$261,510	
Distribution Mains	P-4971	EG	Virginia Ave.	1	Copper	234	12	2 out of 5	\$345	\$80,730	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-4262	EG	Walnut Dr.	6	Asbestos Cement	1,081	46	2.43 out of 5	\$345	\$372,945	
Distribution Mains	P-4417	EG	Wanton Shippee Rd.	6	Asbestos Cement	885	59	2.43 out of 5	\$345	\$305,325	
Distribution Mains	P-4170	EG	Watch Hill	8	Asbestos Cement	831	31	1.58 out of 5	\$345	\$286,695	
Distribution Mains	P-4175	EG	Watch Hill Dr.	8	Asbestos Cement	3,294	31	1.58 out of 5	\$345	\$1,136,430	
Distribution Mains	P-4903	EG	Water St.	4	Asbestos Cement	67	42	3.15 out of 5	\$345	\$23,115	
Distribution Mains	P-4632	EG	Water St.	6	Asbestos Cement	415	42	3.14 out of 5	\$345	\$143,175	
Distribution Mains	P-4899	EG	Water St.	6	Cast iron	341	124	2.58 out of 5	\$345	\$117,645	
Distribution Mains	P-4655	EG	Water St.	6	Ductile Iron	1,196	27	0.86 out of 5	\$345	\$412,620	
Distribution Mains	P-4552	EG	West St.	6	Cast iron	287	128	2.58 out of 5	\$345	\$99,015	
Distribution Mains	P-4554	EG	West St.	6	Cast iron	434	128	2.58 out of 5	\$345	\$149,730	
Distribution Mains	P-4555	EG	West St.	6	Cast iron	353	128	2.58 out of 5	\$345	\$121,785	
Distribution Mains	P-4959	EG	West St.	6	Ductile Iron	29	12	0.71 out of 5	\$345	\$10,005	
Distribution Mains	P-4961	EG	West St.	6	Ductile Iron	23	12	0.71 out of 5	\$345	\$7,935	
Distribution Mains	P-4963	EG	West St.	6	Ductile Iron	30	12	0.71 out of 5	\$345	\$10,350	
Distribution Mains	P-4964	EG	West St.	6	Ductile Iron	25	12	0.71 out of 5	\$345	\$8,625	
Distribution Mains	P-4960	EG	West St.	8	Ductile Iron	20	12	0 out of 5	N/A	\$0	
Distribution Mains	P-4962	EG	West St.	8	Ductile Iron	22	12	0 out of 5	N/A	\$0	
Transmission Mains	P-4165	EG	Westfield Dr	16	Ductile Iron	632	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-40041	EG	Westfield Dr.	16	Ductile Iron	24	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4150	EG	Westfield Dr.	8	Ductile Iron	303	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4152	EG	Westfield Dr.	8	Ductile Iron	783	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4153	EG	Westfield Dr.	16	Ductile Iron	1,328	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-4166	EG	Westfield Dr.	16	Ductile Iron	2,072	21	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4416	EG	Westwood Dr.	6	Asbestos Cement	1,115	45	2.43 out of 5	\$345	\$384,675	
Transmission Mains	P-4231	EG	Westwood Dr.	20	Asbestos Cement	1,641	50	1.72 out of 5	\$345	\$566,145	
Distribution Mains	P-40015	EG	Wildwood Tr.	8	Ductile Iron	195	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4192	EG	Wildwood Tr.	8	Ductile Iron	895	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4169	EG	Winchester Dr.	6	Asbestos Cement	566	51	2.43 out of 5	\$345	\$195,270	
Transmission Mains	P-4620	EG	Wine St.	12	Ductile Iron	41	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4905	EG	Wine St.	8	Ductile Iron	236	3	0 out of 5	N/A	\$0	
Distribution Mains	P-4383	EG	Wintrop Rd.	6	Asbestos Cement	1,046	46	2.43 out of 5	\$345	\$360,870	
Distribution Mains	P-4012	EG	Wood Duck Ct.	8	Ductile Iron	369	22	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4014	EG	Woodbridge Dr.	8	PVC	1,349	36	0.44 out of 5	\$345	\$465,405	
Distribution Mains	P-4015	EG	Woodbridge Dr.	8	PVC	425	36	0.44 out of 5	\$345	\$146,625	
Distribution Mains	P-4017	EG	Woodbridge Dr.	8	PVC	2,083	36	0.44 out of 5	\$345	\$718,635	
Distribution Mains	P-4413	EG	Woodland Rd.	6	Asbestos Cement	841	45	2.43 out of 5	\$345	\$290,145	
Distribution Mains	P-6126	SCIT	Ben Brown Ave.	8	Ductile Iron	26	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-6001	SCIT	Blossom Ln.	8	Asbestos Cement	389	41	1.72 out of 5	\$345	\$134,205	
Distribution Mains	P-6002	SCIT	Blossom Ln.	8	Asbestos Cement	185	41	1.72 out of 5	\$345	\$63,825	
Distribution Mains	P-6085	SCIT	Brown St.	8	Ductile Iron	179	2	0 out of 5	N/A	\$0	
Transmission Mains	P-6041	SCIT	Clinton Ave.	16	Asbestos Cement	438	42	1.72 out of 5	\$345	\$151,110	
Transmission Mains	P-6059	SCIT	Clinton Ave.	16	Asbestos Cement	501	42	1.72 out of 5	\$345	\$172,845	
Transmission Mains	P-6060	SCIT	Clinton Ave.	16	Asbestos Cement	88	42	1.72 out of 5	\$345	\$30,360	
Transmission Mains	P-6101	SCIT	Clinton Ave.	16	Asbestos Cement	253	42	1.72 out of 5	\$345	\$87,285	
Transmission Mains	P-6039	SCIT	Clinton Ave.	24	Ductile Iron	121	9	0 out of 5	N/A	\$0	
Transmission Mains	P-6042	SCIT	Clinton Ave.	24	Ductile Iron	274	9	0 out of 5	N/A	\$0	
Transmission Mains	P-6043	SCIT	Clinton Ave.	24	Ductile Iron	237	9	0 out of 5	N/A	\$0	
Transmission Mains	P-6047	SCIT	Clinton Ave.	24	Ductile Iron	404	9	0 out of 5	N/A	\$0	
Transmission Mains	P-6086	SCIT	Clinton Ave.	24	Ductile Iron	683	9	0 out of 5	N/A	\$0	
Transmission Mains	P-6094	SCIT	Clinton Ave.	30	Steel	387	3	0 out of 5	N/A	\$0	
Transmission Mains	P-6095	SCIT	Clinton Ave.	12	Ductile Iron	116	3	0 out of 5	N/A	\$0	
Transmission Mains	P-6096	SCIT	Clinton Ave.	12	Ductile Iron	154	3	0 out of 5	N/A	\$0	
Transmission Mains	P-6097	SCIT	Clinton Ave.	12	Ductile Iron	124	3	0 out of 5	N/A	\$0	
Transmission Mains	P-6098	SCIT	Clinton Ave.	12	Ductile Iron	127	3	0 out of 5	N/A	\$0	
Transmission Mains	P-6099	SCIT	Clinton Ave.	12	Ductile Iron	144	3	0 out of 5	N/A	\$0	
Transmission Mains	P-6100	SCIT	Clinton Ave.	12	Ductile Iron	124	3	0 out of 5	N/A	\$0	
Transmission Mains	P-6038	SCIT	Clinton Ave. PS	30	Steel	348	8	0 out of 5	N/A	\$0	
Transmission Mains	P-6061	SCIT	Clinton Ave. PS	30	Steel	10	8	0 out of 5	N/A	\$0	
Transmission Mains	P-6062	SCIT	Clinton Ave. PS	30	Steel	5	8	0 out of 5	N/A	\$0	
Transmission Mains	P-6063	SCIT	Clinton Ave. PS	16	Ductile Iron	10	8	0 out of 5	N/A	\$0	
Transmission Mains	P-6064	SCIT	Clinton Ave. PS	30	Steel	5	8	0 out of 5	N/A	\$0	
Transmission Mains	P-6065	SCIT	Clinton Ave. PS	16	Ductile Iron	10	8	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-6066	SCIT	Clinton Ave. PS	30	Steel	5	8	0 out of 5	N/A	\$0	
Transmission Mains	P-6067	SCIT	Clinton Ave. PS	16	Ductile Iron	10	8	0 out of 5	N/A	\$0	
Transmission Mains	P-6068	SCIT	Clinton Ave. PS	30	Steel	5	8	0 out of 5	N/A	\$0	
Transmission Mains	P-6069	SCIT	Clinton Ave. PS	16	Ductile Iron	10	8	0 out of 5	N/A	\$0	
Transmission Mains	P-6070	SCIT	Clinton Ave. PS	30	Steel	100	8	0 out of 5	N/A	\$0	
Transmission Mains	P-6071	SCIT	Clinton Ave. PS	16	Ductile Iron	10	8	0 out of 5	N/A	\$0	
Transmission Mains	P-6072	SCIT	Clinton Ave. PS	30	Steel	5	8	0 out of 5	N/A	\$0	
Transmission Mains	P-6073	SCIT	Clinton Ave. PS	16	Ductile Iron	10	8	0 out of 5	N/A	\$0	
Transmission Mains	P-6074	SCIT	Clinton Ave. PS	30	Steel	5	8	0 out of 5	N/A	\$0	
Transmission Mains	P-6075	SCIT	Clinton Ave. PS	16	Ductile Iron	10	8	0 out of 5	N/A	\$0	
Transmission Mains	P-6076	SCIT	Clinton Ave. PS	30	Steel	5	8	0 out of 5	N/A	\$0	
Transmission Mains	P-6077	SCIT	Clinton Ave. PS	16	Ductile Iron	10	8	0 out of 5	N/A	\$0	
Transmission Mains	P-6102	SCIT	Clinton Ave. PS	30	Steel	5	8	0 out of 5	N/A	\$0	
Transmission Mains	P-6104	SCIT	Clinton Ave. PS	16	Ductile Iron	10	8	0 out of 5	N/A	\$0	
Transmission Mains	P-6105	SCIT	Clinton Ave. PS	16	Ductile Iron	10	8	0 out of 5	N/A	\$0	
Transmission Mains	P-6106	SCIT	Clinton Ave. PS	30	Steel	5	8	0 out of 5	N/A	\$0	
Transmission Mains	P-6045	SCIT	Colvin St.	16	Asbestos Cement	1,427	57	1.72 out of 5	\$345	\$492,315	
Transmission Mains	P-6055	SCIT	Colvin St.	16	Asbestos Cement	211	57	1.72 out of 5	\$345	\$72,795	
Transmission Mains	P-6091	SCIT	Colvin St.	24	Ductile Iron	1,844	9	0 out of 5	N/A	\$0	
Transmission Mains	P-6092	SCIT	Colvin St.	24	Ductile Iron	348	9	0 out of 5	N/A	\$0	
Distribution Mains	P-6031	SCIT	Country Ln.	8	Ductile Iron	122	2	0 out of 5	N/A	\$0	
Distribution Mains	P-6032	SCIT	Country Ln.	8	Ductile Iron	232	2	0 out of 5	N/A	\$0	
Transmission Mains	P-6023	SCIT	Cranberry Dr.	16	Ductile Iron	963	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-6025	SCIT	Cranberry Dr.	16	Ductile Iron	337	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-6027	SCIT	Cranberry Dr.	16	Ductile Iron	1,238	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-6050	SCIT	Doray Dr.	8	Asbestos Cement	349	56	1.72 out of 5	\$345	\$120,405	
Distribution Mains	P-6051	SCIT	Doray Dr.	8	Asbestos Cement	292	56	1.72 out of 5	\$345	\$100,740	
Distribution Mains	P-6130	SCIT	Eagle Dr.	8	Ductile Iron	29	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-6132	SCIT	Eagle Dr.	8	Ductile Iron	30	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-6030	SCIT	Garden Ln.	8	Ductile Iron	472	2	0 out of 5	N/A	\$0	
Distribution Mains	P-6084	SCIT	Goddard St.	8	Ductile Iron	238	2	0 out of 5	N/A	\$0	
Distribution Mains	P-6121	SCIT	Goddard St.	8	Ductile Iron	58	2	0 out of 5	N/A	\$0	
Distribution Mains	P-6008	SCIT	Harrington Ave.	6	Cast iron	800	78	2.29 out of 5	\$345	\$276,000	
Distribution Mains	P-6009	SCIT	Harrington Ave.	6	PVC	173	28	1.15 out of 5	\$345	\$59,685	
Distribution Mains	P-6007	SCIT	High St.	6	PVC	805	28	1.15 out of 5	\$345	\$277,725	
Distribution Mains	P-6021	SCIT	Hope Ave.	8	Asbestos Cement	2,357	47	1.72 out of 5	\$345	\$813,165	
Transmission Mains	P-6087	SCIT	Hope Ave.	24	Ductile Iron	3,024	9	0 out of 5	N/A	\$0	
Transmission Mains	P-6016	SCIT	Hope Furnace Rd.	12	Ductile Iron	604	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-6018	SCIT	Hope Furnace Rd.	12	Ductile Iron	1,045	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-6122	SCIT	Hope Furnace Rd.	12	Ductile Iron	465	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-6123	SCIT	Hope Furnace Rd.	8	Ductile Iron	30	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-6124	SCIT	Hope Furnace Rd.	12	Ductile Iron	574	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-6125	SCIT	Hope Furnace Rd.	8	Ductile Iron	20	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-6019	SCIT	Howard Ave.	12	Ductile Iron	401	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-6020	SCIT	Howard Ave.	12	Ductile Iron	409	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-6107	SCIT	Howard Ave.	12	Ductile Iron	592	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-6127	SCIT	Howard Ave.	12	Ductile Iron	1,518	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-6129	SCIT	Howard Ave.	12	Ductile Iron	483	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-6131	SCIT	Howard Ave.	12	Ductile Iron	81	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-6081	SCIT	Ives St.	6	Cast iron	251	75	2.29 out of 5	\$345	\$86,595	
Distribution Mains	P-6082	SCIT	Ives St. Easement	4	Cast iron	209	75	3.01 out of 5	\$345	\$72,105	
Distribution Mains	P-6115	SCIT	Jackson Flat Rd.	1	Copper	391	1	2 out of 5	\$345	\$134,895	IFR 2014A
Distribution Mains	P-6118	SCIT	Jackson Flat Rd.	6	Ductile Iron	380	24	0.86 out of 5	\$345	\$131,100	
Distribution Mains	P-6117	SCIT	Jackson Flat Rd.	6	Ductile Iron	22	10	0.71 out of 5	\$345	\$7,590	
Distribution Mains	P-6052	SCIT	Jackson Flat Rd.	8	Ductile Iron	110	15	0 out of 5	N/A	\$0	
Distribution Mains	P-6053	SCIT	Jackson Flat Rd.	8	Ductile Iron	535	15	0 out of 5	N/A	\$0	
Transmission Mains	P-6093	SCIT	Jackson Flat Rd.	24	Ductile Iron	65	9	0 out of 5	N/A	\$0	
Distribution Mains	P-6114	SCIT	Jackson Flat Rd.	8	Ductile Iron	37	1	0 out of 5	N/A	\$0	
Distribution Mains	P-6116	SCIT	Jackson Flat Rd.	8	Ductile Iron	26	10	0 out of 5	N/A	\$0	
Transmission Mains	P-6026	SCIT	Kerri Ct.	16	Ductile Iron	563	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-6090	SCIT	Knotty Oak Rd.	24	Ductile Iron	149	9	0 out of 5	N/A	\$0	
Transmission Mains	P-6022	SCIT	Main St.	16	Asbestos Cement	228	58	1.72 out of 5	\$345	\$78,660	IFR 2014A

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-6028	SCIT	Main St.	16	Asbestos Cement	646	58	1.72 out of 5	\$345	\$222,870	IFR 2014A
Transmission Mains	P-6035	SCIT	Main St.	16	Asbestos Cement	231	58	1.72 out of 5	\$345	\$79,695	IFR 2014A
Distribution Mains	P-6015	SCIT	Main St.	8	Ductile Iron	631	26	0.15 out of 5	N/A	\$0	
Distribution Mains	P-6010	SCIT	Main St.	8	Ductile Iron	522	10	0 out of 5	N/A	\$0	
Distribution Mains	P-6011	SCIT	Main St.	8	Ductile Iron	338	10	0 out of 5	N/A	\$0	
Distribution Mains	P-6014	SCIT	Main St.	8	Ductile Iron	229	10	0 out of 5	N/A	\$0	
Distribution Mains	P-6083	SCIT	Main St.	8	Ductile Iron	377	10	0 out of 5	N/A	\$0	
Transmission Mains	P-6088	SCIT	Main St.	24	Ductile Iron	476	9	0 out of 5	N/A	\$0	
Transmission Mains	P-6089	SCIT	Main St.	24	Ductile Iron	1,946	9	0 out of 5	N/A	\$0	
Distribution Mains	P-6029	SCIT	Meadow Rd.	8	Ductile Iron	205	2	0 out of 5	N/A	\$0	
Distribution Mains	P-6033	SCIT	Meadow Rd.	8	Ductile Iron	63	2	0 out of 5	N/A	\$0	
Distribution Mains	P-6034	SCIT	Meadow Rd.	8	Ductile Iron	237	2	0 out of 5	N/A	\$0	
Distribution Mains	P-6013	SCIT	Mill St.	6	Cast iron	1,087	127	2.58 out of 5	\$345	\$375,015	
Distribution Mains	P-6080	SCIT	North Rd.	6	Cast iron	224	75	2.29 out of 5	\$345	\$77,280	
Distribution Mains	P-6003	SCIT	North Rd.	8	Asbestos Cement	102	42	1.72 out of 5	\$345	\$35,190	
Distribution Mains	P-6078	SCIT	North Rd.	8	Asbestos Cement	755	41	1.72 out of 5	\$345	\$260,475	
Distribution Mains	P-6004	SCIT	North Rd.	6	PVC	254	28	1.15 out of 5	\$345	\$87,630	
Distribution Mains	P-6006	SCIT	North Rd.	6	PVC	746	28	1.15 out of 5	\$345	\$257,370	
Distribution Mains	P-6012	SCIT	North Rd.	6	PVC	376	28	1.15 out of 5	\$345	\$129,720	
Distribution Mains	P-6119	SCIT	North Rd.	6	PVC	248	28	1.15 out of 5	\$345	\$85,560	
Distribution Mains	P-6000	SCIT	Orchard Dr.	8	Asbestos Cement	1,976	41	1.72 out of 5	\$345	\$681,720	
Transmission Mains	P-6024	SCIT	Pasture View Ln.	16	Ductile Iron	449	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-6049	SCIT	Patnode Ave.	6	Ductile Iron	454	21	0.86 out of 5	\$345	\$156,630	
Distribution Mains	P-6120	SCIT	Reservation Dr.	6	Asbestos Cement	507	50	2.43 out of 5	\$345	\$174,915	
Distribution Mains	P-6128	SCIT	Talbut Rd.	8	Ductile Iron	35	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-6079	SCIT	White Ln.	6	PVC	556	26	1.15 out of 5	\$345	\$191,820	
Distribution Mains	P-2265	WAR	Abigail St.	6	Asbestos Cement	581	61	2.58 out of 5	\$345	\$200,445	
Distribution Mains	P-2954	WAR	Abigail St.	8	Asbestos Cement	42	61	1.87 out of 5	\$345	\$14,490	
Distribution Mains	P-2565	WAR	Adelaide Ave.	8	Ductile Iron	263	2	0 out of 5	N/A	\$0	
Distribution Mains	P-2567	WAR	Adelaide Ave.	8	Ductile Iron	653	2	0 out of 5	N/A	\$0	
Distribution Mains	P-2572	WAR	Adelaide Ave.	8	Ductile Iron	190	2	0 out of 5	N/A	\$0	
Distribution Mains	P-2662	WAR	Adelaide Ave.	8	Ductile Iron	355	2	0 out of 5	N/A	\$0	
Distribution Mains	P-2161	WAR	Alanna Ct.	8	Ductile Iron	431	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2434	WAR	Alger Ave.	8	Cast iron	269	124	1.87 out of 5	\$345	\$92,805	
Distribution Mains	P-2435	WAR	Alger Ave.	8	Cast iron	752	124	1.87 out of 5	\$345	\$259,440	
Distribution Mains	P-2162	WAR	Alicia Ct.	8	Ductile Iron	367	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2879	WAR	Alvin St.	1.5	Copper	354	77	2.44 out of 5	\$345	\$122,130	
Distribution Mains	P-2878	WAR	Alvin St.	2	Copper	21	6	2 out of 5	\$345	\$7,245	
Distribution Mains	P-2877	WAR	Alvin St.	8	Ductile Iron	25	6	0 out of 5	N/A	\$0	
Distribution Mains	P-2559	WAR	Amy St.	6	Cast iron	189	86	2.43 out of 5	\$345	\$65,205	IFR 2015A
Distribution Mains	P-2512	WAR	Andover Ave.	6	Asbestos Cement	454	52	2.43 out of 5	\$345	\$156,630	
Distribution Mains	P-2740	WAR	Ann Nolst Ct.	8	Ductile Iron	558	17	0 out of 5	N/A	\$0	
Transmission Mains	P-2412	WAR	Arnold Ave.	12	Ductile Iron	328	3	0 out of 5	N/A	\$0	
Distribution Mains	P-2599	WAR	Arnolds Neck Dr.	8	Asbestos Cement	493	68	1.87 out of 5	\$345	\$170,085	
Distribution Mains	P-2600	WAR	Arnolds Neck Dr.	8	Asbestos Cement	744	68	1.87 out of 5	\$345	\$256,680	
Distribution Mains	P-2601	WAR	Arnolds Neck Dr.	8	Asbestos Cement	1,315	68	1.87 out of 5	\$345	\$453,675	
Distribution Mains	P-2605	WAR	Arnolds Neck Dr.	8	Asbestos Cement	712	68	1.87 out of 5	\$345	\$245,640	
Distribution Mains	P-2606	WAR	Arnolds Neck Dr.	8	Asbestos Cement	224	68	1.87 out of 5	\$345	\$77,280	
Distribution Mains	P-2423	WAR	Arnolds Neck Dr.	8	Ductile Iron	1,343	21	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2121	WAR	Arrowhead Way	8	PVC	618	26	0.44 out of 5	\$345	\$213,210	
Distribution Mains	P-2457	WAR	Ashmont St.	6	Asbestos Cement	156	57	2.43 out of 5	\$345	\$53,820	
Distribution Mains	P-2707	WAR	Ashmont St.	6	Asbestos Cement	317	57	2.43 out of 5	\$345	\$109,365	
Distribution Mains	P-2708	WAR	Ashmont St.	6	Asbestos Cement	204	57	2.43 out of 5	\$345	\$70,380	
Distribution Mains	P-2415	WAR	Azalea Ct.	6	Asbestos Cement	438	60	2.58 out of 5	\$345	\$151,110	
Distribution Mains	P-2550	WAR	Baker St.	6	Cast iron	436	86	3.14 out of 5	\$345	\$150,420	IFR 2015A
Distribution Mains	P-2552	WAR	Baker St.	6	Cast iron	462	86	2.43 out of 5	\$345	\$159,390	IFR 2015A
Transmission Mains	P-2231	WAR	Bald Hill Rd.	24	Asbestos Cement	2,241	30	1.58 out of 5	\$345	\$773,145	
Transmission Mains	P-2667	WAR	Bald Hill Rd.	24	Asbestos Cement	1,934	30	1.58 out of 5	\$345	\$667,230	
Transmission Mains	P-2896	WAR	Bald Hill Rd.	24	Asbestos Cement	71	30	1.58 out of 5	\$345	\$24,495	
Distribution Mains	P-2863	WAR	Bald Hill Rd.	6	Ductile Iron	478	34	0.86 out of 5	\$345	\$164,910	
Distribution Mains	P-2864	WAR	Bald Hill Rd.	6	Ductile Iron	112	34	0.86 out of 5	\$345	\$38,640	
Distribution Mains	P-2865	WAR	Bald Hill Rd.	6	Ductile Iron	107	34	0.86 out of 5	\$345	\$36,915	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-2009	WAR	Baldwin Rd.	6	Asbestos Cement	500	54	2.43 out of 5	\$345	\$172,500	
Distribution Mains	P-2011	WAR	Baldwin Rd.	6	Asbestos Cement	567	54	2.43 out of 5	\$345	\$195,615	
Distribution Mains	P-2012	WAR	Baldwin Rd.	6	Asbestos Cement	199	54	2.43 out of 5	\$345	\$68,655	
Distribution Mains	P-2013	WAR	Baldwin Rd.	6	Asbestos Cement	553	54	2.43 out of 5	\$345	\$190,785	
Distribution Mains	P-2017	WAR	Baldwin Rd.	6	Asbestos Cement	522	54	2.43 out of 5	\$345	\$180,090	
Distribution Mains	P-2523	WAR	Bangor St.	6	Asbestos Cement	470	64	2.58 out of 5	\$345	\$162,150	
Distribution Mains	P-2661	WAR	Bay View Ave.	6	Asbestos Cement	586	49	2.43 out of 5	\$345	\$202,170	
Distribution Mains	P-2587	WAR	Bay View Ave.	10	Cast iron	1,160	86	1.72 out of 5	\$345	\$400,200	
Transmission Mains	P-2588	WAR	Bay View Ave.	12	Cast iron	181	86	1.72 out of 5	\$345	\$62,445	
Transmission Mains	P-2590	WAR	Bay View Ave.	12	Cast iron	583	86	1.72 out of 5	\$345	\$201,135	
Transmission Mains	P-2592	WAR	Bay View Ave.	12	Cast iron	674	86	1.72 out of 5	\$345	\$232,530	
Distribution Mains	P-2351	WAR	Bay Vista Pl.	1.5	Copper	438	50	2.29 out of 5	\$345	\$151,110	
Distribution Mains	P-2426	WAR	Beacon Hill Dr.	8	Asbestos Cement	376	39	2.29 out of 5	\$345	\$129,720	
Distribution Mains	P-2921	WAR	Benefit St.	0.8	Copper	260	82	2.58 out of 5	\$345	\$89,700	
Distribution Mains	P-2723	WAR	Benefit St.	6	Cast iron	520	82	2.43 out of 5	\$345	\$179,400	
Distribution Mains	P-2269	WAR	Benjamin St	6	Asbestos Cement	692	63	2.58 out of 5	\$345	\$238,740	
Distribution Mains	P-2952	WAR	Benjamin St	8	Asbestos Cement	24	63	1.87 out of 5	\$345	\$8,280	
Distribution Mains	P-2591	WAR	Berkeley Rd.	6	Cast iron	453	86	2.43 out of 5	\$345	\$156,285	
Distribution Mains	P-2589	WAR	Beverly Rd.	6	Cast iron	247	75	2.29 out of 5	\$345	\$85,215	
Distribution Mains	P-2069	WAR	Birkshire Dr.	8	Asbestos Cement	494	50	1.72 out of 5	\$345	\$170,430	
Distribution Mains	P-2075	WAR	Birkshire Dr.	8	Asbestos Cement	829	50	1.72 out of 5	\$345	\$286,005	
Distribution Mains	P-2730	WAR	Bishop Rd.	6	Asbestos Cement	260	45	2.43 out of 5	\$345	\$89,700	
Distribution Mains	P-2059	WAR	Bishop Rd.	6	Ductile Iron	118	13	0.71 out of 5	\$345	\$40,710	
Distribution Mains	P-2729	WAR	Bishop Rd.	6	Ductile Iron	135	13	0.71 out of 5	\$345	\$46,575	
Distribution Mains	P-2403	WAR	Blackmore St.	8	Ductile Iron	585	3	0 out of 5	N/A	\$0	
Distribution Mains	P-2857	WAR	Blade St.	4	Cast iron	165	86	3.86 out of 5	\$345	\$56,925	IFR 2015A
Distribution Mains	P-2546	WAR	Blade St.	6	Cast iron	1,130	86	2.43 out of 5	\$345	\$389,850	IFR 2015A
Distribution Mains	P-2856	WAR	Blade St.	4	Ductile Iron	27	11	1.43 out of 5	\$345	\$9,315	
Distribution Mains	P-2858	WAR	Blade St.	8	Ductile Iron	299	11	0 out of 5	N/A	\$0	
Distribution Mains	P-2250	WAR	Blair Dr.	8	Asbestos Cement	320	44	1.72 out of 5	\$345	\$110,400	
Distribution Mains	P-2113	WAR	Blossom Ct.	8	PVC	268	27	0.44 out of 5	\$345	\$92,460	
Distribution Mains	P-2496	WAR	Blue Hill Dr.	6	Asbestos Cement	228	60	2.58 out of 5	\$345	\$78,660	
Distribution Mains	P-2497	WAR	Blue Hill Dr.	6	Asbestos Cement	256	60	2.58 out of 5	\$345	\$88,320	
Distribution Mains	P-2501	WAR	Blue Hill Dr.	6	Asbestos Cement	256	60	2.58 out of 5	\$345	\$88,320	
Distribution Mains	P-2502	WAR	Blue Hill Dr.	6	Asbestos Cement	257	60	2.58 out of 5	\$345	\$88,665	
Distribution Mains	P-2909	WAR	Blue Hill Dr.	8	Ductile Iron	27	6	0 out of 5	N/A	\$0	
Distribution Mains	P-2141	WAR	Blue Ridge Rd.	8	Ductile Iron	486	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2146	WAR	Blue Ridge Rd.	8	Ductile Iron	404	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2156	WAR	Blue Ridge Rd.	8	Ductile Iron	412	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2157	WAR	Blue Ridge Rd.	8	Ductile Iron	111	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2927	WAR	Bokar St.	6	Ductile Iron	432	13	0.71 out of 5	\$345	\$149,040	
Distribution Mains	P-2462	WAR	Bokar St.	8	Ductile Iron	232	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2468	WAR	Bokar St.	8	Ductile Iron	255	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2471	WAR	Bokar St.	8	Ductile Iron	550	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2033	WAR	Boulder View Dr.	8	Asbestos Cement	296	37	1.58 out of 5	\$345	\$102,120	
Distribution Mains	P-2034	WAR	Boulder View Dr.	8	Asbestos Cement	300	37	1.58 out of 5	\$345	\$103,500	
Distribution Mains	P-2051	WAR	Boulder View Dr.	8	Asbestos Cement	265	37	1.58 out of 5	\$345	\$91,425	
Distribution Mains	P-2715	WAR	Boulder View Dr.	8	PVC	470	26	0.44 out of 5	\$345	\$162,150	
Distribution Mains	P-2525	WAR	Breana Ln.	6	Ductile Iron	463	26	0.86 out of 5	\$345	\$159,735	
Distribution Mains	P-2880	WAR	Breana Ln.	8	Ductile Iron	30	6	0 out of 5	N/A	\$0	
Distribution Mains	P-2541	WAR	Brian Dr.	8	Asbestos Cement	543	50	1.72 out of 5	\$345	\$187,335	
Distribution Mains	P-2663	WAR	Briarbrook Dr.	8	Ductile Iron	544	29	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2665	WAR	Briarbrook Dr.	8	Ductile Iron	320	29	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2096	WAR	Briarwood Ct.	6	Ductile Iron	209	22	0.86 out of 5	\$345	\$72,105	
Distribution Mains	P-2639	WAR	Bridal Ave.	6	Cast iron	615	92	3.14 out of 5	\$345	\$212,175	IFR 2015B
Distribution Mains	P-2640	WAR	Bridal Ave.	6	Cast iron	407	92	3.14 out of 5	\$345	\$140,415	IFR 2015B
Distribution Mains	P-2945	WAR	Brier Ct.	2	Copper	250	74	2.44 out of 5	\$345	\$86,250	
Distribution Mains	P-2108	WAR	Brightwater Dr.	8	PVC	470	27	0.44 out of 5	\$345	\$162,150	
Distribution Mains	P-2813	WAR	Broadbent St.	8	Ductile Iron	249	9	0 out of 5	N/A	\$0	
Distribution Mains	P-2186	WAR	Brookline Dr.	8	PVC	414	26	0.44 out of 5	\$345	\$142,830	
Distribution Mains	P-2205	WAR	Brookline Dr.	8	PVC	254	26	0.44 out of 5	\$345	\$87,630	
Distribution Mains	P-2207	WAR	Brookline Dr.	8	PVC	612	26	0.44 out of 5	\$345	\$211,140	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-2208	WAR	Brookline Dr.	8	PVC	572	26	0.44 out of 5	\$345	\$197,340	
Distribution Mains	P-2344	WAR	Bruce Ln.	6	Asbestos Cement	436	68	2.58 out of 5	\$345	\$150,420	
Distribution Mains	P-2551	WAR	Burton St.	6	Asbestos Cement	347	35	2.29 out of 5	\$345	\$119,715	IFR 2015A
Distribution Mains	P-2641	WAR	Cactus St.	8	Asbestos Cement	376	58	1.72 out of 5	\$345	\$129,720	
Distribution Mains	P-2642	WAR	Cactus St.	8	Asbestos Cement	228	58	1.72 out of 5	\$345	\$78,660	
Distribution Mains	P-2644	WAR	Cactus St.	8	Asbestos Cement	92	58	1.72 out of 5	\$345	\$31,740	
Distribution Mains	P-2475	WAR	Calhoun Ave.	6	Ductile Iron	215	20	0.86 out of 5	\$345	\$74,175	
Distribution Mains	P-2477	WAR	Calhoun Ave.	6	Ductile Iron	210	20	0.86 out of 5	\$345	\$72,450	
Distribution Mains	P-2936	WAR	Candle Hill Ct.	2	Copper	224	58	2.29 out of 5	\$345	\$77,280	
Distribution Mains	P-2500	WAR	Cardinal St.	6	Asbestos Cement	410	60	2.58 out of 5	\$345	\$141,450	
Distribution Mains	P-2026	WAR	Carriage Hill Dr.	6	Asbestos Cement	334	34	2.29 out of 5	\$345	\$115,230	
Distribution Mains	P-2695	WAR	Carrs Ln.	6	Ductile Iron	543	23	0.86 out of 5	\$345	\$187,335	
Distribution Mains	P-2490	WAR	Carson Ave.	6	Asbestos Cement	328	42	2.43 out of 5	\$345	\$113,160	
Distribution Mains	P-2491	WAR	Carson Ave.	6	Asbestos Cement	142	42	2.43 out of 5	\$345	\$48,990	
Distribution Mains	P-2886	WAR	Carson Ave.	6	Ductile Iron	22	6	0.71 out of 5	\$345	\$7,590	
Distribution Mains	P-2884	WAR	Carson Ave.	8	Ductile Iron	23	6	0 out of 5	N/A	\$0	
Distribution Mains	P-2943	WAR	Carvin Ct.	2	Copper	185	74	2.44 out of 5	\$345	\$63,825	
Distribution Mains	P-2218	WAR	Castle Rocks Rd.	8	Ductile Iron	587	16	0 out of 5	N/A	\$0	
Distribution Mains	P-2219	WAR	Castle Rocks Rd.	8	Ductile Iron	928	16	0 out of 5	N/A	\$0	
Distribution Mains	P-2220	WAR	Castle Rocks Rd.	8	Ductile Iron	59	16	0 out of 5	N/A	\$0	
Distribution Mains	P-2221	WAR	Castle Rocks Rd.	8	Ductile Iron	554	16	0 out of 5	N/A	\$0	
Distribution Mains	P-2222	WAR	Castle Rocks Rd.	8	Ductile Iron	1,368	16	0 out of 5	N/A	\$0	
Distribution Mains	P-2223	WAR	Castle Rocks Rd.	8	Ductile Iron	564	16	0 out of 5	N/A	\$0	
Distribution Mains	P-2498	WAR	Caverly St.	6	Asbestos Cement	404	59	2.43 out of 5	\$345	\$139,380	
Distribution Mains	P-2594	WAR	Cedar St.	6	Asbestos Cement	1,111	48	2.43 out of 5	\$345	\$383,295	
Distribution Mains	P-2694	WAR	Cedar St.	6	Asbestos Cement	729	48	2.43 out of 5	\$345	\$251,505	
Distribution Mains	P-2595	WAR	Cedar St.	6	Cast iron	840	78	2.29 out of 5	\$345	\$289,800	
Distribution Mains	P-2484	WAR	Centennial St.	6	Asbestos Cement	184	72	2.58 out of 5	\$345	\$63,480	
Distribution Mains	P-2486	WAR	Centennial St.	6	Asbestos Cement	232	72	2.58 out of 5	\$345	\$80,040	
Distribution Mains	P-2907	WAR	Centennial St.	6	Ductile Iron	22	6	0.71 out of 5	\$345	\$7,590	
Distribution Mains	P-2906	WAR	Centennial St.	8	Ductile Iron	22	6	0 out of 5	N/A	\$0	
Transmission Mains	P-2023	WAR	Centerville Rd.	12	Asbestos Cement	1,315	56	2.43 out of 5	\$345	\$453,675	
Transmission Mains	P-2427	WAR	Centerville Rd.	12	Asbestos Cement	1,950	56	2.43 out of 5	\$345	\$672,750	
Distribution Mains	P-2024	WAR	Centerville Rd.	8	Asbestos Cement	1,760	60	1.87 out of 5	\$345	\$607,200	
Transmission Mains	P-2000	WAR	Centerville Rd.	12	Asbestos Cement	454	56	1.72 out of 5	\$345	\$156,630	
Transmission Mains	P-2002	WAR	Centerville Rd.	12	Asbestos Cement	273	56	1.72 out of 5	\$345	\$94,185	
Transmission Mains	P-2004	WAR	Centerville Rd.	12	Asbestos Cement	693	56	1.72 out of 5	\$345	\$239,085	
Transmission Mains	P-2006	WAR	Centerville Rd.	12	Asbestos Cement	744	56	1.72 out of 5	\$345	\$256,680	
Transmission Mains	P-2018	WAR	Centerville Rd.	12	Asbestos Cement	386	56	1.72 out of 5	\$345	\$133,170	
Transmission Mains	P-2020	WAR	Centerville Rd.	12	Asbestos Cement	948	56	1.72 out of 5	\$345	\$327,060	
Transmission Mains	P-2021	WAR	Centerville Rd.	12	Asbestos Cement	260	56	1.72 out of 5	\$345	\$89,700	
Distribution Mains	P-2035	WAR	Centerville Rd.	8	Cast iron	107	82	1.72 out of 5	\$345	\$36,915	
Transmission Mains	P-2420	WAR	Centerville Rd.	12	Cast iron	442	86	1.72 out of 5	\$345	\$152,490	
Transmission Mains	P-2685	WAR	Centerville Rd.	12	Cast iron	429	86	1.72 out of 5	\$345	\$148,005	
Transmission Mains	P-2687	WAR	Centerville Rd.	12	Cast iron	99	86	1.72 out of 5	\$345	\$34,155	
Distribution Mains	P-2721	WAR	Centerville Rd.	8	Cast iron	515	82	1.72 out of 5	\$345	\$177,675	
Distribution Mains	P-2722	WAR	Centerville Rd.	8	Cast iron	209	82	1.72 out of 5	\$345	\$72,105	
Distribution Mains	P-2749	WAR	Centerville Rd.	8	Cast iron	158	82	1.72 out of 5	\$345	\$54,510	
Distribution Mains	P-2768	WAR	Centerville Rd.	8	Cast iron	242	82	1.72 out of 5	\$345	\$83,490	
Distribution Mains	P-2775	WAR	Centerville Rd.	8	Asbestos Cement	493	55	1.72 out of 5	\$345	\$170,085	
Transmission Mains	P-2784	WAR	Centerville Rd.	12	Asbestos Cement	546	56	1.72 out of 5	\$345	\$188,370	
Transmission Mains	P-2419	WAR	Centerville Rd. PRV	12	Cast iron	131	86	1.72 out of 5	\$345	\$45,195	
Transmission Mains	P-2686	WAR	Centerville Rd. PRV	12	Cast iron	201	86	1.72 out of 5	\$345	\$69,345	
Distribution Mains	P-2397	WAR	Chace St.	8	Ductile Iron	204	27	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2396	WAR	Chace St.	8	Ductile Iron	258	18	0 out of 5	N/A	\$0	
Distribution Mains	P-2517	WAR	Chapel St.	6	Asbestos Cement	444	64	2.58 out of 5	\$345	\$153,180	
Distribution Mains	P-2440	WAR	Chepiwonxet Way	8	Ductile Iron	579	30	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2393	WAR	Chevy Ct.	1.5	Copper	161	59	2.29 out of 5	\$345	\$55,545	
Distribution Mains	P-2304	WAR	Cindy Ln.	6	Asbestos Cement	310	49	2.43 out of 5	\$345	\$106,950	IFR 2014A
Distribution Mains	P-2303	WAR	Cindy Ln.	8	Asbestos Cement	925	49	1.72 out of 5	\$345	\$319,125	IFR 2014A
Distribution Mains	P-2479	WAR	Clyde Ave.	6	Asbestos Cement	247	47	2.43 out of 5	\$345	\$85,215	
Distribution Mains	P-2145	WAR	Cobble Hill Rd.	8	Asbestos Cement	446	54	1.72 out of 5	\$345	\$153,870	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-2147	WAR	Cobble Hill Rd.	8	Asbestos Cement	47	54	1.72 out of 5	\$345	\$16,215	
Distribution Mains	P-2150	WAR	Cobble Hill Rd.	8	Asbestos Cement	595	54	1.72 out of 5	\$345	\$205,275	
Distribution Mains	P-2151	WAR	Cobble Hill Rd.	8	Asbestos Cement	212	54	1.72 out of 5	\$345	\$73,140	
Distribution Mains	P-2543	WAR	College Hill Rd.	8	PVC	209	29	0.44 out of 5	\$345	\$72,105	
Distribution Mains	P-2859	WAR	College Hill Rd.	8	PVC	120	29	0.44 out of 5	\$345	\$41,400	
Distribution Mains	P-2861	WAR	College Park Ct.	4	Ductile Iron	300	25	1.58 out of 5	\$345	\$103,500	
Distribution Mains	P-2860	WAR	College Park Ct.	6	Ductile Iron	17	25	0.86 out of 5	\$345	\$5,865	
Distribution Mains	P-2915	WAR	College St.	4	Cast iron	419	104	3.3 out of 5	\$345	\$144,555	
Distribution Mains	P-2615	WAR	Colonial Ave.	8	Ductile Iron	195	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2914	WAR	Colonial Ave.	8	Ductile Iron	445	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2542	WAR	Commonwealth Ave.	10	Cast iron	2,089	86	2.43 out of 5	\$345	\$720,705	IFR 2015A
Distribution Mains	P-2296	WAR	Commonwealth Ave.	10	Cast iron	919	86	1.72 out of 5	\$345	\$317,055	IFR 2015A
Distribution Mains	P-2299	WAR	Commonwealth Ave.	8	Asbestos Cement	1,106	55	1.72 out of 5	\$345	\$381,570	
Distribution Mains	P-2308	WAR	Commonwealth Ave.	8	Asbestos Cement	455	55	1.72 out of 5	\$345	\$156,975	
Distribution Mains	P-2538	WAR	Commonwealth Ave.	10	Cast iron	1,300	86	1.72 out of 5	\$345	\$448,500	IFR 2015A
Distribution Mains	P-2798	WAR	Commonwealth Ave.	8	Asbestos Cement	105	55	1.72 out of 5	\$345	\$36,225	
Distribution Mains	P-2313	WAR	Commonwealth Ave.	8	Ductile Iron	641	19	0 out of 5	N/A	\$0	
Distribution Mains	P-2314	WAR	Commonwealth Ave.	8	Ductile Iron	313	19	0 out of 5	N/A	\$0	
Distribution Mains	P-2152	WAR	Contour Rd.	8	PVC	298	26	0.44 out of 5	\$345	\$102,810	
Distribution Mains	P-2153	WAR	Contour Rd.	8	PVC	471	26	0.44 out of 5	\$345	\$162,495	
Distribution Mains	P-2747	WAR	Corey Ave.	6	Cast iron	400	127	2.58 out of 5	\$345	\$138,000	
Distribution Mains	P-2748	WAR	Corey Ave.	8	Ductile Iron	475	18	0 out of 5	N/A	\$0	
Distribution Mains	P-2331	WAR	Country Ln.	6	Asbestos Cement	932	66	2.58 out of 5	\$345	\$321,540	
Distribution Mains	P-2311	WAR	Country View Dr.	8	Asbestos Cement	970	46	1.72 out of 5	\$345	\$334,650	
Distribution Mains	P-2322	WAR	Country View Dr.	8	Asbestos Cement	1,232	46	1.72 out of 5	\$345	\$425,040	IFR 2014A
Distribution Mains	P-2333	WAR	Country View Dr.	8	Asbestos Cement	464	46	1.72 out of 5	\$345	\$160,080	
Distribution Mains	P-2339	WAR	Country View Dr.	8	Asbestos Cement	756	46	1.72 out of 5	\$345	\$260,820	
Transmission Mains	P-2134	WAR	Cowesett Rd.	12	Ductile Iron	228	16	0 out of 5	N/A	\$0	
Distribution Mains	P-2109	WAR	Cowesett Green Rd.	8	PVC	276	28	0.44 out of 5	\$345	\$95,220	
Distribution Mains	P-2111	WAR	Cowesett Green Rd.	8	PVC	426	28	0.44 out of 5	\$345	\$146,970	
Distribution Mains	P-2112	WAR	Cowesett Green Rd.	8	PVC	571	28	0.44 out of 5	\$345	\$196,995	
Distribution Mains	P-2114	WAR	Cowesett Green Rd.	8	PVC	270	28	0.44 out of 5	\$345	\$93,150	
Distribution Mains	P-2115	WAR	Cowesett Green Rd.	8	PVC	741	28	0.44 out of 5	\$345	\$255,645	
Transmission Mains	P-2095	WAR	Cowesett Rd.	12	Asbestos Cement	1,053	48	1.72 out of 5	\$345	\$363,285	
Transmission Mains	P-2105	WAR	Cowesett Rd.	12	Asbestos Cement	238	48	1.72 out of 5	\$345	\$82,110	
Transmission Mains	P-2138	WAR	Cowesett Rd.	12	Asbestos Cement	2,721	48	1.72 out of 5	\$345	\$938,745	
Transmission Mains	P-2166	WAR	Cowesett Rd.	12	Asbestos Cement	83	48	1.72 out of 5	\$345	\$28,635	
Transmission Mains	P-2177	WAR	Cowesett Rd.	12	Asbestos Cement	476	48	1.72 out of 5	\$345	\$164,220	
Transmission Mains	P-2180	WAR	Cowesett Rd.	12	Asbestos Cement	1,766	48	1.72 out of 5	\$345	\$609,270	
Transmission Mains	P-2182	WAR	Cowesett Rd.	12	Asbestos Cement	464	48	1.72 out of 5	\$345	\$160,080	
Transmission Mains	P-2737	WAR	Cowesett Rd.	12	Asbestos Cement	309	48	1.72 out of 5	\$345	\$106,605	
Transmission Mains	P-2738	WAR	Cowesett Rd.	12	Asbestos Cement	365	48	1.72 out of 5	\$345	\$125,925	
Transmission Mains	P-2079	WAR	Cowesett Rd.	12	Ductile Iron	271	26	0.15 out of 5	N/A	\$0	
Transmission Mains	P-2076	WAR	Cowesett Rd.	12	Ductile Iron	259	16	0 out of 5	N/A	\$0	
Transmission Mains	P-2077	WAR	Cowesett Rd.	12	Ductile Iron	134	16	0 out of 5	N/A	\$0	
Transmission Mains	P-2081	WAR	Cowesett Rd.	12	Ductile Iron	589	16	0 out of 5	N/A	\$0	
Transmission Mains	P-2082	WAR	Cowesett Rd.	12	Ductile Iron	751	16	0 out of 5	N/A	\$0	
Transmission Mains	P-2083	WAR	Cowesett Rd.	12	Ductile Iron	129	16	0 out of 5	N/A	\$0	
Transmission Mains	P-2092	WAR	Cowesett Rd.	12	Ductile Iron	447	16	0 out of 5	N/A	\$0	
Transmission Mains	P-2335	WAR	Cowesett Rd.	12	Ductile Iron	894	16	0 out of 5	N/A	\$0	
Transmission Mains	P-2336	WAR	Cowesett Rd.	12	Ductile Iron	160	16	0 out of 5	N/A	\$0	
Transmission Mains	P-2355	WAR	Cowesett Rd.	12	Ductile Iron	422	16	0 out of 5	N/A	\$0	
Transmission Mains	P-2356	WAR	Cowesett Rd.	12	Ductile Iron	342	16	0 out of 5	N/A	\$0	
Transmission Mains	P-2357	WAR	Cowesett Rd.	12	Ductile Iron	605	16	0 out of 5	N/A	\$0	
Transmission Mains	P-2452	WAR	Cowesett Rd.	12	Ductile Iron	118	16	0 out of 5	N/A	\$0	
Transmission Mains	P-2932	WAR	Cowesett Rd.	12	Ductile Iron	56	16	0 out of 5	N/A	\$0	
Distribution Mains	P-2135	WAR	Cowesett Rd. PRV	8	Ductile Iron	73	16	0 out of 5	N/A	\$0	
Distribution Mains	P-2136	WAR	Cowesett Rd. PRV	8	Ductile Iron	60	16	0 out of 5	N/A	\$0	
Distribution Mains	P-2137	WAR	Cowesett Rd. PRV	8	Ductile Iron	76	16	0 out of 5	N/A	\$0	
Distribution Mains	P-2621	WAR	Coyle St.	4	Cast iron	236	104	3.3 out of 5	\$345	\$81,420	
Distribution Mains	P-2623	WAR	Coyle St.	4	Cast iron	265	104	3.3 out of 5	\$345	\$91,425	
Distribution Mains	P-2797	WAR	Craig Dr.	6	Asbestos Cement	532	59	2.43 out of 5	\$345	\$183,540	IFR 2014A

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-2897	WAR	Craig Rd.	6	Asbestos Cement	409	59	3.14 out of 5	\$345	\$141,105	IFR 2014A
Distribution Mains	P-2899	WAR	Craig Rd.	6	Asbestos Cement	236	59	3.14 out of 5	\$345	\$81,420	IFR 2014A
Distribution Mains	P-2307	WAR	Craig Rd.	6	Asbestos Cement	247	59	2.43 out of 5	\$345	\$85,215	IFR 2014A
Distribution Mains	P-2390	WAR	Creston Way	6	Asbestos Cement	487	75	2.58 out of 5	\$345	\$168,015	
Distribution Mains	P-2381	WAR	Crestwood Rd.	6	Asbestos Cement	767	75	2.58 out of 5	\$345	\$264,615	
Distribution Mains	P-2383	WAR	Crestwood Rd.	6	Asbestos Cement	370	75	2.58 out of 5	\$345	\$127,650	
Distribution Mains	P-2944	WAR	Crestwood Rd.	6	Asbestos Cement	393	75	2.58 out of 5	\$345	\$135,585	
Distribution Mains	P-2384	WAR	Crestwood Rd.	8	Asbestos Cement	99	75	1.87 out of 5	\$345	\$34,155	
Distribution Mains	P-2385	WAR	Crestwood Rd.	8	Asbestos Cement	326	75	1.87 out of 5	\$345	\$112,470	
Distribution Mains	P-2386	WAR	Crestwood Rd.	8	Asbestos Cement	196	75	1.87 out of 5	\$345	\$67,620	
Distribution Mains	P-2387	WAR	Crestwood Rd.	8	Asbestos Cement	815	75	1.87 out of 5	\$345	\$281,175	
Distribution Mains	P-2942	WAR	Crestwood Rd.	8	Asbestos Cement	355	75	1.87 out of 5	\$345	\$122,475	
Distribution Mains	P-2643	WAR	Crocus St.	6	Asbestos Cement	630	58	2.43 out of 5	\$345	\$217,350	
Distribution Mains	P-2469	WAR	Cumberland Rd.	8	Ductile Iron	199	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2470	WAR	Cumberland Rd.	8	Ductile Iron	1,141	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2583	WAR	D'Agnillo Dr.	8	Asbestos Cement	1,771	37	1.58 out of 5	\$345	\$610,995	
Distribution Mains	P-2091	WAR	Darling St.	8	Ductile Iron	721	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2918	WAR	Darling St.	8	Ductile Iron	114	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2433	WAR	Dawn Ln.	6	Asbestos Cement	425	43	2.43 out of 5	\$345	\$146,625	
Distribution Mains	P-2388	WAR	Dexterdale Dr.	8	Asbestos Cement	191	75	1.87 out of 5	\$345	\$65,895	
Distribution Mains	P-2389	WAR	Dexterdale Dr.	8	Asbestos Cement	890	74	1.87 out of 5	\$345	\$307,050	
Distribution Mains	P-2025	WAR	Diamond Hill Rd.	8	Ductile Iron	566	14	0 out of 5	N/A	\$0	
Distribution Mains	P-2027	WAR	Diamond Hill Rd.	8	Ductile Iron	406	14	0 out of 5	N/A	\$0	
Distribution Mains	P-2043	WAR	Diamond Hill Rd.	8	Ductile Iron	323	14	0 out of 5	N/A	\$0	
Distribution Mains	P-2044	WAR	Diamond Hill Rd.	8	Ductile Iron	346	14	0 out of 5	N/A	\$0	
Distribution Mains	P-2053	WAR	Diamond Hill Rd.	8	Ductile Iron	567	14	0 out of 5	N/A	\$0	
Distribution Mains	P-2054	WAR	Diamond Hill Rd.	8	Ductile Iron	120	14	0 out of 5	N/A	\$0	
Distribution Mains	P-2084	WAR	Diamond Hill Rd.	8	Ductile Iron	292	14	0 out of 5	N/A	\$0	
Distribution Mains	P-2086	WAR	Diamond Hill Rd.	8	Ductile Iron	157	14	0 out of 5	N/A	\$0	
Distribution Mains	P-2087	WAR	Diamond Hill Rd.	8	Ductile Iron	1,153	14	0 out of 5	N/A	\$0	
Distribution Mains	P-2724	WAR	Diamond Hill Rd.	8	Ductile Iron	136	14	0 out of 5	N/A	\$0	
Distribution Mains	P-2725	WAR	Diamond Hill Rd.	8	Ductile Iron	492	14	0 out of 5	N/A	\$0	
Distribution Mains	P-2919	WAR	Diamond Hill Rd.	8	Ductile Iron	560	14	0 out of 5	N/A	\$0	
Distribution Mains	P-2568	WAR	Dongay Ave.	8	Ductile Iron	245	2	0 out of 5	N/A	\$0	
Distribution Mains	P-2008	WAR	Douglas Rd.	6	Asbestos Cement	862	54	2.43 out of 5	\$345	\$297,390	
Distribution Mains	P-2014	WAR	Douglas Rd.	6	Asbestos Cement	1,462	54	2.43 out of 5	\$345	\$504,390	
Distribution Mains	P-2015	WAR	Douglas Rd.	6	Asbestos Cement	220	54	2.43 out of 5	\$345	\$75,900	
Distribution Mains	P-2016	WAR	Douglas Rd.	6	Asbestos Cement	454	54	2.43 out of 5	\$345	\$156,630	
Distribution Mains	P-2332	WAR	Downing Ln.	8	Asbestos Cement	483	42	1.72 out of 5	\$345	\$166,635	
Distribution Mains	P-2036	WAR	Drum Rock Rd.	8	Cast iron	786	82	1.72 out of 5	\$345	\$271,170	
Distribution Mains	P-2406	WAR	Duane St.	8	Ductile Iron	590	3	0 out of 5	N/A	\$0	
Distribution Mains	P-2408	WAR	Duane St.	8	Ductile Iron	448	3	0 out of 5	N/A	\$0	
Distribution Mains	P-2038	WAR	Duchess St.	8	Ductile Iron	809	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2039	WAR	Duchess St.	8	Ductile Iron	147	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2007	WAR	Dunmore Rd.	8	Asbestos Cement	258	54	1.72 out of 5	\$345	\$89,010	
Transmission Mains	P-2189	WAR	Eagle Run	12	PVC	43	31	0.44 out of 5	\$345	\$14,835	
Distribution Mains	P-2544	WAR	East Ave.	10	Cast iron	228	86	1.72 out of 5	\$345	\$78,660	IFR 2015A
Distribution Mains	P-2549	WAR	East Ave.	10	Cast iron	195	86	1.72 out of 5	\$345	\$67,275	IFR 2015A
Distribution Mains	P-2556	WAR	East Ave.	10	Cast iron	347	86	1.72 out of 5	\$345	\$119,715	IFR 2015A
Distribution Mains	P-2561	WAR	East Ave.	10	Cast iron	94	86	1.72 out of 5	\$345	\$32,430	IFR 2015A
Distribution Mains	P-2562	WAR	East Ave.	10	Cast iron	720	86	1.72 out of 5	\$345	\$248,400	IFR 2015A
Distribution Mains	P-2849	WAR	East Ave.	10	Ductile Iron	31	1	0 out of 5	N/A	\$0	
Transmission Mains	P-2850	WAR	East Ave.	16	Ductile Iron	300	1	0 out of 5	N/A	\$0	
Distribution Mains	P-2851	WAR	East Ave.	10	Ductile Iron	20	1	0 out of 5	N/A	\$0	
Transmission Mains	P-2891	WAR	East Greenwich Ave.	12	Ductile Iron	43	14	0 out of 5	N/A	\$0	
Distribution Mains	P-2133	WAR	Edmond Cir.	6	Asbestos Cement	157	60	2.58 out of 5	\$345	\$54,165	
Distribution Mains	P-2128	WAR	Edmond Dr.	8	Asbestos Cement	648	60	1.87 out of 5	\$345	\$223,560	
Distribution Mains	P-2129	WAR	Edmond Dr.	8	Asbestos Cement	182	60	1.87 out of 5	\$345	\$62,790	
Distribution Mains	P-2130	WAR	Edmond Dr.	8	Asbestos Cement	548	60	1.87 out of 5	\$345	\$189,060	
Distribution Mains	P-2132	WAR	Edmond Dr.	8	Asbestos Cement	394	60	1.87 out of 5	\$345	\$135,930	
Distribution Mains	P-2443	WAR	Elisha St.	4	Cast iron	391	124	3.3 out of 5	\$345	\$134,895	IFR 2014A
Distribution Mains	P-2648	WAR	Elmer Ave.	8	Ductile Iron	370	19	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-2279	WAR	Emily Ln.	8	Ductile Iron	318	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2575	WAR	Fairmount Dr.	6	Asbestos Cement	768	64	3.29 out of 5	\$345	\$264,960	
Transmission Mains	P-2649	WAR	Fairmount Dr.	20	Asbestos Cement	728	50	1.72 out of 5	\$345	\$251,160	
Distribution Mains	P-2282	WAR	Fish's Ln.	8	Asbestos Cement	602	47	1.72 out of 5	\$345	\$207,690	
Distribution Mains	P-2287	WAR	Flagg Ave.	8	Ductile Iron	698	9	0 out of 5	N/A	\$0	
Distribution Mains	P-2815	WAR	Flagg Ave.	8	Ductile Iron	250	9	0 out of 5	N/A	\$0	
Distribution Mains	P-2326	WAR	Forbes St.	6	Asbestos Cement	254	41	2.43 out of 5	\$345	\$87,630	
Distribution Mains	P-2292	WAR	Founder Ave.	8	Ductile Iron	677	9	0 out of 5	N/A	\$0	
Distribution Mains	P-2814	WAR	Founder Ave.	8	Ductile Iron	312	9	0 out of 5	N/A	\$0	
Distribution Mains	P-2363	WAR	Fred Humlak Way	6	PVC	677	32	1.15 out of 5	\$345	\$233,565	
Distribution Mains	P-2465	WAR	Friar Tuck Rd.	8	Ductile Iron	312	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2450	WAR	Garnet St.	8	Ductile Iron	365	22	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2281	WAR	Gauvin Dr.	8	Asbestos Cement	714	47	1.72 out of 5	\$345	\$246,330	
Distribution Mains	P-2285	WAR	Gauvin Dr.	8	Asbestos Cement	349	47	1.72 out of 5	\$345	\$120,405	
Distribution Mains	P-2300	WAR	Gauvin Dr.	8	Asbestos Cement	380	47	1.72 out of 5	\$345	\$131,100	
Distribution Mains	P-2306	WAR	Gauvin Dr.	8	Asbestos Cement	321	47	1.72 out of 5	\$345	\$110,745	
Distribution Mains	P-2276	WAR	Gilbane St.	8	Asbestos Cement	590	47	1.72 out of 5	\$345	\$203,550	
Distribution Mains	P-2428	WAR	Gilbane St.	8	Asbestos Cement	1,101	47	1.72 out of 5	\$345	\$379,845	
Distribution Mains	P-2245	WAR	Gilber Stuart Dr.	8	Asbestos Cement	1,152	48	1.72 out of 5	\$345	\$397,440	
Distribution Mains	P-2286	WAR	Gilbert St.	8	Ductile Iron	238	9	0 out of 5	N/A	\$0	
Distribution Mains	P-2288	WAR	Gilbert St.	8	Ductile Iron	945	9	0 out of 5	N/A	\$0	
Distribution Mains	P-2290	WAR	Gilbert St.	8	Ductile Iron	248	9	0 out of 5	N/A	\$0	
Distribution Mains	P-2291	WAR	Gilbert St.	8	Ductile Iron	238	9	0 out of 5	N/A	\$0	
Distribution Mains	P-2293	WAR	Gilbert St.	8	Ductile Iron	379	9	0 out of 5	N/A	\$0	
Distribution Mains	P-2294	WAR	Gilbert St.	8	Ductile Iron	239	9	0 out of 5	N/A	\$0	
Distribution Mains	P-2252	WAR	Gilbert Stuart Dr	8	Asbestos Cement	1,158	41	1.72 out of 5	\$345	\$399,510	
Distribution Mains	P-2233	WAR	Gilbert Stuart Dr.	8	Asbestos Cement	944	48	1.72 out of 5	\$345	\$325,680	
Distribution Mains	P-2247	WAR	Gilbert Stuart Dr.	8	Asbestos Cement	648	48	1.72 out of 5	\$345	\$223,560	
Distribution Mains	P-2248	WAR	Gilbert Stuart Dr.	8	Asbestos Cement	580	48	1.72 out of 5	\$345	\$200,100	
Distribution Mains	P-2253	WAR	Gilbert Stuart Dr.	8	Asbestos Cement	496	48	1.72 out of 5	\$345	\$171,120	
Distribution Mains	P-2254	WAR	Gilbert Stuart Dr.	8	Asbestos Cement	1,077	48	1.72 out of 5	\$345	\$371,565	
Distribution Mains	P-2085	WAR	Ginger St.	8	Ductile Iron	396	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2476	WAR	Glass St.	6	Ductile Iron	218	20	0.86 out of 5	\$345	\$75,210	
Distribution Mains	P-2900	WAR	Globe St.	6	Asbestos Cement	181	59	2.43 out of 5	\$345	\$62,445	IFR 2014A
Distribution Mains	P-2416	WAR	Goodwin St.	6	Cast iron	625	84	2.43 out of 5	\$345	\$215,625	
Distribution Mains	P-2528	WAR	Gorton Holden Ter.	8	Asbestos Cement	491	36	1.58 out of 5	\$345	\$169,395	
Distribution Mains	P-2883	WAR	Gorton Holden Ter.	8	Ductile Iron	24	6	0 out of 5	N/A	\$0	
Distribution Mains	P-2263	WAR	Governors Dr.	8	Ductile Iron	678	14	0 out of 5	N/A	\$0	
Distribution Mains	P-2267	WAR	Governors Dr.	8	Ductile Iron	400	14	0 out of 5	N/A	\$0	
Distribution Mains	P-2654	WAR	Governors Dr.	8	Ductile Iron	887	14	0 out of 5	N/A	\$0	
Distribution Mains	P-2488	WAR	Great Oak Dr.	8	Ductile Iron	284	16	0 out of 5	N/A	\$0	
Distribution Mains	P-2910	WAR	Great Oak Dr.	8	Ductile Iron	34	6	0 out of 5	N/A	\$0	
Distribution Mains	P-2889	WAR	Green Bush Rd.	8	PVC	47	26	0.44 out of 5	\$345	\$16,215	
Distribution Mains	P-2890	WAR	Green Bush Rd.	8	Ductile Iron	202	9	0 out of 5	N/A	\$0	
Distribution Mains	P-2664	WAR	Green Hill Way	8	Ductile Iron	355	29	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2116	WAR	Green Meadow Dr	8	PVC	163	27	0.44 out of 5	\$345	\$56,235	
Transmission Mains	P-2633	WAR	Greenwich Ave.	12	Cast iron	701	81	1.72 out of 5	\$345	\$241,845	
Transmission Mains	P-2901	WAR	Greenwich Ave.	12	Cast iron	51	81	1.72 out of 5	\$345	\$17,595	
Distribution Mains	P-2868	WAR	Greenwich Ave.	6	Ductile Iron	23	6	0.71 out of 5	\$345	\$7,935	
Transmission Mains	P-2487	WAR	Greenwich Ave.	12	Ductile Iron	323	6	0 out of 5	N/A	\$0	
Transmission Mains	P-2489	WAR	Greenwich Ave.	12	Ductile Iron	630	6	0 out of 5	N/A	\$0	
Transmission Mains	P-2521	WAR	Greenwich Ave.	12	Ductile Iron	264	7	0 out of 5	N/A	\$0	
Transmission Mains	P-2526	WAR	Greenwich Ave.	12	Ductile Iron	290	7	0 out of 5	N/A	\$0	
Transmission Mains	P-2527	WAR	Greenwich Ave.	12	Ductile Iron	221	7	0 out of 5	N/A	\$0	
Transmission Mains	P-2529	WAR	Greenwich Ave.	12	Ductile Iron	131	7	0 out of 5	N/A	\$0	
Transmission Mains	P-2531	WAR	Greenwich Ave.	12	Ductile Iron	295	7	0 out of 5	N/A	\$0	
Transmission Mains	P-2537	WAR	Greenwich Ave.	12	Ductile Iron	512	7	0 out of 5	N/A	\$0	
Transmission Mains	P-2634	WAR	Greenwich Ave.	12	Ductile Iron	1,425	6	0 out of 5	N/A	\$0	
Transmission Mains	P-2758	WAR	Greenwich Ave.	12	Ductile Iron	281	7	0 out of 5	N/A	\$0	
Transmission Mains	P-2872	WAR	Greenwich Ave.	12	Ductile Iron	191	7	0 out of 5	N/A	\$0	
Distribution Mains	P-2873	WAR	Greenwich Ave.	8	Ductile Iron	24	6	0 out of 5	N/A	\$0	
Transmission Mains	P-2876	WAR	Greenwich Ave.	12	Ductile Iron	228	7	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-2902	WAR	Greenwich Ave.	12	Ductile Iron	27	6	0 out of 5	N/A	\$0	
Transmission Mains	P-2903	WAR	Greenwich Ave.	12	Ductile Iron	340	6	0 out of 5	N/A	\$0	
Transmission Mains	P-2908	WAR	Greenwich Ave.	12	Ductile Iron	133	6	0 out of 5	N/A	\$0	
Transmission Mains	P-2411	WAR	Hall St.	12	Ductile Iron	392	3	0 out of 5	N/A	\$0	
Distribution Mains	P-2110	WAR	Hallmark Dr	8	PVC	705	27	0.44 out of 5	\$345	\$243,225	
Distribution Mains	P-2022	WAR	Hardig Rd.	8	Asbestos Cement	203	42	2.43 out of 5	\$345	\$70,035	
Transmission Mains	P-2104	WAR	Hardig Rd.	12	Ductile Iron	380	17	0 out of 5	N/A	\$0	
Distribution Mains	P-2597	WAR	Harrop Ave.	6	Cast iron	688	81	2.43 out of 5	\$345	\$237,360	
Distribution Mains	P-2598	WAR	Harrop Ave.	6	Cast iron	106	81	2.43 out of 5	\$345	\$36,570	
Distribution Mains	P-2424	WAR	Harrop Ave.	8	Asbestos Cement	654	68	1.87 out of 5	\$345	\$225,630	
Distribution Mains	P-2191	WAR	Hedge Row Dr.	8	Asbestos Cement	222	49	1.72 out of 5	\$345	\$76,590	
Distribution Mains	P-2197	WAR	Hedge Row Dr.	8	Asbestos Cement	211	49	1.72 out of 5	\$345	\$72,795	
Distribution Mains	P-2272	WAR	Hedgerow Dr.	6	Asbestos Cement	170	49	2.43 out of 5	\$345	\$58,650	
Distribution Mains	P-2212	WAR	Hedgerow Dr.	1.5	Copper	151	49	2.29 out of 5	\$345	\$52,095	
Distribution Mains	P-2210	WAR	Hedgerow Dr.	8	Asbestos Cement	129	49	1.72 out of 5	\$345	\$44,505	
Distribution Mains	P-2211	WAR	Hedgerow Dr.	8	Asbestos Cement	211	49	1.72 out of 5	\$345	\$72,795	
Distribution Mains	P-2270	WAR	Hedgerow Dr.	8	Asbestos Cement	536	49	1.72 out of 5	\$345	\$184,920	
Distribution Mains	P-2271	WAR	Hedgerow Dr.	8	Asbestos Cement	400	49	1.72 out of 5	\$345	\$138,000	
Distribution Mains	P-2447	WAR	Herbert St.	2	Galvanized iron	260	119	3.59 out of 5	\$345	\$89,700	
Distribution Mains	P-2445	WAR	Herbert St.	4	Cast iron	577	125	3.3 out of 5	\$345	\$199,065	IFR 2014A
Distribution Mains	P-2446	WAR	Herbert St.	8	Ductile Iron	186	22	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2232	WAR	Heritage Dr.	8	Asbestos Cement	621	50	1.72 out of 5	\$345	\$214,245	
Distribution Mains	P-2235	WAR	Heritage Dr.	8	Asbestos Cement	318	48	1.72 out of 5	\$345	\$109,710	
Distribution Mains	P-2240	WAR	Heritage Dr.	8	Asbestos Cement	1,081	48	1.72 out of 5	\$345	\$372,945	
Distribution Mains	P-2241	WAR	Heritage Dr.	8	Asbestos Cement	376	48	1.72 out of 5	\$345	\$129,720	
Distribution Mains	P-2243	WAR	Heritage Dr.	8	Asbestos Cement	452	48	1.72 out of 5	\$345	\$155,940	
Distribution Mains	P-2400	WAR	Hesper Dr.	8	Ductile Iron	555	27	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2453	WAR	Hibiscus Ln.	8	Ductile Iron	371	18	0 out of 5	N/A	\$0	
Distribution Mains	P-2455	WAR	Hibiscus Ln.	8	Ductile Iron	506	18	0 out of 5	N/A	\$0	
Distribution Mains	P-2346	WAR	Highland Ave.	8	Asbestos Cement	1,029	61	2.58 out of 5	\$345	\$355,005	
Distribution Mains	P-2342	WAR	Highland Ave.	8	Cast iron	696	78	1.58 out of 5	\$345	\$240,120	
Distribution Mains	P-2345	WAR	Highland Ave.	8	Cast iron	1,152	78	1.58 out of 5	\$345	\$397,440	
Distribution Mains	P-2414	WAR	Highpoint Dr.	6	Asbestos Cement	659	60	3.29 out of 5	\$345	\$227,355	
Distribution Mains	P-2324	WAR	Hilary St.	6	Asbestos Cement	202	41	2.43 out of 5	\$345	\$69,690	
Distribution Mains	P-2898	WAR	Hilbert St.	6	Asbestos Cement	155	59	2.43 out of 5	\$345	\$53,475	IFR 2014A
Distribution Mains	P-2576	WAR	Hill Top Dr.	6	Asbestos Cement	713	66	3.29 out of 5	\$345	\$245,985	
Distribution Mains	P-2574	WAR	Hill Top Dr.	6	Asbestos Cement	316	66	2.58 out of 5	\$345	\$109,020	
Distribution Mains	P-2578	WAR	Hill Top Dr.	6	Asbestos Cement	821	66	2.58 out of 5	\$345	\$283,245	
Transmission Mains	P-2650	WAR	Hill Top Dr.	20	Asbestos Cement	271	50	1.72 out of 5	\$345	\$93,495	
Distribution Mains	P-2031	WAR	Hollow Ct.	6	Asbestos Cement	283	37	2.29 out of 5	\$345	\$97,635	
Distribution Mains	P-2262	WAR	Indian Hill Rd.	6	Ductile Iron	562	14	0.71 out of 5	\$345	\$193,890	
Distribution Mains	P-2040	WAR	Irene St.	8	Ductile Iron	417	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2041	WAR	Irene St.	8	Ductile Iron	107	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2505	WAR	Irondale St.	6	Asbestos Cement	518	60	2.58 out of 5	\$345	\$178,710	
Distribution Mains	P-2535	WAR	Ironwood Ct.	1.3	Copper	241	57	2.29 out of 5	\$345	\$83,145	
Distribution Mains	P-2348	WAR	Island View Dr.	8	Asbestos Cement	218	39	1.58 out of 5	\$345	\$75,210	
Distribution Mains	P-2349	WAR	Island View Dr.	8	Asbestos Cement	345	39	1.58 out of 5	\$345	\$119,025	
Distribution Mains	P-2570	WAR	Jambray Ave.	8	Ductile Iron	311	2	0 out of 5	N/A	\$0	
Distribution Mains	P-2573	WAR	Jambray Ave.	8	Ductile Iron	1,115	2	0 out of 5	N/A	\$0	
Distribution Mains	P-2093	WAR	Jerry St.	6	Ductile Iron	276	20	0.86 out of 5	\$345	\$95,220	
Distribution Mains	P-2259	WAR	Joesph Ct.	8	PVC	2,196	28	0.44 out of 5	\$345	\$757,620	
Distribution Mains	P-2438	WAR	John Wickes Ave.	6	Ductile Iron	401	26	0.86 out of 5	\$345	\$138,345	
Distribution Mains	P-2394	WAR	Joyce Glen	1.3	Copper	170	58	2.29 out of 5	\$345	\$58,650	
Distribution Mains	P-2045	WAR	Judge St.	6	Asbestos Cement	245	53	2.43 out of 5	\$345	\$84,525	
Distribution Mains	P-2144	WAR	Katelyn Ct.	8	Ductile Iron	381	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2539	WAR	Kearsage Dr.	8	Asbestos Cement	306	51	1.72 out of 5	\$345	\$105,570	
Distribution Mains	P-2540	WAR	Kearsage Dr.	8	Asbestos Cement	140	51	1.72 out of 5	\$345	\$48,300	
Distribution Mains	P-2404	WAR	Ladd St.	8	Ductile Iron	215	3	0 out of 5	N/A	\$0	
Distribution Mains	P-2405	WAR	Ladd St.	8	Ductile Iron	34	3	0 out of 5	N/A	\$0	
Distribution Mains	P-2409	WAR	Ladd St.	8	Ductile Iron	252	3	0 out of 5	N/A	\$0	
Distribution Mains	P-2957	WAR	Ladd St.	8	Ductile Iron	239	3	0 out of 5	N/A	\$0	
Distribution Mains	P-2174	WAR	Ladderlook Dr.	8	Asbestos Cement	995	54	1.72 out of 5	\$345	\$343,275	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-2506	WAR	Lancaster Ave.	6	Asbestos Cement	257	64	2.58 out of 5	\$345	\$88,665	
Distribution Mains	P-2508	WAR	Lancaster Ave.	6	Asbestos Cement	595	64	2.58 out of 5	\$345	\$205,275	
Distribution Mains	P-2518	WAR	Lancaster Ave.	6	Asbestos Cement	247	64	2.58 out of 5	\$345	\$85,215	
Distribution Mains	P-2522	WAR	Lancaster Ave.	6	Asbestos Cement	222	64	2.58 out of 5	\$345	\$76,590	
Distribution Mains	P-2524	WAR	Lancaster Ave.	6	Asbestos Cement	251	64	2.58 out of 5	\$345	\$86,595	
Distribution Mains	P-2882	WAR	Lancaster Ave.	6	Ductile Iron	31	6	0.71 out of 5	\$345	\$10,695	
Distribution Mains	P-2881	WAR	Lancaster Ave.	8	Ductile Iron	21	6	0 out of 5	N/A	\$0	
Distribution Mains	P-2163	WAR	Landmark Rd.	8	Asbestos Cement	1,091	58	1.72 out of 5	\$345	\$376,395	
Distribution Mains	P-2382	WAR	Lantern Ln.	6	Asbestos Cement	192	68	2.58 out of 5	\$345	\$66,240	
Distribution Mains	P-2712	WAR	Lantern Ln.	6	Asbestos Cement	364	68	2.58 out of 5	\$345	\$125,580	
Distribution Mains	P-2028	WAR	Larchmont Rd.	6	Asbestos Cement	915	52	3.86 out of 5	\$345	\$315,675	
Distribution Mains	P-2029	WAR	Larchmont Rd.	6	Asbestos Cement	351	52	2.43 out of 5	\$345	\$121,095	
Distribution Mains	P-2046	WAR	Larchmont Rd.	6	Asbestos Cement	610	52	2.43 out of 5	\$345	\$210,450	
Distribution Mains	P-2049	WAR	Larchmont Rd.	6	Asbestos Cement	234	52	2.43 out of 5	\$345	\$80,730	
Transmission Mains	P-2119	WAR	Larchwood Dr.	12	PVC	367	27	0.44 out of 5	\$345	\$126,615	
Transmission Mains	P-2120	WAR	Larchwood Dr.	12	PVC	1,191	27	0.44 out of 5	\$345	\$410,895	
Transmission Mains	P-2122	WAR	Larchwood Dr.	12	PVC	906	27	0.44 out of 5	\$345	\$312,570	
Transmission Mains	P-2124	WAR	Larchwood Dr.	12	PVC	192	27	0.44 out of 5	\$345	\$66,240	
Transmission Mains	P-2126	WAR	Larchwood Dr.	12	PVC	1,785	27	0.44 out of 5	\$345	\$615,825	
Distribution Mains	P-2312	WAR	Ledgemont Dr.	8	Asbestos Cement	645	42	1.72 out of 5	\$345	\$222,525	
Distribution Mains	P-2315	WAR	Leon Whipple Rd.	8	Ductile Iron	384	19	0 out of 5	N/A	\$0	
Distribution Mains	P-2316	WAR	Leon Whipple Rd.	8	Ductile Iron	673	19	0 out of 5	N/A	\$0	
Distribution Mains	P-2569	WAR	Levesque St.	8	Ductile Iron	315	2	0 out of 5	N/A	\$0	
Distribution Mains	P-2571	WAR	Levesque St.	8	Ductile Iron	956	2	0 out of 5	N/A	\$0	
Distribution Mains	P-2206	WAR	Lisa Marie Cir.	8	PVC	509	26	0.44 out of 5	\$345	\$175,605	
Distribution Mains	P-2941	WAR	Little Ln.	1	Copper	205	65	2.44 out of 5	\$345	\$70,725	
Transmission Mains	P-2268	WAR	Love Ln.	20	Asbestos Cement	171	50	1.72 out of 5	\$345	\$58,995	
Transmission Mains	P-2651	WAR	Love Ln.	20	Asbestos Cement	173	50	1.72 out of 5	\$345	\$59,685	
Transmission Mains	P-2657	WAR	Love Ln.	12	Asbestos Cement	2,396	57	1.72 out of 5	\$345	\$826,620	
Transmission Mains	P-2659	WAR	Love Ln.	12	Asbestos Cement	185	57	1.72 out of 5	\$345	\$63,825	
Transmission Mains	P-2827	WAR	Love Ln.	20	Asbestos Cement	119	50	1.72 out of 5	\$345	\$41,055	
Transmission Mains	P-2828	WAR	Love Ln.	20	Asbestos Cement	346	50	1.72 out of 5	\$345	\$119,370	
Transmission Mains	P-2829	WAR	Love Ln.	20	Asbestos Cement	701	50	1.72 out of 5	\$345	\$241,845	
Transmission Mains	P-2830	WAR	Love Ln.	20	Asbestos Cement	235	50	1.72 out of 5	\$345	\$81,075	
Transmission Mains	P-2831	WAR	Love Ln.	12	Asbestos Cement	50	57	1.72 out of 5	\$345	\$17,250	
Transmission Mains	P-2139	WAR	Love Ln.	12	Ductile Iron	1,285	16	0 out of 5	N/A	\$0	
Transmission Mains	P-2164	WAR	Love Ln.	12	Ductile Iron	2,717	16	0 out of 5	N/A	\$0	
Transmission Mains	P-2165	WAR	Love Ln.	12	Ductile Iron	1,016	16	0 out of 5	N/A	\$0	
Transmission Mains	P-2273	WAR	Love Ln.	12	Ductile Iron	790	16	0 out of 5	N/A	\$0	
Transmission Mains	P-2330	WAR	Love Ln.	16	Ductile Iron	531	13	0 out of 5	N/A	\$0	
Transmission Mains	P-2338	WAR	Love Ln.	16	Ductile Iron	366	13	0 out of 5	N/A	\$0	
Transmission Mains	P-2343	WAR	Love Ln.	16	Ductile Iron	368	13	0 out of 5	N/A	\$0	
Transmission Mains	P-2377	WAR	Love Ln.	16	Ductile Iron	987	13	0 out of 5	N/A	\$0	
Transmission Mains	P-2596	WAR	Love Ln.	16	Ductile Iron	2,927	13	0 out of 5	N/A	\$0	
Transmission Mains	P-2832	WAR	Love Ln.	16	Ductile Iron	342	13	0 out of 5	N/A	\$0	
Transmission Mains	P-2652	WAR	Love Ln. PRV	20	Asbestos Cement	282	50	1.72 out of 5	\$345	\$97,290	
Transmission Mains	P-2658	WAR	Love Ln. PRV	12	Asbestos Cement	252	57	1.72 out of 5	\$345	\$86,940	
Distribution Mains	P-2905	WAR	Luther Ave.	1	Galvanized iron	235	6	2.86 out of 5	\$345	\$81,075	
Distribution Mains	P-2904	WAR	Luther Ave.	6	Ductile Iron	40	6	0.71 out of 5	\$345	\$13,800	
Distribution Mains	P-2127	WAR	Macara Cir.	8	PVC	341	26	0.44 out of 5	\$345	\$117,645	
Distribution Mains	P-2258	WAR	Major Potter Rd.	8	Asbestos Cement	630	39	1.58 out of 5	\$345	\$217,350	
Distribution Mains	P-2260	WAR	Major Potter Rd.	8	Asbestos Cement	295	39	1.58 out of 5	\$345	\$101,775	
Distribution Mains	P-2261	WAR	Major Potter Rd.	8	Asbestos Cement	502	39	1.58 out of 5	\$345	\$173,190	
Transmission Mains	P-2743	WAR	Major Potter Rd.	12	Cast iron	406	45	1.43 out of 5	\$345	\$140,070	
Transmission Mains	P-2118	WAR	Major Potter Rd.	12	PVC	260	26	0.44 out of 5	\$345	\$89,700	
Distribution Mains	P-2184	WAR	Major Potter Rd.	8	PVC	541	28	0.44 out of 5	\$345	\$186,645	
Distribution Mains	P-2185	WAR	Major Potter Rd.	8	PVC	550	28	0.44 out of 5	\$345	\$189,750	
Transmission Mains	P-2225	WAR	Major Potter Rd.	12	PVC	418	26	0.44 out of 5	\$345	\$144,210	
Distribution Mains	P-2256	WAR	Major Potter Rd.	8	PVC	181	28	0.44 out of 5	\$345	\$62,445	
Distribution Mains	P-2257	WAR	Major Potter Rd.	8	PVC	432	28	0.44 out of 5	\$345	\$149,040	
Distribution Mains	P-2645	WAR	Major Potter Rd.	8	PVC	2,693	26	0.44 out of 5	\$345	\$929,085	
Transmission Mains	P-2646	WAR	Major Potter Rd.	12	PVC	1,287	31	0.44 out of 5	\$345	\$444,015	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-2780	WAR	Major Potter Rd.	8	PVC	861	26	0.44 out of 5	\$345	\$297,045	
Transmission Mains	P-2103	WAR	Major Potter Rd.	12	Ductile Iron	335	17	0 out of 5	N/A	\$0	
Transmission Mains	P-2224	WAR	Major Potter Rd.	12	Ductile Iron	528	17	0 out of 5	N/A	\$0	
Distribution Mains	P-2744	WAR	Major Potter Rd.	8	Ductile Iron	806	14	0 out of 5	N/A	\$0	
Distribution Mains	P-2745	WAR	Major Potter Rd.	8	Ductile Iron	358	14	0 out of 5	N/A	\$0	
Distribution Mains	P-2950	WAR	Manton St.	2	Copper	138	86	2.58 out of 5	\$345	\$47,610	IFR 2014A
Distribution Mains	P-2088	WAR	Mark Allen Dr.	8	Ductile Iron	822	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2175	WAR	Martingale Dr.	8	Asbestos Cement	562	34	1.58 out of 5	\$345	\$193,890	
Distribution Mains	P-2176	WAR	Martingale Dr.	8	Asbestos Cement	615	34	1.58 out of 5	\$345	\$212,175	
Distribution Mains	P-2362	WAR	Masthead Dr.	6	Asbestos Cement	570	47	2.43 out of 5	\$345	\$196,650	
Distribution Mains	P-2924	WAR	Matteson Ave.	1.5	Cast iron	154	81	3.15 out of 5	\$345	\$53,130	
Distribution Mains	P-2483	WAR	Matteson Ave.	8	Cast iron	254	81	1.72 out of 5	\$345	\$87,630	
Distribution Mains	P-2418	WAR	Meadow St.	4	Cast iron	539	86	3.15 out of 5	\$345	\$185,955	
Distribution Mains	P-2143	WAR	Meeting House Dr.	8	Asbestos Cement	289	58	1.72 out of 5	\$345	\$99,705	
Distribution Mains	P-2125	WAR	Michelle Cir.	8	PVC	231	26	0.44 out of 5	\$345	\$79,695	
Distribution Mains	P-2495	WAR	Montgomery St.	6	Asbestos Cement	867	62	2.58 out of 5	\$345	\$299,115	
Distribution Mains	P-2507	WAR	Montgomery St.	6	Asbestos Cement	251	62	2.58 out of 5	\$345	\$86,595	
Distribution Mains	P-2917	WAR	Music Ln.	6	Ductile Iron	29	13	0.71 out of 5	\$345	\$10,005	
Distribution Mains	P-2064	WAR	Nanci Karen Dr.	8	Asbestos Cement	355	37	1.58 out of 5	\$345	\$122,475	
Distribution Mains	P-2065	WAR	Nanci Karen Dr.	8	Asbestos Cement	502	37	1.58 out of 5	\$345	\$173,190	
Distribution Mains	P-2066	WAR	Nanci Karen Dr.	8	Asbestos Cement	457	37	1.58 out of 5	\$345	\$157,665	
Distribution Mains	P-2067	WAR	Nanci Karen Dr.	8	Asbestos Cement	218	37	1.58 out of 5	\$345	\$75,210	
Distribution Mains	P-2168	WAR	Nancy Allen Dr.	8	Asbestos Cement	315	53	1.72 out of 5	\$345	\$108,675	
Distribution Mains	P-2321	WAR	Natalie Ln.	8	Ductile Iron	166	19	0 out of 5	N/A	\$0	
Distribution Mains	P-2242	WAR	Nathaniel Green Dr.	6	Asbestos Cement	695	50	2.43 out of 5	\$345	\$239,775	
Distribution Mains	P-2951	WAR	Neptune St.	1	Copper	234	22	2.15 out of 5	\$345	\$80,730	IFR 2014A
Distribution Mains	P-2429	WAR	New England Way	8	Asbestos Cement	447	47	1.72 out of 5	\$345	\$154,215	
Distribution Mains	P-2430	WAR	New England Way	8	Asbestos Cement	391	47	1.72 out of 5	\$345	\$134,895	
Distribution Mains	P-2317	WAR	Nicolas Ln.	8	Ductile Iron	387	19	0 out of 5	N/A	\$0	
Distribution Mains	P-2318	WAR	Nicolas Ln.	8	Ductile Iron	254	19	0 out of 5	N/A	\$0	
Distribution Mains	P-2320	WAR	Nicolas Ln.	8	Ductile Iron	287	19	0 out of 5	N/A	\$0	
Distribution Mains	P-2410	WAR	North Marlborough St.	8	Ductile Iron	149	3	0 out of 5	N/A	\$0	
Distribution Mains	P-2956	WAR	North Marlborough St.	8	Ductile Iron	408	3	0 out of 5	N/A	\$0	
Distribution Mains	P-2154	WAR	North Winnisquam Dr.	8	PVC	183	26	0.44 out of 5	\$345	\$63,135	
Distribution Mains	P-2513	WAR	Northbridge Ave.	8	Asbestos Cement	471	52	1.72 out of 5	\$345	\$162,495	
Distribution Mains	P-2514	WAR	Northbridge Ave.	8	Asbestos Cement	893	52	1.72 out of 5	\$345	\$308,085	
Distribution Mains	P-2437	WAR	Oak Grove St.	8	Ductile Iron	327	30	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2439	WAR	Oak Grove St.	8	Ductile Iron	218	30	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2441	WAR	Oak Grove St.	8	Ductile Iron	124	30	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2442	WAR	Oak Grove St.	8	Ductile Iron	68	30	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2627	WAR	Oak St.	4	Cast iron	247	104	3.3 out of 5	\$345	\$85,215	
Distribution Mains	P-2626	WAR	Oak St.	2	Copper	498	68	2.44 out of 5	\$345	\$171,810	
Distribution Mains	P-2629	WAR	Oak St.	8	Ductile Iron	260	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2089	WAR	Oberlin Dr.	8	Ductile Iron	424	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2731	WAR	Oberlin Dr.	8	Ductile Iron	250	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2732	WAR	Oberlin Dr.	8	Ductile Iron	557	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2920	WAR	Octave St.	8	Ductile Iron	63	14	0 out of 5	N/A	\$0	
Distribution Mains	P-2563	WAR	O'Donnell Ave.	8	Ductile Iron	128	2	0 out of 5	N/A	\$0	
Distribution Mains	P-2564	WAR	O'Donnell Ave.	8	Ductile Iron	296	2	0 out of 5	N/A	\$0	
Distribution Mains	P-2866	WAR	O'Donnell Ave.	8	Ductile Iron	56	2	0 out of 5	N/A	\$0	
Distribution Mains	P-2867	WAR	O'Donnell Ave.	8	Ductile Iron	119	2	0 out of 5	N/A	\$0	
Distribution Mains	P-2532	WAR	Old East Ave.	6	Asbestos Cement	234	57	2.43 out of 5	\$345	\$80,730	
Distribution Mains	P-2534	WAR	Old East Ave.	6	Asbestos Cement	246	57	2.43 out of 5	\$345	\$84,870	
Distribution Mains	P-2536	WAR	Old East Ave.	6	Asbestos Cement	129	57	2.43 out of 5	\$345	\$44,505	
Distribution Mains	P-2869	WAR	Old East Ave.	8	Ductile Iron	32	6	0 out of 5	N/A	\$0	
Distribution Mains	P-2203	WAR	Old Lyme Dr.	8	Asbestos Cement	435	47	1.72 out of 5	\$345	\$150,075	
Distribution Mains	P-2198	WAR	Old Oak Dr.	8	Asbestos Cement	541	47	1.72 out of 5	\$345	\$186,645	
Distribution Mains	P-2499	WAR	Ontario Ave.	6	Asbestos Cement	257	59	2.43 out of 5	\$345	\$88,665	
Distribution Mains	P-2720	WAR	Orchard Ave.	8	Asbestos Cement	1,044	43	1.72 out of 5	\$345	\$360,180	IFR 2015A
Distribution Mains	P-2042	WAR	Orient St.	8	Ductile Iron	569	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2726	WAR	Osborne St.	6	Asbestos Cement	200	50	2.43 out of 5	\$345	\$69,000	
Distribution Mains	P-2584	WAR	Overhill Rd.	6	Cast iron	1,239	128	2.58 out of 5	\$345	\$427,455	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-2171	WAR	Paddock Dr.	8	Asbestos Cement	970	34	1.58 out of 5	\$345	\$334,650	
Distribution Mains	P-2636	WAR	Panto Rd.	6	Asbestos Cement	312	60	2.58 out of 5	\$345	\$107,640	IFR 2015B
Distribution Mains	P-2637	WAR	Panto Rd.	6	Asbestos Cement	598	60	2.58 out of 5	\$345	\$206,310	IFR 2015B
Distribution Mains	P-2123	WAR	Pasco Cir.	8	PVC	607	26	0.44 out of 5	\$345	\$209,415	
Distribution Mains	P-2933	WAR	Patrick Way	8	Ductile Iron	482	10	0 out of 5	N/A	\$0	
Distribution Mains	P-2334	WAR	Patterson Ave.	6	Asbestos Cement	544	68	2.58 out of 5	\$345	\$187,680	
Distribution Mains	P-2340	WAR	Patterson Ave.	6	Asbestos Cement	351	68	2.58 out of 5	\$345	\$121,095	
Distribution Mains	P-2341	WAR	Patterson Ave.	6	Asbestos Cement	341	68	2.58 out of 5	\$345	\$117,645	
Distribution Mains	P-2607	WAR	Paul Ave.	6	Asbestos Cement	215	68	2.58 out of 5	\$345	\$74,175	
Distribution Mains	P-2608	WAR	Paul Ave.	6	Asbestos Cement	228	68	2.58 out of 5	\$345	\$78,660	
Distribution Mains	P-2179	WAR	Peaceful Ln.	8	Ductile Iron	347	16	0 out of 5	N/A	\$0	
Distribution Mains	P-2934	WAR	Peacock Rd.	8	Asbestos Cement	177	42	1.72 out of 5	\$345	\$61,065	
Distribution Mains	P-2713	WAR	Peacock Rd.	8	Ductile Iron	148	22	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2714	WAR	Peacock Rd.	8	Ductile Iron	700	22	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2102	WAR	Pender John Ct.	8	Ductile Iron	509	17	0 out of 5	N/A	\$0	
Distribution Mains	P-2010	WAR	Pitman Rd.	6	Asbestos Cement	987	54	2.43 out of 5	\$345	\$340,515	
Distribution Mains	P-2503	WAR	Plantation St.	6	Asbestos Cement	861	55	2.43 out of 5	\$345	\$297,045	
Distribution Mains	P-2620	WAR	Pleasant St.	4	Cast iron	401	104	4.01 out of 5	\$345	\$138,345	
Distribution Mains	P-2630	WAR	Pleasant St.	8	Ductile Iron	470	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2911	WAR	Pleasant St.	8	Ductile Iron	203	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2948	WAR	Plymouth St.	2	Copper	158	86	2.58 out of 5	\$345	\$54,510	IFR 2014A
Distribution Mains	P-2949	WAR	Plymouth St.	2	Copper	85	86	2.58 out of 5	\$345	\$29,325	IFR 2014A
Distribution Mains	P-2444	WAR	Plymouth St.	8	Asbestos Cement	759	66	1.87 out of 5	\$345	\$261,855	IFR 2014A
Distribution Mains	P-2492	WAR	Pond View Dr.	6	Asbestos Cement	464	42	2.43 out of 5	\$345	\$160,080	
Distribution Mains	P-2554	WAR	Pontiac St.	6	Cast iron	619	86	2.43 out of 5	\$345	\$213,555	IFR 2015A
Distribution Mains	P-2555	WAR	Pontiac St.	6	Cast iron	233	86	2.43 out of 5	\$345	\$80,385	IFR 2015A
Distribution Mains	P-2557	WAR	Pontiac St.	6	Cast iron	272	86	2.43 out of 5	\$345	\$93,840	IFR 2015A
Distribution Mains	P-2454	WAR	Poppy Pl.	8	Ductile Iron	202	18	0 out of 5	N/A	\$0	
Distribution Mains	P-2912	WAR	Post Rd.	2	Copper	255	68	2.44 out of 5	\$345	\$87,975	
Distribution Mains	P-2913	WAR	Post Rd.	2	Copper	328	68	2.44 out of 5	\$345	\$113,160	
Distribution Mains	P-2614	WAR	Post Rd.	8	Cast iron	804	124	1.87 out of 5	\$345	\$277,380	
Distribution Mains	P-2616	WAR	Post Rd.	8	Cast iron	208	124	1.87 out of 5	\$345	\$71,760	
Distribution Mains	P-2617	WAR	Post Rd.	8	Cast iron	245	124	1.87 out of 5	\$345	\$84,525	
Distribution Mains	P-2618	WAR	Post Rd.	8	Cast iron	257	124	1.87 out of 5	\$345	\$88,665	
Distribution Mains	P-2619	WAR	Post Rd.	8	Cast iron	343	124	1.87 out of 5	\$345	\$118,335	
Distribution Mains	P-2701	WAR	Post Rd.	8	Cast iron	331	124	1.87 out of 5	\$345	\$114,195	
Distribution Mains	P-2702	WAR	Post Rd.	8	Cast iron	77	124	1.87 out of 5	\$345	\$26,565	
Distribution Mains	P-2703	WAR	Post Rd.	8	Cast iron	47	124	1.87 out of 5	\$345	\$16,215	
Transmission Mains	P-2699	WAR	Post Rd.	12	Cast iron	296	86	1.72 out of 5	\$345	\$102,120	
Transmission Mains	P-2704	WAR	Post Rd.	12	Cast iron	307	86	1.72 out of 5	\$345	\$105,915	
Transmission Mains	P-2705	WAR	Post Rd.	12	Cast iron	144	86	1.72 out of 5	\$345	\$49,680	
Transmission Mains	P-2347	WAR	Post Rd.	16	Ductile Iron	613	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2352	WAR	Post Rd.	16	Ductile Iron	147	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2353	WAR	Post Rd.	16	Ductile Iron	619	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2364	WAR	Post Rd.	16	Ductile Iron	1,283	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2365	WAR	Post Rd.	16	Ductile Iron	935	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2366	WAR	Post Rd.	16	Ductile Iron	503	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2367	WAR	Post Rd.	16	Ductile Iron	121	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2368	WAR	Post Rd.	16	Ductile Iron	121	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2369	WAR	Post Rd.	16	Ductile Iron	129	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2370	WAR	Post Rd.	16	Ductile Iron	722	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2371	WAR	Post Rd.	16	Ductile Iron	887	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2372	WAR	Post Rd.	16	Ductile Iron	273	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2373	WAR	Post Rd.	16	Ductile Iron	237	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2374	WAR	Post Rd.	16	Ductile Iron	282	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2375	WAR	Post Rd.	16	Ductile Iron	324	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2376	WAR	Post Rd.	16	Ductile Iron	405	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2422	WAR	Post Rd.	16	Ductile Iron	1,766	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2449	WAR	Post Rd.	16	Ductile Iron	89	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2458	WAR	Post Rd.	16	Ductile Iron	861	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2460	WAR	Post Rd.	16	Ductile Iron	231	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2472	WAR	Post Rd.	16	Ductile Iron	276	15	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-2474	WAR	Post Rd.	16	Ductile Iron	241	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2478	WAR	Post Rd.	16	Ductile Iron	258	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2480	WAR	Post Rd.	16	Ductile Iron	108	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2482	WAR	Post Rd.	16	Ductile Iron	294	15	0 out of 5	N/A	\$0	
Distribution Mains	P-2610	WAR	Post Rd.	8	Ductile Iron	230	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2692	WAR	Post Rd.	16	Ductile Iron	593	15	0 out of 5	N/A	\$0	
Distribution Mains	P-2706	WAR	Post Rd.	8	Ductile Iron	38	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2783	WAR	Post Rd.	16	Ductile Iron	213	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2925	WAR	Post Rd.	16	Ductile Iron	58	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2928	WAR	Post Rd.	16	Ductile Iron	40	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2946	WAR	Post Rd.	16	Ductile Iron	110	15	0 out of 5	N/A	\$0	
Transmission Mains	P-2958	WAR	Post Rd.	16	Ductile Iron	44	15	0 out of 5	N/A	\$0	
Distribution Mains	P-2622	WAR	Prospect St.	8	Ductile Iron	217	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2628	WAR	Prospect St.	8	Ductile Iron	352	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2691	WAR	Prospect St.	8	Ductile Iron	192	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2070	WAR	Quaid Ln.	8	Asbestos Cement	449	49	1.72 out of 5	\$345	\$154,905	
Distribution Mains	P-2072	WAR	Quaid Ln.	8	Asbestos Cement	302	49	1.72 out of 5	\$345	\$104,190	
Transmission Mains	P-2196	WAR	Quaker Ln.	20	Asbestos Cement	845	45	1.72 out of 5	\$345	\$291,525	
Distribution Mains	P-2264	WAR	Quaker Ln.	8	Asbestos Cement	1,032	40	1.72 out of 5	\$345	\$356,040	
Distribution Mains	P-2280	WAR	Quaker Ln.	8	Asbestos Cement	517	40	1.72 out of 5	\$345	\$178,365	
Transmission Mains	P-2698	WAR	Quaker Ln.	20	Asbestos Cement	1,037	45	1.72 out of 5	\$345	\$357,765	
Transmission Mains	P-2188	WAR	Quaker Ln.	24	Asbestos Cement	4,722	34	1.58 out of 5	\$345	\$1,629,090	
Transmission Mains	P-2204	WAR	Quaker Ln.	24	Asbestos Cement	59	34	1.58 out of 5	\$345	\$20,355	
Transmission Mains	P-2229	WAR	Quaker Ln.	24	Asbestos Cement	166	34	1.58 out of 5	\$345	\$57,270	
Distribution Mains	P-2230	WAR	Quaker Ln.	8	Asbestos Cement	68	34	1.58 out of 5	\$345	\$23,460	
Distribution Mains	P-2244	WAR	Quaker Ln.	8	Asbestos Cement	108	34	1.58 out of 5	\$345	\$37,260	
Transmission Mains	P-2893	WAR	Quaker Ln.	24	Asbestos Cement	482	34	1.58 out of 5	\$345	\$166,290	
Distribution Mains	P-2894	WAR	Quaker Ln.	6	Ductile Iron	132	15	0.71 out of 5	\$345	\$45,540	
Distribution Mains	P-2895	WAR	Quaker Ln.	6	Ductile Iron	401	12	0.71 out of 5	\$345	\$138,345	
Transmission Mains	P-2750	WAR	Quaker Ln.	16	Ductile Iron	789	8	0 out of 5	N/A	\$0	
Transmission Mains	P-2892	WAR	Quaker Ln.	16	Ductile Iron	1,344	0	0 out of 5	N/A	\$0	
Transmission Mains	P-2668	WAR	Quaker Ln. PS	24	Asbestos Cement	157	30	1.58 out of 5	\$345	\$54,165	
Transmission Mains	P-2674	WAR	Quaker Ln. PS	24	Asbestos Cement	124	30	1.58 out of 5	\$345	\$42,780	
Transmission Mains	P-2675	WAR	Quaker Ln. PS	24	Asbestos Cement	135	30	1.58 out of 5	\$345	\$46,575	
Transmission Mains	P-2678	WAR	Quaker Ln. PS	24	Asbestos Cement	123	30	1.58 out of 5	\$345	\$42,435	
Transmission Mains	P-2681	WAR	Quaker Ln. PS	24	Asbestos Cement	344	30	1.58 out of 5	\$345	\$118,680	
Transmission Mains	P-2682	WAR	Quaker Ln. PS	24	Asbestos Cement	101	30	1.58 out of 5	\$345	\$34,845	
Transmission Mains	P-2683	WAR	Quaker Ln. PS	24	Asbestos Cement	152	30	1.58 out of 5	\$345	\$52,440	
Transmission Mains	P-2684	WAR	Quaker Ln. PS	24	Asbestos Cement	134	30	1.58 out of 5	\$345	\$46,230	
Transmission Mains	P-2669	WAR	Quaker Ln. PS	12	Ductile Iron	280	0	0 out of 5	N/A	\$0	
Distribution Mains	P-2670	WAR	Quaker Ln. PS	10	Ductile Iron	640	0	0 out of 5	N/A	\$0	
Transmission Mains	P-2672	WAR	Quaker Ln. PS	12	Ductile Iron	296	0	0 out of 5	N/A	\$0	
Distribution Mains	P-2673	WAR	Quaker Ln. PS	10	Ductile Iron	652	0	0 out of 5	N/A	\$0	
Transmission Mains	P-2676	WAR	Quaker Ln. PS	12	Ductile Iron	574	0	0 out of 5	N/A	\$0	
Distribution Mains	P-2677	WAR	Quaker Ln. PS	10	Ductile Iron	250	0	0 out of 5	N/A	\$0	
Transmission Mains	P-2679	WAR	Quaker Ln. PS	12	Ductile Iron	602	0	0 out of 5	N/A	\$0	
Distribution Mains	P-2680	WAR	Quaker Ln. PS	10	Ductile Iron	266	0	0 out of 5	N/A	\$0	
Distribution Mains	P-2533	WAR	Quinlan Ct.	1.3	Copper	245	57	2.29 out of 5	\$345	\$84,525	
Distribution Mains	P-2560	WAR	Railroad Row	4	Cast iron	509	86	3.15 out of 5	\$345	\$175,605	IFR 2015A
Distribution Mains	P-2852	WAR	Railroad Row	4	Cast iron	175	86	3.15 out of 5	\$345	\$60,375	IFR 2015A
Distribution Mains	P-2940	WAR	Red Chimney Dr.	1.5	Copper	163	58	2.29 out of 5	\$345	\$56,235	
Distribution Mains	P-2140	WAR	Red Chimney Dr.	8	Asbestos Cement	691	58	1.72 out of 5	\$345	\$238,395	
Distribution Mains	P-2142	WAR	Red Chimney Dr.	8	Asbestos Cement	131	58	1.72 out of 5	\$345	\$45,195	
Distribution Mains	P-2155	WAR	Red Chimney Dr.	8	Asbestos Cement	285	58	1.72 out of 5	\$345	\$98,325	
Distribution Mains	P-2159	WAR	Red Chimney Dr.	8	Asbestos Cement	309	58	1.72 out of 5	\$345	\$106,605	
Distribution Mains	P-2160	WAR	Red Chimney Dr.	8	Asbestos Cement	673	58	1.72 out of 5	\$345	\$232,185	
Distribution Mains	P-2167	WAR	Red Chimney Dr.	8	Asbestos Cement	1,413	58	1.72 out of 5	\$345	\$487,485	
Distribution Mains	P-2169	WAR	Red Chimney Dr.	8	Asbestos Cement	279	58	1.72 out of 5	\$345	\$96,255	
Distribution Mains	P-2170	WAR	Red Chimney Dr.	8	Asbestos Cement	129	58	1.72 out of 5	\$345	\$44,505	
Distribution Mains	P-2172	WAR	Red Chimney Dr.	8	Asbestos Cement	207	58	1.72 out of 5	\$345	\$71,415	
Distribution Mains	P-2173	WAR	Red Chimney Dr.	8	Asbestos Cement	387	58	1.72 out of 5	\$345	\$133,515	
Distribution Mains	P-2935	WAR	Red Chimney Dr.	8	Asbestos Cement	311	58	1.72 out of 5	\$345	\$107,295	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-2939	WAR	Red Chimney Dr.	8	Asbestos Cement	334	58	1.72 out of 5	\$345	\$115,230	
Distribution Mains	P-2473	WAR	Reeland Ave.	6	Asbestos Cement	502	49	2.43 out of 5	\$345	\$173,190	
Distribution Mains	P-2319	WAR	Remy Cir.	8	Ductile Iron	366	19	0 out of 5	N/A	\$0	
Distribution Mains	P-2459	WAR	Rice St.	6	Ductile Iron	468	22	0.86 out of 5	\$345	\$161,460	
Distribution Mains	P-2463	WAR	Rip Van Winkle Cir.	8	Ductile Iron	63	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2464	WAR	Rip Van Winkle Cir.	8	Ductile Iron	102	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2466	WAR	Rip Van Winkle Cir.	8	Ductile Iron	774	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2926	WAR	Robin Hill Rd.	2	Galvanized iron	207	15	2.86 out of 5	\$345	\$71,415	
Distribution Mains	P-2246	WAR	Roelker Dr.	8	Asbestos Cement	535	50	1.72 out of 5	\$345	\$184,575	
Distribution Mains	P-2553	WAR	Rossi St.	4	Cast iron	327	86	3.15 out of 5	\$345	\$112,815	IFR 2015A
Distribution Mains	P-2493	WAR	Rutherford Ave.	6	Asbestos Cement	278	64	2.58 out of 5	\$345	\$95,910	
Distribution Mains	P-2494	WAR	Rutherford Ave.	6	Asbestos Cement	264	64	2.58 out of 5	\$345	\$91,080	
Distribution Mains	P-2696	WAR	Rutherford Ave.	6	Asbestos Cement	445	64	2.58 out of 5	\$345	\$153,525	
Distribution Mains	P-2888	WAR	Rutherford Ave.	6	Ductile Iron	24	6	0.71 out of 5	\$345	\$8,280	
Distribution Mains	P-2887	WAR	Rutherford Ave.	8	Ductile Iron	18	6	0 out of 5	N/A	\$0	
Distribution Mains	P-2697	WAR	Rutherford Ct.	6	Asbestos Cement	223	64	2.58 out of 5	\$345	\$76,935	
Distribution Mains	P-2052	WAR	Sage Dr.	6	Asbestos Cement	409	45	2.43 out of 5	\$345	\$141,105	
Distribution Mains	P-2727	WAR	Sage Dr.	6	Asbestos Cement	409	45	2.43 out of 5	\$345	\$141,105	
Distribution Mains	P-2728	WAR	Sage Dr.	6	Asbestos Cement	234	45	2.43 out of 5	\$345	\$80,730	
Distribution Mains	P-2581	WAR	Sammartino Cir.	8	Asbestos Cement	489	38	1.58 out of 5	\$345	\$168,705	
Distribution Mains	P-2582	WAR	Sammartino Cir.	8	Asbestos Cement	167	38	1.58 out of 5	\$345	\$57,615	
Distribution Mains	P-2736	WAR	Sandro Cir.	6	Asbestos Cement	175	60	2.58 out of 5	\$345	\$60,375	
Distribution Mains	P-2734	WAR	Sandro Dr.	6	Asbestos Cement	256	60	2.58 out of 5	\$345	\$88,320	
Distribution Mains	P-2735	WAR	Sandro Dr.	6	Asbestos Cement	583	60	2.58 out of 5	\$345	\$201,135	
Distribution Mains	P-2228	WAR	Sandy Brook Ct.	8	PVC	165	24	0.44 out of 5	\$345	\$56,925	
Distribution Mains	P-2048	WAR	Saxony Dr.	6	Asbestos Cement	492	52	2.43 out of 5	\$345	\$169,740	
Distribution Mains	P-2056	WAR	Saxony Dr.	6	Asbestos Cement	670	52	2.43 out of 5	\$345	\$231,150	
Distribution Mains	P-2509	WAR	Scarsdale St.	6	Asbestos Cement	425	62	2.58 out of 5	\$345	\$146,625	
Distribution Mains	P-2510	WAR	Scarsdale St.	6	Asbestos Cement	375	62	2.58 out of 5	\$345	\$129,375	
Distribution Mains	P-2350	WAR	Sea Breeze Ln.	6	Asbestos Cement	160	39	2.29 out of 5	\$345	\$55,200	
Distribution Mains	P-2226	WAR	Shadowbrook Dr.	8	PVC	857	24	0.44 out of 5	\$345	\$295,665	
Distribution Mains	P-2227	WAR	Shadowbrook Dr.	8	PVC	1,397	24	0.44 out of 5	\$345	\$481,965	
Distribution Mains	P-2577	WAR	Shady Glen Dr.	6	Asbestos Cement	809	66	2.58 out of 5	\$345	\$279,105	
Distribution Mains	P-2922	WAR	Shattock Ave.	6	Asbestos Cement	15	68	2.58 out of 5	\$345	\$5,175	
Distribution Mains	P-2923	WAR	Shattock Ave.	6	Cast iron	239	68	2.29 out of 5	\$345	\$82,455	
Distribution Mains	P-2602	WAR	Shattock Ave.	6	Ductile Iron	226	12	1.42 out of 5	\$345	\$77,970	
Distribution Mains	P-2461	WAR	Shenandoah Rd.	8	Ductile Iron	1,221	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2467	WAR	Shenandoah Rd.	8	Ductile Iron	1,090	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2938	WAR	Silent Dr.	2	Copper	114	57	2.29 out of 5	\$345	\$39,330	
Distribution Mains	P-2097	WAR	Sleepy Hollow Farm Dr.	8	Ductile Iron	2,434	17	0 out of 5	N/A	\$0	
Distribution Mains	P-2099	WAR	Sleepy Hollow Farm Dr.	8	Ductile Iron	486	17	0 out of 5	N/A	\$0	
Distribution Mains	P-2100	WAR	Sleepy Hollow Farm Dr.	8	Ductile Iron	1,999	17	0 out of 5	N/A	\$0	
Distribution Mains	P-2101	WAR	Sleepy Hollow Farm Dr.	8	Ductile Iron	183	17	0 out of 5	N/A	\$0	
Distribution Mains	P-2217	WAR	Slient Dr.	8	Asbestos Cement	196	48	1.72 out of 5	\$345	\$67,620	
Distribution Mains	P-2937	WAR	Slient Dr.	8	Asbestos Cement	207	48	1.72 out of 5	\$345	\$71,415	
Distribution Mains	P-2178	WAR	So. Cobblehill Rd.	8	Asbestos Cement	764	54	1.72 out of 5	\$345	\$263,580	
Distribution Mains	P-2201	WAR	So. Cobblehill Rd.	8	Asbestos Cement	225	54	1.72 out of 5	\$345	\$77,625	
Distribution Mains	P-2202	WAR	So. Cobblehill Rd.	8	Asbestos Cement	163	54	1.72 out of 5	\$345	\$56,235	
Distribution Mains	P-2638	WAR	Sophia Rd.	6	Asbestos Cement	1,025	60	3.29 out of 5	\$345	\$353,625	IFR 2015B
Distribution Mains	P-2593	WAR	Spencer Ave.	6	Cast iron	735	78	2.29 out of 5	\$345	\$253,575	
Distribution Mains	P-2579	WAR	Spencer Ave.	10	Cast iron	619	124	1.87 out of 5	\$345	\$213,555	
Distribution Mains	P-2580	WAR	Spencer Ave.	10	Cast iron	583	124	1.87 out of 5	\$345	\$201,135	
Distribution Mains	P-2585	WAR	Spencer Ave.	10	Cast iron	810	124	1.87 out of 5	\$345	\$279,450	
Distribution Mains	P-2586	WAR	Spencer Ave.	10	Cast iron	318	124	1.87 out of 5	\$345	\$109,710	
Distribution Mains	P-2742	WAR	Spencer Hill Ct.	8	Ductile Iron	244	17	0 out of 5	N/A	\$0	
Distribution Mains	P-2741	WAR	Spencer Hill Ct. Easement	8	Ductile Iron	479	17	0 out of 5	N/A	\$0	
Distribution Mains	P-2080	WAR	Spinnaker Ln.	8	Ductile Iron	750	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2624	WAR	Spruce St.	4	Cast iron	407	104	3.3 out of 5	\$345	\$140,415	
Distribution Mains	P-2625	WAR	Spruce St.	6	PVC	346	29	1.15 out of 5	\$345	\$119,370	
Distribution Mains	P-2603	WAR	Staples Ave.	6	Asbestos Cement	405	68	2.58 out of 5	\$345	\$139,725	
Distribution Mains	P-2604	WAR	Staples Ave.	6	Asbestos Cement	1,601	68	2.58 out of 5	\$345	\$552,345	
Distribution Mains	P-2361	WAR	Stiness Dr.	2	Copper	668	78	2.44 out of 5	\$345	\$230,460	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-2930	WAR	Stiness Dr.	2	Copper	156	78	2.44 out of 5	\$345	\$53,820	
Distribution Mains	P-2358	WAR	Stiness Dr.	6	PVC	579	26	1.15 out of 5	\$345	\$199,755	
Distribution Mains	P-2193	WAR	Stubtoe Dr.	8	Asbestos Cement	540	47	1.72 out of 5	\$345	\$186,300	
Distribution Mains	P-2213	WAR	Stubtoe Dr.	8	Asbestos Cement	352	47	1.72 out of 5	\$345	\$121,440	
Distribution Mains	P-2214	WAR	Stubtoe Dr.	8	Asbestos Cement	420	47	1.72 out of 5	\$345	\$144,900	
Distribution Mains	P-2073	WAR	Sturbridge Dr.	8	Asbestos Cement	533	35	1.58 out of 5	\$345	\$183,885	
Distribution Mains	P-2074	WAR	Sturbridge Dr.	8	Asbestos Cement	478	35	1.58 out of 5	\$345	\$164,910	
Distribution Mains	P-2078	WAR	Sturbridge Dr.	8	Asbestos Cement	842	35	1.58 out of 5	\$345	\$290,490	
Distribution Mains	P-2055	WAR	Superior St.	6	Asbestos Cement	351	52	2.43 out of 5	\$345	\$121,095	
Distribution Mains	P-2057	WAR	Superior St.	6	Asbestos Cement	328	52	2.43 out of 5	\$345	\$113,160	
Distribution Mains	P-2289	WAR	Sutter Ave.	8	Ductile Iron	530	9	0 out of 5	N/A	\$0	
Distribution Mains	P-2816	WAR	Sutter Ave. Easement	8	Ductile Iron	339	9	0 out of 5	N/A	\$0	
Distribution Mains	P-2283	WAR	Tanner Ave.	8	Ductile Iron	657	9	0 out of 5	N/A	\$0	
Distribution Mains	P-2284	WAR	Tanner Ave.	8	Ductile Iron	578	9	0 out of 5	N/A	\$0	
Distribution Mains	P-2817	WAR	Tanner Ave.	8	Ductile Iron	554	9	0 out of 5	N/A	\$0	
Distribution Mains	P-2709	WAR	Taylor Ln.	8	Ductile Iron	250	11	0 out of 5	N/A	\$0	
Transmission Mains	P-2187	WAR	Telmore Rd.	12	Asbestos Cement	1,020	41	1.72 out of 5	\$345	\$351,900	
Distribution Mains	P-2530	WAR	Thames Ave.	2	Copper	552	74	2.44 out of 5	\$345	\$190,440	
Distribution Mains	P-2871	WAR	Thames Ave.	2	PVC	32	6	1.72 out of 5	\$345	\$11,040	
Distribution Mains	P-2870	WAR	Thames Ave.	8	Ductile Iron	34	6	0 out of 5	N/A	\$0	
Distribution Mains	P-2545	WAR	Tillinghast Ave.	6	Ductile Iron	606	19	0.71 out of 5	\$345	\$209,070	
Distribution Mains	P-2547	WAR	Tillinghast Ave.	6	Ductile Iron	511	19	0.71 out of 5	\$345	\$176,295	
Distribution Mains	P-2548	WAR	Tillinghast Ave.	6	Ductile Iron	758	11	0.71 out of 5	\$345	\$261,510	
Distribution Mains	P-2158	WAR	Timberline Rd.	8	Asbestos Cement	1,853	58	1.72 out of 5	\$345	\$639,285	
Distribution Mains	P-2337	WAR	Tivoli Ct.	8	Ductile Iron	583	26	0.15 out of 5	N/A	\$0	
Transmission Mains	P-2328	WAR	Tollgate Rd.	12	Cast iron	396	86	2.43 out of 5	\$345	\$136,620	IFR 2014A
Transmission Mains	P-2278	WAR	Tollgate Rd.	12	Cast iron	305	86	1.72 out of 5	\$345	\$105,225	IFR 2014A
Distribution Mains	P-2298	WAR	Tollgate Rd.	10	Cast iron	1,969	86	1.72 out of 5	\$345	\$679,305	
Transmission Mains	P-2310	WAR	Tollgate Rd.	12	Cast iron	545	86	1.72 out of 5	\$345	\$188,025	IFR 2014A
Transmission Mains	P-2323	WAR	Tollgate Rd.	12	Cast iron	650	86	1.72 out of 5	\$345	\$224,250	IFR 2014A
Transmission Mains	P-2327	WAR	Tollgate Rd.	12	Cast iron	164	86	1.72 out of 5	\$345	\$56,580	IFR 2014A
Distribution Mains	P-2647	WAR	Tollgate Rd.	10	Cast iron	89	86	1.72 out of 5	\$345	\$30,705	
Transmission Mains	P-2716	WAR	Tollgate Rd.	12	Cast iron	97	86	1.72 out of 5	\$345	\$33,465	
Transmission Mains	P-2717	WAR	Tollgate Rd.	12	Cast iron	721	86	1.72 out of 5	\$345	\$248,745	IFR 2014A
Transmission Mains	P-2718	WAR	Tollgate Rd.	12	Cast iron	1,242	86	1.72 out of 5	\$345	\$428,490	IFR 2014A
Transmission Mains	P-2719	WAR	Tollgate Rd.	12	Cast iron	795	86	1.72 out of 5	\$345	\$274,275	IFR 2014A
Transmission Mains	P-2776	WAR	Tollgate Rd.	12	Cast iron	480	86	1.72 out of 5	\$345	\$165,600	IFR 2014A
Transmission Mains	P-2833	WAR	Tollgate Rd.	12	Cast iron	1,114	86	1.72 out of 5	\$345	\$384,330	IFR 2014A
Distribution Mains	P-2862	WAR	Tollgate Rd.	10	Cast iron	2,804	86	1.72 out of 5	\$345	\$967,380	
Distribution Mains	P-2733	WAR	Tomahawk Ct.	6	Ductile Iron	515	13	1.42 out of 5	\$345	\$177,675	
Distribution Mains	P-2425	WAR	Trellis Dr.	8	Asbestos Cement	209	36	1.58 out of 5	\$345	\$72,105	
Distribution Mains	P-2209	WAR	Turtle Creek Dr.	8	PVC	367	26	0.44 out of 5	\$345	\$126,615	
Distribution Mains	P-2329	WAR	Vale St.	6	Asbestos Cement	200	41	2.43 out of 5	\$345	\$69,000	
Distribution Mains	P-2354	WAR	Valentine Cir.	6	Asbestos Cement	212	41	2.43 out of 5	\$345	\$73,140	
Distribution Mains	P-2359	WAR	Valentine Cir.	6	Cast iron	560	78	2.29 out of 5	\$345	\$193,200	
Distribution Mains	P-2360	WAR	Valentine Cir.	2	Copper	466	41	2.29 out of 5	\$345	\$160,770	
Distribution Mains	P-2929	WAR	Valentine Cir.	2	Copper	46	41	2.29 out of 5	\$345	\$15,870	
Distribution Mains	P-2249	WAR	Valley Brook Dr.	8	Asbestos Cement	701	41	1.72 out of 5	\$345	\$241,845	
Distribution Mains	P-2251	WAR	Valley Brook Dr.	8	Asbestos Cement	150	41	1.72 out of 5	\$345	\$51,750	
Distribution Mains	P-2515	WAR	Vancouver Ave.	6	Asbestos Cement	745	64	3.29 out of 5	\$345	\$257,025	
Distribution Mains	P-2504	WAR	Vancouver Ave.	6	Asbestos Cement	424	64	2.58 out of 5	\$345	\$146,280	
Distribution Mains	P-2511	WAR	Vancouver Ave.	6	Asbestos Cement	448	64	2.58 out of 5	\$345	\$154,560	
Distribution Mains	P-2516	WAR	Vancouver Ave.	6	Asbestos Cement	306	64	2.58 out of 5	\$345	\$105,570	
Distribution Mains	P-2519	WAR	Vancouver Ave.	6	Asbestos Cement	260	64	2.58 out of 5	\$345	\$89,700	
Distribution Mains	P-2520	WAR	Vancouver Ave.	6	Asbestos Cement	251	64	2.58 out of 5	\$345	\$86,595	
Distribution Mains	P-2875	WAR	Vancouver Ave.	6	Ductile Iron	25	6	0.71 out of 5	\$345	\$8,625	
Distribution Mains	P-2874	WAR	Vancouver Ave.	8	Ductile Iron	20	6	0 out of 5	N/A	\$0	
Distribution Mains	P-2237	WAR	Varnum Dr.	8	Asbestos Cement	504	50	1.72 out of 5	\$345	\$173,880	
Distribution Mains	P-2238	WAR	Varnum Dr.	8	Asbestos Cement	1,694	50	1.72 out of 5	\$345	\$584,430	
Distribution Mains	P-2239	WAR	Varnum Dr.	8	Asbestos Cement	1,768	50	1.72 out of 5	\$345	\$609,960	
Distribution Mains	P-2398	WAR	Venus Dr.	8	Ductile Iron	270	27	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2399	WAR	Venus Dr.	8	Ductile Iron	386	27	0.15 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-2148	WAR	Verdant Ln.	8	Asbestos Cement	493	42	1.72 out of 5	\$345	\$170,085	
Distribution Mains	P-2631	WAR	Veterans Memorial Dr.	8	Asbestos Cement	690	65	1.87 out of 5	\$345	\$238,050	
Distribution Mains	P-2632	WAR	Veterans Memorial Dr.	8	Asbestos Cement	1,105	65	1.87 out of 5	\$345	\$381,225	
Distribution Mains	P-2047	WAR	Viceroy Rd.	6	Asbestos Cement	411	52	2.43 out of 5	\$345	\$141,795	
Distribution Mains	P-2058	WAR	Viceroy Rd.	6	Asbestos Cement	933	52	2.43 out of 5	\$345	\$321,885	
Distribution Mains	P-2060	WAR	Viceroy Rd.	6	Asbestos Cement	234	52	2.43 out of 5	\$345	\$80,730	
Distribution Mains	P-2061	WAR	Viceroy Rd.	6	Asbestos Cement	101	52	2.43 out of 5	\$345	\$34,845	
Distribution Mains	P-2062	WAR	Viceroy Rd.	6	Asbestos Cement	484	52	2.43 out of 5	\$345	\$166,980	
Distribution Mains	P-2931	WAR	Viceroy Rd.	8	Ductile Iron	73	9	0 out of 5	N/A	\$0	
Distribution Mains	P-2030	WAR	Wampum Rd.	8	Asbestos Cement	305	37	1.58 out of 5	\$345	\$105,225	
Distribution Mains	P-2032	WAR	Wampum Rd.	8	Asbestos Cement	247	37	1.58 out of 5	\$345	\$85,215	
Transmission Mains	P-2688	WAR	Warwick Tanks	24	Asbestos Cement	118	30	1.58 out of 5	\$345	\$40,710	
Transmission Mains	P-2689	WAR	Warwick Tanks	24	Asbestos Cement	270	30	1.58 out of 5	\$345	\$93,150	
Transmission Mains	P-2690	WAR	Warwick Tanks	24	Asbestos Cement	143	30	1.58 out of 5	\$345	\$49,335	
Distribution Mains	P-2611	WAR	Water St.	8	Ductile Iron	101	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2613	WAR	Water St.	8	Ductile Iron	790	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2916	WAR	Water St.	8	Ductile Iron	60	13	0 out of 5	N/A	\$0	
Distribution Mains	P-2485	WAR	Weber Ave.	6	Asbestos Cement	380	72	2.58 out of 5	\$345	\$131,100	
Distribution Mains	P-2266	WAR	Welthian Ct.	6	Asbestos Cement	321	61	2.58 out of 5	\$345	\$110,745	
Distribution Mains	P-2953	WAR	Welthian Ct.	1	Copper	181	61	2.44 out of 5	\$345	\$62,445	
Distribution Mains	P-2558	WAR	West Pontiac St.	6	Cast iron	319	86	2.43 out of 5	\$345	\$110,055	IFR 2015A
Distribution Mains	P-2853	WAR	West Pontiac St.	6	Cast iron	229	86	2.43 out of 5	\$345	\$79,005	IFR 2015A
Distribution Mains	P-2854	WAR	West Pontiac St.	6	Cast iron	39	86	2.43 out of 5	\$345	\$13,455	IFR 2015A
Distribution Mains	P-2855	WAR	West Pontiac St.	6	Cast iron	162	86	2.43 out of 5	\$345	\$55,890	IFR 2015A
Distribution Mains	P-2391	WAR	Westchester Way	6	Asbestos Cement	285	48	2.43 out of 5	\$345	\$98,325	
Distribution Mains	P-2392	WAR	Westchester Way	6	Asbestos Cement	580	48	2.43 out of 5	\$345	\$200,100	
Distribution Mains	P-2947	WAR	Weymouth Ln.	8	Ductile Iron	391	12	0 out of 5	N/A	\$0	
Distribution Mains	P-2739	WAR	Whispering Ln.	6	PVC	390	26	1.15 out of 5	\$345	\$134,550	
Distribution Mains	P-2301	WAR	Whitehall Dr.	8	Asbestos Cement	290	49	1.72 out of 5	\$345	\$100,050	IFR 2014A
Distribution Mains	P-2302	WAR	Whitehall Dr.	8	Asbestos Cement	179	49	1.72 out of 5	\$345	\$61,755	IFR 2014A
Distribution Mains	P-2431	WAR	Wilcar St.	6	Asbestos Cement	345	43	2.43 out of 5	\$345	\$119,025	
Distribution Mains	P-2432	WAR	Wilcar St.	6	Asbestos Cement	124	43	2.43 out of 5	\$345	\$42,780	
Distribution Mains	P-2401	WAR	Williams St.	8	Ductile Iron	243	3	0 out of 5	N/A	\$0	
Distribution Mains	P-2402	WAR	Williams St.	8	Ductile Iron	251	3	0 out of 5	N/A	\$0	
Distribution Mains	P-2955	WAR	Williams St.	8	Ductile Iron	121	3	0 out of 5	N/A	\$0	
Distribution Mains	P-2710	WAR	Windemere Way	8	Asbestos Cement	267	75	1.87 out of 5	\$345	\$92,115	
Distribution Mains	P-2711	WAR	Windemere Way	8	Asbestos Cement	408	75	1.87 out of 5	\$345	\$140,760	
Distribution Mains	P-2378	WAR	Windemere Way	8	Asbestos Cement	364	75	1.87 out of 5	\$345	\$125,580	
Distribution Mains	P-2380	WAR	Windemere Way	8	Asbestos Cement	660	75	1.87 out of 5	\$345	\$227,700	
Distribution Mains	P-2295	WAR	Winman Ct.	8	Ductile Iron	608	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-2194	WAR	Winnisquam Dr.	8	Asbestos Cement	331	48	1.72 out of 5	\$345	\$114,195	
Distribution Mains	P-2199	WAR	Winnisquam Dr.	8	Asbestos Cement	306	48	1.72 out of 5	\$345	\$105,570	
Distribution Mains	P-2200	WAR	Winnisquam Dr.	8	Asbestos Cement	141	48	1.72 out of 5	\$345	\$48,645	
Distribution Mains	P-2215	WAR	Winnisquam Dr.	8	Asbestos Cement	245	48	1.72 out of 5	\$345	\$84,525	
Distribution Mains	P-2216	WAR	Winnisquam Dr.	8	Asbestos Cement	427	48	1.72 out of 5	\$345	\$147,315	
Distribution Mains	P-2417	WAR	Wolverstone Rd.	6	PVC	998	39	1.15 out of 5	\$345	\$344,310	
Distribution Mains	P-2063	WAR	Zinnia St.	8	Asbestos Cement	256	37	1.58 out of 5	\$345	\$88,320	
Distribution Mains	P-2068	WAR	Zinnia St.	8	Asbestos Cement	404	37	1.58 out of 5	\$345	\$139,380	
Distribution Mains	P-2071	WAR	Zinnia St.	8	Asbestos Cement	358	37	1.58 out of 5	\$345	\$123,510	
Distribution Mains	P-3008	WG	Bailey Dr.	8	Asbestos Cement	102	43	1.72 out of 5	\$345	\$35,190	
Distribution Mains	P-3009	WG	Bailey Dr.	8	Asbestos Cement	1,205	43	1.72 out of 5	\$345	\$415,725	
Distribution Mains	P-3085	WG	Buck Hollow Dr.	8	Ductile Iron	350	10	0 out of 5	N/A	\$0	
Distribution Mains	P-3086	WG	Buck Hollow Dr.	8	Ductile Iron	810	10	0 out of 5	N/A	\$0	
Distribution Mains	P-3139	WG	Buck Hollow Dr.	8	Ductile Iron	833	10	0 out of 5	N/A	\$0	
Distribution Mains	P-3027	WG	Cambio Ct.	8	Ductile Iron	542	17	0 out of 5	N/A	\$0	
Transmission Mains	P-3054	WG	Carrs Pond Rd.	20	Ductile Iron	926	13	0 out of 5	N/A	\$0	
Transmission Mains	P-3056	WG	Carrs Pond Rd.	20	Ductile Iron	1,659	13	0 out of 5	N/A	\$0	
Transmission Mains	P-3080	WG	Carrs Pond Rd.	20	Ductile Iron	2,958	13	0 out of 5	N/A	\$0	
Transmission Mains	P-3055	WG	Carrs Pond Rd. Tank	16	Ductile Iron	549	13	0 out of 5	N/A	\$0	
Transmission Mains	P-3137	WG	Carrs Pond Rd. Tank	12	Ductile Iron	34	13	0 out of 5	N/A	\$0	
Distribution Mains	P-3014	WG	Cheyene Tr.	6	Asbestos Cement	548	43	2.43 out of 5	\$345	\$189,060	
Distribution Mains	P-3020	WG	Clubhouse Rd.	6	Asbestos Cement	614	43	2.43 out of 5	\$345	\$211,830	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-3022	WG	Clubhouse Rd.	6	Asbestos Cement	1,068	43	2.43 out of 5	\$345	\$368,460	
Distribution Mains	P-3023	WG	Clubhouse Rd.	6	Asbestos Cement	1,077	43	2.43 out of 5	\$345	\$371,565	
Distribution Mains	P-3082	WG	Deer Run Dr.	8	Ductile Iron	620	10	0 out of 5	N/A	\$0	
Distribution Mains	P-3083	WG	Deer Run Dr.	8	Ductile Iron	920	10	0 out of 5	N/A	\$0	
Distribution Mains	P-3087	WG	Deer Run Dr.	8	Ductile Iron	500	10	0 out of 5	N/A	\$0	
Transmission Mains	P-3053	WG	Division Rd.	16	Ductile Iron	952	13	0 out of 5	N/A	\$0	
Transmission Mains	P-3057	WG	Division Rd.	20	Ductile Iron	2,315	13	0 out of 5	N/A	\$0	
Transmission Mains	P-3059	WG	Division Rd.	20	Ductile Iron	3,148	13	0 out of 5	N/A	\$0	
Transmission Mains	P-3101	WG	Division Rd.	16	Ductile Iron	1,348	13	0 out of 5	N/A	\$0	
Transmission Mains	P-3133	WG	Division Rd.	20	Ductile Iron	1,148	13	0 out of 5	N/A	\$0	
Transmission Mains	P-3135	WG	Division Rd.	16	Ductile Iron	1,259	13	0 out of 5	N/A	\$0	
Distribution Mains	P-3138	WG	Doe Pl.	8	Ductile Iron	449	10	0 out of 5	N/A	\$0	
Transmission Mains	P-3047	WG	Hopkins Hill Rd.	16	Ductile Iron	968	26	0.15 out of 5	N/A	\$0	
Transmission Mains	P-3049	WG	Hopkins Hill Rd.	12	Ductile Iron	1,229	25	0.15 out of 5	N/A	\$0	
Transmission Mains	P-3130	WG	Hopkins Hill Rd.	16	Ductile Iron	125	26	0.15 out of 5	N/A	\$0	
Transmission Mains	P-3046	WG	Hopkins Hill Rd.	20	Ductile Iron	2,083	13	0 out of 5	N/A	\$0	
Transmission Mains	P-3048	WG	Hopkins Hill Rd.	20	Ductile Iron	599	13	0 out of 5	N/A	\$0	
Transmission Mains	P-3058	WG	Hopkins Hill Rd.	20	Ductile Iron	1,507	13	0 out of 5	N/A	\$0	
Transmission Mains	P-3110	WG	Hopkins Hill Rd.	20	Ductile Iron	516	13	0 out of 5	N/A	\$0	
Transmission Mains	P-3129	WG	Hopkins Hill Rd.	20	Ductile Iron	45	13	0 out of 5	N/A	\$0	
Transmission Mains	P-3131	WG	Hopkins Hill Rd.	12	Ductile Iron	48	13	0 out of 5	N/A	\$0	
Distribution Mains	P-3031	WG	Lake Dr.	8	Asbestos Cement	981	43	1.72 out of 5	\$345	\$338,445	
Distribution Mains	P-3026	WG	Lake Dr.	8	Ductile Iron	643	17	0 out of 5	N/A	\$0	
Distribution Mains	P-3028	WG	Lake Dr.	8	Ductile Iron	2,760	17	0 out of 5	N/A	\$0	
Distribution Mains	P-3025	WG	MacCue Point Rd.	8	Ductile Iron	272	17	0 out of 5	N/A	\$0	
Transmission Mains	P-3006	WG	Mishnock Rd.	12	Asbestos Cement	335	44	1.72 out of 5	\$345	\$115,575	
Transmission Mains	P-3010	WG	Mishnock Rd.	12	Asbestos Cement	1,363	44	1.72 out of 5	\$345	\$470,235	
Transmission Mains	P-3011	WG	Mishnock Rd.	12	Asbestos Cement	1,447	44	1.72 out of 5	\$345	\$499,215	
Transmission Mains	P-3033	WG	Mishnock Rd.	12	Asbestos Cement	636	44	1.72 out of 5	\$345	\$219,420	
Transmission Mains	P-3034	WG	Mishnock Rd.	12	Asbestos Cement	665	44	1.72 out of 5	\$345	\$229,425	
Transmission Mains	P-3036	WG	Mishnock Rd.	12	Asbestos Cement	1,116	44	1.72 out of 5	\$345	\$385,020	
Transmission Mains	P-3060	WG	Mishnock Rd.	12	Asbestos Cement	1,901	44	1.72 out of 5	\$345	\$655,845	
Transmission Mains	P-3061	WG	Mishnock Rd.	12	Asbestos Cement	99	44	1.72 out of 5	\$345	\$34,155	
Transmission Mains	P-3005	WG	Mishnock Rd.	12	Ductile Iron	1,277	25	0.15 out of 5	N/A	\$0	
Distribution Mains	P-3012	WG	Mohawk Tr.	8	Asbestos Cement	409	43	1.72 out of 5	\$345	\$141,105	
Distribution Mains	P-3016	WG	Mohawk Tr.	8	Asbestos Cement	227	43	1.72 out of 5	\$345	\$78,315	
Distribution Mains	P-3017	WG	Mohawk Tr.	8	Asbestos Cement	99	43	1.72 out of 5	\$345	\$34,155	
Distribution Mains	P-3018	WG	Mohawk Tr.	8	Asbestos Cement	173	43	1.72 out of 5	\$345	\$59,685	
Distribution Mains	P-3021	WG	Mohawk Tr.	8	Asbestos Cement	530	43	1.72 out of 5	\$345	\$182,850	
Transmission Mains	P-3136	WG	Moosehorn Rd.	16	Ductile Iron	38	13	0 out of 5	N/A	\$0	
Transmission Mains	P-3134	WG	New London Tpk.	16	Ductile Iron	127	13	0 out of 5	N/A	\$0	
Distribution Mains	P-3001	WG	Nichole Ln.	8	Asbestos Cement	790	33	1.58 out of 5	\$345	\$272,550	
Distribution Mains	P-3002	WG	Nichole Ln.	8	Asbestos Cement	266	33	1.58 out of 5	\$345	\$91,770	
Distribution Mains	P-3003	WG	Nichole Ln.	8	Asbestos Cement	252	33	1.58 out of 5	\$345	\$86,940	
Distribution Mains	P-3004	WG	Nichole Ln. Easement	8	Asbestos Cement	535	33	1.58 out of 5	\$345	\$184,575	
Distribution Mains	P-3038	WG	Nooseneck Hill Rd.	8	Asbestos Cement	998	49	1.72 out of 5	\$345	\$344,310	
Distribution Mains	P-3040	WG	Nooseneck Hill Rd.	8	Asbestos Cement	380	49	1.72 out of 5	\$345	\$131,100	
Distribution Mains	P-3042	WG	Nooseneck Hill Rd.	8	Asbestos Cement	661	49	1.72 out of 5	\$345	\$228,045	
Distribution Mains	P-3044	WG	Nooseneck Hill Rd.	8	Asbestos Cement	96	49	1.72 out of 5	\$345	\$33,120	
Transmission Mains	P-3062	WG	Nooseneck Hill Rd.	12	Asbestos Cement	892	49	1.72 out of 5	\$345	\$307,740	
Distribution Mains	P-3024	WG	Old Hickory Rd.	8	Ductile Iron	1,629	17	0 out of 5	N/A	\$0	
Distribution Mains	P-3029	WG	Pine Tree Ln.	8	Asbestos Cement	887	43	1.72 out of 5	\$345	\$306,015	
Distribution Mains	P-3032	WG	Pine Tree Ln.	8	Asbestos Cement	928	43	1.72 out of 5	\$345	\$320,160	
Distribution Mains	P-3000	WG	Pinehill Rd.	8	Ductile Iron	174	19	0 out of 5	N/A	\$0	
Distribution Mains	P-3030	WG	Pond View Ct.	6	Asbestos Cement	713	38	2.29 out of 5	\$345	\$245,985	
Distribution Mains	P-3035	WG	Ragnell Rd.	6	Asbestos Cement	266	38	2.29 out of 5	\$345	\$91,770	
Distribution Mains	P-3063	WG	Roland Dr.	8	Asbestos Cement	216	43	1.72 out of 5	\$345	\$74,520	
Distribution Mains	P-3064	WG	Roland Dr.	8	Asbestos Cement	1,606	43	1.72 out of 5	\$345	\$554,070	
Distribution Mains	P-3013	WG	Seminole Tr.	8	Asbestos Cement	331	43	1.72 out of 5	\$345	\$114,195	
Distribution Mains	P-3015	WG	Seminole Tr.	8	Asbestos Cement	1,058	43	1.72 out of 5	\$345	\$365,010	
Transmission Mains	P-3051	WG	Technology Park Tank	16	Ductile Iron	203	26	0.15 out of 5	N/A	\$0	
Transmission Mains	P-3065	WG	Technology Park Tank	16	Ductile Iron	313	26	0.15 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-3050	WG	Technology Way	16	Ductile Iron	2,248	26	0.15 out of 5	N/A	\$0	
Transmission Mains	P-3100	WG	Technology Way	16	Ductile Iron	1,826	19	0 out of 5	N/A	\$0	
Distribution Mains	P-3084	WG	Tiffany Ln.	8	Ductile Iron	425	10	0 out of 5	N/A	\$0	
Distribution Mains	P-3041	WG	Valerie Dr.	8	Asbestos Cement	624	45	1.72 out of 5	\$345	\$215,280	
Transmission Mains	P-3052	WG	Welgen - 95 Easement	16	Ductile Iron	5,117	19	0 out of 5	N/A	\$0	
Transmission Mains	P-3132	WG	Welgen-95 Easement	16	Ductile Iron	1,246	26	0.15 out of 5	N/A	\$0	
Distribution Mains	P-1830	WW	Aberdeen St.	6	Cast iron	339	92	2.43 out of 5	\$345	\$116,955	
Distribution Mains	P-971	WW	Aberdeen St.	6	Cast iron	776	92	2.43 out of 5	\$345	\$267,720	
Distribution Mains	P-1829	WW	Aberdeen St.	6	Ductile Iron	22	5	0.71 out of 5	\$345	\$7,590	
Distribution Mains	P-1831	WW	Aberdeen St.	6	Ductile Iron	32	5	0.71 out of 5	\$345	\$11,040	
Distribution Mains	P-1677	WW	Aberdeen St.	8	Ductile Iron	342	5	0 out of 5	N/A	\$0	
Transmission Mains	P-1828	WW	Aberdeen St.	12	Ductile Iron	24	5	0 out of 5	N/A	\$0	
Transmission Mains	P-970	WW	Aberdeen St.	12	Ductile Iron	128	7	0 out of 5	N/A	\$0	
Distribution Mains	P-1456	WW	Acorn La.	8	Asbestos Cement	79	41	1.72 out of 5	\$345	\$27,255	
Distribution Mains	P-1457	WW	Acorn La.	8	Asbestos Cement	57	41	1.72 out of 5	\$345	\$19,665	
Distribution Mains	P-52	WW	Acorn Ln.	8	Asbestos Cement	347	41	1.72 out of 5	\$345	\$119,715	
Distribution Mains	P-53	WW	Acorn Ln.	8	Asbestos Cement	292	41	1.72 out of 5	\$345	\$100,740	
Distribution Mains	P-54	WW	Acorn Ln.	8	Asbestos Cement	234	41	1.72 out of 5	\$345	\$80,730	
Distribution Mains	P-55	WW	Acorn Ln.	8	Asbestos Cement	1,073	41	1.72 out of 5	\$345	\$370,185	
Transmission Mains	P-1275	WW	Acorn Ln.	12	Ductile Iron	624	14	0 out of 5	N/A	\$0	
Distribution Mains	P-1458	WW	Acorn Ln.	8	Ductile Iron	21	14	0 out of 5	N/A	\$0	
Distribution Mains	P-710	WW	Agnes St.	6	Cast iron	331	104	2.58 out of 5	\$345	\$114,195	
Distribution Mains	P-539	WW	Albion St.	6	Asbestos Cement	441	65	2.58 out of 5	\$345	\$152,145	
Distribution Mains	P-1732	WW	Alden Dr.	8	Ductile Iron	153	4	0 out of 5	N/A	\$0	
Distribution Mains	P-1733	WW	Alden Dr.	8	Ductile Iron	47	10	0 out of 5	N/A	\$0	
Distribution Mains	P-1741	WW	Alden Dr.	8	Ductile Iron	118	4	0 out of 5	N/A	\$0	
Distribution Mains	P-1743	WW	Alden Dr.	8	Ductile Iron	283	4	0 out of 5	N/A	\$0	
Distribution Mains	P-1747	WW	Alden Dr.	8	Ductile Iron	246	4	0 out of 5	N/A	\$0	
Distribution Mains	P-199	WW	Alden Dr.	8	Ductile Iron	295	4	0 out of 5	N/A	\$0	
Distribution Mains	P-201	WW	Alden Dr.	8	Ductile Iron	131	4	0 out of 5	N/A	\$0	
Distribution Mains	P-202	WW	Alden Dr.	8	Ductile Iron	154	4	0 out of 5	N/A	\$0	
Distribution Mains	P-207	WW	Alden Dr.	8	Ductile Iron	162	4	0 out of 5	N/A	\$0	
Distribution Mains	P-214	WW	Alden Dr.	8	Ductile Iron	309	4	0 out of 5	N/A	\$0	
Distribution Mains	P-219	WW	Alden Dr.	8	Ductile Iron	183	4	0 out of 5	N/A	\$0	
Distribution Mains	P-1962	WW	Aldrich St.	8	Ductile Iron	705	3	0 out of 5	N/A	\$0	
Distribution Mains	P-600	WW	Aldrich St.	8	Ductile Iron	916	3	0 out of 5	N/A	\$0	
Transmission Mains	P-836	WW	Alexander Dr.	12	Ductile Iron	435	13	0 out of 5	N/A	\$0	
Transmission Mains	P-837	WW	Alexander Dr.	12	Ductile Iron	442	13	0 out of 5	N/A	\$0	
Transmission Mains	P-1834	WW	Alpine St.	12	Ductile Iron	32	7	0 out of 5	N/A	\$0	
Transmission Mains	P-972	WW	Alpine St.	12	Ductile Iron	211	7	0 out of 5	N/A	\$0	
Transmission Mains	P-974	WW	Alpine St.	12	Ductile Iron	204	7	0 out of 5	N/A	\$0	
Transmission Mains	P-978	WW	Alpine St.	12	Ductile Iron	270	7	0 out of 5	N/A	\$0	
Transmission Mains	P-1211	WW	Ames St.	12	Ductile Iron	1,167	4	0 out of 5	N/A	\$0	
Transmission Mains	P-1228	WW	Ames St.	16	Ductile Iron	491	7	0 out of 5	N/A	\$0	
Transmission Mains	P-1612	WW	Ames St.	12	Ductile Iron	175	5	0 out of 5	N/A	\$0	
Transmission Mains	P-1924	WW	Ames St.	12	Ductile Iron	25	5	0 out of 5	N/A	\$0	
Transmission Mains	P-1929	WW	Ames St.	12	Ductile Iron	542	5	0 out of 5	N/A	\$0	
Distribution Mains	P-102	WW	Anderson Ave.	6	Asbestos Cement	221	73	2.58 out of 5	\$345	\$76,245	
Distribution Mains	P-82	WW	Anderson Ave.	6	Asbestos Cement	183	73	2.58 out of 5	\$345	\$63,135	
Distribution Mains	P-715	WW	Andrew Ave.	2	Galvanized iron	350	84	4.15 out of 5	\$345	\$120,750	
Distribution Mains	P-693	WW	Andrew Ave.	2	Galvanized iron	861	104	3.59 out of 5	\$345	\$297,045	
Distribution Mains	P-1951	WW	Andrew Ave.	6	Cast iron	1,250	84	3.14 out of 5	\$345	\$431,250	
Distribution Mains	P-1947	WW	Andrew Ave.	6	Cast iron	307	128	2.58 out of 5	\$345	\$105,915	
Distribution Mains	P-1948	WW	Andrew Ave.	6	Cast iron	156	128	2.58 out of 5	\$345	\$53,820	
Distribution Mains	P-691	WW	Andrew Ave.	6	Cast iron	309	128	2.58 out of 5	\$345	\$106,605	
Distribution Mains	P-937	WW	Angell St.	2	Galvanized iron	319	86	4.15 out of 5	\$345	\$110,055	
Distribution Mains	P-936	WW	Angell St.	6	Asbestos Cement	483	37	3 out of 5	\$345	\$166,635	
Distribution Mains	P-1852	WW	Angell St. Easement	2	Galvanized iron	158	86	3.44 out of 5	\$345	\$54,510	
Distribution Mains	P-1853	WW	Angell St. Easement	2	Galvanized iron	239	86	3.44 out of 5	\$345	\$82,455	
Distribution Mains	P-1945	WW	April Ct.	8	Ductile Iron	220	8	0 out of 5	N/A	\$0	
Distribution Mains	P-1511	WW	Arcadia Rd.	8	Ductile Iron	250	8	0 out of 5	N/A	\$0	
Distribution Mains	P-1512	WW	Arcadia Rd.	8	Ductile Iron	250	8	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-1046	WW	Archambault Ave.	6	Cast iron	331	127	2.58 out of 5	\$345	\$114,195	
Transmission Mains	P-726	WW	Archambault Ave.	12	Asbestos Cement	409	73	2.58 out of 5	\$345	\$141,105	
Transmission Mains	P-1049	WW	Archambault Ave.	12	Asbestos Cement	438	73	1.87 out of 5	\$345	\$151,110	
Transmission Mains	P-1050	WW	Archambault Ave.	12	Asbestos Cement	132	73	1.87 out of 5	\$345	\$45,540	
Transmission Mains	P-1314	WW	Archambault Ave.	12	Asbestos Cement	153	70	1.87 out of 5	\$345	\$52,785	
Transmission Mains	P-1338	WW	Archambault Ave.	12	Asbestos Cement	305	70	1.87 out of 5	\$345	\$105,225	
Transmission Mains	P-1624	WW	Archambault Ave.	12	Asbestos Cement	316	73	1.87 out of 5	\$345	\$109,020	
Transmission Mains	P-1675	WW	Archambault Ave.	12	Asbestos Cement	372	73	1.87 out of 5	\$345	\$128,340	
Transmission Mains	P-1979	WW	Archambault Ave.	12	Asbestos Cement	535	73	1.87 out of 5	\$345	\$184,575	
Transmission Mains	P-746	WW	Archambault Ave.	12	Asbestos Cement	187	73	1.87 out of 5	\$345	\$64,515	
Distribution Mains	P-1388	WW	Arrow Ct.	6	Ductile Iron	210	23	0.86 out of 5	\$345	\$72,450	
Distribution Mains	P-579	WW	Arthur St.	2	Galvanized iron	580	79	3.3 out of 5	\$345	\$200,100	
Distribution Mains	P-562	WW	Arthur St.	6	Asbestos Cement	492	74	2.58 out of 5	\$345	\$169,740	
Distribution Mains	P-571	WW	Arthur St.	6	Asbestos Cement	286	74	2.58 out of 5	\$345	\$98,670	
Distribution Mains	P-543	WW	Ashton St.	6	PVC	348	30	1.15 out of 5	\$345	\$120,060	
Distribution Mains	P-225	WW	Aster St.	6	Asbestos Cement	594	41	2.43 out of 5	\$345	\$204,930	IFR 2015A
Distribution Mains	P-226	WW	Aster St.	6	Asbestos Cement	259	41	2.43 out of 5	\$345	\$89,355	IFR 2015A
Distribution Mains	P-433	WW	Atlantic Ave.	6	Asbestos Cement	548	48	2.43 out of 5	\$345	\$189,060	
Distribution Mains	P-434	WW	Atlantic Ave.	6	Asbestos Cement	443	48	2.43 out of 5	\$345	\$152,835	
Distribution Mains	P-1840	WW	Atwood St.	6	Cast iron	243	129	3.29 out of 5	\$345	\$83,835	
Distribution Mains	P-973	WW	Atwood St.	6	Asbestos Cement	440	37	2.29 out of 5	\$345	\$151,800	
Distribution Mains	P-1833	WW	Atwood St.	6	Ductile Iron	24	5	0.71 out of 5	\$345	\$8,280	
Distribution Mains	P-1832	WW	Atwood St.	8	Ductile Iron	19	5	0 out of 5	N/A	\$0	
Distribution Mains	P-1755	WW	Auburn St.	8	Ductile Iron	241	1	0 out of 5	N/A	\$0	
Distribution Mains	P-282	WW	Auburn St.	8	Ductile Iron	187	1	0 out of 5	N/A	\$0	
Distribution Mains	P-449	WW	Audrey Dr.	6	Asbestos Cement	485	36	2.29 out of 5	\$345	\$167,325	
Distribution Mains	P-296	WW	Babcock St.	8	Asbestos Cement	285	47	1.72 out of 5	\$345	\$98,325	
Distribution Mains	P-298	WW	Babcock St.	8	Asbestos Cement	209	47	1.72 out of 5	\$345	\$72,105	
Distribution Mains	P-300	WW	Babcock St.	8	Asbestos Cement	253	47	1.72 out of 5	\$345	\$87,285	
Distribution Mains	P-1489	WW	Baker St.	2	Galvanized iron	175	114	3.59 out of 5	\$345	\$60,375	
Distribution Mains	P-681	WW	Baker St.	2	Galvanized iron	20	114	3.59 out of 5	\$345	\$6,900	
Distribution Mains	P-1488	WW	Baker St.	4	Cast iron	200	114	3.3 out of 5	\$345	\$69,000	
Distribution Mains	P-275	WW	Ball Ave.	8	Ductile Iron	522	1	0 out of 5	N/A	\$0	
Distribution Mains	P-1054	WW	Bank St.	8	Ductile Iron	244	3	0 out of 5	N/A	\$0	
Distribution Mains	P-1981	WW	Bank St.	8	Ductile Iron	98	3	0 out of 5	N/A	\$0	
Distribution Mains	P-250	WW	Barbers Ct.	6	Ductile Iron	283	14	0.71 out of 5	\$345	\$97,635	
Distribution Mains	P-734	WW	Barnes St.	8	Cast iron	146	78	2.29 out of 5	\$345	\$50,370	
Distribution Mains	P-735	WW	Barnes St.	8	Cast iron	92	78	2.29 out of 5	\$345	\$31,740	
Distribution Mains	P-744	WW	Barnes St.	8	Cast iron	263	78	2.29 out of 5	\$345	\$90,735	
Distribution Mains	P-732	WW	Barnes St.	8	Cast iron	97	78	1.58 out of 5	\$345	\$33,465	
Distribution Mains	P-598	WW	Barnold St.	8	Ductile Iron	599	3	0 out of 5	N/A	\$0	
Distribution Mains	P-624	WW	Barnold St.	8	Ductile Iron	157	3	0 out of 5	N/A	\$0	
Distribution Mains	P-504	WW	Bayberry Dr.	6	Asbestos Cement	740	50	2.43 out of 5	\$345	\$255,300	
Distribution Mains	P-698	WW	Beauchene St.	6	Cast iron	241	126	2.58 out of 5	\$345	\$83,145	
Distribution Mains	P-229	WW	Begonia St.	6	Asbestos Cement	235	36	2.29 out of 5	\$345	\$81,075	IFR 2015A
Distribution Mains	P-405	WW	Bel Air Ave.	6	Asbestos Cement	265	38	2.29 out of 5	\$345	\$91,425	IFR 2014B
Distribution Mains	P-575	WW	Bell St.	6	Asbestos Cement	487	39	2.29 out of 5	\$345	\$168,015	
Distribution Mains	P-541	WW	Berkeley St.	2	PVC	307	30	1.87 out of 5	\$345	\$105,915	
Distribution Mains	P-938	WW	Bettez St.	4	Cast iron	809	129	3.3 out of 5	\$345	\$279,105	
Distribution Mains	P-141	WW	Birchwood Ln.	8	Asbestos Cement	357	45	1.72 out of 5	\$345	\$123,165	
Distribution Mains	P-143	WW	Birchwood Ln.	8	Asbestos Cement	158	45	1.72 out of 5	\$345	\$54,510	
Distribution Mains	P-373	WW	Bishop St.	6	Asbestos Cement	257	74	2.58 out of 5	\$345	\$88,665	IFR 2014B
Distribution Mains	P-1956	WW	Blanchard St.	1	Copper	99	24	2.15 out of 5	\$345	\$34,155	
Distribution Mains	P-578	WW	Bleach Ave.	6	Cast iron	243	78	2.29 out of 5	\$345	\$83,835	
Distribution Mains	P-1754	WW	Blossom St.	8	Ductile Iron	267	1	0 out of 5	N/A	\$0	
Distribution Mains	P-280	WW	Blossom St.	8	Ductile Iron	196	1	0 out of 5	N/A	\$0	
Distribution Mains	P-281	WW	Blossom St.	8	Ductile Iron	235	1	0 out of 5	N/A	\$0	
Distribution Mains	P-283	WW	Blossom St.	8	Ductile Iron	421	1	0 out of 5	N/A	\$0	
Distribution Mains	P-345	WW	Border St.	4	Cast iron	373	129	3.3 out of 5	\$345	\$128,685	IFR 2015B
Distribution Mains	P-347	WW	Border St.	6	Asbestos Cement	749	64	2.58 out of 5	\$345	\$258,405	IFR 2015B
Distribution Mains	P-351	WW	Border St.	6	Asbestos Cement	632	64	2.58 out of 5	\$345	\$218,040	IFR 2015B
Distribution Mains	P-352	WW	Border St.	6	Asbestos Cement	387	64	2.58 out of 5	\$345	\$133,515	IFR 2015B

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-763	WW	Bouchard St.	6	Asbestos Cement	189	47	2.43 out of 5	\$345	\$65,205	
Distribution Mains	P-764	WW	Bouchard St.	6	Asbestos Cement	234	47	2.43 out of 5	\$345	\$80,730	
Distribution Mains	P-522	WW	Boucher St.	6	Asbestos Cement	428	46	2.43 out of 5	\$345	\$147,660	
Distribution Mains	P-523	WW	Boucher St.	6	Asbestos Cement	217	46	2.43 out of 5	\$345	\$74,865	
Transmission Mains	P-265	WW	Bowen Ct.	12	Ductile Iron	106	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-1765	WW	Bowen Ct.	6	Ductile Iron	173	86	0 out of 5	N/A	\$0	
Distribution Mains	P-1661	WW	Bradford Ct.	6	Asbestos Cement	225	39	3 out of 5	\$345	\$77,625	
Distribution Mains	P-1660	WW	Bradford Ct.	6	Asbestos Cement	414	39	2.29 out of 5	\$345	\$142,830	
Distribution Mains	P-1287	WW	Bradley Ct.	6	Cast iron	275	128	2.58 out of 5	\$345	\$94,875	
Distribution Mains	P-59	WW	Bramble Dr.	8	Asbestos Cement	1,172	41	1.72 out of 5	\$345	\$404,340	
Distribution Mains	P-1371	WW	Bratt Ln.	8	Asbestos Cement	170	39	1.58 out of 5	\$345	\$58,650	
Distribution Mains	P-1375	WW	Bratt Ln.	8	Asbestos Cement	861	39	1.58 out of 5	\$345	\$297,045	
Distribution Mains	P-1376	WW	Bratt Ln.	8	Asbestos Cement	192	39	1.58 out of 5	\$345	\$66,240	
Transmission Mains	P-1370	WW	Bratt Ln.	12	Ductile Iron	105	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1372	WW	Bratt Ln.	12	Ductile Iron	1,089	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1373	WW	Bratt Ln.	12	Ductile Iron	168	14	0 out of 5	N/A	\$0	
Distribution Mains	P-1374	WW	Bratt Ln.	8	Ductile Iron	69	14	0 out of 5	N/A	\$0	
Distribution Mains	P-278	WW	Brayton Ave.	8	Ductile Iron	880	13	0 out of 5	N/A	\$0	
Distribution Mains	P-1010	WW	Brayton St.	4	Cast iron	435	129	3.3 out of 5	\$345	\$150,075	
Distribution Mains	P-1011	WW	Brayton St.	4	Cast iron	269	129	3.3 out of 5	\$345	\$92,805	
Distribution Mains	P-548	WW	Brewster Ave.	6	Cast iron	198	104	2.58 out of 5	\$345	\$68,310	
Distribution Mains	P-142	WW	Brichwood Ln.	8	Asbestos Cement	439	45	2.43 out of 5	\$345	\$151,455	
Distribution Mains	P-1614	WW	Bridal Ave.	6	Cast iron	457	92	2.43 out of 5	\$345	\$157,665	
Distribution Mains	P-1615	WW	Bridal Ave.	6	Cast iron	308	92	2.43 out of 5	\$345	\$106,260	
Distribution Mains	P-1616	WW	Bridal Ave.	6	Cast iron	109	92	2.43 out of 5	\$345	\$37,605	
Distribution Mains	P-643	WW	Bridal Ave.	6	Cast iron	138	92	2.43 out of 5	\$345	\$47,610	
Distribution Mains	P-645	WW	Bridal Ave.	6	Cast iron	132	92	2.43 out of 5	\$345	\$45,540	
Distribution Mains	P-997	WW	Bridge St.	4	Cast iron	947	79	3.01 out of 5	\$345	\$326,715	
Distribution Mains	P-1002	WW	Bridge St.	6	Cast iron	512	79	2.29 out of 5	\$345	\$176,640	
Distribution Mains	P-1003	WW	Bridge St.	6	Cast iron	111	79	2.29 out of 5	\$345	\$38,295	
Distribution Mains	P-1017	WW	Bridge St.	6	Cast iron	199	79	2.29 out of 5	\$345	\$68,655	
Distribution Mains	P-1192	WW	Brisas Dr.	6	Asbestos Cement	172	44	2.43 out of 5	\$345	\$59,340	
Transmission Mains	P-1248	WW	Broad St.	12	Ductile Iron	171	7	0 out of 5	N/A	\$0	
Transmission Mains	P-1910	WW	Broad St.	12	Ductile Iron	600	7	0 out of 5	N/A	\$0	
Distribution Mains	P-942	WW	Brook St.	6	Asbestos Cement	192	63	2.58 out of 5	\$345	\$66,240	
Distribution Mains	P-943	WW	Brook St.	6	Asbestos Cement	221	63	2.58 out of 5	\$345	\$76,245	
Distribution Mains	P-1817	WW	Brook St.	2	Copper	218	22	2.15 out of 5	\$345	\$75,210	
Distribution Mains	P-948	WW	Brook St.	6	Ductile Iron	389	22	0.86 out of 5	\$345	\$134,205	
Distribution Mains	P-1816	WW	Brook St.	8	Ductile Iron	23	5	0 out of 5	N/A	\$0	
Distribution Mains	P-203	WW	Brookdale Dr.	6	Asbestos Cement	786	57	2.43 out of 5	\$345	\$271,170	
Distribution Mains	P-204	WW	Brookdale Dr.	8	Asbestos Cement	234	37	1.58 out of 5	\$345	\$80,730	
Distribution Mains	P-848	WW	Brookfield Dr.	6	Asbestos Cement	215	42	2.43 out of 5	\$345	\$74,175	
Distribution Mains	P-1792	WW	Brookfield Dr.	6	Ductile Iron	58	17	0.71 out of 5	\$345	\$20,010	
Distribution Mains	P-1793	WW	Brookfield Sr.	1	Copper	121	59	2.29 out of 5	\$345	\$41,745	
Distribution Mains	P-653	WW	Brookside Ave.	8	Cast iron	735	129	1.87 out of 5	\$345	\$253,575	
Distribution Mains	P-655	WW	Brookside Ave.	8	Cast iron	794	129	1.87 out of 5	\$345	\$273,930	
Distribution Mains	P-664	WW	Brookside Ave.	10	Cast iron	493	129	1.87 out of 5	\$345	\$170,085	
Distribution Mains	P-672	WW	Brookside Ave.	8	Cast iron	215	92	1.72 out of 5	\$345	\$74,175	
Distribution Mains	P-701	WW	Brookside Ave.	8	Cast iron	380	92	1.72 out of 5	\$345	\$131,100	
Distribution Mains	P-702	WW	Brookside Ave.	8	Ductile Iron	309	14	0 out of 5	N/A	\$0	
Distribution Mains	P-637	WW	Bryant Pl.	8	Ductile Iron	422	3	0 out of 5	N/A	\$0	
Distribution Mains	P-520	WW	Buckley Ave.	6	Asbestos Cement	256	60	2.58 out of 5	\$345	\$88,320	
Distribution Mains	P-521	WW	Buckley Ave.	6	Asbestos Cement	242	73	2.58 out of 5	\$345	\$83,490	
Distribution Mains	P-1795	WW	Buehler Dr.	6	Ductile Iron	215	5	0.71 out of 5	\$345	\$74,175	
Distribution Mains	P-897	WW	Buehler Dr.	6	Ductile Iron	271	5	0.71 out of 5	\$345	\$93,495	
Distribution Mains	P-1794	WW	Buehler Dr.	8	Ductile Iron	24	5	0 out of 5	N/A	\$0	
Distribution Mains	P-898	WW	Buehler Dr.	8	Ductile Iron	46	5	0 out of 5	N/A	\$0	
Distribution Mains	P-1787	WW	Burlingame Rd.	6	PVC	18	33	1.15 out of 5	\$345	\$6,210	
Distribution Mains	P-1786	WW	Burlingame Rd.	8	PVC	1,458	33	0.44 out of 5	\$345	\$503,010	
Distribution Mains	P-868	WW	Burlingame Rd.	8	PVC	205	33	0.44 out of 5	\$345	\$70,725	
Distribution Mains	P-1759	WW	Burns St.	8	Ductile Iron	377	1	0 out of 5	N/A	\$0	
Distribution Mains	P-1159	WW	Campbell St.	6	Asbestos Cement	117	62	2.58 out of 5	\$345	\$40,365	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-1161	WW	Campbell St.	6	Asbestos Cement	1,145	62	2.58 out of 5	\$345	\$395,025	
Distribution Mains	P-297	WW	Cantara St.	6	Asbestos Cement	328	47	2.43 out of 5	\$345	\$113,160	
Distribution Mains	P-1487	WW	Capron St.	2	Galvanized iron	260	104	4.3 out of 5	\$345	\$89,700	
Distribution Mains	P-1486	WW	Capron St.	4	Cast iron	367	104	3.3 out of 5	\$345	\$126,615	
Distribution Mains	P-437	WW	Carder St.	6	PVC	491	26	1.15 out of 5	\$345	\$169,395	
Distribution Mains	P-515	WW	Carlson Cir.	6	Asbestos Cement	425	64	2.58 out of 5	\$345	\$146,625	
Distribution Mains	P-516	WW	Carlson Cir.	6	Asbestos Cement	446	64	2.58 out of 5	\$345	\$153,870	
Distribution Mains	P-529	WW	Carlson Cir.	6	Asbestos Cement	803	64	2.58 out of 5	\$345	\$277,035	
Distribution Mains	P-549	WW	Carlton Pl.	6	Asbestos Cement	445	60	3.29 out of 5	\$345	\$153,525	
Distribution Mains	P-1775	WW	Carnival Ter.	8	Ductile Iron	597	10	0 out of 5	N/A	\$0	
Distribution Mains	P-97	WW	Carolyn Dr.	8	Asbestos Cement	403	36	1.58 out of 5	\$345	\$139,035	
Distribution Mains	P-98	WW	Carolyn Dr.	8	Asbestos Cement	525	36	1.58 out of 5	\$345	\$181,125	
Distribution Mains	P-1950	WW	Carpenter Ct.	6	Cast iron	439	129	2.58 out of 5	\$345	\$151,455	
Distribution Mains	P-1	WW	Carriage Rd.	8	Asbestos Cement	252	39	1.58 out of 5	\$345	\$86,940	
Transmission Mains	P-856	WW	Carrie Ann Dr.	12	Ductile Iron	258	24	0.15 out of 5	N/A	\$0	
Transmission Mains	P-858	WW	Carrie Ann Dr.	12	Ductile Iron	128	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-864	WW	Carrie Ann Dr.	8	Ductile Iron	153	21	0.15 out of 5	N/A	\$0	
Distribution Mains	P-865	WW	Carrie Ann Dr.	8	Ductile Iron	405	21	0.15 out of 5	N/A	\$0	
Distribution Mains	P-501	WW	Cedar Dr.	6	Asbestos Cement	710	46	2.43 out of 5	\$345	\$244,950	
Distribution Mains	P-502	WW	Cedar Dr.	6	Asbestos Cement	254	46	2.43 out of 5	\$345	\$87,630	
Distribution Mains	P-1498	WW	Centerville Rd.	8	Asbestos Cement	273	55	1.72 out of 5	\$345	\$94,185	IFR 2014B
Distribution Mains	P-1499	WW	Centerville Rd.	8	Asbestos Cement	2,212	55	1.72 out of 5	\$345	\$763,140	
Distribution Mains	P-1494	WW	Centerville Rd.	8	Cast iron	309	75	1.58 out of 5	\$345	\$106,605	IFR 2014B
Distribution Mains	P-1495	WW	Centerville Rd.	8	Cast iron	252	75	1.58 out of 5	\$345	\$86,940	IFR 2014B
Distribution Mains	P-1496	WW	Centerville Rd.	8	Cast iron	283	75	1.58 out of 5	\$345	\$97,635	IFR 2014B
Distribution Mains	P-1497	WW	Centerville Rd.	8	Cast iron	422	75	1.58 out of 5	\$345	\$145,590	IFR 2014B
Distribution Mains	P-1581	WW	Centerville Rd.	8	Cast iron	473	75	1.58 out of 5	\$345	\$163,185	IFR 2014B
Distribution Mains	P-945	WW	Centracchio St.	6	PVC	299	27	1.15 out of 5	\$345	\$103,155	
Distribution Mains	P-946	WW	Centracchio St.	6	Ductile Iron	204	22	0.86 out of 5	\$345	\$70,380	
Distribution Mains	P-947	WW	Centracchio St.	6	Ductile Iron	198	22	0.86 out of 5	\$345	\$68,310	
Distribution Mains	P-1809	WW	Centracchio St.	6	Ductile Iron	24	8	0.71 out of 5	\$345	\$8,280	
Distribution Mains	P-1810	WW	Centracchio St.	6	Ductile Iron	18	8	0.71 out of 5	\$345	\$6,210	
Distribution Mains	P-1342	WW	Central St.	6	Cast iron	192	128	2.58 out of 5	\$345	\$66,240	
Distribution Mains	P-1000	WW	Central St.	8	Cast iron	61	77	1.58 out of 5	\$345	\$21,045	
Distribution Mains	P-1001	WW	Central St.	8	Cast iron	744	77	1.58 out of 5	\$345	\$256,680	
Transmission Mains	P-1341	WW	Central St.	12	Ductile Iron	102	7	0 out of 5	N/A	\$0	
Transmission Mains	P-1874	WW	Central St.	12	Ductile Iron	31	8	0 out of 5	N/A	\$0	
Distribution Mains	P-1875	WW	Central St.	8	Ductile Iron	10	7	0 out of 5	N/A	\$0	
Transmission Mains	P-1876	WW	Central St.	12	Ductile Iron	12	7	0 out of 5	N/A	\$0	
Distribution Mains	P-1106	WW	Centre St.	4	Cast iron	939	82	3.15 out of 5	\$345	\$323,955	IFR 2014B
Distribution Mains	P-30	WW	Chamber Way	6	Asbestos Cement	253	46	2.43 out of 5	\$345	\$87,285	
Distribution Mains	P-10037	WW	Church St.	4	Cast iron	725	78	3.72 out of 5	\$345	\$250,125	
Distribution Mains	P-10040	WW	Church St.	2	Galvanized iron	450	78	3.3 out of 5	\$345	\$155,250	
Distribution Mains	P-1101	WW	Church St.	4	Cast iron	87	129	3.3 out of 5	\$345	\$30,015	
Distribution Mains	P-1095	WW	Church St.	4	Cast iron	210	78	3.01 out of 5	\$345	\$72,450	
Distribution Mains	P-1102	WW	Church St.	4	Cast iron	490	78	3.01 out of 5	\$345	\$169,050	
Distribution Mains	P-1080	WW	Church St.	6	Cast iron	1,304	129	2.58 out of 5	\$345	\$449,880	
Distribution Mains	P-1081	WW	Church St.	6	Cast iron	189	78	2.29 out of 5	\$345	\$65,205	
Distribution Mains	P-1756	WW	Circle Dr.	8	Ductile Iron	90	1	0 out of 5	N/A	\$0	
Distribution Mains	P-284	WW	Circle Dr.	8	Ductile Iron	259	1	0 out of 5	N/A	\$0	
Distribution Mains	P-109	WW	Claire St.	6	Asbestos Cement	398	50	2.43 out of 5	\$345	\$137,310	
Distribution Mains	P-110	WW	Claire St.	6	Asbestos Cement	246	50	2.43 out of 5	\$345	\$84,870	
Distribution Mains	P-899	WW	Cleveland St.	6	Asbestos Cement	724	66	2.58 out of 5	\$345	\$249,780	
Distribution Mains	P-901	WW	Cleveland St.	6	Asbestos Cement	344	66	2.58 out of 5	\$345	\$118,680	
Distribution Mains	P-903	WW	Cleveland St.	6	Asbestos Cement	131	66	2.58 out of 5	\$345	\$45,195	
Distribution Mains	P-904	WW	Cleveland St.	6	Asbestos Cement	240	66	2.58 out of 5	\$345	\$82,800	
Distribution Mains	P-906	WW	Cleveland St.	6	Asbestos Cement	210	66	2.58 out of 5	\$345	\$72,450	
Distribution Mains	P-1353	WW	Clyde St.	6	Cast iron	406	128	2.58 out of 5	\$345	\$140,070	
Distribution Mains	P-1354	WW	Clyde St.	6	Cast iron	135	128	2.58 out of 5	\$345	\$46,575	
Distribution Mains	P-1861	WW	Clyde St.	6	Cast iron	103	128	2.58 out of 5	\$345	\$35,535	
Distribution Mains	P-1863	WW	Clyde St.	6	Cast iron	244	128	2.58 out of 5	\$345	\$84,180	
Distribution Mains	P-910	WW	Clyde St.	6	Cast iron	782	129	2.58 out of 5	\$345	\$269,790	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-912	WW	Clyde St.	6	Cast iron	539	128	2.58 out of 5	\$345	\$185,955	
Distribution Mains	P-921	WW	Clyde St.	6	Cast iron	773	128	2.58 out of 5	\$345	\$266,685	
Distribution Mains	P-1855	WW	Clyde St.	6	Ductile Iron	54	17	0.71 out of 5	\$345	\$18,630	
Distribution Mains	P-829	WW	Clyde St.	6	Ductile Iron	34	2	0.71 out of 5	\$345	\$11,730	
Transmission Mains	P-1358	WW	Clyde St.	12	PVC	152	34	0.44 out of 5	\$345	\$52,440	
Transmission Mains	P-1859	WW	Clyde St.	12	PVC	489	34	0.44 out of 5	\$345	\$168,705	
Transmission Mains	P-831	WW	Clyde St.	12	PVC	461	34	0.44 out of 5	\$345	\$159,045	
Distribution Mains	P-622	WW	Coaches Ct.	8	Ductile Iron	196	3	0 out of 5	N/A	\$0	
Distribution Mains	P-11	WW	Cobblestone La.	8	Ductile Iron	220	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-467	WW	Cochran St.	6	Asbestos Cement	530	59	2.43 out of 5	\$345	\$182,850	
Distribution Mains	P-468	WW	Cochran St.	6	Asbestos Cement	263	59	2.43 out of 5	\$345	\$90,735	
Distribution Mains	P-472	WW	Cochran St.	6	Asbestos Cement	1,347	59	2.43 out of 5	\$345	\$464,715	
Distribution Mains	P-1476	WW	Coit Ave.	6	Asbestos Cement	212	46	2.43 out of 5	\$345	\$73,140	
Distribution Mains	P-418	WW	Coit Ave.	6	Cast iron	65	76	2.29 out of 5	\$345	\$22,425	
Distribution Mains	P-419	WW	Coit Ave.	6	Cast iron	234	76	2.29 out of 5	\$345	\$80,730	
Distribution Mains	P-422	WW	Coit Ave.	6	Cast iron	70	76	2.29 out of 5	\$345	\$24,150	
Distribution Mains	P-423	WW	Coit Ave.	6	Cast iron	176	76	2.29 out of 5	\$345	\$60,720	
Distribution Mains	P-429	WW	Coit Ave.	6	Cast iron	242	76	2.29 out of 5	\$345	\$83,490	
Distribution Mains	P-430	WW	Coit Ave.	6	Cast iron	174	76	2.29 out of 5	\$345	\$60,030	
Distribution Mains	P-431	WW	Coit Ave.	6	Cast iron	162	76	2.29 out of 5	\$345	\$55,890	
Distribution Mains	P-432	WW	Coit Ave.	6	Cast iron	919	76	2.29 out of 5	\$345	\$317,055	
Distribution Mains	P-445	WW	Coit Ave.	6	Cast iron	222	76	2.29 out of 5	\$345	\$76,590	
Distribution Mains	P-447	WW	Coit Ave.	6	Cast iron	201	76	2.29 out of 5	\$345	\$69,345	
Distribution Mains	P-448	WW	Coit Ave.	6	Cast iron	157	76	2.29 out of 5	\$345	\$54,165	
Distribution Mains	P-451	WW	Coit Ave.	6	Cast iron	254	76	2.29 out of 5	\$345	\$87,630	
Distribution Mains	P-10021	WW	Coit Ave.	8	Asbestos Cement	242	46	1.72 out of 5	\$345	\$83,490	
Distribution Mains	P-1477	WW	Coit Ave.	8	Asbestos Cement	136	46	1.72 out of 5	\$345	\$46,920	
Distribution Mains	P-458	WW	Coit Ave.	8	Asbestos Cement	212	46	1.72 out of 5	\$345	\$73,140	
Distribution Mains	P-462	WW	Coit Ave.	8	Asbestos Cement	543	46	1.72 out of 5	\$345	\$187,335	
Distribution Mains	P-128	WW	Cold Spring Dr.	8	PVC	227	29	0.44 out of 5	\$345	\$78,315	
Distribution Mains	P-129	WW	Cold Spring Dr.	8	PVC	596	29	0.44 out of 5	\$345	\$205,620	
Distribution Mains	P-130	WW	Cold Spring Dr.	8	PVC	505	29	0.44 out of 5	\$345	\$174,225	
Distribution Mains	P-860	WW	Colleen Ln.	8	Ductile Iron	174	21	0.15 out of 5	N/A	\$0	
Distribution Mains	P-597	WW	Colonial Way	6	Asbestos Cement	874	67	3.29 out of 5	\$345	\$301,530	
Distribution Mains	P-1201	WW	Colvin St.	4	Cast iron	192	129	3.3 out of 5	\$345	\$66,240	
Distribution Mains	P-1866	WW	Colvin St.	1	Galvanized iron	162	74	3.3 out of 5	\$345	\$55,890	
Distribution Mains	P-1203	WW	Colvin St.	6	Cast iron	376	74	2.29 out of 5	\$345	\$129,720	
Distribution Mains	P-394	WW	Concord Ave.	2	Galvanized iron	247	86	3.44 out of 5	\$345	\$85,215	IFR 2014B
Distribution Mains	P-1461	WW	Cone Dr.	8	Asbestos Cement	247	41	1.72 out of 5	\$345	\$85,215	
Distribution Mains	P-1462	WW	Cone Dr.	8	Asbestos Cement	99	41	1.72 out of 5	\$345	\$34,155	
Distribution Mains	P-57	WW	Cone Dr.	8	Asbestos Cement	263	41	1.72 out of 5	\$345	\$90,735	
Distribution Mains	P-58	WW	Cone Dr.	8	Asbestos Cement	903	41	1.72 out of 5	\$345	\$311,535	
Transmission Mains	P-1459	WW	Cone Dr.	12	Ductile Iron	116	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1460	WW	Cone Dr.	12	Ductile Iron	220	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1463	WW	Cone Dr.	12	Ductile Iron	41	14	0 out of 5	N/A	\$0	
Distribution Mains	P-1864	WW	Coogan Ct.	1	Galvanized iron	243	128	3.59 out of 5	\$345	\$83,835	
Distribution Mains	P-558	WW	Cottage St.	4	Cast iron	555	104	3.3 out of 5	\$345	\$191,475	
Distribution Mains	P-477	WW	Country Dr.	6	Asbestos Cement	237	58	2.43 out of 5	\$345	\$81,765	
Distribution Mains	P-478	WW	Country Dr.	6	Asbestos Cement	762	58	2.43 out of 5	\$345	\$262,890	
Distribution Mains	P-475	WW	Country Dr.	8	Asbestos Cement	643	58	1.72 out of 5	\$345	\$221,835	
Distribution Mains	P-476	WW	Country Dr.	8	Asbestos Cement	446	58	1.72 out of 5	\$345	\$153,870	
Distribution Mains	P-483	WW	Country Dr. Easement	8	Asbestos Cement	260	58	1.72 out of 5	\$345	\$89,700	
Distribution Mains	P-1058	WW	Coutu Ct.	4	Cast iron	217	78	3.01 out of 5	\$345	\$74,865	
Distribution Mains	P-1135	WW	Cowesett Rd.	4	Cast iron	1,165	119	3.3 out of 5	\$345	\$401,925	
Distribution Mains	P-10039	WW	Cowesett Rd.	6	Cast iron	23	119	2.58 out of 5	\$345	\$7,935	
Distribution Mains	P-1079	WW	Cowesett Rd.	6	Cast iron	794	119	2.58 out of 5	\$345	\$273,930	
Distribution Mains	P-10031	WW	Cowesett Rd.	8	Asbestos Cement	186	74	1.87 out of 5	\$345	\$64,170	
Distribution Mains	P-1134	WW	Cowesett Rd.	8	Asbestos Cement	381	74	1.87 out of 5	\$345	\$131,445	
Distribution Mains	P-1474	WW	Cowesett Rd.	8	Asbestos Cement	381	74	1.87 out of 5	\$345	\$131,445	
Distribution Mains	P-464	WW	Cowesett Rd.	8	Asbestos Cement	549	74	1.87 out of 5	\$345	\$189,405	
Distribution Mains	P-465	WW	Cowesett Rd.	8	Asbestos Cement	313	74	1.87 out of 5	\$345	\$107,985	
Distribution Mains	P-498	WW	Cowesett Rd.	8	Asbestos Cement	61	74	1.87 out of 5	\$345	\$21,045	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-510	WW	Cowesett Rd.	8	Asbestos Cement	381	74	1.87 out of 5	\$345	\$131,445	
Distribution Mains	P-511	WW	Cowesett Rd.	8	Asbestos Cement	105	74	1.87 out of 5	\$345	\$36,225	
Distribution Mains	P-531	WW	Cowesett Rd.	8	Asbestos Cement	600	74	1.87 out of 5	\$345	\$207,000	
Distribution Mains	P-533	WW	Cowesett Rd.	8	Asbestos Cement	147	74	1.87 out of 5	\$345	\$50,715	
Distribution Mains	P-537	WW	Cowesett Rd.	8	Asbestos Cement	312	74	1.87 out of 5	\$345	\$107,640	
Distribution Mains	P-538	WW	Cowesett Rd.	8	Asbestos Cement	189	74	1.87 out of 5	\$345	\$65,205	
Distribution Mains	P-540	WW	Cowesett Rd.	8	Asbestos Cement	289	74	1.87 out of 5	\$345	\$99,705	
Distribution Mains	P-542	WW	Cowesett Rd.	8	Asbestos Cement	247	74	1.87 out of 5	\$345	\$85,215	
Transmission Mains	P-1169	WW	Cowesett Rd.	12	Asbestos Cement	1,558	49	1.72 out of 5	\$345	\$537,510	
Transmission Mains	P-1472	WW	Cowesett Rd.	12	Asbestos Cement	619	49	1.72 out of 5	\$345	\$213,555	
Transmission Mains	P-1473	WW	Cowesett Rd.	12	Asbestos Cement	1,019	49	1.72 out of 5	\$345	\$351,555	
Transmission Mains	P-474	WW	Cowesett Rd.	12	Asbestos Cement	543	42	1.72 out of 5	\$345	\$187,335	
Transmission Mains	P-489	WW	Cowesett Rd.	12	Asbestos Cement	712	42	1.72 out of 5	\$345	\$245,640	
Transmission Mains	P-490	WW	Cowesett Rd.	12	Asbestos Cement	144	42	1.72 out of 5	\$345	\$49,680	
Distribution Mains	P-730	WW	Crawford St.	6	Cast iron	143	78	2.29 out of 5	\$345	\$49,335	
Distribution Mains	P-1608	WW	Creamer Ave.	6	Ductile Iron	15	15	0.71 out of 5	\$345	\$5,175	
Distribution Mains	P-1310	WW	Creamer Ave.	8	Ductile Iron	321	15	0 out of 5	N/A	\$0	
Distribution Mains	P-1311	WW	Creamer Ave.	8	Ductile Iron	291	15	0 out of 5	N/A	\$0	
Distribution Mains	P-619	WW	Creighton Pl.	8	Ductile Iron	276	3	0 out of 5	N/A	\$0	
Distribution Mains	P-849	WW	Crestwood Dr.	6	Asbestos Cement	227	57	2.43 out of 5	\$345	\$78,315	
Distribution Mains	P-841	WW	Crestwood Dr.	8	PVC	503	26	0.44 out of 5	\$345	\$173,535	
Distribution Mains	P-843	WW	Crestwood Dr.	8	PVC	254	26	0.44 out of 5	\$345	\$87,630	
Distribution Mains	P-844	WW	Crestwood Dr.	8	PVC	351	26	0.44 out of 5	\$345	\$121,095	
Distribution Mains	P-846	WW	Crestwood Dr.	8	PVC	241	26	0.44 out of 5	\$345	\$83,145	
Distribution Mains	P-452	WW	Crompton Ave.	6	Asbestos Cement	782	64	2.58 out of 5	\$345	\$269,790	
Transmission Mains	P-1524	WW	Crompton Rd.	16	Ductile Iron	415	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-985	WW	Cross St.	1	Galvanized iron	275	86	3.44 out of 5	\$345	\$94,875	
Distribution Mains	P-22	WW	Crossbow La.	8	Asbestos Cement	691	41	1.72 out of 5	\$345	\$238,395	
Distribution Mains	P-25	WW	Crossbow Ln.	8	Ductile Iron	236	23	0.86 out of 5	\$345	\$81,420	
Distribution Mains	P-1939	WW	Crossbow Ln.	8	Ductile Iron	281	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-23	WW	Crossbow Ln.	8	Ductile Iron	242	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-24	WW	Crossbow Ln.	8	Ductile Iron	209	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-1464	WW	Crossbow Ln.	16	Ductile Iron	642	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1712	WW	Crossbow Ln.	16	Ductile Iron	109	14	0 out of 5	N/A	\$0	
Distribution Mains	P-656	WW	Crossen St.	4	Cast iron	412	129	3.3 out of 5	\$345	\$142,140	
Distribution Mains	P-652	WW	Crossen St.	6	Cast iron	274	129	2.58 out of 5	\$345	\$94,530	
Distribution Mains	P-159	WW	Crossland Dr.	8	Ductile Iron	244	4	0 out of 5	N/A	\$0	
Distribution Mains	P-167	WW	Crossland Dr.	8	Ductile Iron	242	4	0 out of 5	N/A	\$0	
Distribution Mains	P-1722	WW	Crossland Dr.	8	Ductile Iron	109	4	0 out of 5	N/A	\$0	
Distribution Mains	P-1724	WW	Crossland Dr.	8	Ductile Iron	235	4	0 out of 5	N/A	\$0	
Distribution Mains	P-1731	WW	Crossland Dr.	8	Ductile Iron	240	4	0 out of 5	N/A	\$0	
Distribution Mains	P-1735	WW	Crossland Dr.	8	Ductile Iron	103	4	0 out of 5	N/A	\$0	
Distribution Mains	P-218	WW	Crossland Dr.	8	Ductile Iron	247	4	0 out of 5	N/A	\$0	
Distribution Mains	P-220	WW	Crossland Dr.	8	Ductile Iron	125	4	0 out of 5	N/A	\$0	
Distribution Mains	P-236	WW	Crossland Rd.	6	Asbestos Cement	476	75	2.58 out of 5	\$345	\$164,220	
Distribution Mains	P-145	WW	Crossland Rd.	8	Ductile Iron	141	4	0 out of 5	N/A	\$0	
Distribution Mains	P-1721	WW	Crossland Rd.	8	Ductile Iron	42	4	0 out of 5	N/A	\$0	
Transmission Mains	P-76	WW	Crudale Dr.	12	Ductile Iron	1,061	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1566	WW	Crudale Rd.	12	Ductile Iron	242	14	0 out of 5	N/A	\$0	
Transmission Mains	P-71	WW	Crudale Rd.	12	Ductile Iron	195	14	0 out of 5	N/A	\$0	
Transmission Mains	P-74	WW	Crudale Rd.	12	Ductile Iron	237	14	0 out of 5	N/A	\$0	
Distribution Mains	P-1051	WW	Curson St.	4	Cast iron	284	79	3.01 out of 5	\$345	\$97,980	
Distribution Mains	P-753	WW	Curson St.	4	Cast iron	193	79	3.01 out of 5	\$345	\$66,585	
Distribution Mains	P-1052	WW	Curson St.	6	Cast iron	615	124	2.58 out of 5	\$345	\$212,175	
Distribution Mains	P-1055	WW	Curson St.	6	Cast iron	496	67	2.29 out of 5	\$345	\$171,120	
Distribution Mains	P-758	WW	Curson St.	8	Asbestos Cement	544	67	1.87 out of 5	\$345	\$187,680	
Distribution Mains	P-1291	WW	Curson St.	8	Ductile Iron	192	12	0 out of 5	N/A	\$0	
Distribution Mains	P-757	WW	Curson St.	8	Ductile Iron	199	12	0 out of 5	N/A	\$0	
Transmission Mains	P-853	WW	Cyr Ct.	12	Ductile Iron	293	13	0 out of 5	N/A	\$0	
Transmission Mains	P-1268	WW	Cyr Ct. Easement	12	Ductile Iron	435	13	0 out of 5	N/A	\$0	
Transmission Mains	P-1327	WW	Dairy Farm Rd.	12	Ductile Iron	278	11	0 out of 5	N/A	\$0	
Transmission Mains	P-1328	WW	Dairy Farm Rd.	12	Ductile Iron	78	12	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-1782	WW	Dairy Farm Rd.	12	Ductile Iron	351	11	0 out of 5	N/A	\$0	
Distribution Mains	P-227	WW	Daisy St.	6	Asbestos Cement	231	37	2.29 out of 5	\$345	\$79,695	IFR 2015A
Distribution Mains	P-228	WW	Daisy St.	6	Asbestos Cement	140	37	2.29 out of 5	\$345	\$48,300	IFR 2015A
Distribution Mains	P-1968	WW	Dale Ave.	1	Copper	326	66	2.44 out of 5	\$345	\$112,470	
Distribution Mains	P-1492	WW	Danby St.	8	Ductile Iron	166	10	0 out of 5	N/A	\$0	
Distribution Mains	P-408	WW	Davis St.	2	Copper	589	67	3.15 out of 5	\$345	\$203,205	IFR 2014B
Distribution Mains	P-1480	WW	Dawes St.	1	Copper	350	79	2.44 out of 5	\$345	\$120,750	
Distribution Mains	P-10029	WW	Dawes St.	6	PVC	192	28	1.15 out of 5	\$345	\$66,240	
Distribution Mains	P-519	WW	Dawes St.	6	PVC	483	28	1.15 out of 5	\$345	\$166,635	
Distribution Mains	P-453	WW	Deborah Ct.	6	Ductile Iron	438	24	0.86 out of 5	\$345	\$151,110	
Distribution Mains	P-185	WW	Deer Run	8	PVC	215	30	0.44 out of 5	\$345	\$74,175	
Distribution Mains	P-1145	WW	Deerfield Dr.	8	Asbestos Cement	255	42	2.43 out of 5	\$345	\$87,975	
Distribution Mains	P-1141	WW	Deerfield Dr.	8	Asbestos Cement	43	42	1.72 out of 5	\$345	\$14,835	
Distribution Mains	P-1142	WW	Deerfield Dr.	8	Asbestos Cement	617	42	1.72 out of 5	\$345	\$212,865	
Distribution Mains	P-1144	WW	Deerfield Dr.	8	Asbestos Cement	303	42	1.72 out of 5	\$345	\$104,535	
Distribution Mains	P-1146	WW	Deerfield Dr.	8	Asbestos Cement	496	42	1.72 out of 5	\$345	\$171,120	
Distribution Mains	P-1148	WW	Deerfield Dr.	8	Asbestos Cement	332	42	1.72 out of 5	\$345	\$114,540	
Transmission Mains	P-857	WW	Derrick Ct.	12	Ductile Iron	129	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-1766	WW	Diaz Ct.	8	Ductile Iron	211	1	0 out of 5	N/A	\$0	
Distribution Mains	P-1769	WW	DiMasi Ct.	8	Ductile Iron	306	1	0 out of 5	N/A	\$0	
Distribution Mains	P-1013	WW	Dinsdale Ct.	2	Galvanized iron	306	84	4.15 out of 5	\$345	\$105,570	
Distribution Mains	P-1217	WW	Douglas St.	4	Cast iron	320	65	3.01 out of 5	\$345	\$110,400	
Distribution Mains	P-1219	WW	Douglas St.	4	Cast iron	290	65	3.01 out of 5	\$345	\$100,050	
Distribution Mains	P-528	WW	Dounetos St.	6	Asbestos Cement	251	60	2.58 out of 5	\$345	\$86,595	
Distribution Mains	P-530	WW	Dounetos St.	8	Asbestos Cement	666	60	1.87 out of 5	\$345	\$229,770	
Distribution Mains	P-1930	WW	Downing Dr.	6	Asbestos Cement	273	36	2.29 out of 5	\$345	\$94,185	
Distribution Mains	P-804	WW	Downing Dr.	6	Asbestos Cement	95	36	2.29 out of 5	\$345	\$32,775	
Distribution Mains	P-1932	WW	Downing Dr. Easement	6	Asbestos Cement	132	36	2.29 out of 5	\$345	\$45,540	
Transmission Mains	P-78	WW	Draw Bridge Dr.	16	Ductile Iron	163	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-12	WW	Drawbridge Dr.	16	Ductile Iron	225	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-1378	WW	Drawbridge Dr.	16	Ductile Iron	289	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-1379	WW	Drawbridge Dr.	8	Ductile Iron	64	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-1386	WW	Drawbridge Dr.	8	Ductile Iron	292	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-1387	WW	Drawbridge Dr.	8	Ductile Iron	263	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-1530	WW	Drawbridge Dr.	16	Ductile Iron	179	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-17	WW	Drawbridge Dr.	16	Ductile Iron	307	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-1711	WW	Drawbridge Dr.	16	Ductile Iron	146	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-18	WW	Drawbridge Dr.	16	Ductile Iron	604	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-1936	WW	Drawbridge Dr.	16	Ductile Iron	30	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-1937	WW	Drawbridge Dr.	8	Ductile Iron	120	23	0.15 out of 5	N/A	\$0	
Transmission Mains	P-1938	WW	Drawbridge Dr.	16	Ductile Iron	58	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-1490	WW	Duke St.	8	Ductile Iron	389	10	0 out of 5	N/A	\$0	
Distribution Mains	P-1491	WW	Duke St.	8	Ductile Iron	102	10	0 out of 5	N/A	\$0	
Distribution Mains	P-1600	WW	Dyer St.	6	Asbestos Cement	372	40	2.43 out of 5	\$345	\$128,340	
Distribution Mains	P-1988	WW	Earl St.	4	Cast iron	373	79	3.01 out of 5	\$345	\$128,685	IFR 2015B
Distribution Mains	P-343	WW	Earl St.	4	Cast iron	366	79	3.01 out of 5	\$345	\$126,270	IFR 2015B
Distribution Mains	P-349	WW	Earl St.	4	Cast iron	391	79	3.01 out of 5	\$345	\$134,895	IFR 2015B
Distribution Mains	P-360	WW	Earl St.	4	Cast iron	199	79	3.01 out of 5	\$345	\$68,655	IFR 2015B
Distribution Mains	P-364	WW	Earl St.	4	Cast iron	296	79	3.01 out of 5	\$345	\$102,120	IFR 2015B
Distribution Mains	P-366	WW	Earl St.	4	Cast iron	969	79	3.01 out of 5	\$345	\$334,305	IFR 2015B
Distribution Mains	P-353	WW	Earl St.	6	Cast iron	567	79	2.29 out of 5	\$345	\$195,615	IFR 2015B
Distribution Mains	P-1377	WW	Easement	8	Asbestos Cement	308	39	1.58 out of 5	\$345	\$106,260	
Distribution Mains	P-1138	WW	East Greenwich Ave.	4	Cast iron	72	119	3.3 out of 5	\$345	\$24,840	
Distribution Mains	P-1139	WW	East Greenwich Ave.	4	Cast iron	651	119	3.3 out of 5	\$345	\$224,595	
Distribution Mains	P-1140	WW	East Greenwich Ave.	6	Asbestos Cement	161	66	2.58 out of 5	\$345	\$55,545	
Distribution Mains	P-1158	WW	East Greenwich Ave.	6	Asbestos Cement	316	66	2.58 out of 5	\$345	\$109,020	
Distribution Mains	P-1599	WW	East Greenwich Ave.	6	Asbestos Cement	504	66	2.58 out of 5	\$345	\$173,880	
Transmission Mains	P-1187	WW	East Greenwich Ave.	16	Asbestos Cement	162	41	1.72 out of 5	\$345	\$55,890	
Transmission Mains	P-1197	WW	East Greenwich Ave.	20	Asbestos Cement	836	45	1.72 out of 5	\$345	\$288,420	
Transmission Mains	P-1404	WW	East Greenwich Ave.	20	Asbestos Cement	2,560	45	1.72 out of 5	\$345	\$883,200	
Transmission Mains	P-1411	WW	East Greenwich Ave.	20	Asbestos Cement	499	45	1.72 out of 5	\$345	\$172,155	
Transmission Mains	P-1421	WW	East Greenwich Ave.	20	Asbestos Cement	246	45	1.72 out of 5	\$345	\$84,870	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-1428	WW	East Greenwich Ave.	20	Asbestos Cement	387	45	1.72 out of 5	\$345	\$133,515	
Transmission Mains	P-1435	WW	East Greenwich Ave.	20	Asbestos Cement	630	45	1.72 out of 5	\$345	\$217,350	
Transmission Mains	P-1436	WW	East Greenwich Ave.	20	Asbestos Cement	683	45	1.72 out of 5	\$345	\$235,635	
Distribution Mains	P-188	WW	East Greenwich Ave.	6	Ductile Iron	360	26	0.86 out of 5	\$345	\$124,200	
Transmission Mains	P-1294	WW	East Greenwich Ave.	12	PVC	471	28	0.44 out of 5	\$345	\$162,495	
Transmission Mains	P-1579	WW	East Greenwich Ave.	12	PVC	99	28	0.44 out of 5	\$345	\$34,155	
Transmission Mains	P-1687	WW	East Greenwich Ave.	12	PVC	146	28	0.44 out of 5	\$345	\$50,370	
Transmission Mains	P-1295	WW	East Greenwich Ave.	12	Ductile Iron	636	24	0.15 out of 5	N/A	\$0	
Transmission Mains	P-10005	WW	East Greenwich Ave.	12	Ductile Iron	36	14	0 out of 5	N/A	\$0	
Transmission Mains	P-10010	WW	East Greenwich Ave.	12	Ductile Iron	29	14	0 out of 5	N/A	\$0	
Distribution Mains	P-10011	WW	East Greenwich Ave.	8	Ductile Iron	26	17	0 out of 5	N/A	\$0	
Distribution Mains	P-10017	WW	East Greenwich Ave.	8	Ductile Iron	28	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1151	WW	East Greenwich Ave.	12	Ductile Iron	706	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1157	WW	East Greenwich Ave.	12	Ductile Iron	922	14	0 out of 5	N/A	\$0	
Transmission Mains	P-116	WW	East Greenwich Ave.	12	Ductile Iron	506	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1182	WW	East Greenwich Ave.	12	Ductile Iron	347	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1189	WW	East Greenwich Ave.	12	Ductile Iron	496	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1190	WW	East Greenwich Ave.	12	Ductile Iron	373	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1196	WW	East Greenwich Ave.	20	Ductile Iron	208	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1296	WW	East Greenwich Ave.	12	Ductile Iron	588	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1400	WW	East Greenwich Ave.	12	Ductile Iron	117	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1401	WW	East Greenwich Ave.	12	Ductile Iron	173	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1407	WW	East Greenwich Ave.	12	Ductile Iron	118	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1414	WW	East Greenwich Ave.	12	Ductile Iron	158	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1415	WW	East Greenwich Ave.	12	Ductile Iron	191	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1418	WW	East Greenwich Ave.	12	Ductile Iron	413	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1431	WW	East Greenwich Ave.	12	Ductile Iron	397	14	0 out of 5	N/A	\$0	
Transmission Mains	P-187	WW	East Greenwich Ave.	12	Ductile Iron	2,233	14	0 out of 5	N/A	\$0	
Transmission Mains	P-81	WW	East Greenwich Ave.	12	Ductile Iron	76	14	0 out of 5	N/A	\$0	
Transmission Mains	P-86	WW	East Greenwich Ave.	12	Ductile Iron	89	14	0 out of 5	N/A	\$0	
Transmission Mains	P-87	WW	East Greenwich Ave.	12	Ductile Iron	189	14	0 out of 5	N/A	\$0	
Transmission Mains	P-89	WW	East Greenwich Ave.	12	Ductile Iron	297	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1004	WW	East Main St.	12	Asbestos Cement	700	63	2.58 out of 5	\$345	\$241,500	
Distribution Mains	P-1350	WW	East Main St.	6	Cast iron	548	128	2.58 out of 5	\$345	\$189,060	
Distribution Mains	P-1351	WW	East Main St.	6	Cast iron	606	129	2.58 out of 5	\$345	\$209,070	
Distribution Mains	P-984	WW	East Main St.	6	Cast iron	167	128	2.58 out of 5	\$345	\$57,615	
Distribution Mains	P-986	WW	East Main St.	6	Cast iron	198	128	2.58 out of 5	\$345	\$68,310	
Distribution Mains	P-988	WW	East Main St.	6	Cast iron	309	128	2.58 out of 5	\$345	\$106,605	
Distribution Mains	P-995	WW	East Main St.	6	Cast iron	49	128	2.58 out of 5	\$345	\$16,905	
Transmission Mains	P-1005	WW	East Main St.	12	Asbestos Cement	640	63	1.87 out of 5	\$345	\$220,800	
Transmission Mains	P-1348	WW	East Main St.	12	Asbestos Cement	404	63	1.87 out of 5	\$345	\$139,380	
Transmission Mains	P-1349	WW	East Main St.	12	Asbestos Cement	100	63	1.87 out of 5	\$345	\$34,500	
Distribution Mains	P-1955	WW	East St.	6	Ductile Iron	227	24	0.86 out of 5	\$345	\$78,315	
Distribution Mains	P-699	WW	East St.	6	Ductile Iron	291	24	0.86 out of 5	\$345	\$100,395	
Distribution Mains	P-700	WW	East St.	6	Ductile Iron	644	24	0.86 out of 5	\$345	\$222,180	
Distribution Mains	P-659	WW	Eddy St.	6	Cast iron	417	129	2.58 out of 5	\$345	\$143,865	
Distribution Mains	P-660	WW	Eddy St.	6	Cast iron	489	129	2.58 out of 5	\$345	\$168,705	
Distribution Mains	P-385	WW	Edge St.	6	Ductile Iron	237	26	0.86 out of 5	\$345	\$81,765	
Distribution Mains	P-374	WW	Edith St.	6	Asbestos Cement	225	39	2.29 out of 5	\$345	\$77,625	IFR 2014B
Distribution Mains	P-111	WW	Edwards Ct.	6	Asbestos Cement	141	47	2.43 out of 5	\$345	\$48,645	
Distribution Mains	P-606	WW	Eileen Dr.	8	Ductile Iron	235	3	0 out of 5	N/A	\$0	
Distribution Mains	P-607	WW	Eileen Dr.	8	Ductile Iron	228	3	0 out of 5	N/A	\$0	
Distribution Mains	P-1854	WW	Elbow St. Easement	2	Galvanized iron	271	29	3.01 out of 5	\$345	\$93,495	
Distribution Mains	P-94	WW	Elizabeth Ct	8	Asbestos Cement	428	44	1.72 out of 5	\$345	\$147,660	
Distribution Mains	P-1024	WW	Ellison St.	2	Copper	243	74	2.44 out of 5	\$345	\$83,835	
Distribution Mains	P-1025	WW	Ellison St.	2	Copper	283	74	2.44 out of 5	\$345	\$97,635	
Distribution Mains	P-987	WW	Elm St.	1	Galvanized iron	273	86	3.44 out of 5	\$345	\$94,185	
Distribution Mains	P-1514	WW	Emerson Ct.	8	Ductile Iron	310	8	0 out of 5	N/A	\$0	
Distribution Mains	P-1515	WW	Emerson Ct.	8	Ductile Iron	150	8	0 out of 5	N/A	\$0	
Distribution Mains	P-1519	WW	Emerson Ct.	8	Ductile Iron	550	8	0 out of 5	N/A	\$0	
Distribution Mains	P-1966	WW	Emile St.	8	Ductile Iron	197	3	0 out of 5	N/A	\$0	
Transmission Mains	P-10009	WW	Energy Way	12	Ductile Iron	25	2	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-75	WW	Energy Way	12	Ductile Iron	765	14	0 out of 5	N/A	\$0	
Distribution Mains	P-16	WW	Enfield Dr.	6	Asbestos Cement	40	64	2.58 out of 5	\$345	\$13,800	
Distribution Mains	P-1718	WW	Enfield Dr.	8	Ductile Iron	565	4	0 out of 5	N/A	\$0	
Distribution Mains	P-1719	WW	Enfield Dr.	8	Ductile Iron	455	4	0 out of 5	N/A	\$0	
Distribution Mains	P-1736	WW	Enfield Dr.	8	Ductile Iron	280	4	0 out of 5	N/A	\$0	
Distribution Mains	P-196	WW	Enfield Dr.	8	Ductile Iron	148	4	0 out of 5	N/A	\$0	
Distribution Mains	P-649	WW	Epworth Ave.	4	Cast iron	265	129	3.3 out of 5	\$345	\$91,425	
Distribution Mains	P-647	WW	Epworth Ave.	6	Cast iron	205	129	2.58 out of 5	\$345	\$70,725	
Distribution Mains	P-648	WW	Epworth Ave.	6	Cast iron	581	129	2.58 out of 5	\$345	\$200,445	
Distribution Mains	P-1165	WW	Esmond St.	6	Asbestos Cement	367	64	2.58 out of 5	\$345	\$126,615	
Distribution Mains	P-1591	WW	Esmond St.	6	Asbestos Cement	314	64	2.58 out of 5	\$345	\$108,330	
Distribution Mains	P-1598	WW	Esmond St.	6	Asbestos Cement	139	64	2.58 out of 5	\$345	\$47,955	
Distribution Mains	P-399	WW	Ethel St.	6	Asbestos Cement	696	45	2.43 out of 5	\$345	\$240,120	IFR 2014B
Distribution Mains	P-10027	WW	Ethel St.	1	Copper	120	45	2.29 out of 5	\$345	\$41,400	
Distribution Mains	P-427	WW	Evelyn St.	6	Asbestos Cement	258	67	2.58 out of 5	\$345	\$89,010	
Distribution Mains	P-33	WW	Exchange Rd.	8	Asbestos Cement	288	45	1.72 out of 5	\$345	\$99,360	
Distribution Mains	P-39	WW	Exchange Rd.	8	Asbestos Cement	471	45	1.72 out of 5	\$345	\$162,495	
Distribution Mains	P-45	WW	Exchange Rd.	8	Asbestos Cement	224	45	1.72 out of 5	\$345	\$77,280	
Distribution Mains	P-1015	WW	Factory St.	6	Cast iron	208	129	2.58 out of 5	\$345	\$71,760	
Distribution Mains	P-1016	WW	Factory St.	6	Cast iron	847	129	2.58 out of 5	\$345	\$292,215	
Distribution Mains	P-329	WW	Factory St.	8	Asbestos Cement	250	74	1.87 out of 5	\$345	\$86,250	IFR 2015B
Distribution Mains	P-333	WW	Factory St.	8	Asbestos Cement	247	74	1.87 out of 5	\$345	\$85,215	IFR 2015B
Distribution Mains	P-340	WW	Factory St.	8	Asbestos Cement	453	74	1.87 out of 5	\$345	\$156,285	IFR 2015B
Distribution Mains	P-342	WW	Factory St.	8	Asbestos Cement	194	74	1.87 out of 5	\$345	\$66,930	IFR 2015B
Distribution Mains	P-346	WW	Factory St.	8	Asbestos Cement	348	74	1.87 out of 5	\$345	\$120,060	IFR 2015B
Distribution Mains	P-479	WW	Fairgreen Dr.	6	Asbestos Cement	532	58	2.43 out of 5	\$345	\$183,540	
Distribution Mains	P-480	WW	Fairgreen Dr.	6	Asbestos Cement	241	58	2.43 out of 5	\$345	\$83,145	
Distribution Mains	P-482	WW	Fairgreen Dr.	6	Asbestos Cement	409	58	2.43 out of 5	\$345	\$141,105	
Distribution Mains	P-1096	WW	Fairmont St.	6	Asbestos Cement	640	52	2.43 out of 5	\$345	\$220,800	
Distribution Mains	P-1209	WW	Fairview Ave.	6	Cast iron	272	119	2.58 out of 5	\$345	\$93,840	
Distribution Mains	P-1210	WW	Fairview Ave.	6	Cast iron	351	119	2.58 out of 5	\$345	\$121,095	
Transmission Mains	P-1213	WW	Fairview Ave.	16	Asbestos Cement	582	70	1.87 out of 5	\$345	\$200,790	
Transmission Mains	P-1258	WW	Fairview Ave.	12	Cast iron	167	119	1.87 out of 5	\$345	\$57,615	
Transmission Mains	P-1205	WW	Fairview Ave.	16	Ductile Iron	195	4	0 out of 5	N/A	\$0	
Transmission Mains	P-1207	WW	Fairview Ave.	16	Ductile Iron	215	4	0 out of 5	N/A	\$0	
Transmission Mains	P-1259	WW	Fairview Ave.	16	Ductile Iron	180	4	0 out of 5	N/A	\$0	
Transmission Mains	P-1260	WW	Fairview Ave.	16	Ductile Iron	151	4	0 out of 5	N/A	\$0	
Transmission Mains	P-1261	WW	Fairview Ave.	12	Ductile Iron	209	8	0 out of 5	N/A	\$0	
Transmission Mains	P-1611	WW	Fairview Ave.	16	Ductile Iron	535	4	0 out of 5	N/A	\$0	
Transmission Mains	P-1922	WW	Fairview Ave.	12	Ductile Iron	23	4	0 out of 5	N/A	\$0	
Transmission Mains	P-1923	WW	Fairview Ave.	12	Ductile Iron	30	4	0 out of 5	N/A	\$0	
Transmission Mains	P-1928	WW	Fairview Ave.	16	Ductile Iron	140	4	0 out of 5	N/A	\$0	
Distribution Mains	P-1150	WW	Fawn Ln.	8	Asbestos Cement	749	37	1.58 out of 5	\$345	\$258,405	
Distribution Mains	P-402	WW	Faxon St.	6	Asbestos Cement	263	45	2.43 out of 5	\$345	\$90,735	IFR 2014B
Distribution Mains	P-616	WW	Ferland Dr.	8	Ductile Iron	279	3	0 out of 5	N/A	\$0	
Distribution Mains	P-155	WW	Fernwood Dr.	8	Ductile Iron	346	4	0 out of 5	N/A	\$0	
Distribution Mains	P-1725	WW	Fernwood Dr.	8	Ductile Iron	150	4	0 out of 5	N/A	\$0	
Distribution Mains	P-1726	WW	Fernwood Dr.	8	Ductile Iron	26	10	0 out of 5	N/A	\$0	
Distribution Mains	P-1173	WW	Field Ave.	6	Asbestos Cement	803	67	2.58 out of 5	\$345	\$277,035	
Distribution Mains	P-344	WW	First St.	4	Cast iron	318	77	3.01 out of 5	\$345	\$109,710	IFR 2015B
Distribution Mains	P-251	WW	Fiume St.	8	Ductile Iron	137	1	0 out of 5	N/A	\$0	
Distribution Mains	P-252	WW	Fiume St.	8	Ductile Iron	551	1	0 out of 5	N/A	\$0	
Distribution Mains	P-253	WW	Fiume St.	8	Ductile Iron	239	1	0 out of 5	N/A	\$0	
Transmission Mains	P-1298	WW	Flanders Dr.	20	Asbestos Cement	486	45	1.72 out of 5	\$345	\$167,670	
Transmission Mains	P-88	WW	Flanders Dr.	12	Ductile Iron	461	14	0 out of 5	N/A	\$0	
Distribution Mains	P-816	WW	Flynn Ter.	4	Cast iron	292	129	3.3 out of 5	\$345	\$100,740	
Distribution Mains	P-817	WW	Flynn Ter.	6	Asbestos Cement	360	62	2.58 out of 5	\$345	\$124,200	
Distribution Mains	P-90	WW	Forest Ave.	6	Asbestos Cement	198	73	2.58 out of 5	\$345	\$68,310	
Distribution Mains	P-83	WW	Forest Ave.	2	Copper	209	73	2.44 out of 5	\$345	\$72,105	
Distribution Mains	P-292	WW	Fornelli St.	6	Asbestos Cement	546	73	2.58 out of 5	\$345	\$188,370	
Distribution Mains	P-1084	WW	Fountain St.	6	Asbestos Cement	113	45	2.43 out of 5	\$345	\$38,985	
Distribution Mains	P-1087	WW	Fountain St.	6	Asbestos Cement	564	45	2.43 out of 5	\$345	\$194,580	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-85	WW	Fox Run Dr.	6	Ductile Iron	299	24	0.86 out of 5	\$345	\$103,155	
Distribution Mains	P-10032	WW	Freemont St.	6	Asbestos Cement	346	64	2.58 out of 5	\$345	\$119,370	
Distribution Mains	P-62	WW	Friar Tuck La.	8	Asbestos Cement	230	41	2.43 out of 5	\$345	\$79,350	
Distribution Mains	P-819	WW	Fruit St.	4	Cast iron	226	129	3.3 out of 5	\$345	\$77,970	
Transmission Mains	P-1521	WW	Fusaro Ln.	12	Ductile Iron	420	1	0 out of 5	N/A	\$0	
Distribution Mains	P-274	WW	Gage St.	8	Ductile Iron	373	1	0 out of 5	N/A	\$0	
Distribution Mains	P-1047	WW	Gardner Ave.	4	Cast iron	599	127	3.3 out of 5	\$345	\$206,655	
Distribution Mains	P-748	WW	Gareau St.	8	Ductile Iron	82	6	0 out of 5	N/A	\$0	
Distribution Mains	P-902	WW	Garfield Ter.	6	Ductile Iron	221	22	0.86 out of 5	\$345	\$76,245	
Distribution Mains	P-963	WW	Garnet St.	6	Asbestos Cement	424	53	2.43 out of 5	\$345	\$146,280	
Distribution Mains	P-965	WW	Garnet St.	6	Asbestos Cement	211	53	2.43 out of 5	\$345	\$72,795	
Distribution Mains	P-1805	WW	Garnet St.	8	Ductile Iron	39	5	0 out of 5	N/A	\$0	
Distribution Mains	P-1983	WW	Gendron St.	2	Copper	281	76	2.44 out of 5	\$345	\$96,945	
Distribution Mains	P-1508	WW	Gerald St.	1.5	Copper	212	67	2.44 out of 5	\$345	\$73,140	IFR 2015B
Distribution Mains	P-1987	WW	Gerald St.	1.3	Copper	105	15	2 out of 5	\$345	\$36,225	
Distribution Mains	P-1493	WW	Gerald St.	8	Ductile Iron	190	15	0 out of 5	N/A	\$0	
Distribution Mains	P-1986	WW	Gerald St.	8	Ductile Iron	170	15	0 out of 5	N/A	\$0	
Distribution Mains	P-1560	WW	Gilcrest Cir.	8	Ductile Iron	266	13	0 out of 5	N/A	\$0	
Distribution Mains	P-867	WW	Gilcrest Cir.	8	Ductile Iron	355	13	0 out of 5	N/A	\$0	
Distribution Mains	P-868	WW	Gilcrest Cir.	8	Ductile Iron	237	13	0 out of 5	N/A	\$0	
Distribution Mains	P-869	WW	Gilcrest Cir.	8	Ductile Iron	370	13	0 out of 5	N/A	\$0	
Distribution Mains	P-870	WW	Gilcrest Cir.	8	Ductile Iron	253	13	0 out of 5	N/A	\$0	
Distribution Mains	P-871	WW	Gilcrest Dr.	8	Ductile Iron	488	13	0 out of 5	N/A	\$0	
Distribution Mains	P-435	WW	Glen Dr.	6	Asbestos Cement	492	48	2.43 out of 5	\$345	\$169,740	
Distribution Mains	P-440	WW	Glen Dr.	6	PVC	720	27	1.86 out of 5	\$345	\$248,400	
Distribution Mains	P-194	WW	Glendale Dr.	8	Ductile Iron	237	4	0 out of 5	N/A	\$0	
Distribution Mains	P-195	WW	Glendale Dr.	8	Ductile Iron	239	4	0 out of 5	N/A	\$0	
Distribution Mains	P-206	WW	Glendale Dr.	8	Ductile Iron	247	4	0 out of 5	N/A	\$0	
Distribution Mains	P-208	WW	Glendale Dr.	8	Ductile Iron	1,010	4	0 out of 5	N/A	\$0	
Distribution Mains	P-209	WW	Glendale Dr.	8	Ductile Iron	160	4	0 out of 5	N/A	\$0	
Distribution Mains	P-1036	WW	Gough Ave.	6	Cast iron	260	128	2.58 out of 5	\$345	\$89,700	
Distribution Mains	P-1045	WW	Gough Ave.	6	Cast iron	241	128	2.58 out of 5	\$345	\$83,145	
Distribution Mains	P-1076	WW	Gough Ave.	6	Cast iron	435	128	2.58 out of 5	\$345	\$150,075	
Distribution Mains	P-1077	WW	Gough Ave.	6	Cast iron	102	128	2.58 out of 5	\$345	\$35,190	
Distribution Mains	P-1879	WW	Gough Ave.	6	Cast iron	723	128	2.58 out of 5	\$345	\$249,435	
Distribution Mains	P-1881	WW	Gough Ave.	6	Cast iron	19	128	2.58 out of 5	\$345	\$6,555	
Distribution Mains	P-1882	WW	Gough Ave.	6	Cast iron	939	128	2.58 out of 5	\$345	\$323,955	
Distribution Mains	P-1883	WW	Gough Ave.	6	Cast iron	22	128	2.58 out of 5	\$345	\$7,590	
Distribution Mains	P-774	WW	Gough Ave.	6	Asbestos Cement	86	70	2.58 out of 5	\$345	\$29,670	
Distribution Mains	P-1069	WW	Gough Ave.	6	Cast iron	407	77	2.29 out of 5	\$345	\$140,415	
Distribution Mains	P-1072	WW	Gough Ave.	6	Cast iron	200	77	2.29 out of 5	\$345	\$69,000	
Distribution Mains	P-1074	WW	Gough Ave.	6	Cast iron	130	78	2.29 out of 5	\$345	\$44,850	
Distribution Mains	P-1075	WW	Gough Ave.	6	Cast iron	319	78	2.29 out of 5	\$345	\$110,055	
Distribution Mains	P-775	WW	Gough Ave.	6	Cast iron	101	77	2.29 out of 5	\$345	\$34,845	
Distribution Mains	P-777	WW	Gough Ave.	6	Cast iron	225	77	2.29 out of 5	\$345	\$77,625	
Distribution Mains	P-784	WW	Gough Ave.	6	Cast iron	505	77	2.29 out of 5	\$345	\$174,225	
Transmission Mains	P-770	WW	Gough Ave.	16	Asbestos Cement	122	70	1.87 out of 5	\$345	\$42,090	
Transmission Mains	P-771	WW	Gough Ave.	16	Asbestos Cement	544	70	1.87 out of 5	\$345	\$187,680	
Transmission Mains	P-772	WW	Gough Ave.	16	Asbestos Cement	87	70	1.87 out of 5	\$345	\$30,015	
Distribution Mains	P-900	WW	Grace Ct.	6	Asbestos Cement	128	46	2.43 out of 5	\$345	\$44,160	
Distribution Mains	P-911	WW	Grandview Dr.	6	Asbestos Cement	680	56	2.43 out of 5	\$345	\$234,600	
Distribution Mains	P-731	WW	Granite St.	4	Cast iron	563	128	3.3 out of 5	\$345	\$194,235	
Distribution Mains	P-1503	WW	Grant St.	2	Copper	200	27	2.15 out of 5	\$345	\$69,000	
Distribution Mains	P-1505	WW	Grant St.	1.5	Copper	352	27	2.15 out of 5	\$345	\$121,440	
Distribution Mains	P-1504	WW	Grant St.	6	PVC	175	27	1.15 out of 5	\$345	\$60,375	
Transmission Mains	P-1448	WW	Green Bush Rd.	16	Asbestos Cement	501	41	1.72 out of 5	\$345	\$172,845	
Transmission Mains	P-1449	WW	Green Bush Rd.	16	Asbestos Cement	396	41	1.72 out of 5	\$345	\$136,620	
Transmission Mains	P-27	WW	Green Bush Rd.	12	Asbestos Cement	99	41	1.72 out of 5	\$345	\$34,155	
Transmission Mains	P-48	WW	Green Bush Rd.	16	Asbestos Cement	756	41	1.72 out of 5	\$345	\$260,820	
Transmission Mains	P-50	WW	Green Bush Rd.	16	Asbestos Cement	1,326	41	1.72 out of 5	\$345	\$457,470	
Transmission Mains	P-1438	WW	Green Bush Rd.	16	Ductile Iron	1,490	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1452	WW	Green Bush Rd.	12	Ductile Iron	218	14	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-1453	WW	Green Bush Rd.	12	Ductile Iron	685	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1455	WW	Green Bush Rd.	12	Ductile Iron	710	14	0 out of 5	N/A	\$0	
Distribution Mains	P-320	WW	Greenbrier Rd.	8	Asbestos Cement	506	38	1.58 out of 5	\$345	\$174,570	
Distribution Mains	P-321	WW	Greenbrier Rd.	8	Asbestos Cement	420	38	1.58 out of 5	\$345	\$144,900	
Distribution Mains	P-1450	WW	Greenbush Elementary Easeme	10	PVC	1,346	26	0.44 out of 5	\$345	\$464,370	
Distribution Mains	P-1451	WW	Greenbush Elementary Easeme	10	PVC	136	26	0.44 out of 5	\$345	\$46,920	
Distribution Mains	P-1454	WW	Greenbush Elementary Easeme	10	Ductile Iron	29	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1272	WW	Greenbush Rd.	16	Asbestos Cement	71	41	1.72 out of 5	\$345	\$24,495	
Transmission Mains	P-1395	WW	Greenbush Rd.	16	Asbestos Cement	504	41	1.72 out of 5	\$345	\$173,880	
Transmission Mains	P-1396	WW	Greenbush Rd.	12	Asbestos Cement	205	41	1.72 out of 5	\$345	\$70,725	
Transmission Mains	P-1392	WW	Greenbush Rd.	12	Ductile Iron	557	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1393	WW	Greenbush Rd.	12	Ductile Iron	214	14	0 out of 5	N/A	\$0	
Distribution Mains	P-1394	WW	Greenbush Rd.	8	Ductile Iron	212	14	0 out of 5	N/A	\$0	
Distribution Mains	P-797	WW	Greene St.	4	Cast iron	237	127	3.3 out of 5	\$345	\$81,765	
Distribution Mains	P-1397	WW	Greene St.	4	Cast iron	230	81	3.15 out of 5	\$345	\$79,350	
Distribution Mains	P-1399	WW	Greene St.	4	Cast iron	343	81	3.15 out of 5	\$345	\$118,335	
Distribution Mains	P-795	WW	Greene St.	4	Cast iron	402	81	3.15 out of 5	\$345	\$138,690	
Distribution Mains	P-800	WW	Greene St.	4	Cast iron	305	81	3.15 out of 5	\$345	\$105,225	
Distribution Mains	P-1518	WW	Greene St.	6	Asbestos Cement	273	62	2.58 out of 5	\$345	\$94,185	
Distribution Mains	P-809	WW	Greene St.	6	Asbestos Cement	163	62	2.58 out of 5	\$345	\$56,235	
Distribution Mains	P-802	WW	Greene St.	1	Copper	193	64	2.44 out of 5	\$345	\$66,585	
Distribution Mains	P-1398	WW	Greene St.	8	Asbestos Cement	198	81	2.01 out of 5	\$345	\$68,310	
Distribution Mains	P-783	WW	Greene St.	8	Asbestos Cement	528	81	2.01 out of 5	\$345	\$182,160	
Distribution Mains	P-796	WW	Greene St.	8	Asbestos Cement	363	81	2.01 out of 5	\$345	\$125,235	
Distribution Mains	P-1533	WW	Greene St.	8	Ductile Iron	420	8	0 out of 5	N/A	\$0	
Distribution Mains	P-241	WW	Greenhill St.	8	Ductile Iron	638	86	0 out of 5	N/A	\$0	
Transmission Mains	P-1710	WW	Greenview Condos Easement	12	Ductile Iron	523	1	0 out of 5	N/A	\$0	
Distribution Mains	P-1976	WW	Grove St.	4	Cast iron	248	76	3.01 out of 5	\$345	\$85,560	
Distribution Mains	P-760	WW	Guertin St.	2	Galvanized iron	273	64	3.3 out of 5	\$345	\$94,185	
Distribution Mains	P-1904	WW	Hall St.	1	Copper	146	65	2.44 out of 5	\$345	\$50,370	
Distribution Mains	P-1068	WW	Hall St.	6	PVC	157	27	1.15 out of 5	\$345	\$54,165	
Distribution Mains	P-426	WW	Hamilton St.	6	Asbestos Cement	305	61	2.58 out of 5	\$345	\$105,225	
Distribution Mains	P-428	WW	Hamilton St.	6	Asbestos Cement	136	61	2.58 out of 5	\$345	\$46,920	
Distribution Mains	P-444	WW	Hamilton St.	6	Asbestos Cement	491	61	2.58 out of 5	\$345	\$169,395	
Distribution Mains	P-564	WW	Harbour Ave.	6	Asbestos Cement	238	68	2.58 out of 5	\$345	\$82,110	
Distribution Mains	P-568	WW	Harbour Ave.	8	Asbestos Cement	296	68	2.58 out of 5	\$345	\$102,120	
Distribution Mains	P-574	WW	Harbour Ave.	2	Copper	241	68	2.44 out of 5	\$345	\$83,145	
Distribution Mains	P-576	WW	Harbour Ave.	2	Copper	137	68	2.44 out of 5	\$345	\$47,265	
Distribution Mains	P-551	WW	Harbour Ave.	6	Cast iron	453	68	2.29 out of 5	\$345	\$156,285	
Distribution Mains	P-1603	WW	Harbour Ave.	8	Ductile Iron	241	9	0 out of 5	N/A	\$0	
Distribution Mains	P-1605	WW	Harbour Ave.	8	Ductile Iron	235	11	0 out of 5	N/A	\$0	
Distribution Mains	P-1606	WW	Harbour Ave.	8	Ductile Iron	293	11	0 out of 5	N/A	\$0	
Transmission Mains	P-1676	WW	Harding St.	12	Ductile Iron	502	7	0 out of 5	N/A	\$0	
Transmission Mains	P-1790	WW	Harding St.	12	Ductile Iron	183	5	0 out of 5	N/A	\$0	
Transmission Mains	P-891	WW	Harding St.	12	Ductile Iron	192	5	0 out of 5	N/A	\$0	
Transmission Mains	P-895	WW	Harding St.	12	Ductile Iron	130	5	0 out of 5	N/A	\$0	
Transmission Mains	P-896	WW	Harding St.	16	Ductile Iron	1,005	7	0 out of 5	N/A	\$0	
Distribution Mains	P-662	WW	Hare St.	1	Galvanized iron	438	129	3.59 out of 5	\$345	\$151,110	
Distribution Mains	P-1965	WW	Harley St.	8	Ductile Iron	186	3	0 out of 5	N/A	\$0	
Distribution Mains	P-621	WW	Harley St.	8	Ductile Iron	544	3	0 out of 5	N/A	\$0	
Distribution Mains	P-629	WW	Harley St.	8	Ductile Iron	289	3	0 out of 5	N/A	\$0	
Distribution Mains	P-631	WW	Harley St.	8	Ductile Iron	316	3	0 out of 5	N/A	\$0	
Distribution Mains	P-633	WW	Harley St.	8	Ductile Iron	241	3	0 out of 5	N/A	\$0	
Distribution Mains	P-636	WW	Harley St.	8	Ductile Iron	602	3	0 out of 5	N/A	\$0	
Distribution Mains	P-638	WW	Harley St.	8	Ductile Iron	352	3	0 out of 5	N/A	\$0	
Distribution Mains	P-917	WW	Harmony St.	4	Cast iron	516	124	3.3 out of 5	\$345	\$178,020	
Distribution Mains	P-918	WW	Harmony St.	6	Cast iron	399	124	2.58 out of 5	\$345	\$137,655	
Distribution Mains	P-792	WW	Harris Ave.	6	Cast iron	1,087	129	2.58 out of 5	\$345	\$375,015	
Distribution Mains	P-794	WW	Harris Ave.	6	Cast iron	737	129	2.58 out of 5	\$345	\$254,265	
Distribution Mains	P-798	WW	Harris Ave.	8	Asbestos Cement	231	64	1.87 out of 5	\$345	\$79,695	
Distribution Mains	P-799	WW	Harris Ave.	8	Asbestos Cement	871	68	1.87 out of 5	\$345	\$300,495	
Distribution Mains	P-608	WW	Harvest Dr.	8	Ductile Iron	248	3	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-10016	WW	Hatheway Dr.	8	Asbestos Cement	222	36	1.58 out of 5	\$345	\$76,590	
Distribution Mains	P-96	WW	Hatheway Dr.	8	Asbestos Cement	1,096	36	1.58 out of 5	\$345	\$378,120	
Distribution Mains	P-1345	WW	Hay St.	6	Cast iron	93	92	2.43 out of 5	\$345	\$32,085	
Distribution Mains	P-1346	WW	Hay St.	6	PVC	101	41	1.29 out of 5	\$345	\$34,845	
Distribution Mains	P-992	WW	Hay St.	6	PVC	357	41	1.29 out of 5	\$345	\$123,165	
Distribution Mains	P-1686	WW	Hay St.	6	Ductile Iron	84	25	0.86 out of 5	\$345	\$28,980	
Distribution Mains	P-1870	WW	Hay St.	6	Ductile Iron	117	25	0.86 out of 5	\$345	\$40,365	
Distribution Mains	P-716	WW	Hebert St.	2	Galvanized iron	604	86	3.44 out of 5	\$345	\$208,380	
Distribution Mains	P-1935	WW	Hebert St.	1	Copper	154	86	2.58 out of 5	\$345	\$53,130	
Distribution Mains	P-1933	WW	Hebert St.	1.5	PVC	25	37	1.87 out of 5	\$345	\$8,625	
Distribution Mains	P-1934	WW	Hebert St.	2	PVC	81	37	1.87 out of 5	\$345	\$27,945	
Distribution Mains	P-773	WW	Hebert St.	2	PVC	165	37	1.87 out of 5	\$345	\$56,925	
Distribution Mains	P-149	WW	Hemlock Ln.	8	Asbestos Cement	401	45	1.72 out of 5	\$345	\$138,345	
Distribution Mains	P-150	WW	Hemlock Ln.	8	Asbestos Cement	166	45	1.72 out of 5	\$345	\$57,270	
Distribution Mains	P-151	WW	Hemlock Ln.	8	Asbestos Cement	412	45	1.72 out of 5	\$345	\$142,140	
Distribution Mains	P-1123	WW	Hepburn St.	4	Cast iron	423	129	3.3 out of 5	\$345	\$145,935	
Distribution Mains	P-1114	WW	Hepburn St.	6	Cast iron	396	129	2.58 out of 5	\$345	\$136,620	
Distribution Mains	P-1124	WW	Hepburn St.	2	PVC	454	25	1.87 out of 5	\$345	\$156,630	
Distribution Mains	P-532	WW	Hidden Hollow Cir.	6	Asbestos Cement	533	46	2.43 out of 5	\$345	\$183,885	
Distribution Mains	P-534	WW	High View Dr.	8	Asbestos Cement	244	47	1.72 out of 5	\$345	\$84,180	
Distribution Mains	P-535	WW	High View Dr.	8	Asbestos Cement	334	47	1.72 out of 5	\$345	\$115,230	
Distribution Mains	P-536	WW	High View Dr.	8	Asbestos Cement	563	47	1.72 out of 5	\$345	\$194,235	
Distribution Mains	P-1216	WW	Highland St.	6	Cast iron	141	129	2.58 out of 5	\$345	\$48,645	
Distribution Mains	P-1915	WW	Highland St.	6	Cast iron	346	129	2.58 out of 5	\$345	\$119,370	
Distribution Mains	P-981	WW	Highland St.	6	Cast iron	556	129	2.58 out of 5	\$345	\$191,820	
Distribution Mains	P-1250	WW	Highland St.	8	Cast iron	166	129	1.87 out of 5	\$345	\$57,270	
Distribution Mains	P-1252	WW	Highland St.	8	Cast iron	134	129	1.87 out of 5	\$345	\$46,230	
Distribution Mains	P-1253	WW	Highland St.	6	Ductile Iron	178	20	0.86 out of 5	\$345	\$61,410	
Distribution Mains	P-1844	WW	Highland St.	6	Ductile Iron	21	8	0.71 out of 5	\$345	\$7,245	
Distribution Mains	P-1843	WW	Highland St.	8	Ductile Iron	20	8	0 out of 5	N/A	\$0	
Distribution Mains	P-754	WW	Hillcrest Dr.	6	Cast iron	260	65	3 out of 5	\$345	\$89,700	
Distribution Mains	P-1954	WW	Hillcrest Dr.	1	Copper	44	65	2.44 out of 5	\$345	\$15,180	
Distribution Mains	P-756	WW	Hillcrest Dr.	6	Cast iron	214	65	2.29 out of 5	\$345	\$73,830	
Distribution Mains	P-1212	WW	Hillside Ave.	6	Ductile Iron	447	4	0.71 out of 5	\$345	\$154,215	
Distribution Mains	P-330	WW	Hilltop Ave.	6	Asbestos Cement	796	64	2.58 out of 5	\$345	\$274,620	IFR 2015B
Distribution Mains	P-359	WW	Hilltop Ave.	6	Asbestos Cement	176	62	2.58 out of 5	\$345	\$60,720	IFR 2015B
Distribution Mains	P-733	WW	Home St.	6	Cast iron	592	74	2.29 out of 5	\$345	\$204,240	
Distribution Mains	P-894	WW	Hoover St.	6	Ductile Iron	723	26	0.86 out of 5	\$345	\$249,435	
Distribution Mains	P-1300	WW	Hoover St.	6	Ductile Iron	315	13	0.71 out of 5	\$345	\$108,675	
Distribution Mains	P-164	WW	Hopedale Dr.	8	Ductile Iron	468	4	0 out of 5	N/A	\$0	
Distribution Mains	P-169	WW	Hopedale Dr.	8	Ductile Iron	286	4	0 out of 5	N/A	\$0	
Distribution Mains	P-1729	WW	Hopedale Dr.	8	Ductile Iron	21	4	0 out of 5	N/A	\$0	
Distribution Mains	P-1730	WW	Hopedale Dr.	8	Ductile Iron	25	10	0 out of 5	N/A	\$0	
Distribution Mains	P-193	WW	Hopedale Dr.	8	Ductile Iron	444	4	0 out of 5	N/A	\$0	
Distribution Mains	P-152	WW	Hornbeam Ln.	8	Asbestos Cement	231	37	1.58 out of 5	\$345	\$79,695	
Distribution Mains	P-892	WW	Horta Dr.	6	Ductile Iron	409	5	0.71 out of 5	\$345	\$141,105	
Distribution Mains	P-893	WW	Horta Dr.	6	Ductile Iron	178	5	0.71 out of 5	\$345	\$61,410	
Distribution Mains	P-1789	WW	Horta Dr.	8	Ductile Iron	34	5	0 out of 5	N/A	\$0	
Distribution Mains	P-1208	WW	Hoxie Ct.	8	Ductile Iron	657	12	0 out of 5	N/A	\$0	
Distribution Mains	P-1927	WW	Hoxie Ct.	8	Ductile Iron	45	4	0 out of 5	N/A	\$0	
Distribution Mains	P-160	WW	Huckleberry Dr.	8	Asbestos Cement	442	37	1.58 out of 5	\$345	\$152,490	
Transmission Mains	P-1355	WW	Industrial Ln.	12	Ductile Iron	59	2	0 out of 5	N/A	\$0	
Transmission Mains	P-1860	WW	Industrial Ln.	12	Ductile Iron	26	2	0 out of 5	N/A	\$0	
Distribution Mains	P-830	WW	Industrial Ln.	8	Ductile Iron	1,403	2	0 out of 5	N/A	\$0	
Distribution Mains	P-832	WW	Industrial Ln.	8	Ductile Iron	260	2	0 out of 5	N/A	\$0	
Distribution Mains	P-234	WW	Intervale Rd.	6	Asbestos Cement	494	50	2.43 out of 5	\$345	\$170,430	
Distribution Mains	P-322	WW	Iron Dr.	8	Asbestos Cement	189	42	1.72 out of 5	\$345	\$65,205	
Distribution Mains	P-325	WW	Iron Dr.	8	Asbestos Cement	360	42	1.72 out of 5	\$345	\$124,200	
Distribution Mains	P-295	WW	Ivy St.	6	Asbestos Cement	561	66	2.58 out of 5	\$345	\$193,545	
Transmission Mains	P-1315	WW	J.P. Murphy Hwy.	16	Ductile Iron	113	16	0 out of 5	N/A	\$0	
Transmission Mains	P-1549	WW	J.P. Murphy Hwy.	16	Ductile Iron	166	2	0 out of 5	N/A	\$0	
Transmission Mains	P-1550	WW	J.P. Murphy Hwy.	16	Ductile Iron	239	2	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-1573	WW	J.P. Murphy Hwy.	16	Ductile Iron	1,789	2	0 out of 5	N/A	\$0	
Transmission Mains	P-1574	WW	J.P. Murphy Hwy.	16	Ductile Iron	369	8	0 out of 5	N/A	\$0	
Transmission Mains	P-65	WW	J.P. Murphy Hwy.	16	Ductile Iron	2,437	2	0 out of 5	N/A	\$0	
Transmission Mains	P-66	WW	J.P. Murphy Hwy.	16	Ductile Iron	1,395	2	0 out of 5	N/A	\$0	
Transmission Mains	P-67	WW	J.P. Murphy Hwy.	16	Ductile Iron	1,055	2	0 out of 5	N/A	\$0	
Transmission Mains	P-68	WW	J.P. Murphy Hwy.	16	Ductile Iron	809	2	0 out of 5	N/A	\$0	
Transmission Mains	P-80	WW	J.P. Murphy Hwy. Easement	16	Ductile Iron	1,404	16	0 out of 5	N/A	\$0	
Distribution Mains	P-466	WW	Jacques St.	6	Asbestos Cement	435	59	2.43 out of 5	\$345	\$150,075	
Distribution Mains	P-198	WW	Janet Dr.	6	Asbestos Cement	510	64	2.58 out of 5	\$345	\$175,950	
Distribution Mains	P-1390	WW	Jaycee Dr.	8	Asbestos Cement	291	52	1.72 out of 5	\$345	\$100,395	
Distribution Mains	P-1391	WW	Jaycee Dr.	8	Asbestos Cement	231	52	1.72 out of 5	\$345	\$79,695	
Distribution Mains	P-34	WW	Jaycee Dr.	8	Asbestos Cement	575	52	1.72 out of 5	\$345	\$198,375	
Distribution Mains	P-581	WW	Jefferson St.	6	Asbestos Cement	172	65	2.58 out of 5	\$345	\$59,340	
Distribution Mains	P-459	WW	Joaquin Ct.	8	Asbestos Cement	128	35	1.58 out of 5	\$345	\$44,160	
Distribution Mains	P-460	WW	Joaquin Ct.	8	Asbestos Cement	303	35	1.58 out of 5	\$345	\$104,535	
Distribution Mains	P-461	WW	Joaquin Ct.	8	Asbestos Cement	275	35	1.58 out of 5	\$345	\$94,875	
Distribution Mains	P-750	WW	Jodoin St.	6	Cast iron	328	69	3 out of 5	\$345	\$113,160	
Distribution Mains	P-1067	WW	John St.	1	Copper	244	69	2.44 out of 5	\$345	\$84,180	
Distribution Mains	P-1064	WW	John St.	6	Cast iron	215	69	2.29 out of 5	\$345	\$74,175	
Distribution Mains	P-1065	WW	John St.	6	Cast iron	166	69	2.29 out of 5	\$345	\$57,270	
Distribution Mains	P-469	WW	Judy Ter.	6	Asbestos Cement	238	49	2.43 out of 5	\$345	\$82,110	
Distribution Mains	P-470	WW	Judy Ter.	6	Asbestos Cement	199	49	2.43 out of 5	\$345	\$68,655	
Distribution Mains	P-471	WW	Judy Ter.	6	Asbestos Cement	364	49	2.43 out of 5	\$345	\$125,580	
Distribution Mains	P-1343	WW	Junior St.	6	Cast iron	105	92	2.43 out of 5	\$345	\$36,225	
Distribution Mains	P-1867	WW	Junior St.	6	Cast iron	201	92	2.43 out of 5	\$345	\$69,345	
Distribution Mains	P-989	WW	Junior St.	6	Cast iron	493	92	2.43 out of 5	\$345	\$170,085	
Distribution Mains	P-990	WW	Junior St.	6	Cast iron	391	92	2.43 out of 5	\$345	\$134,895	
Distribution Mains	P-991	WW	Junior St.	6	Cast iron	296	92	2.43 out of 5	\$345	\$102,120	
Distribution Mains	P-1868	WW	Junior St.	6	Ductile Iron	31	7	0.71 out of 5	\$345	\$10,695	
Distribution Mains	P-1344	WW	Junior St.	8	Ductile Iron	38	7	0 out of 5	N/A	\$0	
Distribution Mains	P-1347	WW	Junior St.	8	Ductile Iron	217	12	0 out of 5	N/A	\$0	
Distribution Mains	P-1402	WW	Juniper Dr.	8	Asbestos Cement	948	37	2.29 out of 5	\$345	\$327,060	
Distribution Mains	P-10012	WW	Juniper Dr.	8	Asbestos Cement	78	37	1.58 out of 5	\$345	\$26,910	
Distribution Mains	P-1403	WW	Juniper Dr.	8	Asbestos Cement	131	37	1.58 out of 5	\$345	\$45,195	
Distribution Mains	P-178	WW	Juniper Dr.	8	Asbestos Cement	444	37	1.58 out of 5	\$345	\$153,180	
Distribution Mains	P-181	WW	Juniper Dr.	8	Asbestos Cement	238	37	1.58 out of 5	\$345	\$82,110	
Distribution Mains	P-1406	WW	Juniper Dr.	8	Ductile Iron	32	14	0 out of 5	N/A	\$0	
Distribution Mains	P-1270	WW	Juniper Dr. Easement	8	Ductile Iron	319	17	0 out of 5	N/A	\$0	
Distribution Mains	P-862	WW	Kathleen Ct.	8	Ductile Iron	322	21	0.15 out of 5	N/A	\$0	
Distribution Mains	P-863	WW	Kathleen Ct.	8	Ductile Iron	440	21	0.15 out of 5	N/A	\$0	
Distribution Mains	P-1066	WW	Kenmore St.	2	Copper	631	65	2.44 out of 5	\$345	\$217,695	
Distribution Mains	P-1901	WW	Kenmore St.	1	Copper	324	65	2.44 out of 5	\$345	\$111,780	
Distribution Mains	P-1967	WW	Kent St.	8	Ductile Iron	256	13	0 out of 5	N/A	\$0	
Distribution Mains	P-567	WW	Kent St.	8	Ductile Iron	556	13	0 out of 5	N/A	\$0	
Distribution Mains	P-573	WW	Kent St.	8	Ductile Iron	226	13	0 out of 5	N/A	\$0	
Distribution Mains	P-789	WW	Kenyon St.	1.3	Galvanized iron	525	76	4.01 out of 5	\$345	\$181,125	
Transmission Mains	P-10007	WW	Keys Way	12	Ductile Iron	27	2	0 out of 5	N/A	\$0	
Transmission Mains	P-69	WW	Keys Way	12	Ductile Iron	857	16	0 out of 5	N/A	\$0	
Distribution Mains	P-100	WW	Kimberly Ln.	6	Asbestos Cement	688	39	2.29 out of 5	\$345	\$237,360	
Distribution Mains	P-1191	WW	Kimberly Ln.	8	Asbestos Cement	328	44	1.72 out of 5	\$345	\$113,160	
Distribution Mains	P-1193	WW	Kimberly Ln.	8	Asbestos Cement	954	44	1.72 out of 5	\$345	\$329,130	
Distribution Mains	P-101	WW	Kimberly Ln.	8	Asbestos Cement	189	39	1.58 out of 5	\$345	\$65,205	
Distribution Mains	P-99	WW	Kimberly Ln.	8	Asbestos Cement	348	39	1.58 out of 5	\$345	\$120,060	
Distribution Mains	P-8	WW	Kings Forest	8	Ductile Iron	735	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-778	WW	Kinne St.	4	Cast iron	535	65	4.44 out of 5	\$345	\$184,575	
Distribution Mains	P-781	WW	Kinne St.	6	Asbestos Cement	435	65	2.58 out of 5	\$345	\$150,075	
Distribution Mains	P-779	WW	Kinne St.	8	Cast iron	179	65	1.58 out of 5	\$345	\$61,755	
Distribution Mains	P-36	WW	Kiwanis Dr.	8	Asbestos Cement	433	45	1.72 out of 5	\$345	\$149,385	
Transmission Mains	P-1845	WW	Knight St.	20	Ductile Iron	211	8	0 out of 5	N/A	\$0	
Transmission Mains	P-926	WW	Knight St.	20	Ductile Iron	410	8	0 out of 5	N/A	\$0	
Transmission Mains	P-927	WW	Knight St.	20	Ductile Iron	243	8	0 out of 5	N/A	\$0	
Transmission Mains	P-928	WW	Knight St.	20	Ductile Iron	22	8	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-1964	WW	Koch St.	8	Ductile Iron	254	3	0 out of 5	N/A	\$0	
Distribution Mains	P-632	WW	Kowalik Dr.	8	Ductile Iron	569	3	0 out of 5	N/A	\$0	
Distribution Mains	P-1321	WW	Krystal Pond Dr.	8	PVC	317	24	0.44 out of 5	\$345	\$109,365	
Distribution Mains	P-1322	WW	Krystal Pond Dr.	8	PVC	87	24	0.44 out of 5	\$345	\$30,015	
Distribution Mains	P-1323	WW	Krystal Pond Dr.	8	Ductile Iron	210	12	0 out of 5	N/A	\$0	
Distribution Mains	P-1324	WW	Krystal Pond Dr.	8	Ductile Iron	425	12	0 out of 5	N/A	\$0	
Distribution Mains	P-139	WW	Kulas Rd.	8	Asbestos Cement	405	44	1.72 out of 5	\$345	\$139,725	
Distribution Mains	P-1609	WW	Kulas Rd.	8	Asbestos Cement	196	44	1.72 out of 5	\$345	\$67,620	
Distribution Mains	P-499	WW	Kulas Rd.	8	Asbestos Cement	1,050	44	1.72 out of 5	\$345	\$362,250	
Distribution Mains	P-1365	WW	Lachance St.	6	Cast iron	251	76	3 out of 5	\$345	\$86,595	
Distribution Mains	P-719	WW	Lachance St.	6	Cast iron	241	76	2.29 out of 5	\$345	\$83,145	
Transmission Mains	P-1572	WW	Lacroix Dr.	12	Ductile Iron	462	14	0 out of 5	N/A	\$0	
Transmission Mains	P-73	WW	Lacroix Dr.	12	Ductile Iron	80	14	0 out of 5	N/A	\$0	
Distribution Mains	P-634	WW	Lada Dr.	8	Ductile Iron	176	3	0 out of 5	N/A	\$0	
Distribution Mains	P-635	WW	Lada Dr.	8	Ductile Iron	261	3	0 out of 5	N/A	\$0	
Distribution Mains	P-289	WW	Lafayette St.	6	Ductile Iron	722	21	0.86 out of 5	\$345	\$249,090	
Distribution Mains	P-1771	WW	Lancelotta St.	8	Ductile Iron	256	1	0 out of 5	N/A	\$0	
Distribution Mains	P-263	WW	Lancelotta St.	8	Ductile Iron	428	1	0 out of 5	N/A	\$0	
Distribution Mains	P-1447	WW	Lancer Ln.	8	Asbestos Cement	680	36	1.58 out of 5	\$345	\$234,600	
Distribution Mains	P-1224	WW	Lanphear St.	6	Cast iron	153	129	2.58 out of 5	\$345	\$52,785	
Distribution Mains	P-1225	WW	Lanphear St.	6	Cast iron	579	129	2.58 out of 5	\$345	\$199,755	
Distribution Mains	P-572	WW	Laramee Ave.	6	PVC	480	26	1.15 out of 5	\$345	\$165,600	
Distribution Mains	P-563	WW	Laramee Ave.	6	Ductile Iron	498	23	0.86 out of 5	\$345	\$171,810	
Distribution Mains	P-146	WW	Laural Ln.	8	Asbestos Cement	459	45	1.72 out of 5	\$345	\$158,355	
Distribution Mains	P-147	WW	Laural Ln.	8	Asbestos Cement	406	45	1.72 out of 5	\$345	\$140,070	
Distribution Mains	P-148	WW	Laural Ln.	8	Asbestos Cement	551	45	1.72 out of 5	\$345	\$190,095	
Transmission Mains	P-1426	WW	Lauren Ln.	12	PVC	191	27	0.44 out of 5	\$345	\$65,895	
Transmission Mains	P-1427	WW	Lauren Ln.	12	PVC	482	27	0.44 out of 5	\$345	\$166,290	
Transmission Mains	P-1430	WW	Lauren Ln.	12	Ductile Iron	21	14	0 out of 5	N/A	\$0	
Distribution Mains	P-1978	WW	Lavoie Ct.	2	Copper	187	46	2.29 out of 5	\$345	\$64,515	
Distribution Mains	P-1364	WW	Lawrence St.	6	Asbestos Cement	269	59	2.43 out of 5	\$345	\$92,805	
Distribution Mains	P-1811	WW	Lawrence St.	6	Ductile Iron	207	5	0.71 out of 5	\$345	\$71,415	
Distribution Mains	P-1818	WW	Lawrence St.	6	Ductile Iron	31	5	0.71 out of 5	\$345	\$10,695	
Distribution Mains	P-1820	WW	Lawrence St.	8	Ductile Iron	23	5	0 out of 5	N/A	\$0	
Distribution Mains	P-1220	WW	Le Valley St.	4	Cast iron	118	129	3.3 out of 5	\$345	\$40,710	
Distribution Mains	P-1221	WW	Le Valley St.	4	Cast iron	96	129	3.3 out of 5	\$345	\$33,120	
Distribution Mains	P-1226	WW	Le Valley St.	4	Cast iron	249	129	3.3 out of 5	\$345	\$85,905	
Distribution Mains	P-1502	WW	Le Valley St.	4	Cast iron	244	129	3.3 out of 5	\$345	\$84,180	
Distribution Mains	P-10034	WW	Leaf St.	6	Asbestos Cement	163	65	2.58 out of 5	\$345	\$56,235	IFR 2014B
Distribution Mains	P-377	WW	Leaf St.	6	Asbestos Cement	930	65	2.58 out of 5	\$345	\$320,850	IFR 2014B
Distribution Mains	P-10035	WW	Leaf St.	1	Copper	104	64	2.44 out of 5	\$345	\$35,880	IFR 2014B
Distribution Mains	P-10036	WW	Leaf St.	1.5	Copper	331	54	2.29 out of 5	\$345	\$114,195	IFR 2014B
Distribution Mains	P-905	WW	Ledge Dr.	6	Asbestos Cement	334	59	2.43 out of 5	\$345	\$115,230	
Distribution Mains	P-365	WW	Ledgemont Ct.	6	Asbestos Cement	311	39	2.29 out of 5	\$345	\$107,295	IFR 2015B
Distribution Mains	P-514	WW	Lee St.	6	Asbestos Cement	609	64	3.29 out of 5	\$345	\$210,105	
Distribution Mains	P-517	WW	Lee St.	6	Asbestos Cement	394	64	2.58 out of 5	\$345	\$135,930	
Distribution Mains	P-527	WW	Lee St.	6	Asbestos Cement	99	64	2.58 out of 5	\$345	\$34,155	
Distribution Mains	P-570	WW	Leeder St.	2	Galvanized iron	228	86	3.44 out of 5	\$345	\$78,660	
Transmission Mains	P-79	WW	Legend Way	16	Ductile Iron	208	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-1108	WW	Legris Ave.	6	Cast iron	457	82	2.43 out of 5	\$345	\$157,665	IFR 2014B
Distribution Mains	P-1107	WW	Legris Ave.	6	Ductile Iron	274	20	0.86 out of 5	\$345	\$94,530	
Distribution Mains	P-642	WW	Legris Ave.	6	Ductile Iron	122	20	0.86 out of 5	\$345	\$42,090	
Distribution Mains	P-704	WW	Lemoine Ct.	2	Galvanized iron	259	125	3.59 out of 5	\$345	\$89,355	
Distribution Mains	P-10033	WW	Lenox Ave.	2	Galvanized iron	309	82	4.15 out of 5	\$345	\$106,605	IFR 2014B
Distribution Mains	P-396	WW	Lenox Ave.	4	Cast iron	449	82	3.15 out of 5	\$345	\$154,905	IFR 2014B
Distribution Mains	P-391	WW	Lenox Ave.	2	Galvanized iron	199	21	3.01 out of 5	\$345	\$68,655	IFR 2014B
Distribution Mains	P-388	WW	Lenox Ave.	6	Ductile Iron	480	21	0.86 out of 5	\$345	\$165,600	
Distribution Mains	P-395	WW	Lenox Ave.	6	Ductile Iron	231	21	0.86 out of 5	\$345	\$79,695	
Distribution Mains	P-386	WW	Lexington Ave.	6	Cast iron	934	75	3.72 out of 5	\$345	\$322,230	IFR 2014B
Distribution Mains	P-382	WW	Lexington Ave.	6	Asbestos Cement	279	62	2.58 out of 5	\$345	\$96,255	IFR 2014B
Distribution Mains	P-381	WW	Lexington Ave.	6	Cast iron	183	75	2.29 out of 5	\$345	\$63,135	IFR 2014B
Distribution Mains	P-383	WW	Lexington Ave.	6	Cast iron	528	75	2.29 out of 5	\$345	\$182,160	IFR 2014B

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-119	WW	Linden Dr.	8	Ductile Iron	408	4	0 out of 5	N/A	\$0	
Distribution Mains	P-1720	WW	Linden Dr.	8	Ductile Iron	48	10	0 out of 5	N/A	\$0	
Distribution Mains	P-962	WW	Linwood St.	6	Asbestos Cement	388	72	2.58 out of 5	\$345	\$133,860	
Distribution Mains	P-380	WW	Lionel Ave.	6	Asbestos Cement	266	62	2.58 out of 5	\$345	\$91,770	IFR 2014B
Distribution Mains	P-1941	WW	Lions Dr.	8	Asbestos Cement	96	45	1.72 out of 5	\$345	\$33,120	
Distribution Mains	P-1942	WW	Lions Dr.	8	Asbestos Cement	71	45	1.72 out of 5	\$345	\$24,495	
Distribution Mains	P-35	WW	Lions Dr.	8	Asbestos Cement	342	45	1.72 out of 5	\$345	\$117,990	
Distribution Mains	P-37	WW	Lions Dr.	8	Asbestos Cement	202	45	1.72 out of 5	\$345	\$69,690	
Distribution Mains	P-2	WW	Little John La.	8	Ductile Iron	328	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-4	WW	Little John La.	8	Ductile Iron	488	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-450	WW	Lockwood St.	6	Asbestos Cement	2,400	64	3.29 out of 5	\$345	\$828,000	
Distribution Mains	P-441	WW	Lockwood St.	6	Asbestos Cement	234	64	2.58 out of 5	\$345	\$80,730	
Distribution Mains	P-443	WW	Lockwood St.	6	Asbestos Cement	239	64	2.58 out of 5	\$345	\$82,455	
Distribution Mains	P-463	WW	Lockwood St.	6	Asbestos Cement	519	64	2.58 out of 5	\$345	\$179,055	
Distribution Mains	P-436	WW	Lockwood St.	6	PVC	568	27	1.15 out of 5	\$345	\$195,960	
Distribution Mains	P-438	WW	Lockwood St.	6	PVC	244	27	1.15 out of 5	\$345	\$84,180	
Distribution Mains	P-10018	WW	Locust Dr.	6	PVC	134	28	1.15 out of 5	\$345	\$46,230	
Distribution Mains	P-1465	WW	Locust Dr.	6	PVC	332	28	1.15 out of 5	\$345	\$114,540	
Distribution Mains	P-1269	WW	Loggers Run	8	Ductile Iron	491	17	0 out of 5	N/A	\$0	
Distribution Mains	P-131	WW	Loggers Run	8	Ductile Iron	867	17	0 out of 5	N/A	\$0	
Distribution Mains	P-132	WW	Loggers Run	8	Ductile Iron	202	17	0 out of 5	N/A	\$0	
Distribution Mains	P-133	WW	Loggers Run	8	Ductile Iron	330	17	0 out of 5	N/A	\$0	
Transmission Mains	P-875	WW	Lombardi Ln.	12	PVC	622	25	0.44 out of 5	\$345	\$214,590	
Distribution Mains	P-10	WW	Longbow Dr.	8	Ductile Iron	446	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-15	WW	Longbow Dr.	8	Ductile Iron	239	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-21	WW	Longbow Dr.	8	Ductile Iron	442	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-7	WW	Longbow Dr.	8	Ductile Iron	240	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-9	WW	Longbow Dr.	8	Ductile Iron	280	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-10013	WW	Lonsdale St.	8	Asbestos Cement	27	44	1.72 out of 5	\$345	\$9,315	
Transmission Mains	P-10014	WW	Lonsdale St.	12	Asbestos Cement	206	44	1.72 out of 5	\$345	\$71,070	
Transmission Mains	P-1149	WW	Lonsdale St.	12	Asbestos Cement	546	45	1.72 out of 5	\$345	\$188,370	
Transmission Mains	P-1155	WW	Lonsdale St.	12	Asbestos Cement	731	45	1.72 out of 5	\$345	\$252,195	
Transmission Mains	P-135	WW	Lonsdale St.	12	Asbestos Cement	852	45	1.72 out of 5	\$345	\$293,940	
Transmission Mains	P-136	WW	Lonsdale St.	12	Asbestos Cement	884	45	1.72 out of 5	\$345	\$304,980	
Transmission Mains	P-138	WW	Lonsdale St.	12	Asbestos Cement	852	44	1.72 out of 5	\$345	\$293,940	
Distribution Mains	P-1143	WW	Lori Ct.	8	Asbestos Cement	207	42	1.72 out of 5	\$345	\$71,415	
Distribution Mains	P-847	WW	Louise Dr.	6	Asbestos Cement	538	59	2.43 out of 5	\$345	\$185,610	
Distribution Mains	P-966	WW	Lowell St.	6	Asbestos Cement	213	52	2.43 out of 5	\$345	\$73,485	
Distribution Mains	P-1813	WW	Lowell St.	1	Copper	236	52	2.29 out of 5	\$345	\$81,420	
Distribution Mains	P-1812	WW	Lowell St.	8	Ductile Iron	28	5	0 out of 5	N/A	\$0	
Distribution Mains	P-1445	WW	Maid Marian Ln.	8	Asbestos Cement	287	36	1.58 out of 5	\$345	\$99,015	
Distribution Mains	P-1446	WW	Maid Marian Ln.	8	Asbestos Cement	544	36	1.58 out of 5	\$345	\$187,680	
Distribution Mains	P-1009	WW	Main St.	6	Cast iron	364	129	2.58 out of 5	\$345	\$125,580	
Distribution Mains	P-1019	WW	Main St.	6	Cast iron	373	129	2.58 out of 5	\$345	\$128,685	
Distribution Mains	P-1020	WW	Main St.	6	Cast iron	303	129	2.58 out of 5	\$345	\$104,535	
Distribution Mains	P-1021	WW	Main St.	6	Cast iron	266	129	2.58 out of 5	\$345	\$91,770	
Distribution Mains	P-1026	WW	Main St.	6	Cast iron	485	129	2.58 out of 5	\$345	\$167,325	
Distribution Mains	P-1035	WW	Main St.	6	Cast iron	422	129	2.58 out of 5	\$345	\$145,590	
Distribution Mains	P-1037	WW	Main St.	6	Cast iron	793	129	2.58 out of 5	\$345	\$273,585	
Distribution Mains	P-1039	WW	Main St.	6	Cast iron	342	129	2.58 out of 5	\$345	\$117,990	
Distribution Mains	P-1078	WW	Main St.	6	Cast iron	92	129	2.58 out of 5	\$345	\$31,740	
Distribution Mains	P-1137	WW	Main St.	8	Cast iron	942	129	2.58 out of 5	\$345	\$324,990	
Distribution Mains	P-1285	WW	Main St.	6	Cast iron	229	129	2.58 out of 5	\$345	\$79,005	
Distribution Mains	P-1886	WW	Main St.	6	Cast iron	145	129	2.58 out of 5	\$345	\$50,025	
Distribution Mains	P-1892	WW	Main St.	6	Cast iron	43	129	2.58 out of 5	\$345	\$14,835	
Distribution Mains	P-1895	WW	Main St.	6	Cast iron	19	129	2.58 out of 5	\$345	\$6,555	
Distribution Mains	P-1975	WW	Main St.	6	Cast iron	235	129	2.58 out of 5	\$345	\$81,075	
Distribution Mains	P-646	WW	Main St.	6	Cast iron	834	129	2.58 out of 5	\$345	\$287,730	
Distribution Mains	P-650	WW	Main St.	6	Cast iron	575	129	2.58 out of 5	\$345	\$198,375	
Distribution Mains	P-651	WW	Main St.	6	Cast iron	170	129	2.58 out of 5	\$345	\$58,650	
Distribution Mains	P-661	WW	Main St.	6	Cast iron	220	129	2.58 out of 5	\$345	\$75,900	
Distribution Mains	P-663	WW	Main St.	6	Cast iron	137	129	2.58 out of 5	\$345	\$47,265	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-667	WW	Main St.	6	Cast iron	436	129	2.58 out of 5	\$345	\$150,420	
Distribution Mains	P-790	WW	Main St.	6	Cast iron	15	129	2.58 out of 5	\$345	\$5,175	
Distribution Mains	P-1265	WW	Main St.	6	Cast iron	81	78	2.29 out of 5	\$345	\$27,945	
Distribution Mains	P-1884	WW	Main St.	6	Cast iron	22	78	2.29 out of 5	\$345	\$7,590	
Distribution Mains	P-1885	WW	Main St.	6	Cast iron	29	78	2.29 out of 5	\$345	\$10,005	
Distribution Mains	P-1894	WW	Main St.	6	Cast iron	222	78	2.29 out of 5	\$345	\$76,590	
Distribution Mains	P-788	WW	Main St.	6	Cast iron	133	78	2.29 out of 5	\$345	\$45,885	
Distribution Mains	P-1007	WW	Main St.	10	Cast iron	223	129	1.87 out of 5	\$345	\$76,935	
Distribution Mains	P-1008	WW	Main St.	10	Cast iron	126	129	1.87 out of 5	\$345	\$43,470	
Distribution Mains	P-1105	WW	Main St.	8	Cast iron	1,240	129	1.87 out of 5	\$345	\$427,800	
Distribution Mains	P-1110	WW	Main St.	8	Cast iron	60	129	1.87 out of 5	\$345	\$20,700	
Distribution Mains	P-1112	WW	Main St.	8	Cast iron	724	129	1.87 out of 5	\$345	\$249,780	
Distribution Mains	P-1115	WW	Main St.	8	Cast iron	399	129	1.87 out of 5	\$345	\$137,655	
Distribution Mains	P-1116	WW	Main St.	8	Cast iron	388	129	1.87 out of 5	\$345	\$133,860	
Distribution Mains	P-1117	WW	Main St.	8	Cast iron	214	129	1.87 out of 5	\$345	\$73,830	
Distribution Mains	P-1118	WW	Main St.	8	Cast iron	163	129	1.87 out of 5	\$345	\$56,235	
Distribution Mains	P-1119	WW	Main St.	8	Cast iron	622	129	1.87 out of 5	\$345	\$214,590	
Distribution Mains	P-1125	WW	Main St.	8	Cast iron	680	129	1.87 out of 5	\$345	\$234,600	
Distribution Mains	P-1130	WW	Main St.	8	Cast iron	217	129	1.87 out of 5	\$345	\$74,865	
Distribution Mains	P-1251	WW	Main St.	8	Cast iron	1,335	129	1.87 out of 5	\$345	\$460,575	
Distribution Mains	P-1481	WW	Main St.	8	Cast iron	383	129	1.87 out of 5	\$345	\$132,135	
Distribution Mains	P-1482	WW	Main St.	8	Cast iron	168	129	1.87 out of 5	\$345	\$57,960	
Distribution Mains	P-1846	WW	Main St.	8	Cast iron	221	129	1.87 out of 5	\$345	\$76,245	
Distribution Mains	P-1984	WW	Main St.	8	Cast iron	25	129	1.87 out of 5	\$345	\$8,625	
Distribution Mains	P-826	WW	Main St.	10	Cast iron	64	129	1.87 out of 5	\$345	\$22,080	
Distribution Mains	P-827	WW	Main St.	10	Cast iron	273	129	1.87 out of 5	\$345	\$94,185	
Distribution Mains	P-930	WW	Main St.	8	Cast iron	363	129	1.87 out of 5	\$345	\$125,235	
Distribution Mains	P-931	WW	Main St.	8	Cast iron	243	129	1.87 out of 5	\$345	\$83,835	
Distribution Mains	P-1027	WW	Main St.	8	Cast iron	221	79	1.58 out of 5	\$345	\$76,245	
Distribution Mains	P-1029	WW	Main St.	8	Cast iron	115	79	1.58 out of 5	\$345	\$39,675	
Distribution Mains	P-1030	WW	Main St.	8	Cast iron	359	79	1.58 out of 5	\$345	\$123,855	
Distribution Mains	P-1031	WW	Main St.	8	Cast iron	315	79	1.58 out of 5	\$345	\$108,675	
Distribution Mains	P-1033	WW	Main St.	8	Cast iron	1,226	79	1.58 out of 5	\$345	\$422,970	
Distribution Mains	P-1336	WW	Main St.	8	Cast iron	73	79	1.58 out of 5	\$345	\$25,185	
Distribution Mains	P-1337	WW	Main St.	8	Cast iron	247	79	1.58 out of 5	\$345	\$85,215	
Distribution Mains	P-1500	WW	Main St.	8	Cast iron	587	79	1.58 out of 5	\$345	\$202,515	
Distribution Mains	P-1501	WW	Main St.	8	Cast iron	677	79	1.58 out of 5	\$345	\$233,565	
Distribution Mains	P-641	WW	Main St.	8	Cast iron	275	79	1.58 out of 5	\$345	\$94,875	
Transmission Mains	P-1214	WW	Main St.	20	Ductile Iron	850	7	0 out of 5	N/A	\$0	
Transmission Mains	P-1256	WW	Main St.	20	Ductile Iron	266	7	0 out of 5	N/A	\$0	
Distribution Mains	P-1850	WW	Main St.	8	Ductile Iron	23	8	0 out of 5	N/A	\$0	
Transmission Mains	P-1858	WW	Main St.	20	Ductile Iron	24	7	0 out of 5	N/A	\$0	
Distribution Mains	P-1865	WW	Main St.	10	Ductile Iron	190	15	0 out of 5	N/A	\$0	
Distribution Mains	P-1887	WW	Main St.	8	Ductile Iron	21	13	0 out of 5	N/A	\$0	
Distribution Mains	P-1888	WW	Main St.	8	Ductile Iron	24	13	0 out of 5	N/A	\$0	
Transmission Mains	P-1921	WW	Main St.	12	Ductile Iron	33	8	0 out of 5	N/A	\$0	
Transmission Mains	P-828	WW	Main St.	20	Ductile Iron	182	7	0 out of 5	N/A	\$0	
Transmission Mains	P-925	WW	Main St.	20	Ductile Iron	523	7	0 out of 5	N/A	\$0	
Transmission Mains	P-932	WW	Main St.	20	Ductile Iron	25	7	0 out of 5	N/A	\$0	
Transmission Mains	P-941	WW	Main St.	20	Ductile Iron	300	7	0 out of 5	N/A	\$0	
Transmission Mains	P-982	WW	Main St.	20	Ductile Iron	120	7	0 out of 5	N/A	\$0	
Distribution Mains	P-1120	WW	Manchester St.	4	Cast iron	285	129	4.01 out of 5	\$345	\$98,325	
Distribution Mains	P-1121	WW	Manchester St.	4	Cast iron	474	129	3.3 out of 5	\$345	\$163,530	
Distribution Mains	P-1122	WW	Manchester St.	4	Cast iron	144	129	3.3 out of 5	\$345	\$49,680	
Distribution Mains	P-1113	WW	Manchester St.	6	Cast iron	247	129	2.58 out of 5	\$345	\$85,215	
Distribution Mains	P-1132	WW	Manchester St.	8	Cast iron	80	129	1.87 out of 5	\$345	\$27,600	
Distribution Mains	P-1991	WW	Manchester St.	4	Ductile Iron	22	9	1.43 out of 5	\$345	\$7,590	
Transmission Mains	P-1136	WW	Manchester St.	12	Ductile Iron	246	27	0.15 out of 5	N/A	\$0	
Distribution Mains	P-1992	WW	Manchester St.	8	Ductile Iron	23	9	0 out of 5	N/A	\$0	
Distribution Mains	P-1200	WW	Maple Ave.	6	Cast iron	949	129	2.58 out of 5	\$345	\$327,405	
Distribution Mains	P-822	WW	Maple Ave.	6	Cast iron	263	129	2.58 out of 5	\$345	\$90,735	
Distribution Mains	P-823	WW	Maple Ave.	6	Cast iron	660	129	2.58 out of 5	\$345	\$227,700	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-1202	WW	Maple St.	6	Cast iron	683	129	2.58 out of 5	\$345	\$235,635	
Distribution Mains	P-1204	WW	Maple St.	6	Cast iron	638	84	2.43 out of 5	\$345	\$220,110	
Distribution Mains	P-1926	WW	Maple St.	6	Ductile Iron	21	4	0.71 out of 5	\$345	\$7,245	
Transmission Mains	P-1925	WW	Maple St.	12	Ductile Iron	30	4	0 out of 5	N/A	\$0	
Distribution Mains	P-158	WW	Marco Dr.	8	Asbestos Cement	244	37	1.58 out of 5	\$345	\$84,180	
Distribution Mains	P-163	WW	Marco Dr.	8	Asbestos Cement	244	37	1.58 out of 5	\$345	\$84,180	
Distribution Mains	P-166	WW	Marco Dr.	8	Asbestos Cement	244	37	1.58 out of 5	\$345	\$84,180	
Distribution Mains	P-168	WW	Marco Dr.	8	Asbestos Cement	244	37	1.58 out of 5	\$345	\$84,180	
Distribution Mains	P-173	WW	Marco Dr.	8	Asbestos Cement	263	37	1.58 out of 5	\$345	\$90,735	
Distribution Mains	P-174	WW	Marco Dr.	8	Asbestos Cement	173	37	1.58 out of 5	\$345	\$59,685	
Distribution Mains	P-319	WW	Mark Fore Dr.	8	Asbestos Cement	884	34	1.58 out of 5	\$345	\$304,980	
Distribution Mains	P-240	WW	Market St.	8	Ductile Iron	248	86	0 out of 5	N/A	\$0	
Distribution Mains	P-401	WW	Mary Ave.	6	Asbestos Cement	397	45	2.43 out of 5	\$345	\$136,965	IFR 2014B
Distribution Mains	P-403	WW	Mary Ave.	6	Asbestos Cement	133	45	2.43 out of 5	\$345	\$45,885	IFR 2014B
Distribution Mains	P-10026	WW	Mary Ave.	2	Copper	200	45	2.29 out of 5	\$345	\$69,000	IFR 2014B
Distribution Mains	P-140	WW	Maryland Dr.	8	Ductile Iron	477	4	0 out of 5	N/A	\$0	
Distribution Mains	P-1723	WW	Maryland Dr.	8	Ductile Iron	36	10	0 out of 5	N/A	\$0	
Distribution Mains	P-10023	WW	Mason St.	6	Asbestos Cement	19	60	2.58 out of 5	\$345	\$6,555	
Distribution Mains	P-398	WW	Mason St.	6	Asbestos Cement	266	60	2.58 out of 5	\$345	\$91,770	IFR 2014B
Distribution Mains	P-400	WW	Mason St.	6	Asbestos Cement	240	60	2.58 out of 5	\$345	\$82,800	IFR 2014B
Distribution Mains	P-404	WW	Mason St.	2	Copper	237	82	2.58 out of 5	\$345	\$81,765	IFR 2014B
Distribution Mains	P-406	WW	Mason St.	6	Asbestos Cement	176	60	2.58 out of 5	\$345	\$60,720	IFR 2014B
Distribution Mains	P-1604	WW	Matteson Ave.	8	Cast iron	497	114	3.3 out of 5	\$345	\$171,465	
Distribution Mains	P-553	WW	Matteson Ave.	8	Cast iron	338	114	1.87 out of 5	\$345	\$116,610	
Distribution Mains	P-554	WW	Matteson Ave.	8	Cast iron	241	114	1.87 out of 5	\$345	\$83,145	
Distribution Mains	P-157	WW	Maywood Dr.	8	Ductile Iron	475	4	0 out of 5	N/A	\$0	
Distribution Mains	P-1727	WW	Maywood Dr.	8	Ductile Iron	29	10	0 out of 5	N/A	\$0	
Distribution Mains	P-1053	WW	McElroy St.	8	Ductile Iron	365	3	0 out of 5	N/A	\$0	
Distribution Mains	P-740	WW	McGlynn St.	1.5	Copper	477	73	3.15 out of 5	\$345	\$164,565	
Distribution Mains	P-742	WW	McNiff St.	4	Cast iron	84	74	3.01 out of 5	\$345	\$28,980	
Distribution Mains	P-743	WW	McNiff St.	6	Cast iron	344	74	3 out of 5	\$345	\$118,680	
Distribution Mains	P-751	WW	McNiff St.	6	Cast iron	147	74	3 out of 5	\$345	\$50,715	
Distribution Mains	P-1977	WW	McNiff St.	6	Cast iron	44	74	2.29 out of 5	\$345	\$15,180	
Distribution Mains	P-745	WW	McNiff St.	6	Cast iron	488	74	2.29 out of 5	\$345	\$168,360	
Distribution Mains	P-749	WW	McNiff St.	6	Cast iron	124	74	2.29 out of 5	\$345	\$42,780	
Distribution Mains	P-247	WW	McTeers Ct.	8	Ductile Iron	273	1	0 out of 5	N/A	\$0	
Distribution Mains	P-481	WW	Meadow Dr.	6	Asbestos Cement	654	58	2.43 out of 5	\$345	\$225,630	
Distribution Mains	P-845	WW	Meadowchase Ln.	8	PVC	341	26	0.44 out of 5	\$345	\$117,645	
Distribution Mains	P-13	WW	Medeival Way	8	Ductile Iron	534	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-14	WW	Medeival Way	8	Ductile Iron	643	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-20	WW	Medeival Way	8	Ductile Iron	280	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-5	WW	Medeival Way	8	Ductile Iron	442	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-6	WW	Medeival Way	8	Ductile Iron	234	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-838	WW	Medinah Dr.	8	Ductile Iron	444	13	0 out of 5	N/A	\$0	
Transmission Mains	P-1186	WW	Meggan Ct.	12	PVC	279	27	0.44 out of 5	\$345	\$96,255	
Transmission Mains	P-1419	WW	Meggan Ct.	12	PVC	134	27	0.44 out of 5	\$345	\$46,230	
Transmission Mains	P-1420	WW	Meggan Ct.	12	PVC	291	27	0.44 out of 5	\$345	\$100,395	
Transmission Mains	P-1423	WW	Meggan Ct.	12	Ductile Iron	17	14	0 out of 5	N/A	\$0	
Distribution Mains	P-1808	WW	Mello St.	6	Asbestos Cement	45	63	2.58 out of 5	\$345	\$15,525	
Distribution Mains	P-944	WW	Mello St.	6	Asbestos Cement	499	63	2.58 out of 5	\$345	\$172,155	
Distribution Mains	P-1814	WW	Mello St.	1	Copper	248	63	2.44 out of 5	\$345	\$85,560	
Distribution Mains	P-1807	WW	Mello St.	8	Ductile Iron	25	5	0 out of 5	N/A	\$0	
Distribution Mains	P-1799	WW	Melrose St.	6	Cast iron	18	76	2.29 out of 5	\$345	\$6,210	
Distribution Mains	P-958	WW	Melrose St.	6	Cast iron	57	76	2.29 out of 5	\$345	\$19,665	
Distribution Mains	P-959	WW	Melrose St.	6	Cast iron	636	76	2.29 out of 5	\$345	\$219,420	
Distribution Mains	P-1800	WW	Melrose St.	6	Ductile Iron	19	5	0.71 out of 5	\$345	\$6,555	
Distribution Mains	P-1801	WW	Melrose St.	8	Ductile Iron	21	5	0 out of 5	N/A	\$0	
Distribution Mains	P-410	WW	Miami St.	2	Copper	214	65	2.44 out of 5	\$345	\$73,830	IFR 2014B
Distribution Mains	P-107	WW	Michael St.	6	Asbestos Cement	222	43	2.43 out of 5	\$345	\$76,590	
Distribution Mains	P-108	WW	Michael St.	6	Asbestos Cement	267	43	2.43 out of 5	\$345	\$92,115	
Distribution Mains	P-752	WW	Middle St.	2	Galvanized iron	270	81	3.44 out of 5	\$345	\$93,150	
Distribution Mains	P-165	WW	Midland Dr.	8	Asbestos Cement	442	37	1.58 out of 5	\$345	\$152,490	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-1738	WW	Midway Dr.	8	Ductile Iron	113	4	0 out of 5	N/A	\$0	
Distribution Mains	P-191	WW	Midway Dr.	8	Ductile Iron	304	4	0 out of 5	N/A	\$0	
Distribution Mains	P-676	WW	Mill St.	4	Cast iron	429	129	3.3 out of 5	\$345	\$148,005	
Distribution Mains	P-677	WW	Mill St.	4	Cast iron	290	129	3.3 out of 5	\$345	\$100,050	
Distribution Mains	P-968	WW	Miller Dr.	6	Asbestos Cement	470	59	2.43 out of 5	\$345	\$162,150	
Distribution Mains	P-1827	WW	Miller Dr.	6	Ductile Iron	26	5	0.71 out of 5	\$345	\$8,970	
Distribution Mains	P-1826	WW	Miller Dr.	8	Ductile Iron	20	5	0 out of 5	N/A	\$0	
Distribution Mains	P-1380	WW	Misty Oak Ct.	6	Ductile Iron	124	23	0.86 out of 5	\$345	\$42,780	
Distribution Mains	P-500	WW	Monterey Dr.	8	Asbestos Cement	617	51	1.72 out of 5	\$345	\$212,865	
Distribution Mains	P-503	WW	Monterey Dr.	8	Asbestos Cement	245	51	1.72 out of 5	\$345	\$84,525	
Distribution Mains	P-505	WW	Monterey Dr.	8	Asbestos Cement	247	51	1.72 out of 5	\$345	\$85,215	
Distribution Mains	P-506	WW	Monterey Dr.	8	Asbestos Cement	241	51	1.72 out of 5	\$345	\$83,145	
Distribution Mains	P-508	WW	Monterey Dr.	8	Asbestos Cement	251	51	1.72 out of 5	\$345	\$86,595	
Distribution Mains	P-509	WW	Monterey Dr.	8	Asbestos Cement	1,296	51	1.72 out of 5	\$345	\$447,120	
Distribution Mains	P-302	WW	Moran St.	8	Asbestos Cement	267	47	1.72 out of 5	\$345	\$92,115	
Distribution Mains	P-586	WW	Moretti Dr.	8	Ductile Iron	300	11	0 out of 5	N/A	\$0	
Distribution Mains	P-318	WW	Morningside Dr.	8	Asbestos Cement	823	36	2.29 out of 5	\$345	\$283,935	
Distribution Mains	P-308	WW	Morningside Dr.	8	Asbestos Cement	309	36	1.58 out of 5	\$345	\$106,605	
Distribution Mains	P-323	WW	Morningside Dr.	8	Asbestos Cement	287	36	1.58 out of 5	\$345	\$99,015	
Distribution Mains	P-583	WW	Morris St.	6	Asbestos Cement	628	66	2.58 out of 5	\$345	\$216,660	
Distribution Mains	P-1382	WW	Morris St.	8	Ductile Iron	93	8	0 out of 5	N/A	\$0	
Distribution Mains	P-10030	WW	Moskalyk St.	1	Copper	241	42	2.29 out of 5	\$345	\$83,145	
Distribution Mains	P-310	WW	Musket Rd.	8	Asbestos Cement	276	34	1.58 out of 5	\$345	\$95,220	
Distribution Mains	P-314	WW	Musket Rd.	8	Asbestos Cement	722	34	1.58 out of 5	\$345	\$249,090	
Distribution Mains	P-417	WW	Myron St.	6	Asbestos Cement	616	38	2.29 out of 5	\$345	\$212,520	
Distribution Mains	P-299	WW	Napolean St.	6	Asbestos Cement	310	47	2.43 out of 5	\$345	\$106,950	
Distribution Mains	P-512	WW	Narragansett Ave.	8	Ductile Iron	934	13	0 out of 5	N/A	\$0	
Distribution Mains	P-513	WW	Narragansett Ave.	8	Ductile Iron	434	13	0 out of 5	N/A	\$0	
Distribution Mains	P-1837	WW	Navarre St.	6	Cast iron	671	79	2.29 out of 5	\$345	\$231,495	
Distribution Mains	P-1836	WW	Navarre St.	6	Ductile Iron	24	5	0.71 out of 5	\$345	\$8,280	
Distribution Mains	P-1835	WW	Navarre St.	8	Ductile Iron	22	5	0 out of 5	N/A	\$0	
Distribution Mains	P-1085	WW	Nestor St.	2	Galvanized iron	118	129	3.59 out of 5	\$345	\$40,710	
Distribution Mains	P-1086	WW	Nestor St.	2	Galvanized iron	277	129	3.59 out of 5	\$345	\$95,565	
Distribution Mains	P-1082	WW	Nestor St.	6	Cast iron	150	129	2.58 out of 5	\$345	\$51,750	
Distribution Mains	P-1083	WW	Nestor St.	6	Cast iron	410	129	2.58 out of 5	\$345	\$141,450	
Distribution Mains	P-367	WW	New London Ave.	4	Cast iron	1,158	82	4.58 out of 5	\$345	\$399,510	IFR 2015B
Distribution Mains	P-1308	WW	New London Ave.	4	Cast iron	444	82	3.86 out of 5	\$345	\$153,180	IFR 2015B
Distribution Mains	P-1312	WW	New London Ave.	4	Cast iron	239	82	3.15 out of 5	\$345	\$82,455	IFR 2015B
Distribution Mains	P-1985	WW	New London Ave.	1	Cast iron	639	82	3.15 out of 5	\$345	\$220,455	IFR 2015B
Distribution Mains	P-1103	WW	New London Ave.	6	Cast iron	249	82	2.43 out of 5	\$345	\$85,905	
Distribution Mains	P-1104	WW	New London Ave.	6	Cast iron	384	82	2.43 out of 5	\$345	\$132,480	IFR 2014B
Distribution Mains	P-1105	WW	New London Ave.	6	Cast iron	230	82	2.43 out of 5	\$345	\$79,350	IFR 2014B
Distribution Mains	P-324	WW	New London Ave.	8	Asbestos Cement	1,115	42	2.43 out of 5	\$345	\$384,675	
Distribution Mains	P-370	WW	New London Ave.	6	Cast iron	452	82	2.43 out of 5	\$345	\$155,940	IFR 2015B
Distribution Mains	P-371	WW	New London Ave.	6	Cast iron	467	82	2.43 out of 5	\$345	\$161,115	IFR 2014B
Distribution Mains	P-372	WW	New London Ave.	6	Cast iron	335	82	2.43 out of 5	\$345	\$115,575	IFR 2014B
Distribution Mains	P-1334	WW	New London Ave.	8	Asbestos Cement	200	74	1.87 out of 5	\$345	\$69,000	IFR 2015B
Distribution Mains	P-332	WW	New London Ave.	8	Asbestos Cement	635	74	1.87 out of 5	\$345	\$219,075	IFR 2015B
Distribution Mains	P-326	WW	New London Ave.	8	Asbestos Cement	697	42	1.72 out of 5	\$345	\$240,465	
Distribution Mains	P-328	WW	New London Ave.	8	Asbestos Cement	832	42	1.72 out of 5	\$345	\$287,040	
Distribution Mains	P-1168	WW	New London Tpk.	4	Cast iron	1,277	127	3.3 out of 5	\$345	\$440,565	
Transmission Mains	P-112	WW	New London Tpk.	12	Asbestos Cement	758	55	1.72 out of 5	\$345	\$261,510	
Transmission Mains	P-113	WW	New London Tpk.	12	Asbestos Cement	69	55	1.72 out of 5	\$345	\$23,805	
Transmission Mains	P-114	WW	New London Tpk.	12	Asbestos Cement	592	55	1.72 out of 5	\$345	\$204,240	
Distribution Mains	P-1162	WW	New London Tpk.	8	Cast iron	102	86	1.72 out of 5	\$345	\$35,190	
Distribution Mains	P-1164	WW	New London Tpk.	8	Cast iron	599	86	1.72 out of 5	\$345	\$206,655	
Distribution Mains	P-1166	WW	New London Tpk.	8	Cast iron	952	86	1.72 out of 5	\$345	\$328,440	
Distribution Mains	P-1167	WW	New London Tpk.	8	Cast iron	600	86	1.72 out of 5	\$345	\$207,000	
Transmission Mains	P-1170	WW	New London Tpk.	12	Asbestos Cement	1,605	49	1.72 out of 5	\$345	\$553,725	
Transmission Mains	P-1510	WW	New London Tpk.	12	Asbestos Cement	70	55	1.72 out of 5	\$345	\$24,150	
Transmission Mains	P-1993	WW	New London Tpk.	12	Asbestos Cement	712	55	1.72 out of 5	\$345	\$245,640	
Transmission Mains	P-1995	WW	New London Tpk.	12	Asbestos Cement	601	55	1.72 out of 5	\$345	\$207,345	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-26	WW	New London Tpk.	12	Asbestos Cement	357	54	1.72 out of 5	\$345	\$123,165	
Transmission Mains	P-1163	WW	New London Tpk.	12	Asbestos Cement	138	36	1.58 out of 5	\$345	\$47,610	
Transmission Mains	P-1171	WW	New London Tpk.	12	Asbestos Cement	909	36	1.58 out of 5	\$345	\$313,605	
Distribution Mains	P-301	WW	Newell St.	6	Asbestos Cement	790	34	3 out of 5	\$345	\$272,550	
Distribution Mains	P-303	WW	Newell St.	8	Asbestos Cement	131	47	1.72 out of 5	\$345	\$45,195	
Distribution Mains	P-286	WW	Newell St.	6	Ductile Iron	164	21	0.86 out of 5	\$345	\$56,580	
Distribution Mains	P-290	WW	Newell St.	6	Ductile Iron	234	21	0.86 out of 5	\$345	\$80,730	
Distribution Mains	P-291	WW	Newell St.	6	Ductile Iron	231	21	0.86 out of 5	\$345	\$79,695	
Distribution Mains	P-294	WW	Newell St.	6	Ductile Iron	236	21	0.86 out of 5	\$345	\$81,420	
Distribution Mains	P-1362	WW	Newlight St.	6	Asbestos Cement	567	48	2.43 out of 5	\$345	\$195,615	
Distribution Mains	P-1822	WW	Newlight St.	6	Ductile Iron	16	5	0.71 out of 5	\$345	\$5,520	
Distribution Mains	P-1821	WW	Newlight St.	8	Ductile Iron	17	5	0 out of 5	N/A	\$0	
Distribution Mains	P-1824	WW	Newlight St.	8	Ductile Iron	26	5	0 out of 5	N/A	\$0	
Distribution Mains	P-1878	WW	Nichols Ct.	1	Copper	279	60	2.44 out of 5	\$345	\$96,255	
Distribution Mains	P-1180	WW	Nicole Dr.	8	Asbestos Cement	202	34	1.58 out of 5	\$345	\$69,690	
Distribution Mains	P-1181	WW	Nicole Dr.	8	Asbestos Cement	932	34	1.58 out of 5	\$345	\$321,540	
Transmission Mains	P-266	WW	Nobile St.	12	Ductile Iron	409	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-685	WW	Nolan St.	2	PVC	431	36	1.87 out of 5	\$345	\$148,695	
Distribution Mains	P-446	WW	North Gate Dr.	6	Asbestos Cement	758	39	2.29 out of 5	\$345	\$261,510	
Distribution Mains	P-1246	WW	North Pleasant St.	6	Asbestos Cement	132	39	2.29 out of 5	\$345	\$45,540	
Distribution Mains	P-1628	WW	North Pleasant St.	6	Ductile Iron	373	5	0.71 out of 5	\$345	\$128,685	
Transmission Mains	P-1242	WW	North Pleasant St.	12	Ductile Iron	522	7	0 out of 5	N/A	\$0	
Transmission Mains	P-1243	WW	North Pleasant St.	12	Ductile Iron	63	7	0 out of 5	N/A	\$0	
Transmission Mains	P-1245	WW	North Pleasant St.	12	Ductile Iron	398	7	0 out of 5	N/A	\$0	
Transmission Mains	P-1658	WW	North Pleasant St.	12	Ductile Iron	373	7	0 out of 5	N/A	\$0	
Transmission Mains	P-1911	WW	North Pleasant St.	12	Ductile Iron	102	7	0 out of 5	N/A	\$0	
Transmission Mains	P-1912	WW	North Pleasant St.	12	Ductile Iron	25	5	0 out of 5	N/A	\$0	
Distribution Mains	P-10001	WW	Nottingham Dr.	8	Asbestos Cement	390	41	1.72 out of 5	\$345	\$134,550	
Distribution Mains	P-10002	WW	Nottingham Dr.	8	Asbestos Cement	101	41	1.72 out of 5	\$345	\$34,845	
Distribution Mains	P-10003	WW	Nottingham Dr.	8	Asbestos Cement	557	41	1.72 out of 5	\$345	\$192,165	
Distribution Mains	P-10004	WW	Nottingham Dr.	8	Asbestos Cement	168	41	1.72 out of 5	\$345	\$57,960	
Distribution Mains	P-1440	WW	Nottingham Dr.	8	Asbestos Cement	309	41	1.72 out of 5	\$345	\$106,605	
Distribution Mains	P-1441	WW	Nottingham Dr.	8	Asbestos Cement	119	41	1.72 out of 5	\$345	\$41,055	
Distribution Mains	P-63	WW	Nottingham Dr.	8	Asbestos Cement	555	41	1.72 out of 5	\$345	\$191,475	
Distribution Mains	P-64	WW	Nottingham Dr.	8	Asbestos Cement	334	41	1.72 out of 5	\$345	\$115,230	
Distribution Mains	P-10000	WW	Nottingham Dr.	8	Ductile Iron	33	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1277	WW	Nottingham Dr.	16	Ductile Iron	1,189	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1442	WW	Nottingham Dr.	16	Ductile Iron	818	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1443	WW	Nottingham Dr.	16	Ductile Iron	254	14	0 out of 5	N/A	\$0	
Distribution Mains	P-1444	WW	Nottingham Dr.	8	Ductile Iron	4	14	0 out of 5	N/A	\$0	
Distribution Mains	P-415	WW	Noxon St.	6	Asbestos Cement	276	41	2.43 out of 5	\$345	\$95,220	
Distribution Mains	P-416	WW	Noxon St.	6	Asbestos Cement	282	41	2.43 out of 5	\$345	\$97,290	
Distribution Mains	P-1851	WW	Oak St.	6	Cast iron	118	129	2.58 out of 5	\$345	\$40,710	
Distribution Mains	P-914	WW	Oak St.	6	Cast iron	185	129	2.58 out of 5	\$345	\$63,825	
Distribution Mains	P-915	WW	Oak St.	6	Cast iron	112	129	2.58 out of 5	\$345	\$38,640	
Distribution Mains	P-211	WW	Oakland Dr.	6	Asbestos Cement	470	64	2.58 out of 5	\$345	\$162,150	
Distribution Mains	P-212	WW	Oakland Dr.	6	Asbestos Cement	237	64	2.58 out of 5	\$345	\$81,765	
Distribution Mains	P-222	WW	Oakland Dr.	6	Asbestos Cement	361	67	2.58 out of 5	\$345	\$124,545	
Distribution Mains	P-1746	WW	Oakland Dr.	6	Ductile Iron	45	4	0.71 out of 5	\$345	\$15,525	
Distribution Mains	P-1744	WW	Oakland Dr.	8	Ductile Iron	313	4	0 out of 5	N/A	\$0	
Distribution Mains	P-1466	WW	Oakridge Dr.	6	PVC	241	28	1.15 out of 5	\$345	\$83,145	
Transmission Mains	P-10019	WW	Oakridge Dr.	12	PVC	133	28	0.44 out of 5	\$345	\$45,885	
Transmission Mains	P-10020	WW	Oakridge Dr.	12	PVC	174	28	0.44 out of 5	\$345	\$60,030	
Transmission Mains	P-1152	WW	Oakridge Dr.	12	PVC	157	28	0.44 out of 5	\$345	\$54,165	
Transmission Mains	P-1154	WW	Oakridge Dr.	12	PVC	491	28	0.44 out of 5	\$345	\$169,395	
Distribution Mains	P-1156	WW	Oakridge Dr. Easement	8	PVC	473	28	0.44 out of 5	\$345	\$163,185	
Distribution Mains	P-488	WW	Old Carriage Rd.	8	Asbestos Cement	1,209	38	1.58 out of 5	\$345	\$417,105	
Distribution Mains	P-1507	WW	Ontario St.	2	Galvanized iron	250	51	3.15 out of 5	\$345	\$86,250	
Distribution Mains	P-1506	WW	Ontario St.	6	PVC	298	51	1.29 out of 5	\$345	\$102,810	
Distribution Mains	P-1098	WW	Orchard St.	6	Asbestos Cement	191	43	2.43 out of 5	\$345	\$65,895	
Distribution Mains	P-1099	WW	Orchard St.	6	Asbestos Cement	150	43	2.43 out of 5	\$345	\$51,750	
Distribution Mains	P-10038	WW	Orchard St.	2	Copper	101	43	2.29 out of 5	\$345	\$34,845	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-1175	WW	Oriole Ave.	6	Asbestos Cement	744	64	2.58 out of 5	\$345	\$256,680	
Distribution Mains	P-584	WW	Orrin St.	6	Asbestos Cement	274	65	3.29 out of 5	\$345	\$94,530	
Distribution Mains	P-725	WW	Ottawa St.	6	Cast iron	245	129	2.58 out of 5	\$345	\$84,525	
Distribution Mains	P-727	WW	Ottawa St.	6	Cast iron	267	129	2.58 out of 5	\$345	\$92,115	
Distribution Mains	P-728	WW	Ottawa St.	6	Cast iron	87	128	2.58 out of 5	\$345	\$30,015	
Distribution Mains	P-675	WW	Ottawa St.	4	Ductile Iron	240	2	1.43 out of 5	\$345	\$82,800	
Distribution Mains	P-1973	WW	Ottawa St.	6	Ductile Iron	274	2	0.71 out of 5	\$345	\$94,530	
Distribution Mains	P-1734	WW	Overhill Dr.	8	Ductile Iron	49	10	0 out of 5	N/A	\$0	
Distribution Mains	P-1745	WW	Overhill Dr.	8	Ductile Iron	318	4	0 out of 5	N/A	\$0	
Distribution Mains	P-216	WW	Overhill Dr.	8	Ductile Iron	463	4	0 out of 5	N/A	\$0	
Distribution Mains	P-217	WW	Overhill Dr.	8	Ductile Iron	231	4	0 out of 5	N/A	\$0	
Distribution Mains	P-933	WW	Packard St.	6	Cast iron	278	129	2.58 out of 5	\$345	\$95,910	
Distribution Mains	P-1849	WW	Packard St.	8	Cast iron	20	129	1.87 out of 5	\$345	\$6,900	
Distribution Mains	P-339	WW	Park Blvd.	8	Asbestos Cement	254	64	2.58 out of 5	\$345	\$87,630	IFR 2015B
Distribution Mains	P-350	WW	Park Blvd.	8	Asbestos Cement	289	64	2.58 out of 5	\$345	\$99,705	IFR 2015B
Distribution Mains	P-331	WW	Park Blvd.	8	Asbestos Cement	237	64	1.87 out of 5	\$345	\$81,765	IFR 2015B
Distribution Mains	P-337	WW	Park Blvd.	8	Asbestos Cement	264	64	1.87 out of 5	\$345	\$91,080	IFR 2015B
Distribution Mains	P-979	WW	Parker St.	6	Cast iron	142	129	2.58 out of 5	\$345	\$48,990	
Distribution Mains	P-980	WW	Parker St.	6	Cast iron	1,297	129	2.58 out of 5	\$345	\$447,465	
Distribution Mains	P-806	WW	Patrick Quinn Dr.	6	Asbestos Cement	301	36	2.29 out of 5	\$345	\$103,845	
Distribution Mains	P-807	WW	Patrick Quinn Dr.	6	Asbestos Cement	191	36	2.29 out of 5	\$345	\$65,895	
Distribution Mains	P-810	WW	Patrick Quinn Dr.	6	Asbestos Cement	241	36	2.29 out of 5	\$345	\$83,145	
Transmission Mains	P-1367	WW	Pawtuxet Ter.	12	Ductile Iron	200	11	0 out of 5	N/A	\$0	
Transmission Mains	P-1601	WW	Pawtuxet Ter.	12	Ductile Iron	142	11	0 out of 5	N/A	\$0	
Transmission Mains	P-556	WW	Pawtuxet Ter.	12	Ductile Iron	492	11	0 out of 5	N/A	\$0	
Transmission Mains	P-577	WW	Pawtuxet Ter.	12	Ductile Iron	150	11	0 out of 5	N/A	\$0	
Transmission Mains	P-580	WW	Pawtuxet Ter.	12	Ductile Iron	612	11	0 out of 5	N/A	\$0	
Transmission Mains	P-582	WW	Pawtuxet Ter.	12	Ductile Iron	281	11	0 out of 5	N/A	\$0	
Transmission Mains	P-585	WW	Pawtuxet Ter.	12	Ductile Iron	276	11	0 out of 5	N/A	\$0	
Transmission Mains	P-592	WW	Pawtuxet Ter.	12	Ductile Iron	851	11	0 out of 5	N/A	\$0	
Distribution Mains	P-1056	WW	Payan St.	6	Cast iron	239	78	2.29 out of 5	\$345	\$82,455	
Distribution Mains	P-1057	WW	Payan St.	6	Cast iron	128	78	2.29 out of 5	\$345	\$44,160	
Distribution Mains	P-1059	WW	Payan St.	6	Cast iron	168	78	2.29 out of 5	\$345	\$57,960	
Distribution Mains	P-1062	WW	Payan St.	6	Cast iron	241	78	2.29 out of 5	\$345	\$83,145	
Distribution Mains	P-1063	WW	Payan St.	6	Cast iron	216	78	2.29 out of 5	\$345	\$74,520	
Distribution Mains	P-1071	WW	Payan St.	6	Cast iron	311	78	2.29 out of 5	\$345	\$107,295	
Distribution Mains	P-1982	WW	Payan St.	6	Cast iron	253	78	2.29 out of 5	\$345	\$87,285	
Distribution Mains	P-1484	WW	Pearson St.	2	Cast iron	240	129	4.01 out of 5	\$345	\$82,800	
Distribution Mains	P-421	WW	Penel Dr.	6	Asbestos Cement	463	51	2.43 out of 5	\$345	\$159,735	
Distribution Mains	P-1090	WW	Pennsylvania Ave.	6	Cast iron	173	129	2.58 out of 5	\$345	\$59,685	
Distribution Mains	P-10041	WW	Pennsylvania Ave.	1	Copper	96	30	2.15 out of 5	\$345	\$33,120	
Distribution Mains	P-1478	WW	Pennsylvania Ave.	6	PVC	100	30	1.15 out of 5	\$345	\$34,500	
Transmission Mains	P-264	WW	Penta St.	12	Ductile Iron	363	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-267	WW	Penta St.	8	Ductile Iron	344	86	0 out of 5	N/A	\$0	
Distribution Mains	P-486	WW	Pepin St.	8	Asbestos Cement	950	50	1.72 out of 5	\$345	\$327,750	
Distribution Mains	P-487	WW	Pepin St.	8	Asbestos Cement	798	50	1.72 out of 5	\$345	\$275,310	
Distribution Mains	P-378	WW	Perkins St.	6	Asbestos Cement	769	50	3.14 out of 5	\$345	\$265,305	IFR 2014B
Distribution Mains	P-379	WW	Perkins St.	6	Asbestos Cement	150	50	2.43 out of 5	\$345	\$51,750	
Distribution Mains	P-1931	WW	Peters Ln.	8	Asbestos Cement	400	54	1.72 out of 5	\$345	\$138,000	
Distribution Mains	P-801	WW	Peters Ln.	8	Asbestos Cement	415	54	1.72 out of 5	\$345	\$143,175	
Distribution Mains	P-288	WW	Petti Dr.	6	Ductile Iron	209	21	0.86 out of 5	\$345	\$72,105	
Distribution Mains	P-293	WW	Petti Dr.	6	Ductile Iron	412	21	0.86 out of 5	\$345	\$142,140	
Distribution Mains	P-939	WW	Phenix Ave.	6	Cast iron	278	129	2.58 out of 5	\$345	\$95,910	
Distribution Mains	P-940	WW	Phenix Ave.	6	Cast iron	578	129	2.58 out of 5	\$345	\$199,410	
Distribution Mains	P-949	WW	Phenix Ave.	6	Cast iron	189	129	2.58 out of 5	\$345	\$65,205	
Distribution Mains	P-951	WW	Phenix Ave.	6	Cast iron	107	129	2.58 out of 5	\$345	\$36,915	
Distribution Mains	P-1825	WW	Phenix Ave.	8	Cast iron	751	82	1.72 out of 5	\$345	\$259,095	
Distribution Mains	P-950	WW	Phenix Ave.	8	Cast iron	155	82	1.72 out of 5	\$345	\$53,475	
Distribution Mains	P-1842	WW	Phenix Ave.	4	Ductile Iron	22	8	1.43 out of 5	\$345	\$7,590	
Transmission Mains	P-1360	WW	Phenix Ave.	12	Ductile Iron	76	7	0 out of 5	N/A	\$0	
Transmission Mains	P-1361	WW	Phenix Ave.	12	Ductile Iron	215	7	0 out of 5	N/A	\$0	
Transmission Mains	P-1363	WW	Phenix Ave.	12	Ductile Iron	25	7	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-1797	WW	Phenix Ave.	12	Ductile Iron	190	5	0 out of 5	N/A	\$0	
Distribution Mains	P-1798	WW	Phenix Ave.	8	Ductile Iron	133	5	0 out of 5	N/A	\$0	
Transmission Mains	P-1802	WW	Phenix Ave.	12	Ductile Iron	154	7	0 out of 5	N/A	\$0	
Distribution Mains	P-1803	WW	Phenix Ave.	8	Ductile Iron	24	5	0 out of 5	N/A	\$0	
Transmission Mains	P-1804	WW	Phenix Ave.	12	Ductile Iron	33	7	0 out of 5	N/A	\$0	
Transmission Mains	P-1806	WW	Phenix Ave.	12	Ductile Iron	164	7	0 out of 5	N/A	\$0	
Transmission Mains	P-1815	WW	Phenix Ave.	12	Ductile Iron	181	7	0 out of 5	N/A	\$0	
Transmission Mains	P-1819	WW	Phenix Ave.	12	Ductile Iron	19	7	0 out of 5	N/A	\$0	
Transmission Mains	P-1824	WW	Phenix Ave.	12	Ductile Iron	21	7	0 out of 5	N/A	\$0	
Distribution Mains	P-1841	WW	Phenix Ave.	8	Ductile Iron	23	8	0 out of 5	N/A	\$0	
Distribution Mains	P-952	WW	Phenix Ave.	8	Ductile Iron	25	5	0 out of 5	N/A	\$0	
Transmission Mains	P-955	WW	Phenix Ave.	12	Ductile Iron	220	7	0 out of 5	N/A	\$0	
Transmission Mains	P-956	WW	Phenix Ave.	12	Ductile Iron	325	5	0 out of 5	N/A	\$0	
Transmission Mains	P-957	WW	Phenix Ave.	12	Ductile Iron	180	5	0 out of 5	N/A	\$0	
Distribution Mains	P-961	WW	Phenix Ave.	8	Ductile Iron	246	5	0 out of 5	N/A	\$0	
Distribution Mains	P-1352	WW	Pike St.	4	Cast iron	416	129	3.3 out of 5	\$345	\$143,520	
Transmission Mains	P-1994	WW	Pine Hollow Rd.	12	Ductile Iron	655	10	0 out of 5	N/A	\$0	
Transmission Mains	P-134	WW	Pine Orchard Rd.	12	Asbestos Cement	513	45	1.72 out of 5	\$345	\$176,985	
Distribution Mains	P-123	WW	Pine Orchard Rd.	8	Asbestos Cement	531	39	1.58 out of 5	\$345	\$183,195	
Distribution Mains	P-124	WW	Pine Orchard Rd.	8	Asbestos Cement	606	37	1.58 out of 5	\$345	\$209,070	
Distribution Mains	P-125	WW	Pine Orchard Rd.	8	Asbestos Cement	550	37	1.58 out of 5	\$345	\$189,750	
Distribution Mains	P-1607	WW	Pine St.	6	Ductile Iron	312	9	0.71 out of 5	\$345	\$107,640	
Distribution Mains	P-825	WW	Pine St.	6	Ductile Iron	305	9	0.71 out of 5	\$345	\$105,225	
Distribution Mains	P-156	WW	Pinewood Dr.	8	Asbestos Cement	88	37	1.58 out of 5	\$345	\$30,360	
Distribution Mains	P-161	WW	Pinewood Dr.	8	Asbestos Cement	244	37	1.58 out of 5	\$345	\$84,180	
Distribution Mains	P-171	WW	Pinewood Dr.	8	Asbestos Cement	250	37	1.58 out of 5	\$345	\$86,250	
Distribution Mains	P-172	WW	Pinewood Dr.	8	Asbestos Cement	120	37	1.58 out of 5	\$345	\$41,400	
Distribution Mains	P-176	WW	Pinewood Dr.	8	Asbestos Cement	160	37	1.58 out of 5	\$345	\$55,200	
Distribution Mains	P-177	WW	Pinewood Dr.	8	Asbestos Cement	103	37	1.58 out of 5	\$345	\$35,535	
Distribution Mains	P-714	WW	Plante St.	2	PVC	360	33	1.87 out of 5	\$345	\$124,200	
Distribution Mains	P-1229	WW	Pleasant St.	6	Cast iron	173	129	2.58 out of 5	\$345	\$59,685	
Distribution Mains	P-1236	WW	Pleasant St.	6	Cast iron	131	129	2.58 out of 5	\$345	\$45,195	
Distribution Mains	P-1254	WW	Pleasant St.	6	Cast iron	638	129	2.58 out of 5	\$345	\$220,110	
Distribution Mains	P-1908	WW	Pleasant St.	6	Cast iron	445	129	2.58 out of 5	\$345	\$153,525	
Distribution Mains	P-1916	WW	Pleasant St.	6	Cast iron	18	129	2.58 out of 5	\$345	\$6,210	
Transmission Mains	P-1255	WW	Pleasant St.	12	Cast iron	148	129	1.87 out of 5	\$345	\$51,060	
Distribution Mains	P-1257	WW	Pleasant St.	8	Cast iron	232	129	1.87 out of 5	\$345	\$80,040	
Distribution Mains	P-1917	WW	Pleasant St.	8	Cast iron	62	129	1.87 out of 5	\$345	\$21,390	
Distribution Mains	P-1918	WW	Pleasant St.	8	Ductile Iron	64	8	0 out of 5	N/A	\$0	
Transmission Mains	P-1919	WW	Pleasant St.	12	Ductile Iron	15	8	0 out of 5	N/A	\$0	
Transmission Mains	P-1920	WW	Pleasant St.	12	Ductile Iron	30	8	0 out of 5	N/A	\$0	
Distribution Mains	P-589	WW	Podgurski St.	6	Asbestos Cement	444	60	2.58 out of 5	\$345	\$153,180	
Distribution Mains	P-1957	WW	Podgurski St.	6	Ductile Iron	139	10	0.71 out of 5	\$345	\$47,955	
Transmission Mains	P-721	WW	Pond St.	12	Cast iron	291	129	1.87 out of 5	\$345	\$100,395	
Transmission Mains	P-722	WW	Pond St.	12	Cast iron	376	129	1.87 out of 5	\$345	\$129,720	
Transmission Mains	P-723	WW	Pond St.	12	Cast iron	199	129	1.87 out of 5	\$345	\$68,655	
Transmission Mains	P-718	WW	Pond St.	12	Cast iron	540	84	1.72 out of 5	\$345	\$186,300	
Transmission Mains	P-720	WW	Pond St.	12	Cast iron	272	84	1.72 out of 5	\$345	\$93,840	
Distribution Mains	P-1475	WW	Pond View Dr.	8	Ductile Iron	337	16	0 out of 5	N/A	\$0	
Distribution Mains	P-457	WW	Pond View Dr.	8	Ductile Iron	277	16	0 out of 5	N/A	\$0	
Distribution Mains	P-507	WW	Ponderosa Dr.	6	Asbestos Cement	745	45	2.43 out of 5	\$345	\$257,025	
Distribution Mains	P-1749	WW	Pontiac Ave.	10	Ductile Iron	941	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-1043	WW	Potter Ave.	6	Cast iron	1,075	129	2.58 out of 5	\$345	\$370,875	
Distribution Mains	P-1044	WW	Potter Ave.	8	Ductile Iron	300	13	0 out of 5	N/A	\$0	
Distribution Mains	P-244	WW	Prospect Hill Ave.	12	Ductile Iron	244	86	0 out of 5	N/A	\$0	
Distribution Mains	P-246	WW	Prospect Hill Ave.	12	Ductile Iron	514	86	0 out of 5	N/A	\$0	
Transmission Mains	P-248	WW	Prospect Hill Ave.	12	Ductile Iron	279	1	0 out of 5	N/A	\$0	
Transmission Mains	P-249	WW	Prospect Hill Ave.	12	Ductile Iron	59	1	0 out of 5	N/A	\$0	
Transmission Mains	P-254	WW	Prospect Hill Ave.	12	Ductile Iron	561	1	0 out of 5	N/A	\$0	
Transmission Mains	P-255	WW	Prospect Hill Ave.	12	Ductile Iron	121	1	0 out of 5	N/A	\$0	
Transmission Mains	P-257	WW	Prospect Hill Ave.	12	Ductile Iron	226	1	0 out of 5	N/A	\$0	
Distribution Mains	P-1520	WW	Prospect Hill Rd.	8	Ductile Iron	215	1	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-1770	WW	Prospect Hill Rd.	8	Ductile Iron	24	1	0 out of 5	N/A	\$0	
Distribution Mains	P-260	WW	Prospect Hill Rd.	8	Ductile Iron	220	1	0 out of 5	N/A	\$0	
Distribution Mains	P-245	WW	Prospect St.	8	Ductile Iron	525	5	0 out of 5	N/A	\$0	
Distribution Mains	P-1685	WW	Providence St.	6	Cast iron	572	129	3.29 out of 5	\$345	\$197,340	
Distribution Mains	P-1012	WW	Providence St.	6	Cast iron	801	129	2.58 out of 5	\$345	\$276,345	
Distribution Mains	P-1014	WW	Providence St.	6	Cast iron	302	129	2.58 out of 5	\$345	\$104,190	
Distribution Mains	P-1018	WW	Providence St.	6	Cast iron	1,372	129	2.58 out of 5	\$345	\$473,340	
Distribution Mains	P-1022	WW	Providence St.	6	Cast iron	250	129	2.58 out of 5	\$345	\$86,250	
Distribution Mains	P-1023	WW	Providence St.	6	Cast iron	212	129	2.58 out of 5	\$345	\$73,140	
Distribution Mains	P-1032	WW	Providence St.	6	Cast iron	134	129	2.58 out of 5	\$345	\$46,230	
Distribution Mains	P-1877	WW	Providence St.	6	Cast iron	116	129	2.58 out of 5	\$345	\$40,020	
Distribution Mains	P-998	WW	Providence St.	6	Cast iron	638	129	2.58 out of 5	\$345	\$220,110	
Distribution Mains	P-304	WW	Providence St.	6	Cast iron	177	86	2.43 out of 5	\$345	\$61,065	
Distribution Mains	P-1701	WW	Providence St.	10	Cast iron	1,733	86	1.72 out of 5	\$345	\$597,885	
Distribution Mains	P-1762	WW	Providence St.	8	Cast iron	73	86	1.72 out of 5	\$345	\$25,185	
Distribution Mains	P-223	WW	Providence St.	10	Cast iron	121	86	1.72 out of 5	\$345	\$41,745	
Distribution Mains	P-271	WW	Providence St.	8	Cast iron	21	86	1.72 out of 5	\$345	\$7,245	
Distribution Mains	P-305	WW	Providence St.	10	Cast iron	672	86	1.72 out of 5	\$345	\$231,840	
Distribution Mains	P-994	WW	Providence St.	10	Cast iron	1,796	86	1.72 out of 5	\$345	\$619,620	
Transmission Mains	P-70	WW	Providence St.	12	Cast iron	498	46	1.43 out of 5	\$345	\$171,810	
Distribution Mains	P-1872	WW	Providence St.	6	Ductile Iron	23	7	0.71 out of 5	\$345	\$7,935	
Distribution Mains	P-1227	WW	Providence St.	8	Ductile Iron	1,632	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-1316	WW	Providence St.	8	Ductile Iron	650	20	0.15 out of 5	N/A	\$0	
Distribution Mains	P-232	WW	Providence St.	12	Ductile Iron	995	86	0 out of 5	N/A	\$0	
Distribution Mains	P-238	WW	Providence St.	12	Ductile Iron	770	86	0 out of 5	N/A	\$0	
Distribution Mains	P-239	WW	Providence St.	12	Ductile Iron	69	86	0 out of 5	N/A	\$0	
Distribution Mains	P-242	WW	Providence St.	12	Ductile Iron	451	86	0 out of 5	N/A	\$0	
Distribution Mains	P-269	WW	Providence St.	12	Ductile Iron	192	86	0 out of 5	N/A	\$0	
Transmission Mains	P-117	WW	Providence St.	12	Ductile Iron	266	11	0 out of 5	N/A	\$0	
Distribution Mains	P-1307	WW	Providence St.	8	Ductile Iron	352	1	0 out of 5	N/A	\$0	
Distribution Mains	P-1317	WW	Providence St.	8	Ductile Iron	217	1	0 out of 5	N/A	\$0	
Distribution Mains	P-1318	WW	Providence St.	8	Ductile Iron	289	1	0 out of 5	N/A	\$0	
Transmission Mains	P-1340	WW	Providence St.	12	Ductile Iron	441	7	0 out of 5	N/A	\$0	
Transmission Mains	P-153	WW	Providence St.	12	Ductile Iron	236	11	0 out of 5	N/A	\$0	
Transmission Mains	P-154	WW	Providence St.	12	Ductile Iron	245	11	0 out of 5	N/A	\$0	
Transmission Mains	P-162	WW	Providence St.	12	Ductile Iron	246	11	0 out of 5	N/A	\$0	
Transmission Mains	P-1713	WW	Providence St.	12	Ductile Iron	130	10	0 out of 5	N/A	\$0	
Transmission Mains	P-1748	WW	Providence St.	12	Ductile Iron	288	11	0 out of 5	N/A	\$0	
Transmission Mains	P-1750	WW	Providence St.	12	Ductile Iron	365	11	0 out of 5	N/A	\$0	
Distribution Mains	P-1753	WW	Providence St.	8	Ductile Iron	36	1	0 out of 5	N/A	\$0	
Distribution Mains	P-1758	WW	Providence St.	8	Ductile Iron	117	1	0 out of 5	N/A	\$0	
Distribution Mains	P-1760	WW	Providence St.	8	Ductile Iron	25	1	0 out of 5	N/A	\$0	
Transmission Mains	P-1763	WW	Providence St.	12	Ductile Iron	123	10	0 out of 5	N/A	\$0	
Distribution Mains	P-1764	WW	Providence St.	8	Ductile Iron	47	10	0 out of 5	N/A	\$0	
Transmission Mains	P-1869	WW	Providence St.	12	Ductile Iron	94	7	0 out of 5	N/A	\$0	
Transmission Mains	P-1871	WW	Providence St.	12	Ductile Iron	94	7	0 out of 5	N/A	\$0	
Transmission Mains	P-1873	WW	Providence St.	12	Ductile Iron	66	7	0 out of 5	N/A	\$0	
Transmission Mains	P-213	WW	Providence St.	12	Ductile Iron	235	11	0 out of 5	N/A	\$0	
Transmission Mains	P-215	WW	Providence St.	12	Ductile Iron	243	11	0 out of 5	N/A	\$0	
Transmission Mains	P-221	WW	Providence St.	12	Ductile Iron	237	11	0 out of 5	N/A	\$0	
Distribution Mains	P-270	WW	Providence St.	8	Ductile Iron	121	18	0 out of 5	N/A	\$0	
Distribution Mains	P-272	WW	Providence St.	8	Ductile Iron	186	1	0 out of 5	N/A	\$0	
Distribution Mains	P-273	WW	Providence St.	8	Ductile Iron	154	1	0 out of 5	N/A	\$0	
Transmission Mains	P-46	WW	Providence St.	12	Ductile Iron	208	11	0 out of 5	N/A	\$0	
Transmission Mains	P-999	WW	Providence St.	12	Ductile Iron	110	8	0 out of 5	N/A	\$0	
Transmission Mains	P-1693	WW	Providence Water Interconnecti	20	Ductile Iron	50	5	0.29 out of 5	N/A	\$0	
Transmission Mains	P-1694	WW	Providence Water Interconnecti	20	Ductile Iron	25	5	0.29 out of 5	N/A	\$0	
Transmission Mains	P-1695	WW	Providence Water Interconnecti	20	Ductile Iron	25	5	0.29 out of 5	N/A	\$0	
Transmission Mains	P-1696	WW	Providence Water Interconnecti	20	Ductile Iron	25	5	0.29 out of 5	N/A	\$0	
Transmission Mains	P-1697	WW	Providence Water Interconnecti	20	Ductile Iron	25	5	0.29 out of 5	N/A	\$0	
Transmission Mains	P-1698	WW	Providence Water Interconnecti	20	Ductile Iron	400	5	0 out of 5	N/A	\$0	
Transmission Mains	P-1699	WW	Providence Water Interconnecti	16	Ductile Iron	75	5	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-1126	WW	Pulaski St.	12	Ductile Iron	637	11	0 out of 5	N/A	\$0	
Transmission Mains	P-1127	WW	Pulaski St.	12	Ductile Iron	173	11	0 out of 5	N/A	\$0	
Transmission Mains	P-1128	WW	Pulaski St.	12	Ductile Iron	232	11	0 out of 5	N/A	\$0	
Transmission Mains	P-1602	WW	Pulaski St.	12	Ductile Iron	163	11	0 out of 5	N/A	\$0	
Transmission Mains	P-1990	WW	Pulaski St.	12	Ductile Iron	452	11	0 out of 5	N/A	\$0	
Transmission Mains	P-591	WW	Pulaski St.	12	Ductile Iron	544	11	0 out of 5	N/A	\$0	
Transmission Mains	P-593	WW	Pulaski St.	12	Ductile Iron	126	11	0 out of 5	N/A	\$0	
Transmission Mains	P-594	WW	Pulaski St.	12	Ductile Iron	241	11	0 out of 5	N/A	\$0	
Transmission Mains	P-596	WW	Pulaski St.	12	Ductile Iron	233	11	0 out of 5	N/A	\$0	
Transmission Mains	P-599	WW	Pulaski St.	12	Ductile Iron	231	11	0 out of 5	N/A	\$0	
Transmission Mains	P-601	WW	Pulaski St.	12	Ductile Iron	247	11	0 out of 5	N/A	\$0	
Transmission Mains	P-602	WW	Pulaski St.	12	Ductile Iron	187	11	0 out of 5	N/A	\$0	
Transmission Mains	P-605	WW	Pulaski St.	12	Ductile Iron	596	11	0 out of 5	N/A	\$0	
Transmission Mains	P-609	WW	Pulaski St.	12	Ductile Iron	262	11	0 out of 5	N/A	\$0	
Distribution Mains	P-491	WW	Quaker Dr.	8	Asbestos Cement	633	49	1.72 out of 5	\$345	\$218,385	
Distribution Mains	P-492	WW	Quaker Dr.	8	Asbestos Cement	425	49	1.72 out of 5	\$345	\$146,625	
Distribution Mains	P-494	WW	Quaker Dr.	8	Asbestos Cement	693	49	1.72 out of 5	\$345	\$239,085	
Distribution Mains	P-484	WW	Quaker Ln.	8	PVC	380	33	0.44 out of 5	\$345	\$131,100	
Distribution Mains	P-485	WW	Quaker Ln.	8	PVC	700	33	0.44 out of 5	\$345	\$241,500	
Transmission Mains	P-10006	WW	Quaker Ln.	12	Ductile Iron	1,043	10	0 out of 5	N/A	\$0	
Distribution Mains	P-879	WW	Queen Ann Ct.	8	Ductile Iron	256	12	0 out of 5	N/A	\$0	
Distribution Mains	P-334	WW	Queen Ave.	6	Asbestos Cement	311	66	2.58 out of 5	\$345	\$107,295	IFR 2015B
Distribution Mains	P-338	WW	Queen Ave.	6	Asbestos Cement	465	66	2.58 out of 5	\$345	\$160,425	
Distribution Mains	P-354	WW	Queen Ave.	6	Asbestos Cement	328	66	2.58 out of 5	\$345	\$113,160	IFR 2015B
Distribution Mains	P-356	WW	Queen Ave.	6	Asbestos Cement	249	66	2.58 out of 5	\$345	\$85,905	IFR 2015B
Distribution Mains	P-41	WW	Quill Dr.	6	Ductile Iron	467	23	0.86 out of 5	\$345	\$161,115	
Distribution Mains	P-1389	WW	Quill Dr.	8	Ductile Iron	225	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-43	WW	Quiver Dr.	8	Ductile Iron	554	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-692	WW	Rathburn St.	6	Asbestos Cement	264	58	2.43 out of 5	\$345	\$91,080	
Distribution Mains	P-1946	WW	Red Brook Ln.	8	Ductile Iron	148	8	0 out of 5	N/A	\$0	
Distribution Mains	P-776	WW	Regnaiere Ct.	6	PVC	452	32	1.15 out of 5	\$345	\$155,940	
Distribution Mains	P-518	WW	Rei St.	6	Asbestos Cement	134	67	2.58 out of 5	\$345	\$46,230	
Distribution Mains	P-1131	WW	Remington St.	6	Cast iron	282	119	3.29 out of 5	\$345	\$97,290	
Distribution Mains	P-1906	WW	Renaudet St.	0.8	Copper	443	5	2 out of 5	\$345	\$152,835	
Distribution Mains	P-10028	WW	Revere Ave.	6	Asbestos Cement	177	73	2.58 out of 5	\$345	\$61,065	IFR 2014B
Distribution Mains	P-390	WW	Revere Ave.	6	Asbestos Cement	220	73	2.58 out of 5	\$345	\$75,900	IFR 2014B
Distribution Mains	P-392	WW	Revere Ave.	6	Asbestos Cement	623	73	2.58 out of 5	\$345	\$214,935	IFR 2014B
Distribution Mains	P-393	WW	Revere Ave.	6	Asbestos Cement	68	73	2.58 out of 5	\$345	\$23,460	
Distribution Mains	P-397	WW	Revere Ave.	6	Asbestos Cement	774	73	2.58 out of 5	\$345	\$267,030	IFR 2014B
Distribution Mains	P-526	WW	Revere Ave.	6	Asbestos Cement	228	73	2.58 out of 5	\$345	\$78,660	
Distribution Mains	P-335	WW	Rex St.	8	Ductile Iron	309	14	0 out of 5	N/A	\$0	
Distribution Mains	P-336	WW	Rex St.	8	Ductile Iron	480	14	0 out of 5	N/A	\$0	
Distribution Mains	P-1232	WW	Richard St.	6	Asbestos Cement	608	59	2.43 out of 5	\$345	\$209,760	
Distribution Mains	P-389	WW	Ridge St.	6	Asbestos Cement	256	69	2.58 out of 5	\$345	\$88,320	IFR 2014B
Distribution Mains	P-387	WW	Ridge St.	6	Cast iron	226	75	2.29 out of 5	\$345	\$77,970	IFR 2014B
Distribution Mains	P-738	WW	Rita St.	8	Ductile Iron	496	13	0 out of 5	N/A	\$0	
Distribution Mains	P-1953	WW	Ritchotte Ct.	6	Asbestos Cement	398	34	2.29 out of 5	\$345	\$137,310	
Distribution Mains	P-287	WW	River Ave.	6	Ductile Iron	800	21	0.86 out of 5	\$345	\$276,000	
Transmission Mains	P-1319	WW	River Farms Dr.	12	PVC	325	25	0.44 out of 5	\$345	\$112,125	
Transmission Mains	P-1320	WW	River Farms Dr.	12	PVC	474	25	0.44 out of 5	\$345	\$163,530	
Transmission Mains	P-1325	WW	River Farms Dr.	12	PVC	366	25	0.44 out of 5	\$345	\$126,270	
Transmission Mains	P-1326	WW	River Farms Dr.	12	PVC	762	25	0.44 out of 5	\$345	\$262,890	
Transmission Mains	P-1772	WW	River Farms Dr.	12	PVC	157	25	0.44 out of 5	\$345	\$54,165	
Transmission Mains	P-1773	WW	River Farms Dr.	12	PVC	196	25	0.44 out of 5	\$345	\$67,620	
Transmission Mains	P-1774	WW	River Farms Dr.	12	PVC	242	25	0.44 out of 5	\$345	\$83,490	
Transmission Mains	P-1776	WW	River Farms Dr.	12	PVC	231	25	0.44 out of 5	\$345	\$79,695	
Transmission Mains	P-1778	WW	River Farms Dr.	12	PVC	399	25	0.44 out of 5	\$345	\$137,655	
Transmission Mains	P-1780	WW	River Farms Dr.	12	PVC	519	25	0.44 out of 5	\$345	\$179,055	
Distribution Mains	P-877	WW	River Farms Dr.	8	PVC	204	24	0.44 out of 5	\$345	\$70,380	
Transmission Mains	P-878	WW	River Farms Dr.	12	PVC	262	25	0.44 out of 5	\$345	\$90,390	
Transmission Mains	P-881	WW	River Farms Dr.	12	PVC	357	25	0.44 out of 5	\$345	\$123,165	
Distribution Mains	P-883	WW	River Farms Dr.	8	PVC	288	24	0.44 out of 5	\$345	\$99,360	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-884	WW	River Farms Dr.	8	PVC	187	24	0.44 out of 5	\$345	\$64,515	
Transmission Mains	P-885	WW	River Farms Dr.	12	PVC	90	25	0.44 out of 5	\$345	\$31,050	
Transmission Mains	P-886	WW	River Farms Dr.	12	PVC	244	25	0.44 out of 5	\$345	\$84,180	
Transmission Mains	P-1264	WW	River Farms Dr. Easement	12	PVC	1,059	25	0.44 out of 5	\$345	\$365,355	
Transmission Mains	P-1709	WW	River Farms Dr. Easement	12	PVC	270	25	0.44 out of 5	\$345	\$93,150	
Distribution Mains	P-224	WW	River St.	10	Cast iron	208	86	1.72 out of 5	\$345	\$71,760	IFR 2015A
Distribution Mains	P-230	WW	River St.	10	Cast iron	662	86	1.72 out of 5	\$345	\$228,390	IFR 2015A
Distribution Mains	P-231	WW	River St.	8	Cast iron	586	86	1.72 out of 5	\$345	\$202,170	IFR 2015A
Distribution Mains	P-657	WW	Riverdale Ave.	2	Cast iron	128	129	3.3 out of 5	\$345	\$44,160	
Distribution Mains	P-658	WW	Riverdale Ave.	4	Cast iron	608	129	3.3 out of 5	\$345	\$209,760	
Distribution Mains	P-1970	WW	Riverside Ter.	1	Copper	203	64	2.44 out of 5	\$345	\$70,035	
Distribution Mains	P-665	WW	Robert St.	4	Cast iron	283	85	3.15 out of 5	\$345	\$97,635	
Distribution Mains	P-666	WW	Robert St.	4	Cast iron	255	85	3.15 out of 5	\$345	\$87,975	
Distribution Mains	P-673	WW	Robert St.	6	Cast iron	416	85	2.43 out of 5	\$345	\$143,520	
Distribution Mains	P-678	WW	Robert St.	6	Cast iron	502	85	2.43 out of 5	\$345	\$173,190	
Distribution Mains	P-1972	WW	Robert St.	6	Ductile Iron	17	2	0.71 out of 5	\$345	\$5,865	
Distribution Mains	P-1971	WW	Robert St.	8	Ductile Iron	19	2	0 out of 5	N/A	\$0	
Distribution Mains	P-144	WW	Robin Ln.	8	Asbestos Cement	309	45	1.72 out of 5	\$345	\$106,605	
Distribution Mains	P-1700	WW	Robinson Way	8	Ductile Iron	269	11	0 out of 5	N/A	\$0	
Distribution Mains	P-587	WW	Robinson Way	8	Ductile Iron	242	11	0 out of 5	N/A	\$0	
Distribution Mains	P-588	WW	Robinson Way	8	Ductile Iron	260	11	0 out of 5	N/A	\$0	
Distribution Mains	P-590	WW	Robinson Way	8	Ductile Iron	228	11	0 out of 5	N/A	\$0	
Distribution Mains	P-595	WW	Robinson Way	8	Ductile Iron	732	11	0 out of 5	N/A	\$0	
Distribution Mains	P-312	WW	Rolling Green Ln.	8	Asbestos Cement	667	42	1.72 out of 5	\$345	\$230,115	
Distribution Mains	P-674	WW	Roosevelt St.	1	PVC	267	14	1.72 out of 5	\$345	\$92,115	
Distribution Mains	P-1943	WW	Rotary Dr.	8	Asbestos Cement	438	52	1.72 out of 5	\$345	\$151,110	
Distribution Mains	P-1944	WW	Rotary Dr.	8	Asbestos Cement	70	52	1.72 out of 5	\$345	\$24,150	
Distribution Mains	P-29	WW	Rotary Dr.	8	Asbestos Cement	230	52	1.72 out of 5	\$345	\$79,350	
Distribution Mains	P-31	WW	Rotary Dr.	8	Asbestos Cement	260	52	1.72 out of 5	\$345	\$89,700	
Distribution Mains	P-32	WW	Rotary Dr.	8	Asbestos Cement	305	45	1.72 out of 5	\$345	\$105,225	
Distribution Mains	P-1383	WW	Roundway Dr.	8	Ductile Iron	121	9	0 out of 5	N/A	\$0	
Distribution Mains	P-610	WW	Roundway Dr.	8	Ductile Iron	128	3	0 out of 5	N/A	\$0	
Distribution Mains	P-611	WW	Roundway Dr.	8	Ductile Iron	316	3	0 out of 5	N/A	\$0	
Distribution Mains	P-612	WW	Roundway Dr.	8	Ductile Iron	98	3	0 out of 5	N/A	\$0	
Distribution Mains	P-1097	WW	Rowland St.	6	Asbestos Cement	202	43	2.43 out of 5	\$345	\$69,690	
Distribution Mains	P-1188	WW	Royal Dr.	8	Asbestos Cement	101	43	1.72 out of 5	\$345	\$34,845	
Distribution Mains	P-95	WW	Royal Dr.	8	Asbestos Cement	766	37	1.58 out of 5	\$345	\$264,270	
Distribution Mains	P-839	WW	Saddlebrook Dr.	8	PVC	178	25	0.44 out of 5	\$345	\$61,410	
Distribution Mains	P-840	WW	Saddlebrook Dr.	8	PVC	466	26	0.44 out of 5	\$345	\$160,770	
Distribution Mains	P-842	WW	Saddlebrook Dr.	8	PVC	397	26	0.44 out of 5	\$345	\$136,965	
Transmission Mains	P-1779	WW	Sandpiper Dr.	12	Ductile Iron	590	10	0 out of 5	N/A	\$0	
Distribution Mains	P-964	WW	Schofield St.	6	Asbestos Cement	251	53	2.43 out of 5	\$345	\$86,595	
Distribution Mains	P-1796	WW	Schofield St.	8	Ductile Iron	37	5	0 out of 5	N/A	\$0	
Distribution Mains	P-1088	WW	School St.	6	Cast iron	183	129	2.58 out of 5	\$345	\$63,135	
Distribution Mains	P-1089	WW	School St.	6	Cast iron	71	129	2.58 out of 5	\$345	\$24,495	
Distribution Mains	P-1091	WW	School St.	6	Cast iron	318	129	2.58 out of 5	\$345	\$109,710	
Distribution Mains	P-1989	WW	Second St.	1	Copper	183	45	2.29 out of 5	\$345	\$63,135	IFR 2015B
Distribution Mains	P-38	WW	Service Rd.	6	Asbestos Cement	498	45	2.43 out of 5	\$345	\$171,810	
Distribution Mains	P-1940	WW	Service Rd.	8	Ductile Iron	136	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-40	WW	Service Rd.	8	Ductile Iron	211	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-42	WW	Service Rd.	8	Ductile Iron	329	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-44	WW	Service Rd.	8	Ductile Iron	305	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-361	WW	Seth Dr.	6	PVC	260	27	1.15 out of 5	\$345	\$89,700	
Distribution Mains	P-362	WW	Seth Dr.	6	PVC	125	27	1.15 out of 5	\$345	\$43,125	
Transmission Mains	P-1467	WW	Setian Ln.	12	Asbestos Cement	532	45	1.72 out of 5	\$345	\$183,540	
Transmission Mains	P-1468	WW	Setian Ln.	12	Asbestos Cement	913	45	1.72 out of 5	\$345	\$314,985	
Transmission Mains	P-92	WW	Setian Ln.	12	Asbestos Cement	583	45	1.72 out of 5	\$345	\$201,135	
Distribution Mains	P-120	WW	Setian Ln.	8	Asbestos Cement	494	38	1.58 out of 5	\$345	\$170,430	
Distribution Mains	P-121	WW	Setian Ln.	8	Asbestos Cement	108	38	1.58 out of 5	\$345	\$37,260	
Distribution Mains	P-1539	WW	Setian Ln. PS	6	Ductile Iron	6	10	0.71 out of 5	\$345	\$2,070	
Distribution Mains	P-1542	WW	Setian Ln. PS	6	Ductile Iron	6	10	0.71 out of 5	\$345	\$2,070	
Transmission Mains	P-1534	WW	Setian Ln. PS	20	Ductile Iron	163	10	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-1536	WW	Setian Ln. PS	16	Ductile Iron	76	10	0 out of 5	N/A	\$0	
Transmission Mains	P-1537	WW	Setian Ln. PS	16	Ductile Iron	10	10	0 out of 5	N/A	\$0	
Distribution Mains	P-1538	WW	Setian Ln. PS	8	Ductile Iron	6	10	0 out of 5	N/A	\$0	
Transmission Mains	P-1540	WW	Setian Ln. PS	16	Ductile Iron	10	10	0 out of 5	N/A	\$0	
Distribution Mains	P-1541	WW	Setian Ln. PS	8	Ductile Iron	6	10	0 out of 5	N/A	\$0	
Transmission Mains	P-1543	WW	Setian Ln. PS	12	Ductile Iron	10	10	0 out of 5	N/A	\$0	
Transmission Mains	P-1547	WW	Setian Ln. PS	12	Ductile Iron	10	10	0 out of 5	N/A	\$0	
Transmission Mains	P-1548	WW	Setian Ln. PS	12	Ductile Iron	457	10	0 out of 5	N/A	\$0	
Transmission Mains	P-1293	WW	Setian Ln. Tank	20	Asbestos Cement	247	45	1.72 out of 5	\$345	\$85,215	
Transmission Mains	P-1198	WW	Setian Ln. Tank	20	Ductile Iron	234	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1199	WW	Setian Ln. Tank	16	Ductile Iron	202	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1304	WW	Setian Ln. Tank	20	Ductile Iron	195	14	0 out of 5	N/A	\$0	
Transmission Mains	P-1535	WW	Setian Ln. Tank	16	Ductile Iron	89	14	0 out of 5	N/A	\$0	
Distribution Mains	P-493	WW	Shady Hill Dr.	8	Asbestos Cement	1,569	49	1.72 out of 5	\$345	\$541,305	
Distribution Mains	P-496	WW	Shady Hill Dr.	8	Asbestos Cement	271	49	1.72 out of 5	\$345	\$93,495	
Distribution Mains	P-363	WW	Shane Dr.	6	PVC	222	27	1.15 out of 5	\$345	\$76,590	
Distribution Mains	P-859	WW	Shannon Ln.	8	Ductile Iron	202	21	0.15 out of 5	N/A	\$0	
Distribution Mains	P-861	WW	Shannon Ln.	8	Ductile Iron	205	21	0.15 out of 5	N/A	\$0	
Distribution Mains	P-866	WW	Shannon Ln.	8	Ductile Iron	431	21	0.15 out of 5	N/A	\$0	
Distribution Mains	P-1385	WW	Sheffield Ave.	8	Ductile Iron	95	3	0 out of 5	N/A	\$0	
Distribution Mains	P-614	WW	Sheffield Ave.	8	Ductile Iron	130	3	0 out of 5	N/A	\$0	
Distribution Mains	P-615	WW	Sheffield Ave.	8	Ductile Iron	237	3	0 out of 5	N/A	\$0	
Distribution Mains	P-618	WW	Sheffield Ave.	8	Ductile Iron	318	3	0 out of 5	N/A	\$0	
Distribution Mains	P-620	WW	Sheffield Ave.	8	Ductile Iron	221	3	0 out of 5	N/A	\$0	
Distribution Mains	P-630	WW	Sheffield Ave.	8	Ductile Iron	698	3	0 out of 5	N/A	\$0	
Distribution Mains	P-243	WW	Sheldon St.	8	Ductile Iron	583	86	0 out of 5	N/A	\$0	
Distribution Mains	P-613	WW	Sherwood Dr.	8	Ductile Iron	726	3	0 out of 5	N/A	\$0	
Distribution Mains	P-711	WW	Shippee Ave.	8	Cast iron	195	125	2.58 out of 5	\$345	\$67,275	
Distribution Mains	P-712	WW	Shippee Ave.	8	Cast iron	240	125	2.58 out of 5	\$345	\$82,800	
Distribution Mains	P-736	WW	Shippee Ave.	6	Cast iron	77	75	2.29 out of 5	\$345	\$26,565	
Distribution Mains	P-737	WW	Shippee Ave.	6	Cast iron	190	75	2.29 out of 5	\$345	\$65,550	
Distribution Mains	P-739	WW	Shippee Ave.	6	Cast iron	179	75	2.29 out of 5	\$345	\$61,755	
Distribution Mains	P-741	WW	Shippee Ave.	6	Cast iron	281	75	2.29 out of 5	\$345	\$96,945	
Distribution Mains	P-709	WW	Shippee Ave.	8	Cast iron	205	125	1.87 out of 5	\$345	\$70,725	
Distribution Mains	P-713	WW	Shippee Ave.	8	Cast iron	226	125	1.87 out of 5	\$345	\$77,970	
Transmission Mains	P-717	WW	Shippee Ave.	12	Cast iron	302	84	1.72 out of 5	\$345	\$104,190	
Distribution Mains	P-197	WW	Shortway Dr.	6	Asbestos Cement	244	64	3.29 out of 5	\$345	\$84,180	
Distribution Mains	P-190	WW	Shortway Dr.	6	Asbestos Cement	177	64	2.58 out of 5	\$345	\$61,065	
Distribution Mains	P-200	WW	Shortway Dr.	6	Asbestos Cement	234	57	2.43 out of 5	\$345	\$80,730	
Distribution Mains	P-1739	WW	Shortway Dr.	6	Ductile Iron	23	4	0.71 out of 5	\$345	\$7,935	
Distribution Mains	P-1740	WW	Shortway Dr.	8	Ductile Iron	88	4	0 out of 5	N/A	\$0	
Distribution Mains	P-192	WW	Shortway Dr.	8	Ductile Iron	152	4	0 out of 5	N/A	\$0	
Distribution Mains	P-1963	WW	Sidney St.	8	Ductile Iron	321	3	0 out of 5	N/A	\$0	
Distribution Mains	P-623	WW	Sidney St.	8	Ductile Iron	349	3	0 out of 5	N/A	\$0	
Distribution Mains	P-625	WW	Sidney St.	8	Ductile Iron	227	3	0 out of 5	N/A	\$0	
Distribution Mains	P-626	WW	Sidney St.	8	Ductile Iron	210	3	0 out of 5	N/A	\$0	
Distribution Mains	P-627	WW	Sidney St.	8	Ductile Iron	227	3	0 out of 5	N/A	\$0	
Transmission Mains	P-1522	WW	Silvercup Cir.	12	Ductile Iron	500	1	0 out of 5	N/A	\$0	
Transmission Mains	P-1523	WW	Silvercup Cir.	12	Ductile Iron	400	1	0 out of 5	N/A	\$0	
Distribution Mains	P-126	WW	Silverwood Ln.	8	Asbestos Cement	1,345	37	1.58 out of 5	\$345	\$464,025	
Distribution Mains	P-1469	WW	Silverwood Ln.	8	Asbestos Cement	418	37	1.58 out of 5	\$345	\$144,210	
Distribution Mains	P-1470	WW	Silverwood Ln.	8	Asbestos Cement	788	37	1.58 out of 5	\$345	\$271,860	
Distribution Mains	P-1471	WW	Silverwood Ln. Easement	8	Asbestos Cement	234	45	1.72 out of 5	\$345	\$80,730	
Distribution Mains	P-1857	WW	Simon St.	1.5	Galvanized iron	161	26	3.01 out of 5	\$345	\$55,545	
Distribution Mains	P-747	WW	Sinnott St.	6	Cast iron	267	74	2.29 out of 5	\$345	\$92,115	
Distribution Mains	P-1218	WW	Sisson St.	1	Galvanized iron	401	73	3.3 out of 5	\$345	\$138,345	
Distribution Mains	P-916	WW	Smith St.	6	Cast iron	528	129	2.58 out of 5	\$345	\$182,160	
Distribution Mains	P-919	WW	Smith St.	6	Cast iron	144	129	2.58 out of 5	\$345	\$49,680	
Distribution Mains	P-604	WW	Sophia's Way	6	Ductile Iron	177	24	0.86 out of 5	\$345	\$61,065	
Distribution Mains	P-1959	WW	Sophia's Way	6	Ductile Iron	31	3	0.71 out of 5	\$345	\$10,695	
Distribution Mains	P-1958	WW	Sophia's Way	8	Ductile Iron	30	3	0 out of 5	N/A	\$0	
Distribution Mains	P-793	WW	South St.	6	Asbestos Cement	300	60	2.58 out of 5	\$345	\$103,500	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-811	WW	Spencer St.	6	Asbestos Cement	236	64	2.58 out of 5	\$345	\$81,420	
Distribution Mains	P-812	WW	Spencer St.	6	Asbestos Cement	483	64	2.58 out of 5	\$345	\$166,635	
Distribution Mains	P-1093	WW	Spring Ln.	2	Galvanized iron	112	129	3.59 out of 5	\$345	\$38,640	
Distribution Mains	P-456	WW	Spring Meadow Cir.	8	Ductile Iron	182	16	0 out of 5	N/A	\$0	
Distribution Mains	P-1094	WW	Spring St.	2	Galvanized iron	163	129	3.59 out of 5	\$345	\$56,235	
Distribution Mains	P-1092	WW	Spring St.	6	Cast iron	303	129	3.29 out of 5	\$345	\$104,535	
Distribution Mains	P-104	WW	Spruce Ct	6	Asbestos Cement	150	36	2.29 out of 5	\$345	\$51,750	
Distribution Mains	P-357	WW	St. George St.	6	Asbestos Cement	267	66	2.58 out of 5	\$345	\$92,115	IFR 2015B
Distribution Mains	P-358	WW	St. George St.	6	Asbestos Cement	147	66	2.58 out of 5	\$345	\$50,715	IFR 2015B
Distribution Mains	P-1909	WW	St. Germaine Ct.	6	PVC	146	33	1.15 out of 5	\$345	\$50,370	
Distribution Mains	P-1980	WW	St. James St.	8	Ductile Iron	199	3	0 out of 5	N/A	\$0	
Distribution Mains	P-670	WW	St. John St.	6	Cast iron	598	124	2.58 out of 5	\$345	\$206,310	
Distribution Mains	P-1034	WW	St. Mary St.	8	Ductile Iron	316	3	0 out of 5	N/A	\$0	
Distribution Mains	P-1179	WW	St. Onge Dr.	8	Asbestos Cement	347	34	1.58 out of 5	\$345	\$119,715	
Distribution Mains	P-1433	WW	St. Onge Dr.	8	Asbestos Cement	223	34	1.58 out of 5	\$345	\$76,935	
Distribution Mains	P-1434	WW	St. Onge Dr.	8	Asbestos Cement	386	34	1.58 out of 5	\$345	\$133,170	
Distribution Mains	P-1437	WW	St. Onge Dr.	8	Ductile Iron	42	14	0 out of 5	N/A	\$0	
Distribution Mains	P-546	WW	Standard Ave.	2	Galvanized iron	342	104	3.59 out of 5	\$345	\$117,990	
Distribution Mains	P-547	WW	Standard Ave.	6	Cast iron	693	104	2.58 out of 5	\$345	\$239,085	
Distribution Mains	P-1777	WW	Starling Way	8	Ductile Iron	406	10	0 out of 5	N/A	\$0	
Distribution Mains	P-10015	WW	Starlite Ct.	8	Ductile Iron	185	10	0 out of 5	N/A	\$0	
Distribution Mains	P-1757	WW	State St.	8	Ductile Iron	339	1	0 out of 5	N/A	\$0	
Distribution Mains	P-969	WW	Sternbach St.	6	Asbestos Cement	252	49	2.43 out of 5	\$345	\$86,940	
Distribution Mains	P-205	WW	Steven Dr.	8	Asbestos Cement	764	37	1.58 out of 5	\$345	\$263,580	
Distribution Mains	P-170	WW	Stoney Creek Dr.	8	Asbestos Cement	436	37	1.58 out of 5	\$345	\$150,420	
Distribution Mains	P-137	WW	Sturbridge Way	8	Ductile Iron	687	16	0 out of 5	N/A	\$0	
Distribution Mains	P-1223	WW	Summit Ave.	6	Cast iron	237	129	2.58 out of 5	\$345	\$81,765	
Distribution Mains	P-1230	WW	Summit Ave.	6	Cast iron	289	129	2.58 out of 5	\$345	\$99,705	
Distribution Mains	P-1231	WW	Summit Ave.	6	Cast iron	351	129	2.58 out of 5	\$345	\$121,095	
Distribution Mains	P-1233	WW	Summit Ave.	6	Cast iron	318	129	2.58 out of 5	\$345	\$109,710	
Distribution Mains	P-975	WW	Summit Ave.	6	Cast iron	847	129	2.58 out of 5	\$345	\$292,215	
Distribution Mains	P-976	WW	Summit Ave.	6	Cast iron	106	129	2.58 out of 5	\$345	\$36,570	
Distribution Mains	P-977	WW	Summit Ave.	6	Cast iron	270	129	2.58 out of 5	\$345	\$93,150	
Distribution Mains	P-1839	WW	Summit Ave.	6	Ductile Iron	29	5	0.71 out of 5	\$345	\$10,005	
Transmission Mains	P-1235	WW	Summit Ave.	12	Ductile Iron	323	7	0 out of 5	N/A	\$0	
Transmission Mains	P-1680	WW	Summit Ave.	12	Ductile Iron	425	7	0 out of 5	N/A	\$0	
Distribution Mains	P-1838	WW	Summit Ave.	8	Ductile Iron	21	5	0 out of 5	N/A	\$0	
Transmission Mains	P-1907	WW	Summit Ave.	12	Ductile Iron	96	7	0 out of 5	N/A	\$0	
Distribution Mains	P-210	WW	Suncrest Dr.	6	Asbestos Cement	259	64	2.58 out of 5	\$345	\$89,355	
Distribution Mains	P-824	WW	Sunrise Ave.	4	Cast iron	472	129	3.3 out of 5	\$345	\$162,840	
Distribution Mains	P-1516	WW	Sunrise Ave.	6	Asbestos Cement	244	49	2.43 out of 5	\$345	\$84,180	
Distribution Mains	P-813	WW	Sunrise Ave.	6	Asbestos Cement	670	49	2.43 out of 5	\$345	\$231,150	
Distribution Mains	P-1513	WW	Sunrise Ave.	8	Ductile Iron	280	8	0 out of 5	N/A	\$0	
Distribution Mains	P-820	WW	Sunset Ave.	6	Cast iron	418	129	2.58 out of 5	\$345	\$144,210	
Distribution Mains	P-821	WW	Sunset Ave.	6	Cast iron	546	129	2.58 out of 5	\$345	\$188,370	
Distribution Mains	P-1409	WW	Surrey Ln.	8	Asbestos Cement	117	39	1.58 out of 5	\$345	\$40,365	
Distribution Mains	P-1410	WW	Surrey Ln.	8	Asbestos Cement	327	39	1.58 out of 5	\$345	\$112,815	
Distribution Mains	P-122	WW	Surrey Ln.	8	Asbestos Cement	1,539	39	1.58 out of 5	\$345	\$530,955	
Distribution Mains	P-1413	WW	Surrey Ln.	8	Ductile Iron	30	14	0 out of 5	N/A	\$0	
Distribution Mains	P-495	WW	Sycamore Dr.	8	Asbestos Cement	1,013	46	1.72 out of 5	\$345	\$349,485	
Distribution Mains	P-497	WW	Sycamore Dr.	8	Asbestos Cement	906	46	1.72 out of 5	\$345	\$312,570	
Distribution Mains	P-1313	WW	Sykes St.	8	Ductile Iron	527	15	0 out of 5	N/A	\$0	
Transmission Mains	P-10008	WW	Szydlo Dr.	12	Ductile Iron	25	2	0 out of 5	N/A	\$0	
Transmission Mains	P-72	WW	Szydlo Dr.	12	Ductile Iron	617	14	0 out of 5	N/A	\$0	
Distribution Mains	P-411	WW	Tampa St.	4	Cast iron	335	82	3.15 out of 5	\$345	\$115,575	IFR 2014B
Distribution Mains	P-10024	WW	Tampa St.	1	Copper	593	82	2.58 out of 5	\$345	\$204,585	IFR 2014B
Distribution Mains	P-407	WW	Tampa St.	2	Copper	209	82	2.58 out of 5	\$345	\$72,105	IFR 2014B
Distribution Mains	P-409	WW	Tampa St.	2	Copper	201	82	2.58 out of 5	\$345	\$69,345	IFR 2014B
Distribution Mains	P-10025	WW	Tampa St.	6	Asbestos Cement	274	41	2.43 out of 5	\$345	\$94,530	
Distribution Mains	P-414	WW	Tampa St.	6	Asbestos Cement	199	41	2.43 out of 5	\$345	\$68,655	IFR 2014B
Distribution Mains	P-424	WW	Tampa St.	6	Asbestos Cement	430	53	2.43 out of 5	\$345	\$148,350	
Distribution Mains	P-425	WW	Tampa St.	6	Asbestos Cement	317	53	2.43 out of 5	\$345	\$109,365	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-306	WW	Tanglewood Dr.	8	Asbestos Cement	837	36	1.58 out of 5	\$345	\$288,765	
Distribution Mains	P-307	WW	Tanglewood Dr.	8	Asbestos Cement	406	36	1.58 out of 5	\$345	\$140,070	
Distribution Mains	P-316	WW	Tanglewood Dr.	8	Asbestos Cement	490	36	1.58 out of 5	\$345	\$169,050	
Distribution Mains	P-317	WW	Tanglewood Dr.	8	Asbestos Cement	733	36	1.58 out of 5	\$345	\$252,885	
Distribution Mains	P-327	WW	Tanglewood Dr.	8	Asbestos Cement	346	36	1.58 out of 5	\$345	\$119,370	
Distribution Mains	P-10022	WW	Teddy Ct.	8	Ductile Iron	264	4	0 out of 5	N/A	\$0	
Distribution Mains	P-1240	WW	Terrace Ave.	2	Galvanized iron	144	124	3.59 out of 5	\$345	\$49,680	
Distribution Mains	P-1244	WW	Terrace Ave.	4	Ductile Iron	373	5	1.43 out of 5	\$345	\$128,685	
Distribution Mains	P-1880	WW	Terrace Ct.	1	PVC	389	23	1.87 out of 5	\$345	\$134,205	
Distribution Mains	P-115	WW	Terre Mar Dr.	8	Asbestos Cement	487	39	1.58 out of 5	\$345	\$168,015	
Distribution Mains	P-348	WW	Third St.	6	Cast iron	341	73	2.29 out of 5	\$345	\$117,645	IFR 2015B
Distribution Mains	P-524	WW	Tiffany Ave.	6	Asbestos Cement	166	46	2.43 out of 5	\$345	\$57,270	
Distribution Mains	P-525	WW	Tiffany Ave.	6	Asbestos Cement	185	46	2.43 out of 5	\$345	\$63,825	
Distribution Mains	P-1100	WW	Tilton St.	6	Asbestos Cement	399	43	2.43 out of 5	\$345	\$137,655	
Distribution Mains	P-1416	WW	Timber Walk Dr.	8	Ductile Iron	527	12	0 out of 5	N/A	\$0	
Distribution Mains	P-473	WW	Tina Dr.	8	Asbestos Cement	503	74	1.87 out of 5	\$345	\$173,535	
Transmission Mains	P-1172	WW	Tiogue Ave.	12	Asbestos Cement	1,123	49	1.72 out of 5	\$345	\$387,435	
Transmission Mains	P-1174	WW	Tiogue Ave.	12	Asbestos Cement	234	49	1.72 out of 5	\$345	\$80,730	
Transmission Mains	P-1176	WW	Tiogue Ave.	12	Asbestos Cement	151	49	1.72 out of 5	\$345	\$52,095	
Transmission Mains	P-1577	WW	Tiogue Ave.	12	Asbestos Cement	283	49	1.72 out of 5	\$345	\$97,635	
Distribution Mains	P-786	WW	Tobin St.	6	Cast iron	251	69	2.29 out of 5	\$345	\$86,595	
Distribution Mains	P-1898	WW	Tobin St.	6	Ductile Iron	29	6	0.71 out of 5	\$345	\$10,005	
Distribution Mains	P-1900	WW	Tobin St.	6	Ductile Iron	32	6	0.71 out of 5	\$345	\$11,040	
Distribution Mains	P-1899	WW	Tobin St.	8	Ductile Iron	153	6	0 out of 5	N/A	\$0	
Distribution Mains	P-309	WW	Tower Rd.	8	Asbestos Cement	296	38	1.58 out of 5	\$345	\$102,120	
Distribution Mains	P-311	WW	Tower Rd.	8	Asbestos Cement	953	38	1.58 out of 5	\$345	\$328,785	
Distribution Mains	P-313	WW	Tower Rd.	8	Asbestos Cement	654	38	1.58 out of 5	\$345	\$225,630	
Distribution Mains	P-315	WW	Tower Rd.	8	Asbestos Cement	325	38	1.58 out of 5	\$345	\$112,125	
Transmission Mains	P-1768	WW	Tripoli St.	12	Ductile Iron	121	1	0 out of 5	N/A	\$0	
Transmission Mains	P-258	WW	Tripoli St.	12	Ductile Iron	103	1	0 out of 5	N/A	\$0	
Transmission Mains	P-259	WW	Tripoli St.	12	Ductile Iron	136	1	0 out of 5	N/A	\$0	
Distribution Mains	P-1905	WW	Tuckerman St.	2	Copper	130	70	2.44 out of 5	\$345	\$44,850	
Distribution Mains	P-103	WW	Turner Dr.	8	Asbestos Cement	786	39	1.58 out of 5	\$345	\$271,170	
Distribution Mains	P-105	WW	Turner Dr.	8	Asbestos Cement	248	39	1.58 out of 5	\$345	\$85,560	
Distribution Mains	P-106	WW	Turner Dr.	8	Asbestos Cement	221	39	1.58 out of 5	\$345	\$76,245	
Distribution Mains	P-1913	WW	Urquhart St.	6	Cast iron	335	129	2.58 out of 5	\$345	\$115,575	
Distribution Mains	P-1914	WW	Urquhart St.	6	Cast iron	352	129	2.58 out of 5	\$345	\$121,440	
Distribution Mains	P-1902	WW	Valley View Dr.	1.5	Copper	182	65	2.44 out of 5	\$345	\$62,790	
Distribution Mains	P-1903	WW	Valley View Dr.	1.5	Copper	62	65	2.44 out of 5	\$345	\$21,390	
Distribution Mains	P-755	WW	Valley View Dr.	1	Copper	208	64	2.44 out of 5	\$345	\$71,760	
Distribution Mains	P-934	WW	Ventura St.	6	Cast iron	332	129	2.58 out of 5	\$345	\$114,540	
Distribution Mains	P-1848	WW	Ventura St.	8	Cast iron	29	129	1.87 out of 5	\$345	\$10,005	
Distribution Mains	P-1781	WW	Victoria Way	8	Ductile Iron	126	10	0 out of 5	N/A	\$0	
Distribution Mains	P-91	WW	Victory Ave.	6	Asbestos Cement	310	73	2.58 out of 5	\$345	\$106,950	
Distribution Mains	P-889	WW	Vincenzo Dr.	6	PVC	285	33	1.15 out of 5	\$345	\$98,325	
Distribution Mains	P-1791	WW	Vincenzo Dr.	6	Ductile Iron	415	5	0.71 out of 5	\$345	\$143,175	
Distribution Mains	P-1788	WW	Vincenzo Dr.	8	PVC	27	33	0.44 out of 5	\$345	\$9,315	
Distribution Mains	P-890	WW	Vincenzo Dr.	8	Ductile Iron	34	5	0 out of 5	N/A	\$0	
Distribution Mains	P-1359	WW	Vine St.	4	Cast iron	470	128	3.3 out of 5	\$345	\$162,150	
Distribution Mains	P-762	WW	Virginia Ave.	6	Asbestos Cement	230	47	2.43 out of 5	\$345	\$79,350	
Distribution Mains	P-1309	WW	Waite St.	6	Asbestos Cement	351	64	2.58 out of 5	\$345	\$121,095	
Distribution Mains	P-1785	WW	Wakefield Hills Elementary Sch	4	Ductile Iron	43	12	1.43 out of 5	\$345	\$14,835	
Distribution Mains	P-1784	WW	Wakefield Hills Elementary Sch	6	Ductile Iron	19	12	0.71 out of 5	\$345	\$6,555	
Transmission Mains	P-1329	WW	Wakefield Hills Elementary Sch	12	Ductile Iron	200	12	0 out of 5	N/A	\$0	
Transmission Mains	P-1332	WW	Wakefield Hills Elementary Sch	12	Ductile Iron	382	12	0 out of 5	N/A	\$0	
Distribution Mains	P-1783	WW	Wakefield Hills Elementary Sch	8	Ductile Iron	156	12	0 out of 5	N/A	\$0	
Transmission Mains	P-1305	WW	Wakefield St.	12	Asbestos Cement	153	34	1.58 out of 5	\$345	\$52,785	
Transmission Mains	P-1330	WW	Wakefield St.	12	Asbestos Cement	153	34	1.58 out of 5	\$345	\$52,785	
Transmission Mains	P-1331	WW	Wakefield St.	12	Asbestos Cement	852	34	1.58 out of 5	\$345	\$293,940	
Transmission Mains	P-855	WW	Wakefield St.	12	Asbestos Cement	2,225	34	1.58 out of 5	\$345	\$767,625	
Transmission Mains	P-1333	WW	Wakefield St.	12	Ductile Iron	494	17	0 out of 5	N/A	\$0	
Transmission Mains	P-1751	WW	Wakefield St.	16	Ductile Iron	215	1	0 out of 5	N/A	\$0	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Transmission Mains	P-1752	WW	Wakefield St.	16	Ductile Iron	44	1	0 out of 5	N/A	\$0	
Transmission Mains	P-1847	WW	Wakefield St.	12	Ductile Iron	439	17	0 out of 5	N/A	\$0	
Distribution Mains	P-233	WW	Wakefield St.	8	Ductile Iron	591	19	0 out of 5	N/A	\$0	
Distribution Mains	P-235	WW	Wakefield St.	8	Ductile Iron	243	19	0 out of 5	N/A	\$0	
Distribution Mains	P-237	WW	Wakefield St.	8	Ductile Iron	893	19	0 out of 5	N/A	\$0	
Transmission Mains	P-850	WW	Wakefield St.	12	Ductile Iron	389	17	0 out of 5	N/A	\$0	
Transmission Mains	P-851	WW	Wakefield St.	12	Ductile Iron	164	17	0 out of 5	N/A	\$0	
Transmission Mains	P-852	WW	Wakefield St.	12	Ductile Iron	354	17	0 out of 5	N/A	\$0	
Transmission Mains	P-854	WW	Wakefield St.	12	Ductile Iron	134	17	0 out of 5	N/A	\$0	
Transmission Mains	P-887	WW	Wakefield St.	12	Ductile Iron	88	17	0 out of 5	N/A	\$0	
Transmission Mains	P-907	WW	Wakefield St.	12	Ductile Iron	327	17	0 out of 5	N/A	\$0	
Transmission Mains	P-908	WW	Wakefield St.	12	Ductile Iron	744	17	0 out of 5	N/A	\$0	
Transmission Mains	P-909	WW	Wakefield St.	12	Ductile Iron	563	17	0 out of 5	N/A	\$0	
Transmission Mains	P-920	WW	Wakefield St.	12	Ductile Iron	118	17	0 out of 5	N/A	\$0	
Transmission Mains	P-929	WW	Wakefield St.	12	Ductile Iron	247	17	0 out of 5	N/A	\$0	
Transmission Mains	P-935	WW	Wakefield St.	12	Ductile Iron	419	17	0 out of 5	N/A	\$0	
Transmission Mains	P-1267	WW	Wakefield St. Tank	12	Ductile Iron	237	24	0.15 out of 5	N/A	\$0	
Distribution Mains	P-1891	WW	Walker St.	6	Cast iron	50	78	2.29 out of 5	\$345	\$17,250	
Distribution Mains	P-1893	WW	Walker St.	4	Ductile Iron	45	13	1.43 out of 5	\$345	\$15,525	
Distribution Mains	P-1402	WW	Walker St.	8	Ductile Iron	227	13	0.71 out of 5	\$345	\$78,315	
Distribution Mains	P-1040	WW	Walker St.	8	Ductile Iron	235	13	0 out of 5	N/A	\$0	
Distribution Mains	P-1041	WW	Walker St.	8	Ductile Iron	318	13	0 out of 5	N/A	\$0	
Distribution Mains	P-1890	WW	Walker St.	8	Ductile Iron	54	13	0 out of 5	N/A	\$0	
Distribution Mains	P-1897	WW	Walker St.	8	Ductile Iron	66	13	0 out of 5	N/A	\$0	
Distribution Mains	P-1761	WW	Wallace Ave.	8	Ductile Iron	382	2	0 out of 5	N/A	\$0	
Distribution Mains	P-683	WW	Walnut St.	6	Asbestos Cement	444	42	2.43 out of 5	\$345	\$153,180	
Transmission Mains	P-1381	WW	Washington St.	12	Cast iron	176	128	1.87 out of 5	\$345	\$60,720	
Distribution Mains	P-1681	WW	Washington St.	8	Cast iron	254	129	1.87 out of 5	\$345	\$87,630	
Distribution Mains	P-679	WW	Washington St.	8	Cast iron	54	129	1.87 out of 5	\$345	\$18,630	
Transmission Mains	P-680	WW	Washington St.	12	Cast iron	83	129	1.87 out of 5	\$345	\$28,635	
Transmission Mains	P-682	WW	Washington St.	12	Cast iron	319	128	1.87 out of 5	\$345	\$110,055	
Transmission Mains	P-684	WW	Washington St.	12	Cast iron	202	128	1.87 out of 5	\$345	\$69,690	
Transmission Mains	P-686	WW	Washington St.	12	Cast iron	974	128	1.87 out of 5	\$345	\$336,030	
Transmission Mains	P-687	WW	Washington St.	12	Cast iron	374	129	1.87 out of 5	\$345	\$129,030	
Transmission Mains	P-689	WW	Washington St.	12	Cast iron	289	129	1.87 out of 5	\$345	\$99,705	
Distribution Mains	P-724	WW	Washington St.	8	Cast iron	442	129	1.87 out of 5	\$345	\$152,490	
Distribution Mains	P-729	WW	Washington St.	8	Cast iron	279	129	1.87 out of 5	\$345	\$96,255	
Distribution Mains	P-1974	WW	Washington St.	8	Cast iron	119	83	1.72 out of 5	\$345	\$41,055	
Distribution Mains	P-668	WW	Washington St.	8	Cast iron	103	83	1.72 out of 5	\$345	\$35,535	
Distribution Mains	P-669	WW	Washington St.	8	Cast iron	191	83	1.72 out of 5	\$345	\$65,895	
Distribution Mains	P-671	WW	Washington St.	8	Cast iron	263	83	1.72 out of 5	\$345	\$90,735	
Distribution Mains	P-268	WW	Water St.	8	Ductile Iron	518	86	0 out of 5	N/A	\$0	
Distribution Mains	P-183	WW	Watervalley Rd.	8	PVC	444	30	0.44 out of 5	\$345	\$153,180	
Distribution Mains	P-184	WW	Watervalley Rd.	8	PVC	99	30	0.44 out of 5	\$345	\$34,155	
Distribution Mains	P-960	WW	Waverly St.	6	Cast iron	307	76	2.29 out of 5	\$345	\$105,915	
Distribution Mains	P-1061	WW	Weaver St.	4	Cast iron	263	124	3.3 out of 5	\$345	\$90,735	
Distribution Mains	P-1339	WW	Weaver St.	4	Cast iron	250	124	3.3 out of 5	\$345	\$86,250	
Distribution Mains	P-1048	WW	Weaver St.	6	Cast iron	251	124	2.58 out of 5	\$345	\$86,595	
Distribution Mains	P-1060	WW	Weaver St.	6	Cast iron	212	124	2.58 out of 5	\$345	\$73,140	
Distribution Mains	P-341	WW	Webster Knight Dr.	6	Asbestos Cement	384	43	2.43 out of 5	\$345	\$132,480	
Distribution Mains	P-1366	WW	Webster St.	4	Cast iron	297	104	3.3 out of 5	\$345	\$102,465	
Distribution Mains	P-375	WW	Wells St.	6	Asbestos Cement	242	74	2.58 out of 5	\$345	\$83,490	IFR 2014B
Distribution Mains	P-376	WW	Wells St.	6	Asbestos Cement	263	74	2.58 out of 5	\$345	\$90,735	IFR 2014B
Distribution Mains	P-384	WW	Wells St.	6	Ductile Iron	154	21	0.86 out of 5	\$345	\$53,130	
Distribution Mains	P-1147	WW	Wendy Way	6	Asbestos Cement	871	43	2.43 out of 5	\$345	\$300,495	
Distribution Mains	P-1582	WW	West Glen Ln.	8	Ductile Iron	10	1	0 out of 5	N/A	\$0	
Distribution Mains	P-1583	WW	West Glen Ln.	8	Ductile Iron	370	1	0 out of 5	N/A	\$0	
Distribution Mains	P-1584	WW	West Glen Ln.	8	Ductile Iron	370	1	0 out of 5	N/A	\$0	
Distribution Mains	P-1613	WW	West Glen Ln.	8	Ductile Iron	113	1	0 out of 5	N/A	\$0	
Distribution Mains	P-703	WW	West St.	4	Cast iron	292	125	3.3 out of 5	\$345	\$100,740	
Distribution Mains	P-705	WW	West St.	4	Cast iron	298	125	3.3 out of 5	\$345	\$102,810	
Distribution Mains	P-708	WW	West St.	2	Galvanized iron	929	74	3.3 out of 5	\$345	\$320,505	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-1952	WW	West St.	6	Cast iron	645	126	3.29 out of 5	\$345	\$222,525	
Distribution Mains	P-696	WW	West St.	6	Cast iron	47	126	2.58 out of 5	\$345	\$16,215	
Distribution Mains	P-697	WW	West St.	6	Cast iron	219	126	2.58 out of 5	\$345	\$75,555	
Distribution Mains	P-706	WW	West St.	6	Cast iron	122	74	2.29 out of 5	\$345	\$42,090	
Transmission Mains	P-769	WW	West St.	16	Asbestos Cement	341	70	1.87 out of 5	\$345	\$117,645	
Transmission Mains	P-1289	WW	West St.	12	Cast iron	278	84	1.72 out of 5	\$345	\$95,910	
Transmission Mains	P-759	WW	West St.	12	Cast iron	156	84	1.72 out of 5	\$345	\$53,820	
Transmission Mains	P-761	WW	West St.	12	Cast iron	389	84	1.72 out of 5	\$345	\$134,205	
Transmission Mains	P-765	WW	West St.	12	Cast iron	204	84	1.72 out of 5	\$345	\$70,380	
Transmission Mains	P-1282	WW	West St. Tank	12	Cast iron	211	84	1.72 out of 5	\$345	\$72,795	
Distribution Mains	P-1283	WW	West St. Tank	8	Cast iron	75	84	1.72 out of 5	\$345	\$25,875	
Transmission Mains	P-768	WW	West St. Tank	12	Cast iron	99	84	1.72 out of 5	\$345	\$34,155	
Transmission Mains	P-1280	WW	West St. Tank	12	Ductile Iron	160	12	0 out of 5	N/A	\$0	
Transmission Mains	P-1281	WW	West St. Tank	12	Ductile Iron	108	12	0 out of 5	N/A	\$0	
Transmission Mains	P-767	WW	West St. Tank	12	Ductile Iron	148	12	0 out of 5	N/A	\$0	
Distribution Mains	P-1969	WW	West Warwick Ave.	6	Cast iron	223	129	3.29 out of 5	\$345	\$76,935	
Distribution Mains	P-1949	WW	West Warwick Ave.	6	Cast iron	153	129	2.58 out of 5	\$345	\$52,785	
Distribution Mains	P-550	WW	West Warwick Ave.	6	Cast iron	241	129	2.58 out of 5	\$345	\$83,145	
Distribution Mains	P-552	WW	West Warwick Ave.	6	Cast iron	94	129	2.58 out of 5	\$345	\$32,430	
Distribution Mains	P-555	WW	West Warwick Ave.	6	Cast iron	233	129	2.58 out of 5	\$345	\$80,385	
Distribution Mains	P-557	WW	West Warwick Ave.	6	Cast iron	55	129	2.58 out of 5	\$345	\$18,975	
Distribution Mains	P-559	WW	West Warwick Ave.	6	Cast iron	191	129	2.58 out of 5	\$345	\$65,895	
Distribution Mains	P-560	WW	West Warwick Ave.	6	Cast iron	226	129	2.58 out of 5	\$345	\$77,970	
Distribution Mains	P-561	WW	West Warwick Ave.	6	Cast iron	38	129	2.58 out of 5	\$345	\$13,110	
Distribution Mains	P-565	WW	West Warwick Ave.	6	Cast iron	202	129	2.58 out of 5	\$345	\$69,690	
Distribution Mains	P-566	WW	West Warwick Ave.	6	Cast iron	128	129	2.58 out of 5	\$345	\$44,160	
Distribution Mains	P-569	WW	West Warwick Ave.	6	Cast iron	146	129	2.58 out of 5	\$345	\$50,370	
Distribution Mains	P-639	WW	West Warwick Ave.	6	Cast iron	622	129	2.58 out of 5	\$345	\$214,590	
Distribution Mains	P-640	WW	West Warwick Ave.	6	Cast iron	90	129	2.58 out of 5	\$345	\$31,050	
Distribution Mains	P-690	WW	West Warwick Ave.	6	Cast iron	210	124	2.58 out of 5	\$345	\$72,450	
Distribution Mains	P-688	WW	West Warwick Ave. Easement	6	Cast iron	141	124	2.58 out of 5	\$345	\$48,645	
Distribution Mains	P-922	WW	Westly St.	6	Cast iron	176	129	2.58 out of 5	\$345	\$60,720	
Distribution Mains	P-923	WW	Westly St.	6	Cast iron	348	129	2.58 out of 5	\$345	\$120,060	
Transmission Mains	P-924	WW	Westly St.	20	Ductile Iron	177	8	0 out of 5	N/A	\$0	
Transmission Mains	P-1689	WW	Whisper Ct.	12	Ductile Iron	580	5	0 out of 5	N/A	\$0	
Transmission Mains	P-1690	WW	Whisper Ct.	12	Ductile Iron	10	5	0 out of 5	N/A	\$0	
Transmission Mains	P-1691	WW	Whisper Ct.	12	Ductile Iron	130	5	0 out of 5	N/A	\$0	
Transmission Mains	P-1692	WW	Whisper Ct.	12	Ductile Iron	450	5	0 out of 5	N/A	\$0	
Distribution Mains	P-3	WW	Whispering Pines Ct.	8	Ductile Iron	197	23	0.15 out of 5	N/A	\$0	
Distribution Mains	P-175	WW	Whitebirch Ln.	8	Asbestos Cement	434	37	1.58 out of 5	\$345	\$149,730	
Transmission Mains	P-1357	WW	Wightman St.	12	PVC	633	26	1.15 out of 5	\$345	\$218,385	
Transmission Mains	P-835	WW	Wightman St.	12	PVC	478	26	1.15 out of 5	\$345	\$164,910	
Transmission Mains	P-1356	WW	Wightman St.	12	PVC	60	26	0.44 out of 5	\$345	\$20,700	
Transmission Mains	P-1856	WW	Wightman St.	12	PVC	371	26	0.44 out of 5	\$345	\$127,995	
Distribution Mains	P-1625	WW	Wildberry Senior Housing	8	Ductile Iron	387	6	0 out of 5	N/A	\$0	
Distribution Mains	P-694	WW	Willow St.	6	Cast iron	233	124	2.58 out of 5	\$345	\$80,385	
Distribution Mains	P-695	WW	Willow St.	6	Cast iron	404	124	2.58 out of 5	\$345	\$139,380	
Distribution Mains	P-1384	WW	Wilshire Way	8	Ductile Iron	170	3	0 out of 5	N/A	\$0	
Distribution Mains	P-617	WW	Wilshire Way	8	Ductile Iron	251	3	0 out of 5	N/A	\$0	
Distribution Mains	P-628	WW	Wilshire Way	8	Ductile Iron	464	3	0 out of 5	N/A	\$0	
Transmission Mains	P-1704	WW	Wilson St.	12	Ductile Iron	168	1	0 out of 5	N/A	\$0	
Transmission Mains	P-1767	WW	Wilson St.	12	Ductile Iron	770	1	0 out of 5	N/A	\$0	
Transmission Mains	P-256	WW	Wilson St.	12	Ductile Iron	708	1	0 out of 5	N/A	\$0	
Distribution Mains	P-1960	WW	Windsor Park Dr.	8	Ductile Iron	56	3	0 out of 5	N/A	\$0	
Distribution Mains	P-1961	WW	Windsor Park Dr.	8	Ductile Iron	234	3	0 out of 5	N/A	\$0	
Distribution Mains	P-603	WW	Windsor Park Dr.	8	Ductile Iron	168	3	0 out of 5	N/A	\$0	
Distribution Mains	P-544	WW	Winthrop Ave.	2	Galvanized iron	590	104	5.00 out of 5	\$345	\$203,550	
Distribution Mains	P-545	WW	Winthrop Ave.	4	Cast iron	691	104	3.3 out of 5	\$345	\$238,395	
Distribution Mains	P-707	WW	Wood St.	6	Asbestos Cement	269	64	2.58 out of 5	\$345	\$92,805	
Transmission Mains	P-1679	WW	Woodbine St.	12	Ductile Iron	331	7	0 out of 5	N/A	\$0	
Transmission Mains	P-967	WW	Woodbine St.	12	Ductile Iron	427	7	0 out of 5	N/A	\$0	
Distribution Mains	P-180	WW	Woodland Dr.	6	Asbestos Cement	237	64	2.58 out of 5	\$345	\$81,765	

Infrastructure Subtype	Pipe ID	Town	Street Name	Pipe Diameter	Pipe Material	Length in Linear Feet	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per Linear Foot (Includes additional 15% for Engineering and Construction Services)	Replacement Cost (in dollars)	Notes
Distribution Mains	P-189	WW	Woodland Dr.	6	Asbestos Cement	389	64	2.58 out of 5	\$345	\$134,205	
Distribution Mains	P-814	WW	Woodside Ave.	6	Cast iron	1,048	129	2.58 out of 5	\$345	\$361,560	
Distribution Mains	P-815	WW	Woodside Ave.	6	Cast iron	183	129	2.58 out of 5	\$345	\$63,135	
Distribution Mains	P-818	WW	Woodside Ave.	6	Cast iron	528	129	2.58 out of 5	\$345	\$182,160	
Distribution Mains	P-803	WW	Woodside Ave.	6	Cast iron	347	76	2.29 out of 5	\$345	\$119,715	
Distribution Mains	P-805	WW	Woodside Ave.	6	Cast iron	171	76	2.29 out of 5	\$345	\$58,995	
Distribution Mains	P-808	WW	Woodside Ave.	6	Cast iron	632	76	2.29 out of 5	\$345	\$218,040	
Distribution Mains	P-1555	WW	WW Buisness Park PS	8	Ductile Iron	10	10	0 out of 5	N/A	\$0	
Distribution Mains	P-1552	WW	WW Business Park PS	6	Ductile Iron	6	10	0.71 out of 5	\$345	\$2,070	
Distribution Mains	P-1556	WW	WW Business Park PS	6	Ductile Iron	6	10	0.71 out of 5	\$345	\$2,070	
Distribution Mains	P-1551	WW	WW Business Park PS	8	Ductile Iron	218	10	0 out of 5	N/A	\$0	
Distribution Mains	P-1553	WW	WW Business Park PS	8	Ductile Iron	6	10	0 out of 5	N/A	\$0	
Distribution Mains	P-1554	WW	WW Business Park PS	8	Ductile Iron	224	10	0 out of 5	N/A	\$0	
Distribution Mains	P-1557	WW	WW Business Park PS	8	Ductile Iron	6	10	0 out of 5	N/A	\$0	
Distribution Mains	P-1558	WW	WW Business Park PS	8	Ductile Iron	10	10	0 out of 5	N/A	\$0	
Distribution Mains	P-1483	WW	Wyman St.	6	Cast iron	248	129	2.58 out of 5	\$345	\$85,560	
Distribution Mains	P-1485	WW	Wyman St.	6	Cast iron	85	129	2.58 out of 5	\$345	\$29,325	
Distribution Mains	P-1038	WW	Youngs Ave.	2	Galvanized iron	855	129	4.3 out of 5	\$345	\$294,975	
Distribution Mains	P-785	WW	Youngs Ave.	6	Cast iron	350	129	2.58 out of 5	\$345	\$120,750	
Distribution Mains	P-787	WW	Youngs Ave.	6	Cast iron	1,588	129	2.58 out of 5	\$345	\$547,860	
Distribution Mains	P-780	WW	Youngs Ave.	6	Asbestos Cement	267	58	2.43 out of 5	\$345	\$92,115	
Distribution Mains	P-782	WW	Youngs Ave.	8	Ductile Iron	800	13	0 out of 5	N/A	\$0	
									Remaining Cost to Replace:	\$543,316,695	

Total Infrastructure Rehabilitation and Replacement Costs Kent County Water Authority		
Infrastructure Type	5-year Costs	Total Costs Over 20 Years
Source	\$1,000,000	\$1,000,000
Treatment	\$1,500,000	\$1,500,000
Disinfection	\$0	\$0
Transmission_Distribution**	\$32,450,000	\$135,550,000
Storage	\$0	\$1,800,000
Other	\$50,000	\$150,000
TOTAL*	\$35,000,000	\$140,000,000

*Totals are based on proposed annual restricted replacement fund of \$7,000,000.

**Remaining cost to replace transmission and distribution infrastructure is estimated at \$543,316,695

Financial Component	Questions	Brief Description
Infrastructure Replacement Fund	Does the water system have an Infrastructure Replacement Fund?	Yes, the system is approved by the RIPUC to collect rates to finance an annual restricted replacement fund of \$7,000,000.
Planning for Replacements (Impact on Rate Structure)	Did the plan incorporate proposed rate structure impacts, a schedule of proposed rate changes, and schedule for fully funding the replacement projects based on the schedule included in the plan?	Determined by RIPUC